

Dividends Horizon

Price List
March 2020



Knoll

Introduction	Knoll and Sustainable Design	3
	Knoll Color Program Finishes	4
	Dividends Legacy Finishes	6
	Dividends Horizon Fabrics	7
Planning Guidelines	Panel Specifications	8
Panels, Pre-Configured	Monolithic Panels	14
	Tiled Panels	24
	Beltway Panels	42
Panels, Build-To-Spec	Topway and Full View Panel Frame Assemblies	48
	Base Raceway Covers	53
	Stack Frames	54
	Monolithic Panel Fabric Inserts	58
	Monolithic Laminate Inserts	62
	Tiled Fabric Inserts	68
	Tiled Laminate Inserts	72
	Beltway Inserts	76
	High Acoustic Core Inserts	82
	Window Insert Kits	84
	Markerboard Tiles	86
	Steel Insert Kits	90
	Slatwall Tiles	100
	Technology Tiles	102
	Freestanding Foot	106
	Rolling Door	108
	Glass Screens	112
	Glass Stacking Screens	120
	Standard Frameless Add Up	124
	Recessed Frameless Add Up	127
Post Connectors/End Trim	Dividends Horizon DP8 Post Assemblies	134
	Dividends Horizon DP8 Post Components	138
	Panel End Trim and Panel Top Caps	146
	Panel Wall Starter, Panel-to-Panel Top Cap Transition	156
	Wall Mount Tracks and Components	158
	Coat Hooks and Reveal Fillers	162
Alternative Planning	Universal Gallery Panels	166
	Concealed Post	174
	120° Planning	200
Electrical/Data Components	Electrical Specifications	208
	Base Raceway Electrical	212
	Receptacles	216
	Vertical Electrical	220
	Single Vertical Electrical	223
	Double Vertical Electrical	225
	Desktop Power and Data Modules	226
	Beltway Electrical	230
	Electrical Infeeds and Power Poles	234
	Electrical Infeeds	237
	New York City, San Francisco and Chicago Electrical	238
	Cable Management	242

Storage Components	Flip-Up Door Overheads	246
	Sliding Door Overheads	250
	Up Mounted Overheads	262
	Overhead Bookshelf	264
	Mounting Brackets and Accessories	266
	Task Lights	270
	Pedestals	272
	Credenzas	278
	Flip-up Door Overdesk and Tackboards	290
	Sliding Door Overdesks	294
	Sliding Door Overdesks with Tackboard	303
Worksurfaces	Worksurface Specifications	314
	Rectangular Worksurfaces	318
	Curvilinear Wave End Worksurfaces	328
	Smooth Wave Worksurfaces	330
	Faceted Worksurfaces	332
	Trapezoidal Worksurfaces	338
	Corner Worksurfaces	340
	Peninsula Worksurfaces	348
	Curvilinear Half- and Corner-Round Worksurfaces	352
	Transaction Counter Worksurfaces	354
Cascade Edge Worksurfaces	Rectangular with Cascade Edge	356
	Blended “D” and Curvilinear Corner with Cascade Edge	357
	Blended “L” with Cascade Edge	358
	Half Round and Corner Round with Cascade Edge	359
	Wave End with Cascade Edge	360
Postformed	Postformed Worksurfaces, 1 3/4”	361
	Postformed Worksurfaces, 1 1/4”	367
	Postformed Options worksurfaces 1 1/4”	378
Worksurface Supports	Panel Mounted Worksurface Brackets	388
	Network Privacy screens	393
	Screen-to-Worksurface Brackets	396
	Panel Mounted Worksurface Supports	398
	Peninsula Worksurface Supports	400
Tables	Y Leg Tables	402
	X Base Tables	410
	Table Supports	415
	Conference Tables	418
	Dividends Horizon EQ Tables	422
Freestanding Desks	Preconfigured Desks	424
	Desk Components	436
	Desk Accessories	442
Wall Mounting of Knoll Products		445
Alpha-Numeric Index		447
Selling Policy		463
KnollKey Lock Program		465
General Ordering Information		466

Knoll and Sustainable Design

Each year Knoll sets key initiatives in the journey to sustainability. Focused on our impact to people and planet, Knoll reports material health product attributes and sets operational targets to reduce greenhouse gas emissions, waste generation and water use (in our North American facilities.)

Material transparency is a core Knoll sustainable design value, enabling us to optimize the design and performance of our products. Our material health program utilizes independent third-party certifications that provide an impartial and trustworthy foundation for industry-wide transparency. Certification by respected third parties ensures that all manufacturers are held to the same high standards. Knoll certifications include: Forest Stewardship Council (FSC®), Intertek's Clean Air Program, Business and Institutional Furniture Manufacturer's Association (BIFMA) LEVEL® certification, International Living Future Institute's (ILFI) Declare labelling and Certified Environmental Product Declarations. In addition, Knoll is aligned with the U.S. Green Building Council and can help organizations achieve credits for Leadership in Energy and Environmental Design (LEED®), WELL and the Living Building Challenge (LBC) building certifications.

In our manufacturing operations, we focus on efficiency and impact. Knoll Office and Knoll Europe manufacturing locations are ISO 14001:2015 certified. Knoll sets objectives and targets to reduce energy, water and waste. These initiatives are part of a long-term strategy to further reduce energy consumption and lower our carbon footprint.

We also believe in helping our customers find viable options when decommissioning furniture or other related assets. ANEW's Full Circle Program, in partnership with Knoll, allows customers to leverage buy-back and re-sale programs as well as explore options for repurposing or recycling that mitigate landfill impact through energy-from-waste conversion.

For more information about Knoll and sustainable design, visit www.knoll.com/environment.

Specify Core finishes for all new customers**Paint Finishes:**

Beige Mist Metallic (611T)
 Black Brown (120T)
 Bright White (118T)
 Brown (112T)
 Dark Grey (113T)
 Folkstone Grey (114T)
 Jet Black (111T)
 Medium Grey (115T)
 Medium Metallic Grey (612T)
 Sandstone (116T)
 Silver (613)
 Soft Grey (117T)

Paint Finish Applications:

Panel base raceway covers
 Screen frames
 Steel and slatwall tile inserts
 D1 style tile supports
 DP8 metal panel trim
 DP8 power poles
 Worksurface supports
 Overhead and overdesk cases and doors
 Credenza case, top and door
 Pedestal case and fronts
 Table bases

Laminate Finishes:

Barnwood (149)* **
 Bright White (118)**
 Brushed Grey (123)*
 Brushed Sand (122)*
 Classic Oak (143)**
 Fog (128)* **
 Folkstone Grey (114)**
 Graphite Pear (144)**
 Grey Ash (142)**
 Jet Black (111)* **
 Light Ash (139)**
 Medium Cherry (124)**
 Medium Grey (115)**
 Micro Grey (121)*
 Micro Sand (129)*
 Natural Cherry (126)**
 Natural Maple (125)**
 Pumice (119)**
 Silverwood (147)* **
 Smokewood (148)* **
 Soft Grey (117)**
 Walnut (127)**
 Warm Ash (140)**
 Whitened Ash (141)**
 Zebra (145)

Laminate Finish Applications:

Worksurfaces
 Overhead and overdesk doors
 Credenza top and door
 Laminate tile inserts
 Freestanding desk worksurfaces
 Table tops

2mm Edgeband Finishes:

Barnwood (149)
 Bright White (118)
 Classic Oak (143)
 Fog (128)
 Folkstone Grey (114)
 Graphite Pear (144)
 Grey Ash (142)
 Jet Black (111)
 Light Ash (139)
 Medium Cherry (124)
 Medium Grey (115)
 Natural Cherry (126)
 Natural Maple (125)
 Pumice (119)
 Silverwood (147)
 Smokewood (148)
 Soft Grey (117)
 Walnut (127)
 Warm Ash (140)
 Whitened Ash (141)
 Zebra (145)

2mm Edgeband Finish Applications:

Worksurfaces
 Freestanding desk worksurfaces
 Table tops

Cascade Worksurface Finishes:

Bright White (118)
 Folkstone Grey (114)
 Medium Cherry (124)
 Natural Cherry (126)
 Natural Maple (125)
 Pumice (119)
 Soft Grey (117)
 Walnut (127)

Cascade Worksurface**Finish Applications:**

Cascade edge worksurface

Techwood Finishes:

Black Oak (641)
 Blond Maple (638)
 Cherry (509)
 Dark Mahogany (628)
 Espresso (514)

Light Cherry (639)
 Maple (506)
 Medium Teak (513)
 Medium Walnut (512)
 Natural (637)
 Light Walnut (644)
 Dove Grey (645)

Techwood Finish Applications:

Worksurfaces
 Overhead and overdesk doors
 Credenza top and door
 Panel trim
 Veneer tile inserts
 Table tops

Note: All Dividends Horizon products except DS2 pedestals and doublewide pedestals are painted with a textured finish excluding 613 Silver, which is available as a smooth finish only. X and Y base tables and the freestanding screen kits are always painted with a textured finish, including 613 Silver.

Note: Laminates and other finishes may vary in color due to different dye lots. Slight variations are to be expected.

Note: Worksurfaces, overhead and overdesk doors, credenza tops and doors, and veneer tile inserts will have the same Techwood finish on the surface and the edge.

**Finish not available on laminate panel inserts*

*** Melamine worksurface finish.*

Worksurfaces manufactured in Melamine are available in High Pressure Laminate at a 10% upcharge. Other products are also available in High Pressure Laminate and would need to be quoted separately.

Order Code	Color Name	Old Order Code	Paint Grade	Paint Finishes	Laminate Finishes	2mm Edgeband Finishes	Cascade Worksurface Finishes	Techwood Finishes	Plastic Trim Finishes
Paints and Laminates									
149	Barnwood				•	•			
611T*	Beige Mist Metallic		P2	•					
120T	Black Brown		P1	•					
118T*	Bright White	LH	P1	•	•	•	•		
112T*	Brown		P1	•					
123	Brushed Grey				•				
122	Brushed Sand				•				
143	Classic Oak				•	•			
113T*	Dark Grey	Y3	P1	•		•			•
128	Fog	G			•	•			
114T*	Folkstone Grey		P1	•	•	•	•		
144	Graphite Pear				•	•			
142	Grey Ash				•	•			
111T*	Jet Black	27	P1	•	•	•			
139	Light Ash				•	•			
124	Medium Cherry				•	•	•		
115	Medium Grey				•	•			
115T*	Medium Grey	Y2	P1	•					•
612T*	Medium Metallic Grey	J	P2	•					
121	Micro Grey				•				
129	Micro Sand				•				
126	Natural Cherry				•	•	•		
125	Natural Maple				•	•	•		
119	Pumice	LB, F			•	•	•		
116T*	Sandstone		P1	•					
613	Silver	3	P3	•					
147	Silverwood				•	•			
148	Smokewood				•	•			
117T*	Soft Grey	E, M42	P1	•	•	•	•		•
127	Walnut				•	•	•		
140	Warm Ash				•	•			
141	Whitened Ash				•	•			
145	Zebra				•	•			

* T suffix is for paint finish only

Most products introduced after 2004 are not available in Legacy finishes. See individual pricing pages for availability.

Specify Legacy finishes to match existing product only. Legacy finishes are not available for new customers.

Trim Finishes

Panel top caps
Panel post trim
Pedestal drawer top caps
Overhead drawer top caps
Pedestal drawer pulls

Y1 Pewter

Paint Finishes

Panel base raceway covers
Panel tiled insert supports
Solid Steel panel inserts
Perforated steel panel inserts
Embossed steel panel inserts
Overhead storage components
Pedestals
Desk components
Metal panel topcaps and trim

P1 Finishes

Y1 Pewter

P2 Finishes

H Beige Metallic
W Light Tan Metallic

All other Knoll paint finishes and custom finishes (Series 2 components only)

Laminates

Worksurfaces

An upcharge applies where specifying Legacy laminates. Add an amount equal to 10% of the solid PVC edgeband list price to the price of any product specified with a Legacy laminate.

MC Caramel Maple
CM Clear Maple
M1 Light Grey
PA Pearwood
SD Sand
B Snow
WM Warm Cherry
MR6 Winter Grey Matrix

Note: Laminates and other finishes may vary in color due to different dye lots. Slight variations are to be expected.

Worksurface Edges

2mm edgeband

MC Caramel Maple
Y3 Dark Grey
Y2 Medium Grey
MT Metal
Y1 Pewter
SD Sand
B Snow
WM Warm Cherry

Order Code	Color Name	Old Order Code	Paint Grade	Paint Finishes	Laminate Finishes	2mm Edgeband Finishes	Cascade Worksurface Finishes	Techwood Finishes	Plastic Trim Finishes	DS1 Storage Plastic Finishes
Techwoods										
641	Black Oak							•		
638	Blond Maple (formerly known as maple techgrain)							•		
509	Cherry							•		
628	Dark Mahogany							•		
514	Espresso							•		
639	Light Cherry (formerly known as cherry techgrain)							•		
506	Maple							•		
513	Medium Teak							•		
512	Medium Walnut							•		
637	Natural							•		
644	Light Walnut							•		
645	Dove Grey							•		

Gloss Level		Fill Level
A	Low Gloss	Closed Pore
B	Medium Gloss	Closed Pore
C	High Gloss	Closed Pore
D	Low Gloss	Open Pore
E	Medium Gloss	Open Pore
F	High Gloss	Open Pore

Edge Options for Veneers	
WOOD	Complimentary Wood
SYN	Complimentary Synthetic
WPLY	Wood Ply Edge*
SPLY	Synthetic Ply Edge*

For more detailed information on Veneer finishes, please refer to the Wood Finish Matrix on the Knoll.com

Fabric Options**Grade 10**

Annex (W1360)*
 Beacon (W14975)
 Broadcloth II (W1619)
 Circuit (W17545)
 Element (W1077)
 Growth Spurt (W692)
 Messa (W2061)
 Skylark (W17187)
 Symbolic Details (W693)
 Tailor Made II (1610)
 Twister (W1923)
 Versatility (W432)

Grade 20

Circle Line (W1146)
 Criss Cross (W305)
 Delite (K2026)
 Edo (W211)
 Mainframe (W17835)
 Photon (W1293)
 Reflect (W884)

Grade 30

Commuter Cloth (K1779)
 Micro (W465)
 Relay (W1020)
 Synth (K1693)

Grade 40

Amplify (W1215)
 Bandwidth (W1219)
 Crossroad (K2085)
 Hourglass (K1523)
 Palladium (W1030)
 Spellbound (W1464)

Grade 50

Presto (K1000)

Grade 55

Transition (W816)

COM (Customer's Own Material)

COM can be applied to Dividends Horizon product on a select basis. Please consult your Knoll Customer Service Representative for details on the COM approval process and testing requirements.

Pricing for COM fabrics is at Grade 10.

Note: Always contact your Customer Service Representative prior to sending any COM (including pre-approved KnollTextiles) to the manufacturing facility.

Note: All fabric components greater than 60" wide (54" for "K" fabrics) may need to have the fabric railroaded (turned 90°). If any larger panels are railroaded, the smaller panels will also be railroaded to match. This must be considered when utilizing a patterned textile.

*Annex is not available in colorway Salt (W136011) on Dividends Horizon fabric inserts

Dividends Horizon Panels

Dividends Horizon is a furniture system comprised of a wide variety of panels, hanging components, storage, screens and freestanding desks.

At the heart of the system is a universal panel frame. The universal frame is an open design that accepts many styles of panel inserts. These include:

- Monolithic Fabric Insert
- Monolithic Laminate Insert
- Tiled Fabric Insert
- Tiled Laminate Insert
- Technology Tile
- Painted Steel
- Perforated Steel
- Embossed Steel
- Window Kits
- Markerboard

Panel Dimensions

- Widths: 15", 18", 24", 30", 36", 42", 48" and 60"
- Heights: worksurface height, 36", 42", 50", 57", 64" and 78"
- Thickness: 3"


Panel Frame Options

Dividends Horizon offers two panel frame options, which are selected depending on customer's aesthetic and functional needs. Both frames are available in preconfigured and build-to-spec panels.


Topway panel frames feature an integral top cable trough, and are used with D1 style stack frames.

Full View frames have no top trough, leaving a larger window opening in the top position. Full View frames are used with D2 style stack frames.


Dividends Horizon Panels and Components (Base Raceway shown)



Monolithic Panel



Beltway Panel



Tiled Panel

Panel Frame Construction

Panel frames are robotically welded and consist of vertical channels, horizontal rails and panel feet with leveling glides.

- Topway trough: 22-gauge roll-formed steel (topway frames only)
- Vertical channels: 16-gauge roll-formed steel with 5/8" integral slotted standard with adjustments in 1-1/2" increments
- Horizontal rails: 15-gauge roll-formed steel
- Panel feet: extruded aluminum
- Leveling glides: Steel threads with 2-1/4" height adjustment and 1-1/2" diameter nylon foot

Preconfigured Panels

Dividends Horizon panels can be specified "Preconfigured" in various styles including:

- Monolithic Panel
- Tiled Panel
- Beltway Panel

Monolithic Panel Components

Monolithic panels provide a single fabric or laminate insert per panel side.

Preconfigured Dividends Horizon panels are shipped complete with panel frame, base components, top cap, panel to panel connection hardware and one full height panel insert per side.

Tiled Panel Components

Individual tiled panels allow for a "segmented" aesthetic. Individual tile supports create separation within the panel frame.

"Preconfigured" Dividends Horizon panels ship complete with panel frame, base components, top cap, panel to panel connection hardware, tile supports and tiles.

Beltway Panel Components

Beltway panels allow for electrical and/or data to be accessed above worksurface height. Beltway electrical/data can be specified on one or both sides of a panel. "Preconfigured" Dividends Horizon beltway panels ship complete with panel frame, base components, top cap, panel to panel connection hardware, beltway panel inserts, beltway covers and beltway insert supports.

Base Options


- Base Raceway
- Open Base
- Tile to the Floor

Note: Standard base, Open base and Tile to the floor components can be retrofitted in either a topway or full view frame.


Stack Frames

Dividends Horizon stack frames increase the overall height of a standard panel.

The stack frame is available in three panel heights, 14", 21" and 28". Dividends Horizon stack panels may be attached to standard 36", 42", 50", 57", 64" and 78" high panel. Maximum stacking height above a base panel height is 28".



Topway Frame Construction



Panel Foot Construction

Open Position Planner

Dividends Horizon now offers an industry leading technology called Open Position Planner, allowing customers and dealers to design, specify and order factory-assembled Dividends Horizon panels in virtually any configuration.

This powerful specification tool eliminates the need for most built-to-spec panels. Since panels arrive at the job site assembled, installation labor is also reduced.

The functionality of Open Position Planner is available only to electronic specification users, and is not available in this price list.

"Build-to-Spec" Panels

"Build-to-Spec" panels are specified by component for special applications. These include: when a different fabric is required on each panel side and when retrofitting existing panels to another style. Panels and components are not shipped assembled.

Modular Panel Connections

Modular panel connections are made from two parts: Universal Panel Connection Hardware and Panel Top Connectors.

Panel connection hardware includes:

- lower connectors: 14 gauge steel cactus style connectors
- Upper frame connector: Die cast wedge block with 7 " torx head screw.

Panel Top Connectors, depending upon application, are either 11 gauge stamped steel or 1/4" HSLA steel.

Panel to Panel Specification Tip:

- When connecting same height DP8 Full View to DP8 Full View, select the 'V' Top Connector option
- When connecting same height DP8 Top Way to DP8 Top Way, select the 'C' Top Connector option
- All other applications require the 'U' Universal Top Connector option

Panel Attachment

The lower cactus style connectors engage the lower frames of adjacent panels. The upper wedge block engages the upper frames. The connection is secured by tightening the upper connector's tension screw.

Panel-to-Panel Top Cap Transition

Top cap transitions fill the gap between panel top cap sections in straight panel-to-panel configurations.



- **Construction:** Trim-color black when used with veneer top caps
- **Size:** 1" wide by 3" deep
- **Attachment:** Snaps between top cap sections in straight, same-height panel configurations

Note: Panel-to-panel top cap transitions are ordered separately from panels.


Top Cap

Top cap is included with preconfigured panels.

- **Construction:** Panel top caps are trim colored and are either radius or flat metal. Veneer top caps are techgrain veneer over radius or flat metal substrate.



Panel Connection Hardware



Panel Attachment

- **Attachment:** Snaps onto the trough of a topway panel frame. Retainer clips are used to attach the top cap to the top rail of a full view frame.

Panel End Trim

Panel end trim matches the aesthetics of the panel top cap. It is used to end a panel run and for high-low, panel-to-panel applications.

Three panel end trim options are available:

- Radius Metal
- Flat Metal
- Thin Profile Flat

Note: Panel end trim is ordered separately from panels. Included with the panel end trim are panel end trim brackets.

- **Construction:** End trims are trim colored with a die cast aluminum end cap.

Panel top caps and end trim are either extruded aluminum or roll formed steel.


Metal trim is extruded aluminum with powder coat finish. All metal trim have a powder coat finish.

- **Attachment:** Panel-mount brackets are fastened to the panel with thread-forming screws into pre-punched holes. End trim snaps onto panel mount brackets.

The panel end top cap snaps over the panel end trim and panel top trim.

Panel to Panel Specification Tip:

- When connecting DP8 Full View to DP8 Full View, select the 'V' Top Connector option
- When connecting DP8 Top Way to DP8 Top Way, select the 'C' Top Connector option
- All other applications require the 'U' Universal Top Connector option



Panel End Trim Attachment

Post Connectors

Post connectors are required for all "L", "T", and "X" configurations. For same-height applications, post connectors are available as an assembly and include the post, vertical trim and top cap.

For high-low panel-to-post applications, post connectors are specified by component.

Post and Post Component Construction

- Post: 3" square extruded aluminum
- Metal Post Cover: 18 gauge steel with powder coat finish
- Post Top Cap: Powder coated metal in Knoll core colors

Attachment: Post connectors use the universal panel connection hardware from adjacent panels

Electrical and data access: Posts have cut-outs that match the wire and cable access channels provided by panel frames. This allows wire conduits and data cables to be routed through the post at the topway, beltway and base raceway.

Electrical and Communications

Dividends Horizon provides a logical approach for planning and installing electrical systems and communication cables.

Power is installed along the base raceway with access available in both the base raceway and optional beltway.


Topway Panel Frame Electrical

Allows data cables to be routed horizontally and vertically within the panel.


- Interior dimension: 2 1/2"H x 3/4"W

Cables can be routed along the tops of panels, routed through the interior of panels and along both the beltway and base raceway. The primary channel for distributing cable is provided in the horizontal topway along the top of panels. The topway allows cables to be easily laid-in during initial installation and additional cables to be added as required. It also separates data from power to reduce the chance of interference. A vertical wire pathway is provided in the center of the topway. This allows cables to be run vertically through the interior of the panel to the beltway or base raceway without the use of exterior cable managers.


Data Cabling Bend Radius




Beltway Electrical




"L" Post Connection



"L" Post Cover Attachment



Base Raceway Electrical



Beltway Electrical

Provides duplex receptacle and data port access at desk-height level.

- Exterior dimension: 4 1/4"H x 3"D
- Interior dimension: 3 1/2"H x 2 3/4"D
- Height from floor: 32 3/4" to center of beltway cover
- Beltway cover construction: Trim-color painted steel
- Beltway cover attachment: Snaps onto beltway panel insert supports
- Duplex access: 30" and wider beltway covers have two duplex knockouts per panel side (18" and 24" wide beltways do not have duplex knockouts)
- Duplex location: Knockouts located 12" on center from each end of cover
- Data access: All beltway covers (except 30 wide) have one center-located data port knockout per panel side
- Additional data access: In panels 30" and wider, the two duplex knockouts can be used as additional data ports when the beltway is not used for duplex receptacles.
- Power capacity: One power module per panel (single or double-sided).

Panel Base Options

Dividends Horizon panels are available with three base options:

- Base Raceway
- Open Base
- Tile-to-Floor.

Overall panel heights, tile configurations and application rules are the same for all three base options.

Base Raceway

Provides duplex receptacle and data port access at base height. Base Raceway panels feature two roll formed steel raceway covers, which are available with or without electrical/data knockouts.


- Exterior dimension: 5"H x 2 15/16"D
- Interior dimension: 5"H x 2 7/8"D
- Dataport Knockout dimension: 1 3/8"H x 2 5/8"D
- Construction: Paint-colored 22-gauge roll-form steel cover
- Duplex access: 24" and wider base raceway covers have two duplex knockouts per panel side (18"W panels do not have duplex knockouts)

- Duplex location: 9" on center from each end
- Data access: All base raceway covers have one center-located data port knockout
- Additional data access: In panels 24" and wider, the outer knockouts can be used as additional data ports when the raceway is not used for duplex receptacles
- Power capacity: One power module or jumper


Note: Knockouts are standard unless specified without.

Open Base panels feature two extruded aluminum feet positioned at the end of each panel. A horizontal trim is located below the bottom tile.

Tile-To-Floor panels eliminate the raceway cover and access on one side, replaced by a fabric or steel tile extended to the floor. A heavy gauge steel internal raceway cover protects the raceway contents and the tile from deflecting when hit by shoes or vacuum cleaners. The other side of the panel features a raceway cover, available with or without electrical/data knockouts. If needed, use one-sided electrical and one-sided base cable trays with this base option.



- Openings in frame sides permit data and communications cables to be run between frames at up to five levels in a 78" frame.
- Cables can enter/exit through frame sides at junctions between panels or up through the base of the panel.

**Cable Management Capacities**

This chart shows the number of category 6 4-pair cables that can be routed through various Dividends Horizon pathways. Cable capacities are based on 0.280, 0.300, and 0.310 diameter cables at a full fill capacity.

Pathway Description	Cable Pathway Area (Square Inches)	Cable Dia. 0.28"	Cable Dia. 0.30"	Cable Dia. 0.31"
Panel Top Way (thru post)	1.90	24	21	19
Panel Top Way	4.8	61	53	49
Panel Base Raceway (without electrical)	8.4	107	93	87
Panel Base Raceway (with electrical)	3.5	44	38	36
Beltway (w/o electrical)	3.9	50	43	40
Beltway (with electrical)	3.5	45	38	36
Vertical Drop (within panel)	2.1	26	23	21
5" Vertical Hole	3.9	50	43	40
2" Vertical Hole	1.6	20	17	16

Panel Planning Guidelines

The following panel planning guidelines are provided to ensure stability of Dividends Horizon panels.


Three different scenarios are shown:

- Panel run supported by panels on one end
- Panel run supported by panels on both ends
- High density storage



Panel Run Supported by Panels at One End

- Minimum of an "L" panel connection on one end
- Maximum number of panels in run: 4
- End of panel run must be supported by a pedestal, panel-mounted Open Leg Support, C-leg Support or any height panel



Formula for Depth of Return





Panel Run Supported by Panels at One End





End of Run Supported by Pedestal



End of Run Supported by Panel Mount C-Leg Support



End of Run Supported by Open Leg Support



End of Run Supported by Panel of Any Height

Panel Run Supported by Panels at Both Ends

- Minimum of an "L" panel connection on both ends (see Formulas 2 and 3 below)
- Maximum length panel run: 12'
- Maximum number of panels in run: 4





- Both ends of panel run must be supported by matching height panels (see Formulas 2 and 3 below)
- Panel run must be floor supported every 8' with a pedestal, panel mounted Open Support Leg or C-Leg support

High Density Storage



If hanging more than one overhead component vertically per panel side the following is required:

- Panel must be supported by matching height return panels on both ends of the panel

Panel Run Supported by Panels at Both Ends




High Density Storage




Formulas for Depth Return


Formula 1



Formula 2



Formula 3



Return panel must be a minimum of 36" wide when laminate tiles are used along the spine panel run.

Monolithic Panel

Monolithic panels provide a single fabric insert per panel side.

Preconfigured Dividends Horizon panels are shipped complete with topway or full view panel frame, base components, top cap, panel to panel connection hardware and one full height fabric panel insert per side.

Panels may also be ordered by components for "Build-to-Spec" applications. This includes when different fabric insert is required on each side of the panel.

Monolithic Panel Insert Construction

Fabric laminated with web adhesive heat-cured to 7/16" thick tackable acoustical board.

Monolithic Panel Ratings

- Noise Reduction Coefficient (NRC) rating: .70
- Sound Transmission Class (STC) rating: 11

Dividends Horizon panels meet the flame spread and smoke generation criteria established in UL1286 safety standard for office furnishings.

Monolithic Panel Insert Attachment

Fabric panel inserts flex to attach to the troughs in the upper and lower horizontal frame supports. Mounting spring clips are attached to inserts for connection to the vertical frame for additional support. No tools are required for the insert attachment.

Top Cap Options

Two top cap options are available:

- Radius Metal
- Flat Metal

Top Cap Construction

Radius metal and flat metal top caps are made from extruded aluminum.

Top Cap Attachment

Snaps onto the trough of a topway panel frame. Retainer clips are included to attach top caps to a full view frame.

If additional support for monolithic panel inserts is required, a beltway cable tray can be installed.

Three Base Options Available:

- Base Raceway
- Tile to the Floor
- Open Base

Base Raceway covers are available with or without knockouts.

NOTE: 72", 84" and 96" wide panels are only available with railroaded fabric (fabric runs horizontal vs. vertical). This is important to note with any fabric selection that is directional or has a pattern.

If you mix the 72" or longer panels with shorter fabric panels they will not match. Smaller railroaded fabric inserts are available if ordered separately.

NOTE: 72" or longer panels ship knock down (only). Two frames attached together create the longer length. One insert covers both panels.

See the preconfigured tiled panel pages for more information on base options.

Carpet Grippers

Carpet grippers should be specified to increase rigidity of unsupported panel runs. The carpet grippers snap onto leveling glides to prevent panel runs from shifting on carpet. The glides rotate in carpet grippers to permit leveling. Carpet grippers have a black finish.

Universal Panel Connectors

Dividends Horizon panels include universal panel connectors to allow same-height straight panel-to-panel connections, high-low straight panel-to-panel connections and straight and high-low panel-to-post connections.


Modular Panel Connections

Modular panel connections are made from two parts: Universal Panel Connection Hardware and Panel Top Connectors.


Electrical

Panels 24" and wider will accept two duplex receptacles per panel base side. 18" wide panels will provide pass-through electrical only. All electrical components are ordered separately and must be field-installed.

Preconfigured Monolithic Panel



Panel Base Options



Monolithic Panels

Standard Base Raceway

Worksurface Height and 36" High

Dividends Horizon

Panels, Pre-Configured

description	h	w	d	pattern no.	grade 10	20	30	40
 Worksurface Height Monolithic Standard Base Raceway	28 1/2"	15"	3"	DP8CMMRRWH15	\$496.	\$534.	\$557.	\$572.
	28 1/2"	18"	3"	DP8CMMRRWH18	496.	534.	557.	572.
	28 1/2"	24"	3"	DP8CMMRRWH24	550.	592.	614.	634.
	28 1/2"	30"	3"	DP8CMMRRWH30	575.	619.	644.	664.
	28 1/2"	36"	3"	DP8CMMRRWH36	644.	694.	724.	748.
	28 1/2"	42"	3"	DP8CMMRRWH42	712.	768.	798.	826.
	28 1/2"	48"	3"	DP8CMMRRWH48	751.	806.	842.	873.
	28 1/2"	60"	3"	DP8CMMRRWH60	894.	960.	1,005.	1,040.
	28 1/2"	72"	3"	DP8CMMRRWH72RR*	1,107.	1,189.	1,245.	1,288.
	28 1/2"	84"	3"	DP8CMMRRWH84RR*	1,152.	1,236.	1,295.	1,340.
	28 1/2"	96"	3"	DP8CMMRRWH96RR*	1,198.	1,286.	1,347.	1,393.
 36" High, Monolithic Standard Base Raceway	35 1/8"	15"	3"	DP8CMMRR3615	496.	534.	557.	572.
	35 1/8"	18"	3"	DP8CMMRR3618	496.	534.	557.	572.
	35 1/8"	24"	3"	DP8CMMRR3624	550.	592.	614.	634.
	35 1/8"	30"	3"	DP8CMMRR3630	575.	619.	644.	664.
	35 1/8"	36"	3"	DP8CMMRR3636	644.	694.	724.	748.
	35 1/8"	42"	3"	DP8CMMRR3642	712.	768.	798.	826.
	35 1/8"	48"	3"	DP8CMMRR3648	751.	806.	842.	873.
	35 1/8"	60"	3"	DP8CMMRR3660	894.	960.	1,005.	1,040.
	35 1/8"	72"	3"	DP8CMMRR3672RR*	1,016.	1,091.	1,142.	1,182.
	35 1/8"	84"	3"	DP8CMMRR3684RR*	1,163.	1,248.	1,308.	1,330.
	35 1/8"	96"	3"	DP8CMMRR3696RR*	1,210.	1,298.	1,360.	1,382.

Dimensions listed under h w d are actual to the nearest 1/16"

* RR = Pattern only available with railroaded fabric

Ordering Information	Order Code	Included with:	Options
Monolithic Panel with Standard Base Raceway: 1. Pattern number 2. Top cap type 3. Top cap finish 4. Raceway knockout option 5. Raceway trim finish 6. Panel fabric	Monolithic Panel Standard Base Raceway <i>Example:</i> DP8CMMRR3618 4/117/K/117/B191 DP8 Dividends Horizon Panel C Topway frame MM Monolithic both sides RR Base Raceway 4 Radius Metal top cap 117 Soft Grey top cap finish K Base raceway with knockouts both sides 117 Soft Grey base raceway finish B191 Fairfield fabric	Monolithic Panel with Standard Base Raceway: • Panel frame • Acoustic panel inserts (2) • Base raceway covers • Top cap • Connection hardware Note: Preconfigured Worksurface Height panels are not available with plastic top caps. Note: Panel to panel connector specified separately: DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others. Note: Frames larger than 72" wide ship knock down with two panels to achieve the 72" width.	Monolithic Panel with Standard Base Raceway Options: Full View Frame Option: To specify full view frame for window or stacking applications, replace the "C" in pattern number with "V", No upcharge. Top Cap Options: No Top Cap - Deduct \$40; Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4 Raceway Options: (K) = Knockouts both side (N) = No Knockouts

Monolithic Panels

Standard Base Raceway

42" and 50" High

Dividends Horizon

description	h	w	d	pattern no.	grade 10	20	30	40
42" High, Monolithic Standard Base Raceway 	42 ^{3/16} "	15"	3"	DP8CMMRR4215	\$516.	\$557.	\$578.	\$600.
	42 ^{3/16} "	18"	3"	DP8CMMRR4218	516.	557.	578.	600.
	42 ^{3/16} "	24"	3"	DP8CMMRR4224	557.	599.	623.	640.
	42 ^{3/16} "	30"	3"	DP8CMMRR4230	605.	652.	682.	703.
	42 ^{3/16} "	36"	3"	DP8CMMRR4236	658.	708.	742.	764.
	42 ^{3/16} "	42"	3"	DP8CMMRR4242	724.	778.	811.	840.
	42 ^{3/16} "	48"	3"	DP8CMMRR4248	766.	822.	858.	886.
	42 ^{3/16} "	60"	3"	DP8CMMRR4260	910.	978.	1,023.	1,056.
	42 ^{3/16} "	72"	3"	DP8CMMRR4272RR*	1,127.	1,211.	1,268.	1,308.
	42 ^{3/16} "	84"	3"	DP8CMMRR4284RR*	1,173.	1,260.	1,318.	1,360.
	42 ^{3/16} "	96"	3"	DP8CMMRR4296RR*	1,220.	1,310.	1,371.	1,415.
50" High, Monolithic Standard Base Raceway 	49 ^{1/2} "	15"	3"	DP8CMMRR5015	550.	592.	614.	634.
	49 ^{1/2} "	18"	3"	DP8CMMRR5018	550.	592.	614.	634.
	49 ^{1/2} "	24"	3"	DP8CMMRR5024	594.	635.	661.	684.
	49 ^{1/2} "	30"	3"	DP8CMMRR5030	651.	698.	731.	753.
	49 ^{1/2} "	36"	3"	DP8CMMRR5036	712.	768.	798.	826.
	49 ^{1/2} "	42"	3"	DP8CMMRR5042	780.	840.	878.	904.
	49 ^{1/2} "	48"	3"	DP8CMMRR5048	841.	903.	942.	972.
	49 ^{1/2} "	60"	3"	DP8CMMRR5060	999.	1,075.	1,122.	1,162.
	49 ^{1/2} "	72"	3"	DP8CMMRR5072RR*	1,238.	1,333.	1,391.	1,439.
	49 ^{1/2} "	84"	3"	DP8CMMRR5084RR*	1,288.	1,386.	1,446.	1,497.
	49 ^{1/2} "	96"	3"	DP8CMMRR5096RR*	1,340.	1,442.	1,504.	1,557.

Dimensions listed under h w d are actual to the nearest 1/16"

* RR = Pattern only available with railroaded fabric

Ordering Information	Order Code	Included with:	Options
Monolithic Panel with Standard Base Raceway: 1. Pattern number 2. Top cap type 3. Top cap finish 4. Raceway knockout option 5. Raceway trim finish 6. Panel fabric	Monolithic Panel Standard Base Raceway <i>Example:</i> DP8CMMRR3618 4/117/K/117/B191 DP8 Dividends Horizon Panel C Topway frame MM Monolithic both sides RR Base Raceway 4 Radius Metal top cap 117 Soft Grey top cap finish K Base raceway with knockouts both sides 117 Soft Grey base raceway finish B191 Fairfield fabric	Monolithic Panel with Standard Base Raceway: - Panel frame - Acoustic panel inserts (2) - Base raceway covers - Top cap - Connection hardware Note: Preconfigured Worksurface Height panels are not available with plastic top caps. Note: Panel to panel connector specified separately: DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others. Note: Frames larger than 72" wide ship knock down with two panels to achieve the 72" width.	Monolithic Panel with Standard Base Raceway Options: Full View Frame Option: To specify full view frame for window or stacking applications, replace the "C" in pattern number with "V", No upcharge. Top Cap Options: No Top Cap - Deduct \$40; Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4 Raceway Options: (K) = Knockouts both side (N) = No Knockouts


Monolithic Panels

Standard Base Raceway

57", 64" and 78" High

Dividends Horizon

Panels, Pre-Configured

description	h	w	d	pattern no.	grade 10	20	30	40
57" High, Monolithic Standard Base Raceway 	56 ¹³ / ₁₆ "	15"	3"	DP8CMMRR5715	\$592.	\$632.	\$660.	\$682.
	56 ¹³ / ₁₆ "	18"	3"	DP8CMMRR5718	592.	632.	660.	682.
	56 ¹³ / ₁₆ "	24"	3"	DP8CMMRR5724	634.	682.	710.	735.
	56 ¹³ / ₁₆ "	30"	3"	DP8CMMRR5730	701.	752.	786.	811.
	56 ¹³ / ₁₆ "	36"	3"	DP8CMMRR5736	764.	820.	857.	885.
	56 ¹³ / ₁₆ "	42"	3"	DP8CMMRR5742	828.	890.	929.	959.
	56 ¹³ / ₁₆ "	48"	3"	DP8CMMRR5748	888.	957.	998.	1,031.
	56 ¹³ / ₁₆ "	60"	3"	DP8CMMRR5760	1,000.	1,078.	1,125.	1,164.
64" High, Monolithic Standard Base Raceway 	64 ¹ / ₁₆ "	15"	3"	DP8CMMRR6415	628.	676.	703.	729.
	64 ¹ / ₁₆ "	18"	3"	DP8CMMRR6418	628.	676.	703.	729.
	64 ¹ / ₁₆ "	24"	3"	DP8CMMRR6424	676.	726.	754.	783.
	64 ¹ / ₁₆ "	30"	3"	DP8CMMRR6430	749.	805.	840.	870.
	64 ¹ / ₁₆ "	36"	3"	DP8CMMRR6436	813.	876.	913.	942.
	64 ¹ / ₁₆ "	42"	3"	DP8CMMRR6442	874.	937.	978.	1,013.
	64 ¹ / ₁₆ "	48"	3"	DP8CMMRR6448	935.	1,007.	1,051.	1,086.
	64 ¹ / ₁₆ "	60"	3"	DP8CMMRR6460	1,116.	1,204.	1,256.	1,297.
78" High, Monolithic Standard Base Raceway 	78 ⁹ / ₁₆ "	15"	3"	DP8CMMRR7815	879.	944.	992.	1,019.
	78 ⁹ / ₁₆ "	18"	3"	DP8CMMRR7818	879.	944.	992.	1,019.
	78 ⁹ / ₁₆ "	24"	3"	DP8CMMRR7824	964.	1,043.	1,086.	1,123.
	78 ⁹ / ₁₆ "	30"	3"	DP8CMMRR7830	1,045.	1,123.	1,175.	1,213.
	78 ⁹ / ₁₆ "	36"	3"	DP8CMMRR7836	1,136.	1,223.	1,280.	1,324.
	78 ⁹ / ₁₆ "	42"	3"	DP8CMMRR7842	1,228.	1,329.	1,383.	1,432.
	78 ⁹ / ₁₆ "	48"	3"	DP8CMMRR7848	1,310.	1,414.	1,475.	1,525.

Dimensions listed under h w d are actual to the nearest 1/16"





Ordering Information	Order Code	Included with:	Options
Monolithic Panel with Standard Base Raceway: 1. Pattern number 2. Top cap type 3. Top cap finish 4. Raceway knockout option 5. Raceway trim finish 6. Panel fabric	Monolithic Panel Standard Base Raceway <i>Example:</i> DP8CMMRR3618 4/117/K/117/B191 DP8 Dividends Horizon Panel C Topway frame MM Monolithic both sides RR Base Raceway 4 Radius Metal top cap 117 Soft Grey top cap finish K Base raceway with knockouts both sides 117 Soft Grey base raceway finish B191 Fairfield fabric	Monolithic Panel with Standard Base Raceway: • Panel frame • Acoustic panel inserts (2) • Base raceway covers • Top cap • Connection hardware Note: Panel to panel connector specified separately: DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others	Monolithic Panel with Standard Base Raceway Options: Full View Frame Option: To specify full view frame for window or stacking applications, replace the "C" in pattern number with "V", No upcharge. Top Cap Options: No Top Cap - Deduct \$40; Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4 Raceway Options: (K) = Knockouts both side (N) = No Knockouts

Monolithic Panels

Dividends Horizon

Open Base

Worksurface Height, 36", 42" and 50" High

description	h	w	d	pattern no.	grade 10	20	30	40
Worksurface Height, Monolithic Open Base 	28 1/2"	18"	3"	DP8CMMLLWH18	\$496.	\$534.	\$557.	\$572.
	28 1/2"	24"	3"	DP8CMMLLWH24	550.	592.	614.	634.
	28 1/2"	30"	3"	DP8CMMLLWH30	575.	619.	644.	664.
	28 1/2"	36"	3"	DP8CMMLLWH36	644.	694.	724.	748.
	28 1/2"	42"	3"	DP8CMMLLWH42	712.	768.	798.	826.
	28 1/2"	48"	3"	DP8CMMLLWH48	751.	806.	842.	873.
	28 1/2"	60"	3"	DP8CMMLLWH60	894.	960.	1,005.	1,040.
36" High, Monolithic Open Base 	35 1/8"	18"	3"	DP8CMMLL3618	496.	534.	557.	572.
	35 1/8"	24"	3"	DP8CMMLL3624	550.	592.	614.	634.
	35 1/8"	30"	3"	DP8CMMLL3630	575.	619.	644.	664.
	35 1/8"	36"	3"	DP8CMMLL3636	644.	694.	724.	748.
	35 1/8"	42"	3"	DP8CMMLL3642	712.	768.	798.	826.
	35 1/8"	48"	3"	DP8CMMLL3648	751.	806.	842.	873.
	35 1/8"	60"	3"	DP8CMMLL3660	894.	960.	1,005.	1,040.
42" High, Monolithic Open Base 	42 3/16"	18"	3"	DP8CMMLL4218	516.	557.	578.	600.
	42 3/16"	24"	3"	DP8CMMLL4224	557.	599.	623.	640.
	42 3/16"	30"	3"	DP8CMMLL4230	605.	652.	682.	703.
	42 3/16"	36"	3"	DP8CMMLL4236	658.	708.	742.	764.
	42 3/16"	42"	3"	DP8CMMLL4242	724.	778.	811.	840.
	42 3/16"	48"	3"	DP8CMMLL4248	766.	822.	858.	886.
	42 3/16"	60"	3"	DP8CMMLL4260	910.	978.	1,023.	1,056.
50" High, Monolithic Open Base 	49 1/2"	18"	3"	DP8CMMLL5018	550.	592.	614.	634.
	49 1/2"	24"	3"	DP8CMMLL5024	594.	635.	661.	684.
	49 1/2"	30"	3"	DP8CMMLL5030	651.	698.	731.	753.
	49 1/2"	36"	3"	DP8CMMLL5036	712.	768.	798.	826.
	49 1/2"	42"	3"	DP8CMMLL5042	780.	840.	878.	904.
	49 1/2"	48"	3"	DP8CMMLL5048	841.	903.	942.	972.
	49 1/2"	60"	3"	DP8CMMLL5060	999.	1,075.	1,122.	1,162.

Dimensions listed under h w d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Monolithic Panel with Open Base: 1. Pattern Number 2. Top cap type 3. Top cap finish 4. Base finish 5. Panel fabric	Monolithic Panel with Open Base <i>Example:</i> DP8CMMLL 3618 4/117/117/B191 DP8 Dividends Horizon Panel C Topway frame MM Monolithic both sides LL Open base 4 Radius Metal top cap 117 Soft Grey top cap finish 117 Soft Grey raceway finish B191 Fairfield light fabric	Monolithic Panel with Open Base: - Panel frame - Acoustic panel inserts (2) - Open base - Top cap - Connection hardware Note: Preconfigured Worksurface Height panels are not available with plastic top caps. Note: Panel to panel connector specified separately: DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others.	Monolithic Panel with Open Base: Full View Frame Option: To specify full view frame for window or stacking applications, replace the "C" in pattern number with "V". No upcharge. Top Cap Options: No Top Cap - Deduct \$40; Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4



Monolithic Panels

Open Base

57", 64" and 78" High

Dividends Horizon

Panels, Pre-Configured

description	h	w	d	pattern no.	grade 10	20	30	40
57" High, Monolithic Open Base 	56 ¹³ / ₁₆ "	18"	3"	DP8CMMLL5718	\$592.	\$632.	\$660.	\$682.
	56 ¹³ / ₁₆ "	24"	3"	DP8CMMLL5724	634.	682.	710.	735.
	56 ¹³ / ₁₆ "	30"	3"	DP8CMMLL5730	701.	752.	786.	811.
	56 ¹³ / ₁₆ "	36"	3"	DP8CMMLL5736	764.	820.	857.	885.
	56 ¹³ / ₁₆ "	42"	3"	DP8CMMLL5742	828.	890.	929.	959.
	56 ¹³ / ₁₆ "	48"	3"	DP8CMMLL5748	888.	957.	998.	1,031.
	56 ¹³ / ₁₆ "	60"	3"	DP8CMMLL5760	1,000.	1,078.	1,125.	1,164.
64" High, Monolithic Open Base 	64 ¹ / ₁₆ "	18"	3"	DP8CMMLL6418	628.	676.	703.	729.
	64 ¹ / ₁₆ "	24"	3"	DP8CMMLL6424	676.	726.	754.	783.
	64 ¹ / ₁₆ "	30"	3"	DP8CMMLL6430	749.	805.	840.	870.
	64 ¹ / ₁₆ "	36"	3"	DP8CMMLL6436	813.	876.	913.	942.
	64 ¹ / ₁₆ "	42"	3"	DP8CMMLL6442	874.	937.	978.	1,013.
	64 ¹ / ₁₆ "	48"	3"	DP8CMMLL6448	935.	1,007.	1,051.	1,086.
	64 ¹ / ₁₆ "	60"	3"	DP8CMMLL6460	1,116.	1,204.	1,256.	1,297.
78" High, Monolithic Open Base 	78 ³ / ₁₆ "	18"	3"	DP8CMMLL7818	879.	944.	992.	1,019.
	78 ³ / ₁₆ "	24"	3"	DP8CMMLL7824	964.	1,043.	1,086.	1,123.
	78 ³ / ₁₆ "	30"	3"	DP8CMMLL7830	1,045.	1,123.	1,175.	1,213.
	78 ³ / ₁₆ "	36"	3"	DP8CMMLL7836	1,136.	1,223.	1,280.	1,324.
	78 ³ / ₁₆ "	42"	3"	DP8CMMLL7842	1,228.	1,329.	1,383.	1,432.
	78 ³ / ₁₆ "	48"	3"	DP8CMMLL7848	1,310.	1,414.	1,475.	1,525.

Dimensions listed under h w d are actual to the nearest ¹/₁₆"




Ordering Information	Order Code	Included with:	Options
Monolithic Panel with Open Base:	Monolithic Panel with Open Base	Monolithic Panel with Open Base:	Monolithic Panel with Open Base:
1. Pattern Number	<i>Example:</i> DP8CMMLL3618	- Panel frame - Acoustic panel inserts (2) - Open base - Top cap - Connection hardware	Full View Frame Option:
2. Top cap type	4/117/117/B191		To specify full view frame for window or stacking applications, replace the "C" in pattern number with "V". No upcharge.
3. Top cap finish	DP8 Dividends Horizon Panel		
4. Base finish	C Topway frame	Note: Panel to panel connector specified separately; DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others	Top Cap Options:
5. Panel fabric	MM Monolithic both sides		No Top Cap - Deduct \$40;
	LL Open Base		Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4
	4 Radius Metal top cap		
	117 Soft Grey top cap finish		
	117 Soft Grey base raceway finish		
	B191 Fairfield light fabric		

Monolithic Panels

Tile to Floor One Side

Worksurface Height, 36" and 42" High

Dividends Horizon

description	h	w	d	pattern no.	grade 10	20	30	40
Worksurface Height, Monolithic Tile to Floor 	28 1/2"	15"	3"	DP8CMMFRWH15	\$531.	\$569.	\$592.	\$607.
	28 1/2"	18"	3"	DP8CMMFRWH18	531.	569.	592.	607.
	28 1/2"	24"	3"	DP8CMMFRWH24	585.	627.	649.	669.
	28 1/2"	30"	3"	DP8CMMFRWH30	610.	654.	679.	699.
	28 1/2"	36"	3"	DP8CMMFRWH36	679.	729.	759.	783.
	28 1/2"	42"	3"	DP8CMMFRWH42	747.	803.	833.	861.
	28 1/2"	48"	3"	DP8CMMFRWH48	786.	841.	877.	908.
	28 1/2"	60"	3"	DP8CMMFRWH60	929.	995.	1,040.	1,075.
36" High, Monolithic Tile to Floor 	35 1/8"	15"	3"	DP8CMMFR3615	531.	569.	592.	607.
	35 1/8"	18"	3"	DP8CMMFR3618	531.	569.	592.	607.
	35 1/8"	24"	3"	DP8CMMFR3624	585.	627.	649.	669.
	35 1/8"	30"	3"	DP8CMMFR3630	610.	654.	679.	699.
	35 1/8"	36"	3"	DP8CMMFR3636	679.	729.	759.	783.
	35 1/8"	42"	3"	DP8CMMFR3642	747.	803.	833.	861.
	35 1/8"	48"	3"	DP8CMMFR3648	786.	841.	877.	908.
	35 1/8"	60"	3"	DP8CMMFR3660	929.	995.	1,040.	1,075.
42" High, Monolithic Tile to Floor 	42 3/16"	15"	3"	DP8CMMFR4215	551.	592.	613.	635.
	42 3/16"	18"	3"	DP8CMMFR4218	551.	592.	613.	635.
	42 3/16"	24"	3"	DP8CMMFR4224	592.	634.	658.	675.
	42 3/16"	30"	3"	DP8CMMFR4230	640.	687.	717.	738.
	42 3/16"	36"	3"	DP8CMMFR4236	693.	743.	777.	799.
	42 3/16"	42"	3"	DP8CMMFR4242	759.	813.	846.	875.
	42 3/16"	48"	3"	DP8CMMFR4248	801.	857.	893.	921.
	42 3/16"	60"	3"	DP8CMMFR4260	945.	1,013.	1,058.	1,091.

Dimensions listed under h w d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Monolithic Panel with Tile to Floor: 1. Pattern Number 2. Top cap type 3. Top cap finish 4. Raceway knockout option 5. Base raceway finish 6. Panel fabric	Monolithic Panel with Tile to Floor <i>Example:</i> DP8CMMFR 3618 4/117/K/117/B191 DP8 Dividends Horizon Panel C Topway frame MM Monolithic both sides FR Tile to Floor 4 Radius Metal top cap 117 Soft Grey top cap finish K Base raceway with knockouts one side 117 Soft Grey base raceway finish B191 Fairfield light fabric	Monolithic Panel with Tile to Floor: - Panel frame - Acoustic panel inserts (2) - Top cap - Connection hardware - Base raceway on one side Note: Preconfigured Worksurface Height panels are not available with plastic top caps. Note: Panel to panel connector specified separately: DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others.	Monolithic Panel with Tile to Floor: Full View Frame Option: To specify full view frame for window or stacking applications, replace the "C" in pattern number with "V". No upcharge. Tile to Floor Side Option: Tile to Floor standard on side 2. To specify tile to floor on side 1, change "FR" in pattern number to "RF". Top Cap Options: No Top Cap - Deduct \$40; Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4 Raceway Knockout Options: (K) = Knockouts on raceway side (N) = No Knockouts




Monolithic Panels

Tile to Floor One Side

50", 57" and 64" High

Dividends Horizon

Panels, Pre-Configured

description	h	w	d	pattern no.	grade 10	20	30	40
50" High, Monolithic Tile to Floor 	49 1/2"	15"	3"	DP8CMMFR5015	\$585.	\$627.	\$649.	\$669.
	49 1/2"	18"	3"	DP8CMMFR5018	585.	627.	649.	669.
	49 1/2"	24"	3"	DP8CMMFR5024	629.	670.	696.	719.
	49 1/2"	30"	3"	DP8CMMFR5030	686.	733.	766.	788.
	49 1/2"	36"	3"	DP8CMMFR5036	747.	803.	833.	861.
	49 1/2"	42"	3"	DP8CMMFR5042	815.	875.	913.	939.
	49 1/2"	48"	3"	DP8CMMFR5048	876.	938.	977.	1,007.
	49 1/2"	60"	3"	DP8CMMFR5060	1,034.	1,110.	1,157.	1,197.
57" High, Monolithic Tile to Floor 	56 13/16"	15"	3"	DP8CMMFR5715	627.	667.	695.	717.
	56 13/16"	18"	3"	DP8CMMFR5718	627.	667.	695.	717.
	56 13/16"	24"	3"	DP8CMMFR5724	669.	717.	745.	770.
	56 13/16"	30"	3"	DP8CMMFR5730	736.	787.	821.	846.
	56 13/16"	36"	3"	DP8CMMFR5736	799.	855.	892.	920.
	56 13/16"	42"	3"	DP8CMMFR5742	863.	925.	964.	994.
	56 13/16"	48"	3"	DP8CMMFR5748	923.	992.	1,033.	1,066.
	56 13/16"	60"	3"	DP8CMMFR5760	1,035.	1,113.	1,160.	1,199.
64" High, Monolithic Tile to Floor 	64 1/16"	15"	3"	DP8CMMFR6415	663.	711.	738.	764.
	64 1/16"	18"	3"	DP8CMMFR6418	663.	711.	738.	764.
	64 1/16"	24"	3"	DP8CMMFR6424	711.	761.	789.	818.
	64 1/16"	30"	3"	DP8CMMFR6430	784.	840.	875.	905.
	64 1/16"	36"	3"	DP8CMMFR6436	848.	911.	948.	977.
	64 1/16"	42"	3"	DP8CMMFR6442	909.	972.	1,013.	1,048.
	64 1/16"	48"	3"	DP8CMMFR6448	970.	1,042.	1,086.	1,121.
	64 1/16"	60"	3"	DP8CMMFR6460	1,151.	1,239.	1,291.	1,332.

Dimensions listed under h w d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Monolithic Panel with Tile to Floor: 1. Pattern Number 2. Top cap type 3. Top cap finish 4. Raceway knockout option 5. Base raceway finish 6. Panel fabric	Monolithic Panel with Tile to Floor <i>Example:</i> DP8CMMFR 3618 4/117/K/117/B191 DP8 Dividends Horizon Panel C Topway frame MM Monolithic both sides FR Tile to Floor 4 Radius Metal top cap 117 Soft Grey top cap finish K Base raceway with knockouts one side 117 Soft Grey raceway finish B191 Fairfield light fabric	Monolithic Panel with Tile to Floor: - Panel frame - Acoustic panel inserts (2) - Top cap - Connection hardware - Base raceway on one side Note: Panel to panel connector specified separately: DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others	Monolithic Panel with Tile to Floor: Full View Frame Option: To specify full view frame for window or stacking applications, replace the "C" in pattern number with "V". No upcharge. Tile to Floor Side Option: Tile to Floor standard on side 2. To specify tile to floor on side 1, change "FR" in pattern number to "RF". Top Cap Options: No Top Cap - Deduct \$40; Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4 Raceway Knockout Options: (K) = Knockouts on raceway side (N) = No Knockouts

Monolithic Panels

Tile to Floor One Side

78" High

Dividends Horizon

description	h	w	d	pattern no.	grade 10	20	30	40
78" High, Monolithic Tile to Floor	78 ⁹ / ₁₆ "	15"	3"	DP8CMMFR7815	\$914.	\$979.	\$1,027.	\$1,054.
	78 ⁹ / ₁₆ "	18"	3"	DP8CMMFR7818	914.	979.	1,027.	1,054.
	78 ⁹ / ₁₆ "	24"	3"	DP8CMMFR7824	999.	1,078.	1,121.	1,158.
	78 ⁹ / ₁₆ "	30"	3"	DP8CMMFR7830	1,080.	1,158.	1,210.	1,248.
	78 ⁹ / ₁₆ "	36"	3"	DP8CMMFR7836	1,171.	1,258.	1,315.	1,359.
	78 ⁹ / ₁₆ "	42"	3"	DP8CMMFR7842	1,263.	1,364.	1,418.	1,467.
	78 ⁹ / ₁₆ "	48"	3"	DP8CMMFR7848	1,345.	1,449.	1,510.	1,560.



Dimensions listed under h w d are actual to the nearest ¹/₁₆"

Ordering Information	Order Code	Included with:	Options
Monolithic Panel with Tile to Floor: 1. Pattern Number 2. Top cap type 3. Top cap finish 4. Raceway knockout option 5. Base raceway finish 6. Panel fabric	Monolithic Panel with Tile to Floor <i>Example:</i> DP8CMMFR 3618 4/117/K/117/B191 DP8 Dividends Horizon Panel C Topway frame MM Monolithic both sides FR Tile to Floor 4 Radius Metal top cap 117 Soft Grey top cap finish K Base raceway with knockouts one side 117 Soft Grey raceway finish B191 Fairfield light fabric	Monolithic Panel with Tile to Floor: • Panel frame • Acoustic panel inserts (2) • Top cap • Connection hardware • Base raceway on one side Note: Panel to panel connector specified separately: DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others	Monolithic Panel with Tile to Floor: Full View Frame Option: To specify full view frame for window or stacking applications, replace the "C" in pattern number with "V". No upcharge. Tile to Floor Side Option: Tile to Floor standard on side 2. To specify tile to floor on side 1, change "FR" in pattern number to "RF". Top Cap Options: No Top Cap - Deduct \$40; Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4 Raceway Knockout Options: (K) = Knockouts on raceway side (N) = No Knockouts

This page intentionally left blank

Tiled Panel Components

"Preconfigured" Dividends Horizon tiled panels ship completely assembled with a topway or full view panel frame, choice of standard base options including a standard raceway, open base, and tile to the floor. Also, included with every tiled panel are the panel-to-panel connection hardware, top cap, tile inserts and supports.

Tiled Panel Insert Construction

Fabric laminated with roll coat adhesive, heat-cured to $\frac{7}{16}$ " thick tackable acoustical board.

One-Sided Tiled Panel

Tiled panels are available with fabric tiled inserts attached to one or both panel sides. Non-tiled panel side will have a monolithic insert.

Tiled Panel Insert Supports

All Dividends Horizon panel frames are prepunched to accept tiled panel insert supports which span horizontally across the panel frame. Tiled panel insert supports are mounted above a tiled insert with the exception of the uppermost tile. D2 style recessed insert supports are available in black only.

Tiled Panel Insert Attachment

Tiled panel inserts attach to the troughs in the horizontal panel frame and tiled insert supports. Mounting clips are attached to inserts for connection to frame for additional support. No tools are required for attachment.

Top Cap Options

Two Top Cap Options Available:

- Radius Metal
- Flat Metal


Top Cap Construction

Radius metal and flat metal top caps are made from extruded aluminum.

Top Cap Attachment

Snap onto the trough of a topway panel frame. Retainer clips are included to attach top caps to full view frames.

Preconfigured Tiled Panel



Tiled Panel Standard Configurations

Tiled panels include the following inserts and insert supports per panel side:

36" High • Two 14"H tiles • One tile supports		42" High • One 7"H tile and two 14"H tiles • Two tile supports	
50" High • Three 14"H tiles • Two tile supports		57" High • One 7"H tile and three 14"H tiles • Three tile supports	
64" High • Four 14"H tiles • Three tile supports		78" High • Five 14"H tiles • Four tile supports	

Panel Base Options

Dividends Horizon panels are available with three base options:

- Base Raceway
- Open Base
- Tile-to-Floor

Overall panel heights, tile configurations and application rules are the same for all three base options.

Base Raceway panels feature two roll formed steel raceway covers, which are available with or without electrical/data knockouts.

Open Base panels feature two extruded aluminum feet with triangular profile, positioned at the end of each panel. Open base panels offer a lighter aesthetic and improved ventilation over raceway panels.

Tile-To-Floor panels eliminate the raceway cover and access on one side, replaced by a fabric tile extended to the floor. A heavy gauge steel internal raceway cover protects the raceway contents and the tile from deflecting when hit by shoes or vacuum cleaners. The other side of the panel features a raceway cover, available with or without electrical/data knockouts. If electrical access is required, one-sided electrical and one-sided base cable trays must be used.

Open Position Planner

Dividends Horizon now offers an industry leading technology called Open Position Planner, allowing customers and dealers to design, specify and order factory-assembled Dividends Horizon panel frames in virtually any configuration.

This powerful specification tool eliminates the need for built-to-spec panels. Since panels arrive at the job site assembled, installation labor is also reduced.

The functionality of Open Position Planner is available only to Electronic Specification users, and is not available in this price list.


Panels may be ordered by component throughout the "Built-to-Spec" option, allowing personalized combinations of the tile types and colors.

Note: Standard configurations of "Preconfigured" tiled panels are also available with 28" base tiles with a standard base raceway, open base or tile to the floor options.


Note: Overheads can only be attached to the upper most position of tiled panels. On 78" high panels the overhead may be positioned on the 4th or 5th tile location from the bottom, but not both locations of a single panel.

Note: Insert dimensions are nominal


Panel Base Options



Base Raceway



Tile-to-Floor
(single-sided only)



Open Base

Tiled Panels

Base Raceway

36", 42" and 50" High

Dividends Horizon

description	h	w	d	pattern no.	grade 10	20	30	40	Deduct for Monolithic One Side
 36" High Tiled Standard Base Raceway	35 1/8"	15"	3"	DP8CTRR3615	\$774.	\$834.	\$870.	\$898.	\$88.
	35 1/8"	18"	3"	DP8CTRR3618	774.	834.	870.	898.	88.
	35 1/8"	24"	3"	DP8CTRR3624	820.	883.	920.	954.	89.
	35 1/8"	30"	3"	DP8CTRR3630	868.	930.	970.	1,006.	90.
	35 1/8"	36"	3"	DP8CTRR3636	944.	1,014.	1,060.	1,097.	92.
	35 1/8"	42"	3"	DP8CTRR3642	1,011.	1,086.	1,135.	1,175.	91.
	35 1/8"	48"	3"	DP8CTRR3648	1,056.	1,137.	1,186.	1,227.	93.
	35 1/8"	60"	3"	DP8CTRR3660	1,260.	1,356.	1,416.	1,464.	95.
 42" High Tiled Standard Base Raceway	42 3/16"	15"	3"	DP8CTRR4215	792.	853.	891.	920.	88.
	42 3/16"	18"	3"	DP8CTRR4218	792.	853.	891.	920.	88.
	42 3/16"	24"	3"	DP8CTRR4224	840.	902.	941.	971.	89.
	42 3/16"	30"	3"	DP8CTRR4230	898.	964.	1,007.	1,044.	90.
	42 3/16"	36"	3"	DP8CTRR4236	958.	1,031.	1,075.	1,115.	92.
	42 3/16"	42"	3"	DP8CTRR4242	1,022.	1,098.	1,145.	1,182.	91.
	42 3/16"	48"	3"	DP8CTRR4248	1,073.	1,156.	1,208.	1,247.	93.
	42 3/16"	60"	3"	DP8CTRR4260	1,281.	1,380.	1,441.	1,488.	95.
 50" High Tiled Standard Base Raceway	49 1/2"	15"	3"	DP8CTRR5015	845.	909.	948.	983.	87.
	49 1/2"	18"	3"	DP8CTRR5018	845.	909.	948.	983.	87.
	49 1/2"	24"	3"	DP8CTRR5024	908.	981.	1,024.	1,054.	90.
	49 1/2"	30"	3"	DP8CTRR5030	957.	1,030.	1,077.	1,113.	87.
	49 1/2"	36"	3"	DP8CTRR5036	1,016.	1,088.	1,135.	1,176.	81.
	49 1/2"	42"	3"	DP8CTRR5042	1,076.	1,159.	1,210.	1,249.	76.
	49 1/2"	48"	3"	DP8CTRR5048	1,131.	1,216.	1,271.	1,317.	74.
	49 1/2"	60"	3"	DP8CTRR5060	1,307.	1,406.	1,471.	1,520.	95.

Dimensions listed under h w d are actual to the nearest 1/8"

Ordering Information	Order Code	Included with:	Options
Tiled Panel with Standard Base Raceway: - Pattern Number - Top cap type - Top cap finish - Raceway knockout option - Raceway finish - Tile Support profile - Panel fabric	Tiled Panel with Standard Base Raceway <i>Example:</i> DP8CTRR3618 4/117/K/117/2/B191 DP8 Dividends Horizon Panel C Topway frame TT Tiled both sides RR Base raceway 36 Height 18 Width 4 Radius Metal top cap 117 Soft Grey top cap finish K Base raceway with knockouts both sides 117 Soft Grey base raceway finish 2 D2 style tile supports B191 Fairfield light fabric	Tiled Panel with Standard Base Raceway: - Panel frame - Acoustic panel inserts - Base raceway covers - Top cap - Connection hardware Note: Panel to panel connector specified separately: DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others	Tiled Panels with Standard Base Raceway: Full View Frame Option: To specify full view frame for window or stacking applications, replace the "C" in pattern number with "V". No upcharge. Monolithic Side Option: For one side tiled, one side monolithic, change "TT" in pattern number to "MT" and deduct amount in far right column. Top Cap Options: No Top Cap - Deduct \$40; Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4 Raceway Knockout Options: (K) = Knockouts (N) = No knockouts Tile Support Options: (1) = D1 External Reveal (2) = D2 Recessed Reveal

Tiled Panels

Base Raceway

57", 64" and 78" High

Dividends Horizon

Panels, Pre-Configured

description	h	w	d	pattern no.	grade 10	20	30	40	Deduct for Monolithic One Side
 57" High Tiled Standard Base Raceway	56 ^{13/16"}	15"	3"	DP8CTTRR5715	\$1,019.	\$1,093.	\$1,141.	\$1,179.	\$109.
	56 ^{13/16"}	18"	3"	DP8CTTRR5718	1,019.	1,093.	1,141.	1,179.	109.
	56 ^{13/16"}	24"	3"	DP8CTTRR5724	1,088.	1,170.	1,221.	1,264.	113.
	56 ^{13/16"}	30"	3"	DP8CTTRR5730	1,149.	1,240.	1,294.	1,336.	116.
	56 ^{13/16"}	36"	3"	DP8CTTRR5736	1,216.	1,311.	1,372.	1,416.	118.
	56 ^{13/16"}	42"	3"	DP8CTTRR5742	1,289.	1,385.	1,447.	1,500.	121.
	56 ^{13/16"}	48"	3"	DP8CTTRR5748	1,359.	1,463.	1,525.	1,578.	123.
	56 ^{13/16"}	60"	3"	DP8CTTRR5760	1,571.	1,693.	1,769.	1,830.	125.
 64" High Tiled Standard Base Raceway	64 ^{1/16"}	15"	3"	DP8CTTRR6415	1,074.	1,155.	1,208.	1,247.	131.
	64 ^{1/16"}	18"	3"	DP8CTTRR6418	1,074.	1,155.	1,208.	1,247.	131.
	64 ^{1/16"}	24"	3"	DP8CTTRR6424	1,149.	1,240.	1,290.	1,335.	138.
	64 ^{1/16"}	30"	3"	DP8CTTRR6430	1,212.	1,306.	1,368.	1,411.	134.
	64 ^{1/16"}	36"	3"	DP8CTTRR6436	1,284.	1,383.	1,445.	1,496.	135.
	64 ^{1/16"}	42"	3"	DP8CTTRR6442	1,361.	1,466.	1,530.	1,581.	137.
	64 ^{1/16"}	48"	3"	DP8CTTRR6448	1,432.	1,538.	1,609.	1,663.	138.
	64 ^{1/16"}	60"	3"	DP8CTTRR6460	1,656.	1,787.	1,868.	1,929.	138.
 78" High Tiled Standard Base Raceway	78 ^{9/16"}	15"	3"	DP8CTTRR7815	1,611.	1,736.	1,812.	1,877.	235.
	78 ^{9/16"}	18"	3"	DP8CTTRR7818	1,611.	1,736.	1,812.	1,877.	235.
	78 ^{9/16"}	24"	3"	DP8CTTRR7824	1,730.	1,864.	1,949.	2,013.	243.
	78 ^{9/16"}	30"	3"	DP8CTTRR7830	1,830.	1,969.	2,061.	2,132.	237.
	78 ^{9/16"}	36"	3"	DP8CTTRR7836	1,953.	2,105.	2,200.	2,277.	258.
	78 ^{9/16"}	42"	3"	DP8CTTRR7842	2,066.	2,225.	2,331.	2,409.	263.
	78 ^{9/16"}	48"	3"	DP8CTTRR7848	2,186.	2,360.	2,467.	2,553.	315.

Dimensions listed under h w d are actual to the nearest 1/8"




Ordering Information	Order Code	Included with:	Options
Tiled Panel with Standard Base Raceway: - Pattern Number - Top cap type - Top cap finish - Raceway knockout option - Raceway finish - Tile support profile - Tile support finish - Panel fabric	Tiled Panel with Standard Base Raceway <i>Example:</i> DP8CTTRR3618 4/117/K/117/2/B191 DP8 Dividends Horizon Panel C Topway frame TT Tiled both sides RR Base raceway 36 Height 18 Width 4 Radius Metal top cap 117 Soft Grey top cap finish K Base raceway with knockouts both sides 117 Soft Grey base raceway finish 2 D2 style tile supports B191 Fairfield light fabric	Tiled Panel with Standard Base Raceway: - Panel frame - Acoustic panel inserts - Base raceway covers - Top cap - Connection hardware Note: Panel to panel connector specified separately: DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others	Tiled Panels with Standard Base Raceway: Full View Frame Option: To specify full view frame for window or stacking applications, replace the "C" in pattern number with "V". No upcharge. Monolithic Side Option: For one side tiled, one side monolithic, change "TT" in pattern number to "MT" and deduct amount in far right column. Top Cap Options: (3) = No Top Cap (4) = Radius Metal, add \$40 P1, \$42 P2, \$44 P3 paint grades (5) = Flat Metal, add \$40 P1, \$42 P2, \$44 P3 paint grades Raceway Knockout Options: (K) = Knockouts (N) = No knockouts Tile Support Options: (1) = D1 External Reveal (2) = D2 Recessed Reveal

Tiled Panels

Open Base

36", 42" and 50" High

Dividends Horizon

description	h	w	d	pattern no.	10	20	30	40	Deduct for Monolithic One Side
36" High Tiled Open Base 	35 1/8"	18"	3"	DP8CTTLL3618	\$774.	\$834.	\$870.	\$898.	\$88.
	35 1/8"	24"	3"	DP8CTTLL3624	820.	883.	920.	954.	89.
	35 1/8"	30"	3"	DP8CTTLL3630	868.	930.	970.	1,006.	90.
	35 1/8"	36"	3"	DP8CTTLL3636	944.	1,014.	1,060.	1,097.	92.
	35 1/8"	42"	3"	DP8CTTLL3642	1,011.	1,086.	1,135.	1,175.	91.
	35 1/8"	48"	3"	DP8CTTLL3648	1,056.	1,137.	1,186.	1,227.	93.
	35 1/8"	60"	3"	DP8CTTLL3660	1,260.	1,356.	1,416.	1,464.	95.
42" High Tiled Open Base 	42 3/16"	18"	3"	DP8CTTLL4218	792.	853.	891.	920.	88.
	42 3/16"	24"	3"	DP8CTTLL4224	840.	902.	941.	971.	89.
	42 3/16"	30"	3"	DP8CTTLL4230	898.	964.	1,007.	1,044.	90.
	42 3/16"	36"	3"	DP8CTTLL4236	958.	1,031.	1,075.	1,115.	92.
	42 3/16"	42"	3"	DP8CTTLL4242	1,022.	1,098.	1,145.	1,182.	91.
	42 3/16"	48"	3"	DP8CTTLL4248	1,073.	1,156.	1,208.	1,247.	93.
	42 3/16"	60"	3"	DP8CTTLL4260	1,281.	1,380.	1,441.	1,488.	95.
50" High Tiled Open Base 	49 1/2"	18"	3"	DP8CTTLL5018	820.	883.	920.	954.	87.
	49 1/2"	24"	3"	DP8CTTLL5024	882.	952.	994.	1,023.	90.
	49 1/2"	30"	3"	DP8CTTLL5030	929.	1,000.	1,046.	1,081.	87.
	49 1/2"	36"	3"	DP8CTTLL5036	986.	1,056.	1,102.	1,142.	81.
	49 1/2"	42"	3"	DP8CTTLL5042	1,045.	1,125.	1,175.	1,213.	76.
	49 1/2"	48"	3"	DP8CTTLL5048	1,098.	1,181.	1,234.	1,279.	74.
	49 1/2"	60"	3"	DP8CTTLL5060	1,307.	1,406.	1,471.	1,520.	95.

Dimensions listed under h w d are actual to the nearest 1/8"

Ordering Information	Order Code	Included with:	Options
Tiled Panel with Open Base: 1. Pattern Number 2. Top cap type 3. Top Cap finish 4. Base finish 5. Tile support profile 6. Panel fabric	Tiled Panel with Open Base <i>Example:</i> DP8CTTLL3618 4/117/117/2/B191 DP8 Dividends Horizon Panel C Topway frame TT Tiled both sides LL Open base 36 Height 18 Width 4 Radius Metal top cap 117 Soft Grey top cap finish 117 Soft Grey base finish 2 D2 style tile supports B191 Fairfield light fabric	Tiled Panel with Open Base: • Panel frame • Acoustic panel inserts • Open base • Top cap • Connection hardware Note: Panel to panel connector specified separately; DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others	Tiled Panel with Open Base: Full View Frame Option: To specify full view frame for window or stacking applications, replace the "C" in pattern number with "V". No upcharge. Monolithic Side Option: For one side tiled, one side monolithic, change "TT" in pattern number to "MT" and deduct amount in far right column. Top Cap Options: No Top Cap - Deduct \$40; Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4 Tile Support Options: (1) = D1 External Reveal (2) = D2 Recessed Reveal




Tiled Panels

Open Base

57", 64" and 78" High

Dividends Horizon

Panels, Pre-Configured

description	h	w	d	pattern no.	10	20	30	40	deduct for Monolithic One Side
57" High Tiled Open Base 	56 ¹³ / ₁₆ "	18"	3"	DP8CTTLL5718	\$989.	\$1,061.	\$1,108.	\$1,145.	\$109.
	56 ¹³ / ₁₆ "	24"	3"	DP8CTTLL5724	1,056.	1,136.	1,185.	1,227.	113.
	56 ¹³ / ₁₆ "	30"	3"	DP8CTTLL5730	1,116.	1,204.	1,256.	1,297.	116.
	56 ¹³ / ₁₆ "	36"	3"	DP8CTTLL5736	1,181.	1,273.	1,332.	1,375.	118.
	56 ¹³ / ₁₆ "	42"	3"	DP8CTTLL5742	1,251.	1,345.	1,405.	1,456.	121.
	56 ¹³ / ₁₆ "	48"	3"	DP8CTTLL5748	1,319.	1,420.	1,481.	1,532.	123.
	56 ¹³ / ₁₆ "	60"	3"	DP8CTTLL5760	1,571.	1,693.	1,769.	1,830.	125.
64" High Tiled Open Base 	64 ¹ / ₁₆ "	18"	3"	DP8CTTLL6418	1,043.	1,121.	1,173.	1,211.	131.
	64 ¹ / ₁₆ "	24"	3"	DP8CTTLL6424	1,116.	1,204.	1,252.	1,296.	138.
	64 ¹ / ₁₆ "	30"	3"	DP8CTTLL6430	1,177.	1,268.	1,328.	1,370.	134.
	64 ¹ / ₁₆ "	36"	3"	DP8CTTLL6436	1,247.	1,343.	1,403.	1,452.	135.
	64 ¹ / ₁₆ "	42"	3"	DP8CTTLL6442	1,321.	1,423.	1,485.	1,535.	137.
	64 ¹ / ₁₆ "	48"	3"	DP8CTTLL6448	1,390.	1,493.	1,562.	1,615.	138.
	64 ¹ / ₁₆ "	60"	3"	DP8CTTLL6460	1,656.	1,787.	1,868.	1,929.	138.
78" High Tiled Open Base 	78 ⁹ / ₁₆ "	18"	3"	DP8CTTLL7818	1,611.	1,736.	1,812.	1,877.	235.
	78 ⁹ / ₁₆ "	24"	3"	DP8CTTLL7824	1,730.	1,864.	1,949.	2,013.	243.
	78 ⁹ / ₁₆ "	30"	3"	DP8CTTLL7830	1,830.	1,969.	2,061.	2,132.	237.
	78 ⁹ / ₁₆ "	36"	3"	DP8CTTLL7836	1,953.	2,105.	2,200.	2,277.	258.
	78 ⁹ / ₁₆ "	42"	3"	DP8CTTLL7842	2,066.	2,225.	2,331.	2,409.	263.
	78 ⁹ / ₁₆ "	48"	3"	DP8CTTLL7848	2,186.	2,360.	2,467.	2,553.	315.

Dimensions listed under h w d are actual to the nearest 1/8"



Ordering Information	Order Code	Included with:	Options
Tiled Panel with Open Base:	Tiled Panel with Open Base	Tiled Panel with Open Base:	Tiled Panel with Open Base:
1. Pattern Number	<i>Example:</i> DP8CTTLL3618	• Panel frame	Full View Frame Option:
2. Top cap type	4/117/117/2/B191	• Acoustic panel inserts	To specify full view frame for window or stacking applications, replace the "C" in pattern number with "V". No upcharge.
3. Top Cap finish	DP8 Dividends Horizon Panel	• Open base	
4. Base finish	TT Topway frame	• Top cap	
5. Tile support profile	LL Tiled both sides	• Connection hardware	
6. Panel fabric	36 Open base	Note: Panel to panel connector specified separately; DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others	Monolithic Side Option:
	18 Height		For one side tiled, one side monolithic, change "TT" in pattern number to "MT" and deduct amount in far right column.
	4 Width		
	117 Radius Metal top cap		Top Cap Options:
	117 Soft Grey top cap finish		No Top Cap - Deduct \$40;
	2 Soft Grey base finish		Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4
	B191 D2 style tile supports		Tile Support Options:
			(1) = D1 External Reveal
			(2) = D2 Recessed Reveal

Tiled Panels

Tile To Floor One Side

36" and 42" High

Dividends Horizon

description	h	w	d	pattern no.	10	20	30	40	Deduct for Monolithic One Sideide 1
36" High Tiled Panel Tile to Floor One Side 	35 1/8"	15"	3"	DP8CTTFR3615	\$809.	\$869.	\$905.	\$933.	\$88.
	35 1/8"	18"	3"	DP8CTTFR3618	809.	869.	905.	933.	88.
	35 1/8"	24"	3"	DP8CTTFR3624	855.	918.	955.	989.	89.
	35 1/8"	30"	3"	DP8CTTFR3630	903.	965.	1,005.	1,041.	90.
	35 1/8"	36"	3"	DP8CTTFR3636	979.	1,049.	1,095.	1,132.	92.
	35 1/8"	42"	3"	DP8CTTFR3642	1,046.	1,121.	1,170.	1,210.	91.
	35 1/8"	48"	3"	DP8CTTFR3648	1,091.	1,172.	1,221.	1,262.	93.
	35 1/8"	60"	3"	DP8CTTFR3660	1,295.	1,391.	1,451.	1,499.	95.
42" High Tiled Panel Tile to Floor One Side 	42 3/16"	15"	3"	DP8CTTFR4215	827.	888.	926.	955.	88.
	42 3/16"	18"	3"	DP8CTTFR4218	827.	888.	926.	955.	88.
	42 3/16"	24"	3"	DP8CTTFR4224	875.	937.	976.	1,006.	89.
	42 3/16"	30"	3"	DP8CTTFR4230	933.	999.	1,042.	1,079.	90.
	42 3/16"	36"	3"	DP8CTTFR4236	993.	1,066.	1,110.	1,150.	92.
	42 3/16"	42"	3"	DP8CTTFR4242	1,057.	1,133.	1,180.	1,217.	91.
	42 3/16"	48"	3"	DP8CTTFR4248	1,108.	1,191.	1,243.	1,282.	93.
	42 3/16"	60"	3"	DP8CTTFR4260	1,316.	1,415.	1,476.	1,523.	95.

Dimensions listed under h w d are actual to the nearest 1/8"

Ordering Information	Order Code	Included with:	Options
Tiled Panel with Tile to Floor: 1. Pattern Number 2. Top cap type 3. Top cap finish 4. Base raceway finish 5. Tile support profile 6. Panel fabric	Tiled Panel with Tile to Floor <i>Example:</i> DP8CTTFR3618 4/117/K/117/2/B191 DP8 Dividends Horizon Panel C Topway frame TT Tiled both sides FR Tile to floor side one, raceway side two 36 Height 18 Width 4 Radius Metal top cap 117 Soft Grey top cap finish K Knockouts for one-sided base raceway 117 Soft Grey base raceway finish 2 D2 style tile supports B191 Fairfield light fabric	Tiled Panel with Tile to Floor: - Panel frame - Acoustic panel inserts - Top cap - Connection hardware - Base raceway with knockout one side - Tile to the floor one side Note: Panel to panel connector specified separately: DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others	Tiled Panels With Tile To Floor One Side: Full View Frame Option: To specify full view frame for window or stacking applications, replace the "C" in pattern number with "V". No upcharge. Monolithic Side Option: For side 1 monolithic, side 2 tiled, change "TT" in pattern number to "MT" and deduct amount in far right column. Tile to Floor Side Option: Tile to floor standard on side 2. To specify tile to floor on side 1, change "RF" in pattern number to "FR". Top Cap Options: No Top Cap - Deduct \$40; Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4 Raceway Knockout Options: (K) = Knockouts on raceway side (N) = No knockouts on raceway side Tile Support Options: (1) = D1 External Reveal (2) = D2 Recessed Reveal


Tiled Panels


Tile To Floor One Side

50" and 57" High

Dividends Horizon

Panels, Pre-Configured

description	h	w	d	pattern no.	grade 10	20	30	40	deduct for Monolithic One Side
50" High Tiled Panel Tile to Floor One Side 	49 1/2"	15"	3"	DP8CTTFR5015	\$880.	\$944.	\$998.	\$1,018.	\$87.
	49 1/2"	18"	3"	DP8CTTFR5018	880.	944.	998.	1,018.	87.
	49 1/2"	24"	3"	DP8CTTFR5024	943.	1,016.	1,059.	1,089.	90.
	49 1/2"	30"	3"	DP8CTTFR5030	992.	1,065.	1,112.	1,148.	87.
	49 1/2"	36"	3"	DP8CTTFR5036	1,051.	1,123.	1,170.	1,211.	81.
	49 1/2"	42"	3"	DP8CTTFR5042	1,111.	1,194.	1,245.	1,284.	76.
	49 1/2"	48"	3"	DP8CTTFR5048	1,166.	1,251.	1,306.	1,352.	74.
	49 1/2"	60"	3"	DP8CTTFR5060	1,342.	1,441.	1,506.	1,555.	95.

57" High Tiled Panel Tile to Floor One Side 	56 13/16"	15"	3"	DP8CTTFR5715	1,054.	1,128.	1,176.	1,214.	109.
	56 13/16"	18"	3"	DP8CTTFR5718	1,054.	1,128.	1,176.	1,214.	109.
	56 13/16"	24"	3"	DP8CTTFR5724	1,123.	1,205.	1,256.	1,299.	113.
	56 13/16"	30"	3"	DP8CTTFR5730	1,184.	1,275.	1,329.	1,371.	116.
	56 13/16"	36"	3"	DP8CTTFR5736	1,251.	1,346.	1,407.	1,451.	118.
	56 13/16"	42"	3"	DP8CTTFR5742	1,324.	1,420.	1,482.	1,535.	121.
	56 13/16"	48"	3"	DP8CTTFR5748	1,394.	1,498.	1,560.	1,613.	123.
	56 13/16"	60"	3"	DP8CTTFR5760	1,606.	1,728.	1,804.	1,865.	125.

Dimensions listed under h w d are actual to the nearest 1/8"

Ordering Information	Order Code	Included with:	Options																								
Tiled Panel with Tile to Floor: 1. Pattern Number 2. Top cap type 3. Top cap finish 4. Base raceway finish 5. Tile support profile 6. Panel fabric	Tiled Panel with Tile to Floor <i>Example:</i> DP8CTTFR5018 4/117/K/117/2/B191 <table><tr><td>DP8</td><td>Dividends Horizon Panel</td></tr><tr><td>C</td><td>Topway frame</td></tr><tr><td>TT</td><td>Tiled both sides</td></tr><tr><td>FR</td><td>Tile to floor side one, raceway side two</td></tr><tr><td>50</td><td>Height</td></tr><tr><td>18</td><td>Width</td></tr><tr><td>4</td><td>Radius Metal top cap</td></tr><tr><td>117</td><td>Soft Grey top cap finish</td></tr><tr><td>K</td><td>Knockouts for one-sided base raceway</td></tr><tr><td>117</td><td>Soft Grey base raceway finish</td></tr><tr><td>2</td><td>D2 style tile supports</td></tr><tr><td>B191</td><td>Fairfield light fabric</td></tr></table>	DP8	Dividends Horizon Panel	C	Topway frame	TT	Tiled both sides	FR	Tile to floor side one, raceway side two	50	Height	18	Width	4	Radius Metal top cap	117	Soft Grey top cap finish	K	Knockouts for one-sided base raceway	117	Soft Grey base raceway finish	2	D2 style tile supports	B191	Fairfield light fabric	Tiled Panel with Tile to Floor: • Panel frame • Acoustic panel inserts • Top cap • Connection hardware • Base raceway with knockout one side • Tile to the floor one side Note: Panel to panel connector specified separately: DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others	Tiled Panels With Tile To Floor One Side: Full View Frame Option: To specify full view frame for window or stacking applications, replace the “C” in pattern number with “V”. No upcharge. Monolithic Side Options: For side 1 monolithic, side 2 tiled, change “TT” in pattern number to “MT” and deduct amount in far right column. Tile to Floor Side Option: Tile to floor standard on side 1. To specify tile to floor on side 2, change “RF” in pattern number to “FR”. Top Cap Options: No Top Cap - Deduct \$40; Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4 Raceway Knockout Options: (K) = Knockouts on raceway side (N) = No knockouts on raceway side Tile Support Options: (1) = D1 External Reveal (2) = D2 Recessed Reveal
DP8	Dividends Horizon Panel																										
C	Topway frame																										
TT	Tiled both sides																										
FR	Tile to floor side one, raceway side two																										
50	Height																										
18	Width																										
4	Radius Metal top cap																										
117	Soft Grey top cap finish																										
K	Knockouts for one-sided base raceway																										
117	Soft Grey base raceway finish																										
2	D2 style tile supports																										
B191	Fairfield light fabric																										


Tiled Panels

Tile To Floor One Side


64" and 78" High

Dividends Horizon

description	h	w	d	pattern no.	grade 10	20	30	40	deduct for Monolithic One Side
64" High Tiled Panel Tile to Floor One Side	64 1/16"	15"	3"	DP8CTTFR6415	\$1,109.	\$1,190.	\$1,243.	\$1,282.	\$131.
	64 1/16"	18"	3"	DP8CTTFR6418	1,109.	1,190.	1,243.	1,282.	131.
	64 1/16"	24"	3"	DP8CTTFR6424	1,184.	1,275.	1,325.	1,370.	138.
	64 1/16"	30"	3"	DP8CTTFR6430	1,247.	1,341.	1,403.	1,446.	134.
	64 1/16"	36"	3"	DP8CTTFR6436	1,319.	1,418.	1,480.	1,531.	135.
	64 1/16"	42"	3"	DP8CTTFR6442	1,396.	1,501.	1,565.	1,616.	137.
	64 1/16"	48"	3"	DP8CTTFR6448	1,467.	1,573.	1,644.	1,698.	138.
	64 1/16"	60"	3"	DP8CTTFR6460	1,691.	1,822.	1,903.	1,964.	138.



78" High Tiled Panel Tile to Floor One Side	78 9/16"	15"	3"	DP8CTTFR7815	1,646.	1,771.	1,847.	1,912.	235.
	78 9/16"	18"	3"	DP8CTTFR7818	1,646.	1,771.	1,847.	1,912.	235.
	78 9/16"	24"	3"	DP8CTTFR7824	1,765.	1,899.	1,984.	2,048.	243.
	78 9/16"	30"	3"	DP8CTTFR7830	1,865.	2,004.	2,096.	2,167.	237.
	78 9/16"	36"	3"	DP8CTTFR7836	1,988.	2,140.	2,235.	2,312.	258.
	78 9/16"	42"	3"	DP8CTTFR7842	2,101.	2,260.	2,366.	2,444.	263.
	78 9/16"	48"	3"	DP8CTTFR7848	2,221.	2,395.	2,502.	2,588.	315.



Dimensions listed under h w d are actual to the nearest 1/8"

Ordering Information	Order Code	Included with:	Options
Tiled Panel with Tile to Floor: 1. Pattern Number 2. Top cap type 3. Top cap finish 4. Base raceway finish 5. Tile support profile 6. Panel fabric	Tiled Panel with Tile to Floor <i>Example:</i> DP8CTTFR6418 4/117/K/117/2/B191 DP8 Dividends Horizon Panel C Topway frame TT Tiled both sides FR Tile to floor side one, raceway side two 64 Height 18 Width 4 Radius Metal top cap 117 Soft Grey top cap finish K Knockouts for one-sided base raceway 117 Soft Grey base raceway finish 2 D2 style tile supports B191 Fairfield light fabric	Tiled Panel with Tile to Floor: - Panel frame - Acoustic panel inserts - Top cap - Connection hardware - Base raceway with knockout one side - Tile to the floor one side Note: Panel to panel connector specified separately: DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others	Tiled Panels With Tile To Floor One Side: Full View Frame Option: To specify full view frame for window or stacking applications, replace the "C" in pattern number with "V". No upcharge. Monolithic Side Options: For side 1 monolithic, side 2 tiled, change "TT" in pattern number to "MT" and deduct amount in far right column. Tile to Floor Side Option: Tile to floor standard on side 1. To specify tile to floor on side 2, change "FR" in pattern number to "RF". Top Cap Options: No Top Cap - Deduct \$40; Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4 Raceway Knockout Options: (K) = Knockouts on raceway side (N) = No knockouts on raceway side Tile Support Options: (1) = D1 External Reveal (2) = D2 Recessed Reveal

Tiled Panels

28" Lower Tile and Base Raceway

42" and 50" High

Dividends Horizon

Panels, Pre-Configured

description	h	w	d	pattern no.	grade 10	20	30	40	Deduct for Monolithic One Side
42" High Tiled Panel with 28" Lower Tile and Base Raceway	42 3/16"	15"	3"	DP8CPPRR4215	\$722.	\$779.	\$817.	\$848.	\$59.
	42 3/16"	18"	3"	DP8CPPRR4218	722.	779.	817.	848.	59.
	42 3/16"	24"	3"	DP8CPPRR4224	768.	831.	868.	900.	59.
	42 3/16"	30"	3"	DP8CPPRR4230	825.	893.	932.	966.	60.
	42 3/16"	36"	3"	DP8CPPRR4236	885.	958.	1,004.	1,043.	62.
	42 3/16"	42"	3"	DP8CPPRR4242	947.	1,024.	1,072.	1,111.	62.
	42 3/16"	48"	3"	DP8CPPRR4248	1,000.	1,083.	1,135.	1,176.	63.
	42 3/16"	60"	3"	DP8CPPRR4260	1,208.	1,306.	1,367.	1,419.	64.
50" High Tiled Panel with 28" Lower Tile and Base Raceway	49 1/2"	15"	3"	DP8CPPRR5015	747.	807.	848.	881.	58.
	49 1/2"	18"	3"	DP8CPPRR5018	747.	807.	848.	881.	58.
	49 1/2"	24"	3"	DP8CPPRR5024	806.	878.	918.	952.	60.
	49 1/2"	30"	3"	DP8CPPRR5030	855.	927.	970.	1,008.	58.
	49 1/2"	36"	3"	DP8CPPRR5036	910.	986.	1,028.	1,068.	54.
	49 1/2"	42"	3"	DP8CPPRR5042	967.	1,051.	1,100.	1,140.	50.
	49 1/2"	48"	3"	DP8CPPRR5048	1,024.	1,110.	1,165.	1,206.	49.
	49 1/2"	60"	3"	DP8CPPRR5060	1,232.	1,335.	1,397.	1,449.	64.

Dimensions listed under h w d are actual to the nearest 1/8"

Ordering Information	Order Code	Included with:	Options
Tiled Panel with 28" Lower Tile and Base Raceway: - Pattern Number - Top cap type - Top cap finish - Raceway knockout option - Raceway trim finish - Tile support profile - Panel fabric	Tiled Panels with 28" Lower Tile and Base Raceway <i>Example:</i> DP8CPPRR4218 4/117/K/117/2/B191 DP8 Dividends Horizon Panel C Topway frame PP Tiled both sides, 28" Lower Tile RR Raceway both sides 42 Height 18 Width 4 Radius Metal top cap 117 Soft Grey top cap finish K Base raceway with knockouts both sides 117 Soft Grey base raceway finish 2 D2 style tile supports B191 Fairfield light fabric	Tiled Panel with Standard Base Raceway and 28" Base Tile: - Panel frame - Acoustic panel inserts - Base raceway covers - Top cap - Connection hardware Note: Panel to panel connector specified separately: DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others	Tiled Panel with 28" Lower Tile and Base Raceway: Full View Frame Option: To specify full view frame for window or stacking applications, replace the "C" in pattern number with "V". No upcharge. Monolithic Side Option: For side 1 monolithic, side 2 tiled, change "PP" in pattern number to "MP" and deduct amount in far right column. Top Cap Options: No Top Cap - Deduct \$40; Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4 Raceway Knockout Options: (K) = Knockouts on raceway side (N) = No knockouts Tile Support Options: (1) = D1 External Reveal (2) = D2 Recessed Reveal


Tiled Panels

28" Lower Tile and Base Raceway


57" and 64" High

Dividends Horizon

description	h	w	d	pattern no.	grade 10	20	30	40	Deduct for Monolithic One Side
57" High Tiled Panel with 28" Lower Tile and Base Raceway	56 13/16"	15"	3"	DP8CPPRR5715	\$912.	\$990.	\$1,035.	\$1,072.	\$73.
	56 13/16"	18"	3"	DP8CPPRR5718	912.	990.	1,035.	1,072.	73.
	56 13/16"	24"	3"	DP8CPPRR5724	986.	1,062.	1,115.	1,154.	76.
	56 13/16"	30"	3"	DP8CPPRR5730	1,044.	1,129.	1,179.	1,223.	78.
	56 13/16"	36"	3"	DP8CPPRR5736	1,110.	1,200.	1,260.	1,300.	79.
	56 13/16"	42"	3"	DP8CPPRR5742	1,177.	1,273.	1,334.	1,382.	81.
	56 13/16"	48"	3"	DP8CPPRR5748	1,241.	1,344.	1,406.	1,459.	82.
	56 13/16"	60"	3"	DP8CPPRR5760	1,499.	1,616.	1,696.	1,757.	85.



64" High Tiled Panel with 28" Lower Tile and Base Raceway	64 1/16"	15"	3"	DP8CPPRR6415	965.	1,048.	1,098.	1,137.	89.
	64 1/16"	18"	3"	DP8CPPRR6418	965.	1,048.	1,098.	1,137.	89.
	64 1/16"	24"	3"	DP8CPPRR6424	1,044.	1,129.	1,178.	1,222.	93.
	64 1/16"	30"	3"	DP8CPPRR6430	1,103.	1,190.	1,256.	1,297.	90.
	64 1/16"	36"	3"	DP8CPPRR6436	1,176.	1,271.	1,332.	1,380.	91.
	64 1/16"	42"	3"	DP8CPPRR6442	1,244.	1,349.	1,415.	1,461.	92.
	64 1/16"	48"	3"	DP8CPPRR6448	1,319.	1,423.	1,487.	1,546.	93.
	64 1/16"	60"	3"	DP8CPPRR6460	1,586.	1,713.	1,793.	1,857.	93.



Dimensions listed under h w d are actual to the nearest 1/8"

Ordering Information	Order Code	Included with:	Options
Tiled Panel with 28" Lower Tile and Base Raceway: - Pattern Number - Top cap type - Top cap finish - Raceway knockout option - Raceway trim finish - Tile support style - Panel fabric	Tiled Panels with 28" Lower Tile and Base Raceway <i>Example:</i> DP8CPPRR5718 4/117/K/117/2/B191 DP8 Dividends Horizon Panel C Topway frame PP Tiled both sides, 28" Lower Tile RR Raceway both sides 57 Height 18 Width 4 Radius Metal top cap 117 Soft Grey top cap finish K Base raceway with knockouts both sides 117 Soft Grey base raceway finish 2 D2 style tile support B191 Fairfield light fabric	Tiled Panel with Standard Base Raceway and 28" Base Tile: - Panel frame - Acoustic panel inserts - Base raceway covers - Top cap - Connection hardware Note: Panel to panel connector specified separately: DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others	Tiled Panels with 28" Lower Tile and Base Raceway: Full View Frame Option: To specify full view frame for window or stacking applications, replace the "C" in pattern number with "V". No upcharge. Monolithic Side Option: For side 1 monolithic, side 2 tiled, change "PP" in pattern number to "MP" and deduct amount in far right column. Top Cap Options: No Top Cap - Deduct \$40; Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4 Raceway Knockout Options: (K) = Knockouts on raceway side (N) = No knockouts Tile Support Options: (1) = D1 External Reveal (2) = D2 Recessed Reveal

Tiled Panels


28" Lower Tile and Base Raceway

78" High

Dividends Horizon

Panels, Pre-Configured

description	h	w	d	pattern no.	grade 10	20	30	40	deduct for Monolithic One Side
78" High Tiled Panel with 28" Lower Tile and Base Raceway	78 ⁹ / ₁₆ "	15"	3"	DP8CPPRR7815	\$1,542.	\$1,662.	\$1,738.	\$1,803.	\$158.
	78 ⁹ / ₁₆ "	18"	3"	DP8CPPRR7818	1,542.	1,662.	1,738.	1,803.	158.
	78 ⁹ / ₁₆ "	24"	3"	DP8CPPRR7824	1,655.	1,791.	1,877.	1,940.	163.
	78 ⁹ / ₁₆ "	30"	3"	DP8CPPRR7830	1,757.	1,895.	1,984.	2,060.	160.
	78 ⁹ / ₁₆ "	36"	3"	DP8CPPRR7836	1,881.	2,029.	2,128.	2,201.	173.
	78 ⁹ / ₁₆ "	42"	3"	DP8CPPRR7842	1,993.	2,152.	2,254.	2,338.	176.
	78 ⁹ / ₁₆ "	48"	3"	DP8CPPRR7848	2,115.	2,288.	2,395.	2,479.	211.



Dimensions listed under h w d are actual to the nearest 1/8"

Ordering Information	Order Code	Included with:	Options
Tiled Panel with 28" Lower Tile and Base Raceway: - Pattern Number - Top cap type - Top cap finish - Raceway knockout option - Raceway trim finish - Tile support style - Panel fabric	Tiled Panels with 28" Lower Tile and Base Raceway <i>Example:</i> DP8CPPRR7818 4/117/K/117/2/B191 DP8 Dividends Horizon Panel C Topway frame PP Tiled both sides, 28" Lower Tile RR Raceway both sides 78 Height 18 Width 4 Radius Metal top cap 117 Soft Grey top cap finish K Base raceway with knockouts both sides 117 Soft Grey base raceway finish 2 D2 style tile support B191 Fairfield light fabric	Tiled Panel with Standard Base Raceway and 28" Base Tile: - Panel frame - Acoustic panel inserts - Base raceway covers - Top cap - Connection hardware Note: Panel to panel connector specified separately: DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others	Tiled Panels with 28" Lower Tile and Base Raceway: Full View Frame Option: To specify full view frame for window or stacking applications, replace the "C" in pattern number with "V". No upcharge. Monolithic Side Option: For side 1 monolithic, side 2 tiled, change "PP" in pattern number to "MP" and deduct amount in far right column. Top Cap Options: No Top Cap - Deduct \$40; Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4 Raceway Knockout Options: (K) = Knockouts on raceway side (N) = No knockouts Tile Support Options: (1) = D1 External Reveal (2) = D2 Recessed Reveal

Tiled Panels

28" Lower Tile and Open Base

42" and 50" High

Dividends Horizon

description	h	w	d	pattern no.	grade 10	20	30	40	Deduct for Monolithic One Side
42" High Tiled Panel with 28" Lower Tile and Open Base	42 3/16"	18"	3"	DP8CPPLL4218	\$722.	\$779.	\$817.	\$848.	\$59.
	42 3/16"	24"	3"	DP8CPPLL4224	768.	831.	868.	900.	59.
	42 3/16"	30"	3"	DP8CPPLL4230	825.	893.	932.	966.	60.
	42 3/16"	36"	3"	DP8CPPLL4236	885.	958.	1,004.	1,043.	62.
	42 3/16"	42"	3"	DP8CPPLL4242	947.	1,024.	1,072.	1,111.	62.
	42 3/16"	48"	3"	DP8CPPLL4248	1,000.	1,083.	1,135.	1,176.	63.
	42 3/16"	60"	3"	DP8CPPLL4260	1,208.	1,306.	1,367.	1,419.	64.
50" High Tiled Panel with 28" Lower Tile and Open Base	49 1/2"	18"	3"	DP8CPPLL5018	747.	807.	848.	881.	58.
	49 1/2"	24"	3"	DP8CPPLL5024	806.	878.	918.	952.	60.
	49 1/2"	30"	3"	DP8CPPLL5030	855.	927.	970.	1,008.	58.
	49 1/2"	36"	3"	DP8CPPLL5036	910.	986.	1,028.	1,068.	54.
	49 1/2"	42"	3"	DP8CPPLL5042	967.	1,051.	1,100.	1,140.	50.
	49 1/2"	48"	3"	DP8CPPLL5048	1,024.	1,110.	1,165.	1,206.	49.
	49 1/2"	60"	3"	DP8CPPLL5060	1,232.	1,335.	1,397.	1,449.	64.

Dimensions listed under h w d are actual to the nearest 1/8"


Ordering Information	Order Code	Included with:	Options
Tiled Panels with 28" Lower Tile and Open Base: 1. Pattern Number 2. Top cap type 3. Top cap trim finish 4. Base support trim finish 5. Tile support style 6. Panel fabric	Tiled Panels with 28" Lower Tile and Open Base <i>Example:</i> DP8CPPLL4218 4/117/KK/117/2/B191 DP8 Dividends Horizon Panel C Topway frame PP Tiled both sides, 28" Lower Tile LL Open Base 42 Height 18 Width 4 Radius Metal top cap 117 Soft Grey top cap finish 117 Soft Grey base support finish 2 D2 style tile supports B191 Fairfield light fabric	Tiled Panels with 28" Lower Tile and Open Base: • Panel frame • Acoustic panel inserts • Open base • Top cap • Connection hardware Note: Panel to panel connector specified separately: DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others	Tiled Panels with 28" Lower Tile and Open Base: Full View Frame Option: To specify full view frames for window or stacking applications, replace the "C" in pattern number with "V". No upcharge. Monolithic Side Option: To specify monolithic on side one of panel, change "PP" in pattern number to "MP" and deduct amount in far right column. Top Cap Options: No Top Cap - Deduct \$40; Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4 Base Raceway Knockout Options: (K) = Knockouts on raceway side (N) = No knockouts Tile Support Options: (1) = D1 External Reveal (2) = D2 Recessed Reveal

Tiled Panels


28" Lower Tile and Open Base

57" and 64" High

description	h	w	d	pattern no.	grade 10	20	30	40	deduct for Monolithic One Side
57" High Tiled Panel with 28" Lower Tile and Open Base	56 ¹³ / ₁₆ "	18"	3"	DP8CPPLL5718	\$912.	\$990.	\$1,035.	\$1,072.	\$73.
	56 ¹³ / ₁₆ "	24"	3"	DP8CPPLL5724	986.	1,062.	1,115.	1,154.	76.
	56 ¹³ / ₁₆ "	30"	3"	DP8CPPLL5730	1,044.	1,129.	1,179.	1,223.	78.
	56 ¹³ / ₁₆ "	36"	3"	DP8CPPLL5736	1,110.	1,200.	1,260.	1,300.	79.
	56 ¹³ / ₁₆ "	42"	3"	DP8CPPLL5742	1,177.	1,273.	1,334.	1,382.	81.
	56 ¹³ / ₁₆ "	48"	3"	DP8CPPLL5748	1,241.	1,344.	1,406.	1,459.	82.
	56 ¹³ / ₁₆ "	60"	3"	DP8CPPLL5760	1,499.	1,616.	1,696.	1,757.	85.



64" High Tiled Panel with 28" Lower Tile and Open Base	64 ¹ / ₁₆ "	18"	3"	DP8CPPLL6418	965.	1,048.	1,098.	1,137.	89.
	64 ¹ / ₁₆ "	24"	3"	DP8CPPLL6424	1,044.	1,129.	1,178.	1,222.	93.
	64 ¹ / ₁₆ "	30"	3"	DP8CPPLL6430	1,103.	1,190.	1,256.	1,297.	90.
	64 ¹ / ₁₆ "	36"	3"	DP8CPPLL6436	1,176.	1,271.	1,332.	1,380.	91.
	64 ¹ / ₁₆ "	42"	3"	DP8CPPLL6442	1,244.	1,349.	1,415.	1,461.	92.
	64 ¹ / ₁₆ "	48"	3"	DP8CPPLL6448	1,319.	1,423.	1,487.	1,546.	93.
	64 ¹ / ₁₆ "	60"	3"	DP8CPPLL6460	1,586.	1,713.	1,793.	1,857.	93.



Dimensions listed under h w d are actual to the nearest 1/8"

Ordering Information	Order Code	Included with:	Options
Tiled Panels with 28" Lower Tile and Open Base: 1. Pattern Number 2. Top cap type 3. Top cap trim finish 4. Base support trim finish 5. Tile support style 6. Panel fabric	Tiled Panels with 28" Lower Tile and Open Base <i>Example:</i> DP8CPPLL5718 4/117/KK/117/2/B191 DP8 Dividends Horizon Panel C Topway frame PP Tiled both sides, 28" Lower Tile LL Open Base 57 Height 18 Width 4 Radius Metal top cap 117 Soft Grey top cap finish 117 Soft Grey base support finish 2 D2 style tile support B191 Fairfield light fabric	Tiled Panels with 28" Lower Tile and Open Base: • Panel frame • Acoustic panel inserts • Open base • Top cap • Connection hardware Note: Panel to panel connector specified separately: DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others	Tiled Panels with 28" Lower Tile and Open Base: Full View Frame Option: To specify full view frames for window or stacking applications, replace the "C" in pattern number with "V". No upcharge. Monolithic Side Option: To specify monolithic on side one of panel, change "PP" in pattern number to "MP" and deduct amount in far right column. Top Cap Options: No Top Cap - Deduct \$40; Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4 Base Raceway Knockout Options: (K) = Knockouts on raceway side (N) = No knockouts Tile Support Options: (1) = D1 External Reveal (2) = D2 Recessed Reveal


Tiled Panels

28" Lower Tile and Open Base

78" High

Dividends Horizon

description	h	w	d	pattern no.	grade 10	20	30	40	deduct for Monolithic One Side
78" High Tiled Panel with 28" Lower Tile and Open Base	78 ⁹ / ₁₆ "	18"	3"	DP8CPPLL7818	\$1,542.	\$1,662.	\$1,738.	\$1,803.	\$158.
	78 ⁹ / ₁₆ "	24"	3"	DP8CPPLL7824	1,655.	1,791.	1,877.	1,940.	163.
	78 ⁹ / ₁₆ "	30"	3"	DP8CPPLL7830	1,757.	1,895.	1,984.	2,060.	160.
	78 ⁹ / ₁₆ "	36"	3"	DP8CPPLL7836	1,881.	2,029.	2,128.	2,201.	173.
	78 ⁹ / ₁₆ "	42"	3"	DP8CPPLL7842	1,993.	2,152.	2,254.	2,338.	176.
	78 ⁹ / ₁₆ "	48"	3"	DP8CPPLL7848	2,115.	2,288.	2,395.	2,479.	211.



Dimensions listed under h w d are actual to the nearest 1/8"

Ordering Information	Order Code	Included with:	Options
Tiled Panels with 28" Lower Tile and Open Base: 1. Pattern Number 2. Top cap type 3. Top cap trim finish 4. Base support trim finish 5. Tile support style 6. Panel fabric	Tiled Panels with 28" Lower Tile and Open Base <i>Example:</i> DP8CPPLL7818 4/117/KK/117/2/B191 DP8 Dividends Horizon Panel C Topway frame PP Tiled both sides, 28" Lower Tile LL Open Base 78 Height 18 Width 4 Radius Metal top cap 117 Soft Grey top cap finish 117 Soft Grey base support finish 2 D2 style tile support B191 Fairfield light fabric	Tiled Panels with 28" Lower Tile and Open Base: • Panel frame • Acoustic panel inserts • Open base • Top cap • Connection hardware Note: Panel to panel connector specified separately: DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others	Tiled Panels with 28" Lower Tile and Open Base: Full View Frame Option: To specify full view frames for window or stacking applications, replace the "C" in pattern number with "V". No upcharge. Monolithic Side Option: To specify monolithic on side one of panel, change "PP" in pattern number to "MP" and deduct amount in far right column. Top Cap Options: No Top Cap - Deduct \$40; Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4 Base Raceway Knockout Options: (K) = Knockouts on raceway side (N) = No knockouts Tile Support Options: (1) = D1 External Reveal (2) = D2 Recessed Reveal

Tiled Panels

28" Lower Tile and Tile To Floor

42" and 50" High

Dividends Horizon

Panels, Pre-Configured

description	h	w	d	pattern no.	grade 10	20	30	40	Deduct for 1 side Monolithic
42" High Tiled Panel with 28" Lower Tile and Tile to Floor	42 3/16"	15"	3"	DP8CPPFR4215	\$757.	\$814.	\$852.	\$883.	\$59.
	42 3/16"	18"	3"	DP8CPPFR4218	757.	814.	852.	883.	59.
	42 3/16"	24"	3"	DP8CPPFR4224	803.	866.	903.	935.	59.
	42 3/16"	30"	3"	DP8CPPFR4230	860.	928.	967.	1,001.	60.
	42 3/16"	36"	3"	DP8CPPFR4236	920.	993.	1,039.	1,078.	62.
	42 3/16"	42"	3"	DP8CPPFR4242	982.	1,059.	1,107.	1,146.	62.
	42 3/16"	48"	3"	DP8CPPFR4248	1,035.	1,118.	1,170.	1,211.	63.
	42 3/16"	60"	3"	DP8CPPFR4260	1,243.	1,341.	1,402.	1,454.	64.
50" High Tiled Panel with 28" Lower Tile and Tile to Floor	49 1/2"	15"	3"	DP8CPPFR5015	782.	842.	883.	916.	58.
	49 1/2"	18"	3"	DP8CPPFR5018	782.	842.	883.	916.	58.
	49 1/2"	24"	3"	DP8CPPFR5024	841.	913.	953.	987.	60.
	49 1/2"	30"	3"	DP8CPPFR5030	890.	962.	1,005.	1,043.	58.
	49 1/2"	36"	3"	DP8CPPFR5036	945.	1,021.	1,063.	1,103.	54.
	49 1/2"	42"	3"	DP8CPPFR5042	1,002.	1,086.	1,135.	1,175.	50.
	49 1/2"	48"	3"	DP8CPPFR5048	1,059.	1,145.	1,200.	1,241.	49.
	49 1/2"	60"	3"	DP8CPPFR5060	1,267.	1,370.	1,432.	1,484.	64.

Dimensions listed under h w d are actual to the nearest 1/8"

Ordering Information	Order Code	Included with:	Options																
Tiled Panels with 28" Lower Tile and Tile To Floor: 1. Pattern Number 2. Top cap type 3. Top cap finish 4. Knockout option 5. Base raceway finish 6. Tile support style 7. Panel fabric	Tiled Panels with 28" Lower Tile and Tile To Floor: <i>Example:</i> DP8CPPFF4218 4/117/K/117/2B191 <table><tr><td>DP8CPP</td><td>Pattern number</td></tr><tr><td>FF4218</td><td></td></tr><tr><td>4</td><td>Radius Metal top cap</td></tr><tr><td>117</td><td>Soft Grey top cap finish</td></tr><tr><td>K</td><td>Base raceway with knockouts</td></tr><tr><td>117</td><td>Soft grey base raceway finish</td></tr><tr><td>2</td><td>D2 style tile supports</td></tr><tr><td>B191</td><td>Fairfield light fabric</td></tr></table>	DP8CPP	Pattern number	FF4218		4	Radius Metal top cap	117	Soft Grey top cap finish	K	Base raceway with knockouts	117	Soft grey base raceway finish	2	D2 style tile supports	B191	Fairfield light fabric	Tiled Panels with 28" Lower Tile and Tile To Floor: • Panel frame • Acoustic panel inserts • Top cap • Connection hardware • Tile to floor side 1 • Base raceway with knockout when required side 2 Note: Panel to panel connector specified separately: DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others	Tiled Panels with 28" Lower Tile and Tile To Floor: Full View Frame Option: To specify full view frames for window or stacking applications, replace the "C" in pattern number with "V". No upcharge. Tile to Floor Side Option: Tile to Floor standard on side 1. To specify tile to floor on side 2, change "FR" in pattern number to "RF". Monolithic Side Option: To specify monolithic on side one of panel, change "PP" in pattern number to "MP" and deduct amount in far right column. Top Cap Options: No Top Cap - Deduct \$40; Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4 Raceway Knockout Options: (K) = Knockouts on raceway side (N) = No knockouts Tile Support Options: (1) = D1 External Reveal (2) = D2 Recessed Reveal
DP8CPP	Pattern number																		
FF4218																			
4	Radius Metal top cap																		
117	Soft Grey top cap finish																		
K	Base raceway with knockouts																		
117	Soft grey base raceway finish																		
2	D2 style tile supports																		
B191	Fairfield light fabric																		


Tiled Panels

28" Lower Tile and Tile To Floor


57" and 64" High

Dividends Horizon

description	h	w	d	pattern no.	grade 10	20	30	40	deduct for 1 side Monolithic
57" High Tiled Panel with 28" Lower Tile and Tile to Floor	56 ¹³ / ₁₆ "	15"	3"	DP8CPPFR5715	\$947.	\$1,025.	\$1,070.	\$1,107.	\$73.
	56 ¹³ / ₁₆ "	18"	3"	DP8CPPFR5718	947.	1,025.	1,070.	1,107.	73.
	56 ¹³ / ₁₆ "	24"	3"	DP8CPPFR5724	1,021.	1,097.	1,150.	1,189.	76.
	56 ¹³ / ₁₆ "	30"	3"	DP8CPPFR5730	1,079.	1,164.	1,214.	1,258.	78.
	56 ¹³ / ₁₆ "	36"	3"	DP8CPPFR5736	1,145.	1,235.	1,295.	1,335.	79.
	56 ¹³ / ₁₆ "	42"	3"	DP8CPPFR5742	1,212.	1,308.	1,369.	1,417.	81.
	56 ¹³ / ₁₆ "	48"	3"	DP8CPPFR5748	1,276.	1,379.	1,441.	1,494.	82.
	56 ¹³ / ₁₆ "	60"	3"	DP8CPPFR5760	1,534.	1,651.	1,731.	1,792.	85.



64" High Tiled Panel with 28" Lower Tile and Tile to Floor	64 ¹ / ₁₆ "	15"	3"	DP8CPPFR6415	1,000.	1,083.	1,133.	1,172.	89.
	64 ¹ / ₁₆ "	18"	3"	DP8CPPFR6418	1,000.	1,083.	1,133.	1,172.	89.
	64 ¹ / ₁₆ "	24"	3"	DP8CPPFR6424	1,079.	1,164.	1,213.	1,257.	93.
	64 ¹ / ₁₆ "	30"	3"	DP8CPPFR6430	1,138.	1,225.	1,291.	1,332.	90.
	64 ¹ / ₁₆ "	36"	3"	DP8CPPFR6436	1,211.	1,306.	1,367.	1,415.	91.
	64 ¹ / ₁₆ "	42"	3"	DP8CPPFR6442	1,279.	1,384.	1,450.	1,496.	92.
	64 ¹ / ₁₆ "	48"	3"	DP8CPPFR6448	1,354.	1,458.	1,522.	1,581.	93.
	64 ¹ / ₁₆ "	60"	3"	DP8CPPFR6460	1,621.	1,748.	1,828.	1,892.	93.



Dimensions listed under h w d are actual to the nearest 1/8"

Ordering Information	Order Code	Included with:	Options																
Tiled Panels with 28" Lower Tile and Tile To Floor: 1. Pattern Number 2. Top cap type 3. Top cap finish 4. Knockout option 5. Base raceway finish 6. Tile support style 7. Panel fabric	Tiled Panels with 28" Lower Tile and Tile To Floor: <i>Example:</i> DP8CPPFF4218 4/117/K/117/2/B191 <table><tr><td>DP8CPP</td><td>Pattern number</td></tr><tr><td>FF4218</td><td></td></tr><tr><td>4</td><td>Radius Metal top cap</td></tr><tr><td>117</td><td>Soft Grey top cap finish</td></tr><tr><td>K</td><td>Base raceway with knockouts</td></tr><tr><td>117</td><td>Soft Grey base raceway finish</td></tr><tr><td>2</td><td>D2 style tile supports</td></tr><tr><td>B191</td><td>Fairfield light fabric</td></tr></table>	DP8CPP	Pattern number	FF4218		4	Radius Metal top cap	117	Soft Grey top cap finish	K	Base raceway with knockouts	117	Soft Grey base raceway finish	2	D2 style tile supports	B191	Fairfield light fabric	Tiled Panels with 28" Lower Tile and Tile To Floor: • Panel frame • Acoustic panel inserts • Top cap • Connection hardware • Tile to floor side 1 • Base raceway with knockout when required side 2 Note: Panel to panel connector specified separately: DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others	Tiled Panels with 28" Lower Tile and Tile To Floor: Full View Frame Option: To specify full view frames for window or stacking applications, replace the "C" in pattern number with "V". No upcharge. Tile to Floor Side Option: Tile to Floor standard on side 1. To specify tile to floor on side 2, change "FR" in pattern number to "RF". Monolithic Side Option: To specify monolithic on side one of panel, change "PP" in pattern number to "MP" and deduct amount in far right column. Top Cap Options: No Top Cap - Deduct \$40; Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4 Raceway Knockout Options: (K) = Knockouts on raceway side (N) = No knockouts Tile Support Options: (1) = D1 External Reveal (2) = D2 Recessed Reveal
DP8CPP	Pattern number																		
FF4218																			
4	Radius Metal top cap																		
117	Soft Grey top cap finish																		
K	Base raceway with knockouts																		
117	Soft Grey base raceway finish																		
2	D2 style tile supports																		
B191	Fairfield light fabric																		

Tiled Panels


28" Lower Tile and Tile To Floor

78" High

Dividends Horizon

Panels, Pre-Configured

description	h	w	d	pattern no.	grade 10	20	30	40	deduct for 1 side Monolithic
78" High Tiled Panel with 28" Lower Tile and Tile to Floor	78 ⁹ / ₁₆ "	15"	3"	DP8CPPFR7815	\$1,577.	\$1,697.	\$1,773.	\$1,838.	\$158.
	78 ⁹ / ₁₆ "	18"	3"	DP8CPPFR7818	1,577.	1,697.	1,773.	1,838.	158.
	78 ⁹ / ₁₆ "	24"	3"	DP8CPPFR7824	1,690.	1,826.	1,912.	1,975.	163.
	78 ⁹ / ₁₆ "	30"	3"	DP8CPPFR7830	1,792.	1,930.	2,019.	2,095.	160.
	78 ⁹ / ₁₆ "	36"	3"	DP8CPPFR7836	1,916.	2,064.	2,163.	2,236.	173.
	78 ⁹ / ₁₆ "	42"	3"	DP8CPPFR7842	2,028.	2,187.	2,289.	2,373.	176.
	78 ⁹ / ₁₆ "	48"	3"	DP8CPPFR7848	2,150.	2,323.	2,430.	2,514.	211.



Ordering Information

Tiled Panels with 28" Lower Tile and Tile To Floor:

1. Pattern Number
2. Top cap type
3. Top cap finish
4. Knockout option
5. Base raceway finish
6. Tile support style
7. Panel fabric

Order Code

Tiled Panels with 28" Lower Tile and Tile To Floor:

<i>Example:</i>	DP8CPPFF4218
	4/117/K/117/2/B191
DP8CPP	Pattern number
FF4218	
4	Radius Metal top cap
117	Soft Grey top cap finish
K	Base raceway with knockouts
117	Soft Grey base raceway finish
2	D2 style tile supports
B191	Fairfield light fabric

Included with:

Tiled Panels with 28" Lower Tile and Tile To Floor:

- Panel frame
- Acoustic panel inserts
- Top cap
- Connection hardware
- Base raceway with knockout when required

Note: Panel to panel connector specified separately: DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others

Options

Tiled Panels with 28" Lower Tile and Tile To Floor:

Full View Frame Option:

To specify full view frames for window or stacking applications, replace the "C" in pattern number with "V". No upcharge.

Tile to Floor Side Option:

Tile to Floor standard on side 1. To specify tile to floor on side 2, change "FR" in pattern number to "RF".

Monolithic Side Option:

To specify monolithic on side one of panel, change "PP" in pattern number to "MP" and deduct amount in far right column.

Top Cap Options:

No Top Cap - Deduct \$40;
Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4

Raceway Knockout Options:

(K) = Knockouts on raceway side
(N) = No knockouts

Tile Support Options:

(1) = D1 External Reveal
(2) = D2 Recessed Reveal

Beltway Panel Components

"Preconfigured" Dividends Horizon beltway panels ship completely assembled with a universal panel frame, choice of standard base raceway or tiled to the floor base options, top cap, panel-to-panel connection hardware and beltway inserts.

Beltway panels may be ordered by component for "Build-to-Spec" applications. This includes when panel inserts are required on one side only or when a different fabric color or material is required on opposite panel sides.

Beltway Panel Insert Supports

All Dividends Horizon panel frames are pre-punched to accept beltway supports which span horizontally across the panel frame. Beltway panel inserts are mounted above and below the beltway and attach to the upper and lower panel frame and the beltway supports. Beltway supports are painted black.

Note: Slatwall tiles may not be specified or installed with beltway.

Beltway Panel Insert Construction

Fabric inserts are constructed of fabric laminated with a web adhesive and heat cured to 1/2" thick tackable acoustic board. Laminate inserts are constructed of a particle board core with laminate on the front and back. Steel tiles are constructed of formed steel that is painted in any Knoll core paint finish.

Beltway Cover Construction

Painted steel in Knoll core paint colors.

Electrical

Panel base raceways 24" and wider will accept two duplex receptacles per panel side. 18" wide panels provide pass-through electrical only. Beltway raceways 30" and wider will accept two duplex receptacles per panel side. 18" and 24" wide beltways provide pass-through electrical only. All electrical components are ordered separately and must be field-installed.

One-Sided Beltway Panel

Beltway panels are available with one beltway per panel or per panel sides. Non-beltway side will have a monolithic insert.

Two Top Cap Options Available

- Radius Metal
- Flat Metal


Top Cap Construction

Radius and flat metal top caps are made from extruded aluminum.


Top Cap Attachment

Snap onto the trough of a topway panel frame. Retainer clips are included to attach top caps to full view frames.

Preconfigured Beltway Panel




Panel Base Options



Beltway Panel Standard Configurations


42"H Panels

- One 7"H upper insert
- One 4"H beltway cover and insert support
- One 24"H lower insert




50"H Panels

- One 14"H upper panel insert
- One 4"H beltway cover and insert support
- One 24"H lower insert




57"H Panels

- One 21"H upper insert
- One 4"H beltway cover and insert support
- One 24"H lower insert




78"H Panels

- One 50"H upper insert
- One 4"H beltway cover and insert support
- One 24"H lower panel insert



64"H Panels

- One 28"H upper insert
- One 4"H beltway cover and insert support
- One 24"H lower insert




Beltway Panels

Standard Base Raceway

42" and 50" High

Dividends Horizon

Panels, Pre-Configured

description	h	w	d	pattern no.	grade 10	20	30	40	Deduct for Monolithic on side 2
 42" Beltway Panels with Standard Base Raceway	42 3/16"	18"	3"	DP8CBBRR4218	\$758.	\$817.	\$851.	\$878.	\$92.
	42 3/16"	24"	3"	DP8CBBRR4224	855.	916.	958.	991.	114.
	42 3/16"	30"	3"	DP8CBBRR4230	934.	1,006.	1,050.	1,081.	123.
	42 3/16"	36"	3"	DP8CBBRR4236	1,021.	1,098.	1,146.	1,185.	136.
	42 3/16"	42"	3"	DP8CBBRR4242	1,101.	1,187.	1,241.	1,280.	142.
	42 3/16"	48"	3"	DP8CBBRR4248	1,174.	1,265.	1,317.	1,363.	153.
	42 3/16"	60"	3"	DP8CBBRR4260	1,325.	1,428.	1,490.	1,542.	153.
 50" Beltway Panels with Standard Base Raceway	49 1/2"	18"	3"	DP8CBBRR5018	785.	846.	881.	910.	91.
	49 1/2"	24"	3"	DP8CBBRR5024	894.	959.	1,004.	1,036.	115.
	49 1/2"	30"	3"	DP8CBBRR5030	969.	1,038.	1,081.	1,121.	119.
	49 1/2"	36"	3"	DP8CBBRR5036	1,043.	1,122.	1,174.	1,210.	125.
	49 1/2"	42"	3"	DP8CBBRR5042	1,123.	1,210.	1,268.	1,310.	131.
	49 1/2"	48"	3"	DP8CBBRR5048	1,196.	1,291.	1,347.	1,397.	136.
	49 1/2"	60"	3"	DP8CBBRR5060	1,353.	1,457.	1,525.	1,575.	136.

Dimensions listed under h w d are actual to the nearest 1/16"



Ordering Information	Order Code	Included with:	Options
Beltway Panel with Standard Base Raceway: 1. Pattern Number 2. Top cap type 3. Top cap finish 4. Base raceway knockout option 5. Base raceway finish 6. Beltway finish 7. Panel fabric	Beltway Panel with Standard Base Raceway <i>Example:</i> DP8CBBRR4218 4/117/K/117/117/B191 DP8CBB Pattern number RR4218 4 Radius Metal top cap 117 Soft Grey top cap finish K Base Raceway with knockouts both sides 117 Soft Grey base raceway finish 117 Beltway finish B191 Fairfield light fabric	Beltway Panel with Standard Base Raceway: • Panel frame • Acoustic panel inserts • Base raceway covers • Beltway covers • Top cap • Connection hardware Note: Panel to panel connector specified separately: DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others	Beltway Panel with Standard Raceway Options: Full View Frame Option: To specify full view frames for window or stacking applications, replace the "C" in pattern number with "V". No upcharge. Monolithic Side Option: To specify monolithic on side one of panel, change "BB" in pattern number to "MB" and deduct amount in far right column. Top Cap Options: No Top Cap - Deduct \$40; Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4 Raceway Knockout Options: (K) = Knockouts on raceway side (N) = No Knockouts

Beltway Panels

Standard Base Raceway

57", 64" and 78" High

Dividends Horizon

description	h	w	d	pattern no.	grade 10	20	30	40	Deduct for Monolithic on side 2
 57" Beltway Panels with Standard Base Raceway	56 ¹³ / ₁₆ "	18"	3"	DP8CBBRR5718	\$836.	\$900.	\$938.	\$973.	\$91.
	56 ¹³ / ₁₆ "	24"	3"	DP8CBBRR5724	941.	1,017.	1,061.	1,097.	115.
	56 ¹³ / ₁₆ "	30"	3"	DP8CBBRR5730	1,017.	1,094.	1,144.	1,182.	119.
	56 ¹³ / ₁₆ "	36"	3"	DP8CBBRR5736	1,114.	1,198.	1,252.	1,294.	125.
	56 ¹³ / ₁₆ "	42"	3"	DP8CBBRR5742	1,190.	1,283.	1,341.	1,388.	131.
	56 ¹³ / ₁₆ "	48"	3"	DP8CBBRR5748	1,274.	1,371.	1,434.	1,482.	136.
	56 ¹³ / ₁₆ "	60"	3"	DP8CBBRR5760	1,429.	1,540.	1,610.	1,665.	136.
 64" Beltway Panels with Standard Base Raceway	64 ¹ / ₁₆ "	18"	3"	DP8CBBRR6418	885.	953.	993.	1,029.	98.
	64 ¹ / ₁₆ "	24"	3"	DP8CBBRR6424	992.	1,068.	1,116.	1,153.	121.
	64 ¹ / ₁₆ "	30"	3"	DP8CBBRR6430	1,064.	1,146.	1,195.	1,239.	121.
	64 ¹ / ₁₆ "	36"	3"	DP8CBBRR6436	1,182.	1,271.	1,325.	1,370.	138.
	64 ¹ / ₁₆ "	42"	3"	DP8CBBRR6442	1,262.	1,354.	1,415.	1,461.	146.
	64 ¹ / ₁₆ "	48"	3"	DP8CBBRR6448	1,350.	1,455.	1,522.	1,571.	159.
	64 ¹ / ₁₆ "	60"	3"	DP8CBBRR6460	1,520.	1,637.	1,710.	1,769.	159.
 78" Beltway Panels with Standard Base Raceway	78 ³ / ₁₆ "	18"	3"	DP8CBBRR7818	1,101.	1,187.	1,241.	1,280.	89.
	78 ³ / ₁₆ "	24"	3"	DP8CBBRR7824	1,232.	1,324.	1,379.	1,430.	102.
	78 ³ / ₁₆ "	30"	3"	DP8CBBRR7830	1,316.	1,420.	1,482.	1,532.	105.
	78 ³ / ₁₆ "	36"	3"	DP8CBBRR7836	1,453.	1,565.	1,637.	1,694.	123.
	78 ³ / ₁₆ "	42"	3"	DP8CBBRR7842	1,559.	1,675.	1,757.	1,816.	126.
	78 ³ / ₁₆ "	48"	3"	DP8CBBRR7848	1,710.	1,845.	1,927.	1,996.	156.

Dimensions listed under h w d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Beltway Panel with Standard Base Raceway: 1. Pattern Number 2. Top cap type 3. Top cap finish 4. Base raceway knockout option 5. Base raceway finish 6. Beltway finish 7. Panel fabric	Beltway Panel with Standard Base Raceway <i>Example:</i> DP8CBBRR4218 4/117/K/117/117/B191 DP8CBB Pattern number RR4218 4 Radius Metal top cap 117 Soft Grey top cap finish K Base Raceway with knockouts both sides 117 Soft Grey base raceway finish 117 Beltway finish B191 Fairfield light fabric	Beltway Panel with Standard Base Raceway: - Panel frame - Acoustic panel inserts - Base raceway covers - Beltway covers - Top cap - Connection hardware Note: Panel to panel connector specified separately: DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others	Beltway Panel with Standard Raceway Options: Full View Frame Option: To specify full view frames for window or stacking applications, replace the "C" in pattern number with "V". No upcharge. Monolithic Side Option: To specify monolithic on side one of panel, change "BB" in pattern number to "MB" and deduct amount in far right column. Top Cap Options: No Top Cap - Deduct \$40; Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4 Raceway Knockout Options: (K) = Knockouts on raceway side (N) = No Knockouts



Beltway Panels

Tile to the Floor

42" and 50" High

Dividends Horizon

Panels, Pre-Configured

description	h	w	d	pattern no.	grade 10	20	30	40	Deduct for Monolithic side 1
 42" Beltway Panels with Tile to the Floor	42 ³ / ₁₆ "	18"	3"	DP8CBBFR4218	\$793.	\$852.	\$886.	\$913.	\$92.
	42 ³ / ₁₆ "	24"	3"	DP8CBBFR4224	890.	951.	993.	1,026.	114.
	42 ³ / ₁₆ "	30"	3"	DP8CBBFR4230	969.	1,041.	1,085.	1,116.	123.
	42 ³ / ₁₆ "	36"	3"	DP8CBBFR4236	1,056.	1,133.	1,181.	1,220.	136.
	42 ³ / ₁₆ "	42"	3"	DP8CBBFR4242	1,136.	1,222.	1,276.	1,315.	142.
	42 ³ / ₁₆ "	48"	3"	DP8CBBFR4248	1,209.	1,300.	1,352.	1,398.	153.
	42 ³ / ₁₆ "	60"	3"	DP8CBBFR4260	1,360.	1,463.	1,525.	1,577.	153.
 50" Beltway Panels with Tile to the Floor	49 ¹ / ₂ "	18"	3"	DP8CBBFR5018	820.	881.	916.	945.	91.
	49 ¹ / ₂ "	24"	3"	DP8CBBFR5024	929.	994.	1,039.	1,071.	115.
	49 ¹ / ₂ "	30"	3"	DP8CBBFR5030	1,004.	1,073.	1,116.	1,156.	119.
	49 ¹ / ₂ "	36"	3"	DP8CBBFR5036	1,078.	1,157.	1,209.	1,245.	125.
	49 ¹ / ₂ "	42"	3"	DP8CBBFR5042	1,158.	1,245.	1,303.	1,345.	131.
	49 ¹ / ₂ "	48"	3"	DP8CBBFR5048	1,231.	1,326.	1,382.	1,432.	136.
	49 ¹ / ₂ "	60"	3"	DP8CBBFR5060	1,388.	1,492.	1,560.	1,610.	136.

Dimensions listed under h w c are actual to the nearest ¹/₁₆"



Ordering Information	Order Code	Included with:	Options																
Beltway Panel with Tile to the Floor: 1. Pattern Number 2. Top cap type 3. Top cap finish 4. Base raceway knockout option 5. Base raceway finish 6. Beltway finish 7. Panel fabric	Beltway Panel with Tile to the Floor: <i>Example:</i> DP8CBBFR4218 4/117/K/117/117/B191 <table><tr><td>DP8CBB</td><td>Pattern number</td></tr><tr><td>FR4218</td><td></td></tr><tr><td>4</td><td>Radius Metal top cap</td></tr><tr><td>117</td><td>Soft Grey top cap finish</td></tr><tr><td>K</td><td>Base raceway with knockouts both sides</td></tr><tr><td>117</td><td>Soft Grey base raceway finish</td></tr><tr><td>117</td><td>Soft Grey beltway cover finish</td></tr><tr><td>B191</td><td>Fairfield light fabric</td></tr></table>	DP8CBB	Pattern number	FR4218		4	Radius Metal top cap	117	Soft Grey top cap finish	K	Base raceway with knockouts both sides	117	Soft Grey base raceway finish	117	Soft Grey beltway cover finish	B191	Fairfield light fabric	Beltway Panel with Tile to the Floor: • Panel frame • Acoustic panel inserts • Top cap • Connection hardware • Base raceway side 2 • Beltway with covers • Tile to the floor side 1 Note: Panel to panel connector specified separately: DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others	Beltway Panel with Tile to the Floor: Full View Frame Option: To specify full view frames for window or stacking applications, replace the “C” in pattern number with “V”. No upcharge. Monolithic Side Option: For side 1 monolithic, side 2 beltway, change “BB” in pattern number to “MB” and deduct amount in far right column. Tile to Floor Side Option: Panels are standard with tile to floor side 1, raceway side 2. To specify raceway side one and tile to floor side 2, change “FR” in pattern number to “RF”. Top Cap Options: No Top Cap - Deduct \$40; Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4 Raceway Knockout Options: (K) = Knockouts on raceway side (N) = No Knockouts
DP8CBB	Pattern number																		
FR4218																			
4	Radius Metal top cap																		
117	Soft Grey top cap finish																		
K	Base raceway with knockouts both sides																		
117	Soft Grey base raceway finish																		
117	Soft Grey beltway cover finish																		
B191	Fairfield light fabric																		

Beltway Panels

Tile to the Floor

57" and 64" High

Dividends Horizon

description	height	width	depth	pattern number	10	20	30	40	Deduct for Monolithic side 1
 57" Beltway Panels with Tile to the Floor	56 ¹³ / ₁₆ "	18"	3"	DP8CBBFR5718	\$871.	\$935.	\$973.	\$1,008.	\$91.
	56 ¹³ / ₁₆ "	24"	3"	DP8CBBFR5724	976.	1,052.	1,096.	1,132.	115.
	56 ¹³ / ₁₆ "	30"	3"	DP8CBBFR5730	1,052.	1,129.	1,179.	1,217.	119.
	56 ¹³ / ₁₆ "	36"	3"	DP8CBBFR5736	1,149.	1,233.	1,287.	1,329.	125.
	56 ¹³ / ₁₆ "	42"	3"	DP8CBBFR5742	1,225.	1,318.	1,376.	1,423.	131.
	56 ¹³ / ₁₆ "	48"	3"	DP8CBBFR5748	1,309.	1,406.	1,469.	1,517.	136.
	56 ¹³ / ₁₆ "	60"	3"	DP8CBBFR5760	1,464.	1,575.	1,645.	1,700.	136.
 64" Beltway Panels with Tile to the Floor	64 ¹ / ₁₆ "	18"	3"	DP8CBBFR6418	920.	988.	1,028.	1,064.	98.
	64 ¹ / ₁₆ "	24"	3"	DP8CBBFR6424	1,027.	1,103.	1,151.	1,188.	121.
	64 ¹ / ₁₆ "	30"	3"	DP8CBBFR6430	1,099.	1,181.	1,230.	1,274.	121.
	64 ¹ / ₁₆ "	36"	3"	DP8CBBFR6436	1,217.	1,306.	1,360.	1,405.	138.
	64 ¹ / ₁₆ "	42"	3"	DP8CBBFR6442	1,297.	1,389.	1,450.	1,496.	146.
	64 ¹ / ₁₆ "	48"	3"	DP8CBBFR6448	1,385.	1,490.	1,557.	1,606.	159.
	64 ¹ / ₁₆ "	60"	3"	DP8CBBFR6460	1,555.	1,672.	1,745.	1,804.	159.

Dimensions listed under h w c are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Beltway Panel with Tile to the Floor: 1. Pattern Number 2. Top cap type 3. Top cap finish 4. Base raceway knockout option 5. Base raceway finish 6. Beltway finish 7. Panel fabric	Beltway Panel with Tile to the Floor: <i>Example:</i> DP8CBBFR5718 4/117/K/117/117/B191 DP8CBB Pattern number FR5718 4 Radius Metal top cap 117 Soft Grey top cap finish K Base raceway with knockouts both sides 117 Soft Grey base raceway finish 117 Soft Grey beltway cover finish B191 Fairfield light fabric	Beltway Panel with Tile to the Floor: • Panel frame • Acoustic panel inserts • Top cap • Connection hardware • Base raceway • Beltway with covers • Tile to the floor side 1 Note: Panel to panel connector specified separately: DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others	Beltway Panel with Tile to the Floor: Full View Frame Option: To specify full view frames for window or stacking applications, replace the "C" in pattern number with "V". No upcharge. Monolithic Side Option: For side 1 monolithic, side 2 beltway, change "BB" in pattern number to "MB" and deduct amount in far right column. Tile to Floor Side Option: Panels are standard with tile to floor side 1, raceway side 2. To specify raceway side one and tile to floor side 2, change "FR" in pattern number to "RF". Top Cap Options: No Top Cap - Deduct \$40; Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4 Raceway Knockout Options: (K) = Knockouts on raceway side (N) = No Knockouts

Beltway Panels


Tile to the Floor

78" High

Dividends Horizon

Panels, Pre-Configured

description	height	width	depth	pattern number	10	20	30	40	Deduct for Monolithic side 1
78" Beltway Panels with Tile to the Floor	78 ⁹ / ₁₆ "	18"	3"	DP8CBBFR7818	\$1,136.	\$1,222.	\$1,276.	\$1,315.	\$89.
	78 ⁹ / ₁₆ "	24"	3"	DP8CBBFR7824	1,267.	1,359.	1,414.	1,465.	102.
	78 ⁹ / ₁₆ "	30"	3"	DP8CBBFR7830	1,351.	1,455.	1,517.	1,567.	105.
	78 ⁹ / ₁₆ "	36"	3"	DP8CBBFR7836	1,488.	1,600.	1,672.	1,729.	123.
	78 ⁹ / ₁₆ "	42"	3"	DP8CBBFR7842	1,594.	1,710.	1,792.	1,851.	126.
	78 ⁹ / ₁₆ "	48"	3"	DP8CBBFR7848	1,745.	1,880.	1,962.	2,031.	156.



Dimensions listed under h w c are actual to the nearest ¹/₁₆"

Ordering Information	Order Code	Included with:	Options
Beltway Panel with Tile to the Floor: 1. Pattern Number 2. Top cap type 3. Top cap finish 4. Base raceway knockout option 5. Base raceway finish 6. Beltway finish 7. Panel fabric	Beltway Panel with Tile to the Floor: <i>Example:</i> DP8CBBFR7818 4/117/K/117/117/B191 DP8CBB Pattern number FR7818 4 Radius Metal top cap 117 Soft Grey top cap finish K Base raceway with knockouts both sides 117 Soft Grey base raceway finish 117 Soft Grey beltway cover finish B191 Fairfield light fabric	Beltway Panel with Tile to the Floor: - Panel frame - Acoustic panel inserts - Top cap - Connection hardware - Base raceway - Beltway with covers - Tile to the floor side 1 Note: Panel to panel connector specified separately: DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others	Beltway Panel with Tile to the Floor: Full View Frame Option: To specify full view frames for window or stacking applications, replace the "C" in pattern number with "V". No upcharge. Monolithic Side Option: For side 1 monolithic, side 2 beltway, change "BB" in pattern number to "MB" and deduct amount in far right column. Tile to Floor Side Option: Panels are standard with tile to floor side 1, raceway side 2. To specify raceway side one and tile to floor side 2, change "FR" in pattern number to "RF". Top Cap Options: No Top Cap - Deduct \$40; Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4 Raceway Knockout Options: (K) = Knockouts on raceway side (N) = No Knockouts

Panel Frame Options

Dividends Horizon offers two panel frame options, which are selected depending on customer's aesthetic and functional needs. Both frames are available in preconfigured and build-to-spec panels, and may also be specified in CAP.

Dividends Horizon panel frames may be specified separately for "Build-to-Spec" applications. These include when panel inserts are only required on one side or when a beltway is required on one side and tiled inserts are on the other.

Panel frames may be specified with a standard base raceway, an open base or a tile to the floor. Panel frames ship complete with the base components, top cap and universal connection hardware. Raceway cover knockouts are standard with standard base raceway. If not required raceway covers without knockouts may be specified.

Topway panel frames feature an integral top cable trough, and are used with D1 style stack panels.

Full View frames have no top trough, leaving a larger window opening in the top position. Full view panels frames are designed for use with windows in the top position. They are also required when stacking with D2 style stack frames or DP8 stacking screens.

Topway and full view panel frames are offered in worksurface height, 36", 42", 50", 57", 64" and 78" high.

Two Top Cap Options Available:

- Radius Metal
- Flat Metal

Top Cap Construction

Radius and flat metal top caps are made from steel.


Top Cap Attachment

Full view frames ordered with top caps include top cap attachment clips on the panel frame.


If top caps are ordered separately, top cap attachment clips ship with the top cap and must be field-installed to the panel frame.

Open Position Planner

Open Position Planner allows specifiers to design and order factory assembled panels in virtually any configuration. Open Position Planner is available only through CAP, and is not available in this price list.



Topway Panel Frame



Full View Panel Frame

Panel Base Options

Dividends Horizon panels are available with three base options:

- Base Raceway
- Open Base
- Tile-to-Floor.

Overall panel heights, tile configurations and application rules are the same for all three base options.

Base Raceway

Provides duplex receptacle and data port access at base height. Base Raceway panels feature two roll formed steel raceway covers, which are available with or without electrical/data knockouts.

- Exterior dimension: 5"H x 2 15/16"D
- Interior dimension: 5"H x 2 7/8"D
- Dataport Knockout dimension: 1 3/8"H x 2 5/8"D
- Construction: Paint-colored 22-gauge roll-form steel cover
- Duplex access: 24" and wider base raceway covers have two duplex knockouts per panel side (18"W panels do not have duplex knockouts)
- Duplex location: 9" on center from each end

- Data access: All base raceway covers have one center-located data port knockout
- Additional data access: In panels 24" and wider, the outer knockouts can be used as additional data ports when the raceway is not used for duplex receptacles
- Power capacity: One power module or jumper

Note: Knockouts are standard unless specified without.


Open Base panels feature two extruded aluminum feet positioned at the end of each panel. A horizontal trim is located below the bottom tile.

Tile-To-Floor panels eliminate the raceway cover and access on one side, replaced by a fabric tile extended to the floor. A heavy gauge steel internal raceway cover protects the raceway contents and the tile from deflecting when hit by shoes or vacuum cleaners. The other side of the panel features a raceway cover, available with or without electrical/data knockouts. If needed, use one-sided electrical and one-sided base cable trays with this base option.


Note: Worksurface height monolithic tiles are to be used with worksurface height panel frames only.

Note: 24"H inserts are to only be used below beltways.


Panel Base Options



Base Raceway



Tile-to-Floor
(single-sided only)



Open Base

Monolithic and Tiled Panel Standard Configuration

Worksurface Height



- Monolithic
- One worksurface height monolithic insert

36"H Panel Frames



- Monolithic
- One 28"H monolithic insert



- Tiled
- Two 14"H tiled inserts

42"H Panel Frames



- Monolithic
- One 35"H monolithic insert



- Tiled
- One 7"H tiled insert
 - Two 14"H tiled inserts



- Beltway
- One 7"H upper insert
 - One 4"H beltway cover
 - One 24"H lower insert

50"H Panel Frames



- Monolithic
- One 42"H monolithic insert



- Tiled
- Three 14"H tiled inserts



- Beltway
- One 14"H upper insert
 - One 4"H beltway cover
 - One 24"H lower insert


57"H Panel Frames



- Monolithic
- One 49"H monolithic insert



- Tiled
- One 7"H tiled inserts
 - Three 14"H tiled inserts




- Beltway
- One 7"H tiled insert
 - One 14"H tiled insert
 - One 4"H beltway cover
 - One 24"H lower insert

64"H Panel Frames



- Monolithic
- One 56"H monolithic insert




- Tiled
- Four 14" H tiled inserts



- Beltway
- One 28"H upper insert
 - One 4"H beltway cover
 - One 24"H lower insert

78"H Panel Frames



- Monolithic
- One 70"H monolithic insert



- Tiled
- Five 14"H tiled inserts



- Beltway
- One 50"H Upper insert
 - One 4"H Beltway cover
 - One 24"H Lower insert

Note: Insert dimensions are nominal. Inserts are for one side only.

Topway and Full View Panel Frame Assemblies

Worksurface Height, 36" and 42" High

Dividends Horizon

description	h	w	d	pattern no.	list
Worksurface Height	28 1/2"	15"	3"	DP8()RRWH15	\$347.
Panel Frame Assembly	28 1/2"	18"	3"	DP8()RRWH18	347.
Standard Base Raceway	28 1/2"	24"	3"	DP8()RRWH24	355.
	28 1/2"	30"	3"	DP8()RRWH30	365.
	28 1/2"	36"	3"	DP8()RRWH36	387.
	28 1/2"	42"	3"	DP8()RRWH42	424.
	28 1/2"	48"	3"	DP8()RRWH48	424.
	28 1/2"	60"	3"	DP8()RRWH60	482.
36" High Panel Frame Assembly	35 1/8"	15"	3"	DP8()RR3615	347.
Standard Base Raceway	35 1/8"	18"	3"	DP8()RR3618	347.
	35 1/8"	24"	3"	DP8()RR3624	355.
	35 1/8"	30"	3"	DP8()RR3630	365.
	35 1/8"	36"	3"	DP8()RR3636	387.
	35 1/8"	42"	3"	DP8()RR3642	424.
	35 1/8"	48"	3"	DP8()RR3648	424.
	35 1/8"	60"	3"	DP8()RR3660	482.
42" High Panel Frame Assembly	42 3/16"	15"	3"	DP8()RR4215	315.
Standard Base Raceway	42 3/16"	18"	3"	DP8()RR4218	315.
	42 3/16"	24"	3"	DP8()RR4224	322.
	42 3/16"	30"	3"	DP8()RR4230	347.
	42 3/16"	36"	3"	DP8()RR4236	365.
	42 3/16"	42"	3"	DP8()RR4242	391.
	42 3/16"	48"	3"	DP8()RR4248	409.
	42 3/16"	60"	3"	DP8()RR4260	461.

Dimensions listed under h w d are actual to the nearest 1/16"




Ordering Information	Order Code	Included with:	Options
Panel Frame Assembly 1. Pattern Number 2. Top cap type 3. Top cap trim finish 4. Raceway knockout option 5. Base raceway finish if required	Topway Panel Frame Assembly <i>Example:</i> DP8CRR6448 4/117K/117 DP8CRR Topway Panel Frame 6448 Assemblies with Base Raceway 4 Radius metal topcap 117 Soft Grey top cap finish K Raceway knockouts 117 Soft Grey raceway finish	Panel Frame Assembly: • Panel frame • Top cap (optional) • Connection hardware • Base raceway Note: Worksurface Height panel frame assemblies are not available with plastic top caps. Note: 15" wide panels are only available with standard base raceway or tile to floor. Note: Panel to panel connector specified separately; DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others.	Panel Frame Assembly: Option: (C) = Topway Panel Frame (V) = Full View Panel Frame Panel Base Options Open Panel Base Option: For open panel base, change 'RR' to 'LL'. Tile to Floor Option: For tile to floor on one side and base raceway on the other side change 'RR' to 'FR' and add \$35 to list price. Top Cap Options: No Top Cap - Deduct \$40; Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4 Base Raceway Knockout Options: (for RR and RF bases only) (K) = Knockouts on raceway side (N) = No knockouts

Topway and Full View Panel Frame Assemblies

50", 57" and 64" High

Dividends Horizon

Panels, Build-To-Spec

description	h	w	d	pattern no.	list
50" High Panel Frame Assembly Standard Base Raceway  (topway and full view shown)	49 1/2"	15"	3"	DP8()RR5015	\$322.
	49 1/2"	18"	3"	DP8()RR5018	322.
	49 1/2"	24"	3"	DP8()RR5024	337.
	49 1/2"	30"	3"	DP8()RR5030	359.
	49 1/2"	36"	3"	DP8()RR5036	373.
	49 1/2"	42"	3"	DP8()RR5042	399.
	49 1/2"	48"	3"	DP8()RR5048	416.
	49 1/2"	60"	3"	DP8()RR5060	449.
57" High Panel Frame Assembly Standard Base Raceway  (topway and full view shown)	56 13/16"	15"	3"	DP8()RR5715	322.
	56 13/16"	18"	3"	DP8()RR5718	322.
	56 13/16"	24"	3"	DP8()RR5724	337.
	56 13/16"	30"	3"	DP8()RR5730	352.
	56 13/16"	36"	3"	DP8()RR5736	371.
	56 13/16"	42"	3"	DP8()RR5742	390.
	56 13/16"	48"	3"	DP8()RR5748	410.
	56 13/16"	60"	3"	DP8()RR5760	429.
64" High Panel Frame Assembly Standard Base Raceway  (topway and full view shown)	64 1/16"	15"	3"	DP8()RR6415	339.
	64 1/16"	18"	3"	DP8()RR6418	339.
	64 1/16"	24"	3"	DP8()RR6424	362.
	64 1/16"	30"	3"	DP8()RR6430	373.
	64 1/16"	36"	3"	DP8()RR6436	395.
	64 1/16"	42"	3"	DP8()RR6442	416.
	64 1/16"	48"	3"	DP8()RR6448	438.
	64 1/16"	60"	3"	DP8()RR6460	500.

Dimensions listed under h w d are actual to the nearest 1/16"


Ordering Information	Order Code	Included with:	Options
Panel Frame Assembly 1. Pattern Number 2. Top cap type 3. Top cap trim finish 4. Raceway knockout option 5. Base raceway finish if required	Topway Panel Frame Assembly <i>Example:</i> DP8CRR6448 4/117K/117 DP8CRR Topway Panel Frame 6448 Assembly with Base Raceway 4 Radius metal topcap 117 Soft Grey top cap finish K Raceway knockouts 117 Soft Grey raceway finish	Panel Frame Assembly: - Panel frame - Top cap (optional) - Connection hardware - Base raceway Note: 15" wide panels are only available with a standard base raceway or tile to floor. Note: Panel to panel connector specified separately: DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others	Panel Frame Assembly: Option: (C) = Topway Panel Frame (V) = Full View Panel Frame Panel Base Options Open Panel Base Option: For open panel base, change 'RR' to 'LL'. Tile to Floor Option: For tile to floor on one side and base raceway on the other side change 'RR' to 'FR' and add \$35 to list price. Top Cap Options: No Top Cap - Deduct \$40; Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4 Base Raceway Knockout Options: (for RR and RF base only) (K) = Knockouts on raceway side (N) = No knockouts

Topway and Full View Panel Frame Assemblies

78" High

Dividends Horizon

description	h	w	d	pattern no.	list
78" High Panel Frame Assembly	78 ⁹ / ₁₆ "	15"	3"	DP8()RR7815	\$492.
Standard Base Raceway	78 ⁹ / ₁₆ "	18"	3"	DP8()RR7818	492.
	78 ⁹ / ₁₆ "	24"	3"	DP8()RR7824	517.
	78 ⁹ / ₁₆ "	30"	3"	DP8()RR7830	538.
	78 ⁹ / ₁₆ "	36"	3"	DP8()RR7836	571.
	78 ⁹ / ₁₆ "	42"	3"	DP8()RR7842	603.
	78 ⁹ / ₁₆ "	48"	3"	DP8()RR7848	626.




(topway and full view shown)

Dimensions listed under h w d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Panel Frame Assembly	Topway Panel Frame Assembly	Panel Frame Assembly:	Panel Frame Assembly:
1. Pattern Number	<i>Example:</i> DP8CRR7848	- Panel frame - Top cap (optional) - Connection hardware - Base raceway	Option:
2. Top cap type	4/117K/117		(C) = Topway Panel Frame
3. Top cap trim finish			(V) = Full View Panel Frame
4. Raceway knockout option	DP8CRR		Panel Base Options
5. Base raceway finish if required	7848		Open Panel Base Option:
		Note: 15" wide panels are only available with a standard base raceway or tile to floor.	For open panel base, change 'RR' to 'LL'.
	4		Tile to Floor Option:
	117		For tile to floor on one side and base raceway on the other side change 'RR' to 'FR' and add \$35 to list price.
	K	Note: Panel to panel connector specified separately: DP8PPC for all DP8 to DP8 same height and type panel connections. DP8HLC for all others.	
	117		Top Cap Options:
			No Top Cap - Deduct \$40;
			Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4
			Base Raceway Knockout Options:
			(for RR and RF base only)
			(K) = Knockouts on raceway side
			(N) = No knockouts

description	h	w	d	pattern no.	list
Base Raceway Covers	6"	15"	1/8"	DP8PBRN15	\$67.
	6"	18"	1/8"	DP8PBR()18	69.
	6"	24"	1/8"	DP8PBR()24	72.
	6"	30"	1/8"	DP8PBR()30	76.
	6"	36"	1/8"	DP8PBR()36	84.
	6"	42"	1/8"	DP8PBR()42	87.
	6"	48"	1/8"	DP8PBR()48	92.
	6"	60"	1/8"	DP8PBR()60	97.
	6"	72"	1/8"	DP8PBR()72	101.
	6"	84"	1/8"	DP8PBR()84	106.
	6"	96"	1/8"	DP8PBR()96	110.



Panels, Build-To-Spec

Dimensions listed under h w d are actual to the nearest 1/16".

Ordering Information	Order Code	Options
Base Raceway 1. Pattern Number 2. Raceway knockout option 3. Raceway trim finish	Topway Panel Frame Assembly <i>Example:</i> DP8PBRK60117 DP8PBR Base Raceway K Raceway knockouts 117 Soft Grey raceway finish	Base Raceway Knockout Options: (for RR and RF base only) (K) = Knockouts on raceway side (N) = No knockouts

Stack Frames

Dividends Horizon stack frames provide the flexibility to increase the overall height of a standard Dividends Horizon panel.

Stack frames are available in three panel heights, 14", 21" and 28" all capable of attaching to any panel height. Maximum stacking height above the "base" standard panel is 28". This can be accomplished with one 28" high stack panel or by stacking two 14" high panels on each other.

21" Stack panel frames may be attached to 42" standard Dividends Horizon panels allowing the overall panel height to be 64" or to 57" panels for an overall height of 78".

Note: If stacking is added to 78" high panels, 36" wide returns must be used for stability.

The 28" high stack panel frame is prepunched to accept tile insert support rails to provide a tiled look if required.

Note: Stack panels must have matching height stack or full height return panels to support load bearing.

Stack Frame Options

Dividends Horizon offers two stack panel frame options, which are selected depending on customer's aesthetic and functional needs.

D1 Style Stack Frame Planning

D1 style stack frames feature a D1 style painted aluminum horizontal trim at the bottom of each stack frame. D1 style stack frames mount on top of Dividends Horizon topway panel frames only. D1 style stack panels are load bearing on the first tier only.

Note: When stacking (2) D1 style stack frames, the stack frame in the first tier position must have a topway to be able to accept the second tier stack frame.

D2 Style Stack Frame Planning

D2 style stack frames feature a D2 style black recessed horizontal reveal at the bottom of each stack frame. D2 style stack frames mount on top of Dividends Horizon full view panel frames only. D2 style stack frames are load bearing on the first or second tier, and are designed to align overhead storage components hung at 64" with overhead components hung off 64" full height panels. Components hung on stack panels at 50" or 57" will not align with components hung off 50" or 57" full height panels.

D2 style stack frames also have the option to be used with tiled or monolithic tiles on one or both side of the base/stack panel assembly. See options on panel pricing page.

Note: The single and double pane window insert kits are not compatible with the D2 style stack frame. Use D1 style stack frames with single or double pane window insert kits.

Note: D2 style stack frames are not compatible with slatwall tiles.

Stack Panel Dimensions

- Widths: 18", 24", 30", 36", 42", and 48"
- Heights: 14", 21" and 28"
- Thickness: 3"

Construction

The stack panel frame is an all-welded steel construction.

- Topway: 22-gauge roll-formed steel (if applicable)
- Vertical channels: 16-gauge roll-formed steel
- Horizontal rails: 16-gauge steel tubing

Panel Trim

When stack panels are installed, the "base" standard panel's top cap is utilized by attaching to the top of the stack panel.

Panel end trim is ordered separately from the stack panel. To specify panel end trim for the end of a panel run, simply add the stack panel and base panel frame height (i.e., a 50" high base panel frame with one 14 high stack panel will require a 64" high panel end trim kit).

In a high-to-low panel-to-panel application where stack panels are used, simply deduct the panel height difference between the two panels to determine size of the high-to-low panel end trim required.

Post Trim

Post trim covers must match the overall height of the "base" standard post and stack post.

Stack Post (Same-height panels)

When two or more stack panels are connected together in a 2-way "L", 3-way "T" or a 4-way "X" condition, and all the panel heights are of the same height, a stack panel post kit may be used.

The stack post kit attaches to the top of a base universal post and is available in a 14" or 28" height and ships with connecting hardware.


Stack Post (Multi-height panels)

When stack panels are used in a high-to-low panel-to-post applications, high-to-low post trim must be ordered separately.


Note: A universal post must match the height of the tallest base standard panel being connected.

Construction

Posts are 3" square extruded aluminum construction.



Stack Frame







Stack Post (Same-Height Panels)

Stack Frames

D1 Style With External Reveal

(For Use With Topway Panels Only)




Dividends Horizon

description	h	w	d	pattern no.	with topway	full view (without topway)
28" High Stack Panel Frame Only (full view shown) 	29 1/4"	18"	3"	DP2S(T/N)F 2818	\$214.	\$256.
	29 1/4"	24"	3"	DP2S(T/N)F 2824	217.	269.
	29 1/4"	30"	3"	DP2S(T/N)F 2830	236.	285.
	29 1/4"	36"	3"	DP2S(T/N)F 2836	266.	308.
	29 1/4"	42"	3"	DP2S(T/N)F 2842	284.	334.
	29 1/4"	48"	3"	DP2S(T/N)F 2848	298.	343.
21" High Stack Panel Frame Only 	21 7/8"	18"	3"	DP2STF 2118	218.	n/a
	21 7/8"	24"	3"	DP2STF 2124	234.	n/a
	21 7/8"	30"	3"	DP2STF 2130	250.	n/a
	21 7/8"	36"	3"	DP2STF 2136	275.	n/a
	21 7/8"	42"	3"	DP2STF 2142	302.	n/a
	21 7/8"	48"	3"	DP2STF 2148	315.	n/a
14" High Stack Panel, load bearing 	14"	18"	3"	DP2 STFL1418	177.	n/a
	14"	24"	3"	DP2 STFL1424	184.	n/a
	14"	30"	3"	DP2 STFL1430	214.	n/a
	14"	36"	3"	DP2 STFL1436	235.	n/a
	14"	42"	3"	DP2 STFL1442	262.	n/a
	14"	48"	3"	DP2 STFL1448	279.	n/a
14" High Stack Panel non-load bearing 	14"	18"	3"	DP2S(T/N)F 1418	177.	214.
	14"	24"	3"	DP2S(T/N)F 1424	184.	217.
	14"	30"	3"	DP2S(T/N)F 1430	214.	236.
	14"	36"	3"	DP2S(T/N)F 1436	235.	266.
	14"	42"	3"	DP2S(T/N)F 1442	262.	284.
	14"	48"	3"	DP2S(T/N)F 1448	279.	298.

NOTE: D1 Stack Frames may be used with Topway Panels only.

Ordering Information	Order Code	Included with:	Options
Stack Panel Frame 1. Pattern Number 2. Trim Finish	Stack Panel Frame <i>Example:</i> DP2STF 1448, 113 DP1STF Pattern Number 1448 113 Dark grey paint finish Stack Panel Post <i>Example:</i> DP2ASPO 14 DP2ASPO Pattern Number 14	Stack Panel Frame Note: When stacking (2) D1 style stack frames, the stack frame in the first tier position must have a topway trough to be able to accept the second tier stack frame.	Stack Panel Frame Stack frame option: (T) = with topway (N) = without topway Note: 21" stack panel frame not available without a topway. Note: D1 Stack Frames are load bearing on first tier only.

*D2 Style With Recessed Reveal**(For Use With DP8 Full View Panels Only)*

description	w	h	d	pattern no.	list
 14" High Dividends Stack Frame	18"	14 ⁵ / ₈ "	3"	DPS7V1418()	\$269.
	24"	14 ⁵ / ₈ "	3"	DPS7V1424()	272.
	30"	14 ⁵ / ₈ "	3"	DPS7V1430()	296.
	36"	14 ⁵ / ₈ "	3"	DPS7V1436()	321.
	42"	14 ⁵ / ₈ "	3"	DPS7V1442()	334.
	48"	14 ⁵ / ₈ "	3"	DPS7V1448()	342.
	60"	14 ⁵ / ₈ "	3"	DPS7V1460()	353.
 21" High Dividends Stack Frame	18"	21 ⁷ / ₈ "	3"	DPS7V2118()	312.
	24"	21 ⁷ / ₈ "	3"	DPS7V2124()	328.
	30"	21 ⁷ / ₈ "	3"	DPS7V2130()	343.
	36"	21 ⁷ / ₈ "	3"	DPS7V2136()	366.
	42"	21 ⁷ / ₈ "	3"	DPS7V2142()	377.
	48"	21 ⁷ / ₈ "	3"	DPS7V2148()	389.
	60"	21 ⁷ / ₈ "	3"	DPS7V2160()	408.
 28" High Dividends Stack Frame	18"	29 ¹ / ₄ "	3"	DPS7V2818()	297.
	24"	29 ¹ / ₄ "	3"	DPS7V2824()	314.
	30"	29 ¹ / ₄ "	3"	DPS7V2830()	335.
	36"	29 ¹ / ₄ "	3"	DPS7V2836()	361.
	42"	29 ¹ / ₄ "	3"	DPS7V2842()	377.
	48"	29 ¹ / ₄ "	3"	DPS7V2848()	390.
	60"	29 ¹ / ₄ "	3"	DPS7V2860()	420.

NOTE: D2 Stack Frames may be used with DP8 Full View Panels only.

Ordering Information	Order Code	Included with:	Options
Stack Frames: 1. Pattern Number 2. Tile Support Configuration	Stack Panel Frame Assembly <i>Example:</i> DPS7V1418TT DPS7 Stack Panel Frame V Full View 14 Height 18 Width TT Segmented Tile Supports Both Side	Stack Panel Frame: • Stack Frame Note: Slatwall tiles, single pane and double pane window kits cannot be used with D2 stack frames. Note: D2 Stack Frames are load bearing on first and second tier.	Tile Options/Pattern Number Suffix: (TT) = Tile support located at the base of stacker to support segmented tiles on both sides of a panel. (TM) = Tile support located at the base of the stacker to support segmented tiles on one side and a monolithic tile on the other side of the panel. (MM) = Monolithic tiles on both sides of the panel.

This page intentionally left blank

Monolithic Fabric Inserts

Dividends Horizon monolithic inserts are available by component for use with panel frames or wall mount tracks for "Build-to-Spec" applications. These applications include when inserts are only required on one panel side, when a different fabric is required on each panel side, or when wall mount tracks are being used.

Tile to floor option available for worksurface height, 36", 42", 50", 57", 64" and 78" panel heights.

72", 84" and 96" wide inserts are only available with railroaded fabric (fabric runs horizontal vs. vertical). This is important to note with any fabric selection that is directional or has a pattern. If you mix the longer inserts with standard sized inserts less than 60" they will not match unless they are ordered railroaded also. Add "RR" to the end of the pattern number to signify railroaded fabric. There are size limitations for railroading the fabric tiles due to the fabric roll width. "K" fabrics are limited to 48" tile maximum height while "W" fabrics are limited to 64" tile maximum height.

Monolithic Fabric Insert Construction

Fabric laminated with adhesive, heat-cured to $\frac{7}{16}$ " thick tackable acoustical board.

Monolithic Fabric Insert Ratings

Noise Reduction Coefficient (NRC) rating: .70
Sound Transmission Class (STC) rating: 11

The materials in Dividends Horizon panels meet the flame spread and smoke generation criteria established in UL1286 safety standard for office furniture.

Monolithic Fabric Insert Attachment



Panel inserts flex to attach to the troughs in the upper and lower horizontal panel frame supports or to the bottom tile channel in a wall mount track application. Mounting clips are attached to panel inserts for connection to the vertical frame or wall mount tracks for additional support. No tools are required for insert attachment.

Note: If additional mid-span support for monolithic panel inserts is required, a beltway cable tray can be installed.

Note: Insert dimensions are nominal. Inserts are for one side only.

Note: Worksurface height monolithic tiles are to be used with worksurface height panel frames only.

Monolithic Fabric Insert



Monolithic Fabric Insert Attachment

Monolithic Fabric Insert Configurations



Worksurface Height
• One worksurface height monolithic insert



36"H Panel Frames
• One 28"H monolithic insert



42"H Panel Frames
• One 35"H monolithic insert



50"H Panel Frames
• One 42"H monolithic insert



57"H Panel Frames
• One 49"H monolithic insert



64"H Panel Frames
• One 56"H monolithic insert



78"H Panel Frames
• One 70"H monolithic insert

For Worksurface Height, 36", 42" and 50" High Panel Frames

description	w*	w	h	d	pattern no.	grade 10	20	30	40
 Worksurface Height Individual Monolithic Fabric Insert (For worksurface height Panel Frame only)	15"	14 ⁵ / ₈ "	22 ¹ / ₂ "	7 ¹ / ₁₆ "	DP1SOWH15	\$121.	\$138.	\$153.	\$167.
	18"	17 ⁵ / ₈ "	22 ¹ / ₂ "	7 ¹ / ₁₆ "	DP1SOWH18	121.	138.	153.	167.
	24"	23 ⁵ / ₈ "	22 ¹ / ₂ "	7 ¹ / ₁₆ "	DP1SOWH24	150.	171.	187.	197.
	30"	29 ⁵ / ₈ "	22 ¹ / ₂ "	7 ¹ / ₁₆ "	DP1SOWH30	164.	187.	203.	220.
	36"	35 ⁵ / ₈ "	22 ¹ / ₂ "	7 ¹ / ₁₆ "	DP1SOWH36	179.	203.	229.	240.
	42"	41 ⁵ / ₈ "	22 ¹ / ₂ "	7 ¹ / ₁₆ "	DP1SOWH42	186.	205.	231.	245.
	48"	47 ⁵ / ₈ "	22 ¹ / ₂ "	7 ¹ / ₁₆ "	DP1SOWH48	194.	220.	238.	261.
	60"	59 ⁵ / ₈ "	22 ¹ / ₂ "	7 ¹ / ₁₆ "	DP1SOWH60	221.	237.	250.	265.
	72"	71 ⁵ / ₈ "	22 ¹ / ₂ "	7 ¹ / ₁₆ "	DP1SOWH72RR*	349.	375.	392.	405.
	84"	83 ⁵ / ₈ "	22 ¹ / ₂ "	7 ¹ / ₁₆ "	DP1SOWH84RR*	363.	390.	407.	422.
	96"	95 ⁵ / ₈ "	22 ¹ / ₂ "	7 ¹ / ₁₆ "	DP1SOWH96RR*	401.	431.	450.	465.
 28" High Individual Tiled Fabric Insert	15"	14 ⁵ / ₈ "	29"	7 ¹ / ₁₆ "	DP1SO2815	135.	143.	154.	170.
	18"	17 ⁵ / ₈ "	29"	7 ¹ / ₁₆ "	DP1SO2818	135.	143.	154.	170.
	24"	23 ⁵ / ₈ "	29"	7 ¹ / ₁₆ "	DP1SO2824	153.	177.	194.	203.
	30"	29 ⁵ / ₈ "	29"	7 ¹ / ₁₆ "	DP1SO2830	169.	194.	207.	225.
	36"	35 ⁵ / ₈ "	29"	7 ¹ / ₁₆ "	DP1SO2836	183.	207.	235.	249.
	42"	42 ⁵ / ₈ "	29"	7 ¹ / ₁₆ "	DP1SO2842	191.	208.	237.	253.
	48"	47 ⁵ / ₈ "	29"	7 ¹ / ₁₆ "	DP1SO2848	198.	225.	246.	264.
	60"	59 ⁵ / ₈ "	29"	7 ¹ / ₁₆ "	DP1SO2860	235.	251.	261.	276.
	72"	71 ⁵ / ₈ "	29"	7 ¹ / ₁₆ "	DP1SO2872RR*	436.	467.	500.	535.
	84"	83 ⁵ / ₈ "	29"	7 ¹ / ₁₆ "	DP1SO2884RR*	453.	485.	519.	556.
	96"	95 ⁵ / ₈ "	29"	7 ¹ / ₁₆ "	DP1SO2896RR*	482.	516.	552.	564.
 35" High Individual Monolithic Fabric Insert (For 42"H Panel Frame)	15"	14 ⁵ / ₈ "	36 ³ / ₈ "	7 ¹ / ₁₆ "	DP1SO4215	140.	160.	175.	187.
	18"	17 ⁵ / ₈ "	36 ³ / ₈ "	7 ¹ / ₁₆ "	DP1SO4218	140.	160.	175.	187.
	24"	23 ⁵ / ₈ "	36 ³ / ₈ "	7 ¹ / ₁₆ "	DP1SO4224	160.	180.	195.	206.
	30"	29 ⁵ / ₈ "	36 ³ / ₈ "	7 ¹ / ₁₆ "	DP1SO4230	175.	203.	223.	232.
	36"	35 ⁵ / ₈ "	36 ³ / ₈ "	7 ¹ / ₁₆ "	DP1SO4236	195.	226.	234.	253.
	42"	41 ⁵ / ₈ "	36 ³ / ₈ "	7 ¹ / ₁₆ "	DP1SO4242	225.	250.	270.	286.
	48"	47 ⁵ / ₈ "	36 ³ / ₈ "	7 ¹ / ₁₆ "	DP1SO4248	234.	267.	289.	304.
	60"	59 ⁵ / ₈ "	36 ³ / ₈ "	7 ¹ / ₁₆ "	DP1SO4260	243.	264.	277.	286.
	72"	71 ⁵ / ₈ "	36 ³ / ₈ "	7 ¹ / ₁₆ "	DP1SO4272RR*	448.	480.	512.	548.
	84"	83 ⁵ / ₈ "	36 ³ / ₈ "	7 ¹ / ₁₆ "	DP1SO4284RR*	459.	491.	526.	562.
	96"	95 ⁵ / ₈ "	36 ³ / ₈ "	7 ¹ / ₁₆ "	DP1SO4296RR*	501.	526.	571.	613.

* Note: 72", 84", 96"; Inserts are only available with Railroad Fabric.

w* = nominal width

Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Monolithic Fabric Inserts	Monolithic Fabric Inserts	Monolithic Fabric Inserts	Monolithic Fabric Inserts
1. Pattern Number	<i>Example:</i> DP1 SO6442, W1077	• Attachment clips	Tile to Floor Option:
2. Fabric	DP1 Pattern Number	Note: Worksurface height monolithic tiles are to be used with worksurface height panel frames only.	To specify tile to floor for use with panel frames, add an "F" suffix to the pattern number and add \$11 to the list price.
	SO6442		Railroading fabric option:
	W1077 Element		To specify railroaded fabric, add "RR" to the suffix of the pattern number.
			Note: Tile to floor option available for Worksurface Heights, 36", 42", 50", 57", 64" and 78" panel heights.

For Worksurface Height, 36", 42" and 50" High Panel Frames

description	w*	w	h	d	pattern no.	grade 10	20	30	40
42" High Individual Monolithic Fabric Insert (For 50"H Panel Frame) 	15"	14 ⁵ / ₈ "	43 ¹¹ / ₁₆ "	7 ¹ / ₁₆ "	DP1SO5015	\$155.	\$175.	\$190.	\$203.
	18"	17 ⁵ / ₈ "	43 ¹¹ / ₁₆ "	7 ¹ / ₁₆ "	DP1SO5018	155.	175.	190.	203.
	24"	23 ⁵ / ₈ "	43 ¹¹ / ₁₆ "	7 ¹ / ₁₆ "	DP1SO5024	173.	197.	210.	227.
	30"	29 ⁵ / ₈ "	43 ¹¹ / ₁₆ "	7 ¹ / ₁₆ "	DP1SO5030	195.	226.	239.	253.
	36"	35 ⁵ / ₈ "	43 ¹¹ / ₁₆ "	7 ¹ / ₁₆ "	DP1SO5036	226.	251.	270.	288.
	42"	41 ⁵ / ₈ "	43 ¹¹ / ₁₆ "	7 ¹ / ₁₆ "	DP1SO5042	247.	283.	301.	317.
	48"	47 ⁵ / ₈ "	43 ¹¹ / ₁₆ "	7 ¹ / ₁₆ "	DP1SO5048	275.	307.	331.	348.
	60"	59 ⁵ / ₈ "	43 ¹¹ / ₁₆ "	7 ¹ / ₁₆ "	DP1SO5060	314.	340.	358.	366.
	72"	71 ⁵ / ₈ "	43 ¹¹ / ₁₆ "	7 ¹ / ₁₆ "	DP1SO5072RR*	514.	550.	573.	593.
	84"	83 ⁵ / ₈ "	43 ¹¹ / ₁₆ "	7 ¹ / ₁₆ "	DP1SO5084RR*	521.	558.	582.	601.
	96"	95 ⁵ / ₈ "	43 ¹¹ / ₁₆ "	7 ¹ / ₁₆ "	DP1SO5096RR*	530.	567.	591.	610.

* Note: 72", 84", 96"; Inserts are only available with Railroad Fabric.

w* = nominal width

Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Monolithic Fabric Inserts 1. Pattern Number 2. Fabric	Monolithic Fabric Inserts <i>Example:</i> DP1 SO6442, W1077 DP1 Pattern Number SO6442 W1077 Element	Monolithic Fabric Inserts • Attachment clips Note: Worksurface height monolithic tiles are to be used with worksurface height panel frames only.	Monolithic Fabric Inserts Tile to Floor Option: To specify tile to floor for use with panel frames, add an "F" suffix to the pattern number and add \$11 to the list price. Railroading fabric option: To specify railroading fabric, add "RR" to the suffix of the pattern number. Note: Tile to floor option available for Worksurface Heights, 36", 42", 50", 57", 64" and 78" panel heights.

Monolithic Panel Fabric Inserts

For 57", 64" and 78" High Panel Frames

Dividends Horizon

description	w*	w	h	d	pattern no.	grade 10	20	30	40
49" High Individual Monolithic Fabric Insert (For 57"H Panel Frame)	15"	14 5/8"	50 1/16"	7/16"	DP1SO5715	\$171.	\$187.	\$195.	\$201.
	18"	17 5/8"	50 1/16"	7/16"	DP1SO5718	171.	187.	195.	201.
	24"	23 5/8"	50 1/16"	7/16"	DP1SO5724	191.	204.	217.	226.
	30"	29 5/8"	50 1/16"	7/16"	DP1SO5730	221.	237.	244.	254.
	36"	35 5/8"	50 1/16"	7/16"	DP1SO5736	244.	266.	278.	289.
	42"	41 5/8"	50 1/16"	7/16"	DP1SO5742	274.	292.	305.	317.
	48"	47 5/8"	50 1/16"	7/16"	DP1SO5748	296.	316.	334.	343.
	60"	59 5/8"	50 1/16"	7/16"	DP1SO5760	341.	366.	387.	401.
56" High Individual Monolithic Fabric Insert (For 64"H Panel Frame)	15"	14 5/8"	58 1/4"	7/16"	DP1SO6415	190.	219.	233.	243.
	18"	17 5/8"	58 1/4"	7/16"	DP1SO6418	190.	219.	233.	243.
	24"	23 5/8"	58 1/4"	7/16"	DP1SO6424	205.	235.	251.	265.
	30"	29 5/8"	58 1/4"	7/16"	DP1SO6430	240.	275.	294.	308.
	36"	35 5/8"	58 1/4"	7/16"	DP1SO6436	267.	304.	325.	341.
	42"	41 5/8"	58 1/4"	7/16"	DP1SO6442	292.	329.	352.	368.
	48"	47 5/8"	58 1/4"	7/16"	DP1SO6448	318.	359.	386.	403.
	60"	59 5/8"	58 1/4"	7/16"	DP1SO6460	331.	359.	371.	389.
70" High Individual Monolithic Fabric Insert (For 78"H Panel Frame)	15"	14 5/8"	72 7/8"	7/16"	DP1SO7815	223.	235.	247.	254.
	18"	17 5/8"	72 7/8"	7/16"	DP1SO7818	223.	235.	247.	254.
	24"	23 5/8"	72 7/8"	7/16"	DP1SO7824	261.	278.	290.	301.
	30"	29 5/8"	72 7/8"	7/16"	DP1SO7830	292.	316.	331.	341.
	36"	35 5/8"	72 7/8"	7/16"	DP1SO7836	325.	351.	366.	384.
	42"	41 5/8"	72 7/8"	7/16"	DP1SO7842	363.	393.	408.	426.
	48"	47 5/8"	72 7/8"	7/16"	DP1SO7848	398.	433.	452.	464.

w* = nominal width

Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Monolithic Fabric Inserts	Monolithic Fabric Inserts	Monolithic Fabric Inserts	Monolithic Fabric Inserts
1. Pattern Number	<i>Example:</i> DP1 SO6442, W1077	• Attachment clips	Tile to Floor Option:
2. Fabric	DP1 Pattern Number	Note: Worksurface height monolithic tiles are to be used with worksurface height panel frames only.	To specify tile to floor for use with panel frames, add an "F" suffix to the pattern number and add \$11 to the list price.
	SO6442		Railroading fabric option:
	W1077 Element		To specify railroaded fabric, add "RR" to the suffix of the pattern number.
			Note: Tile to floor option available for Worksurface Heights, 36", 42", 50" 57", 64" and 78" panel heights.

Panels, Build-To-Spec

Monolithic Laminate Inserts

Dividends Horizon monolithic laminate inserts provide another material option for Dividends Horizon panels and wall mount applications. Monolithic tile sizes are for use with frames from worksurface height to 57", and widths of up to 48" in tile to raceway, open base and tile to floor applications. Monolithic laminate tiles may also be wall mounted using wall mount tracks. Monolithic laminate inserts with matching surface and edge are available in the following finishes:

- (114) Folkstone Grey
- (115) Medium Grey
- (117) Soft Grey
- (118) Bright White
- (119) Pumice
- (124) Medium Cherry
- (125) Natural Maple
- (126) Natural Cherry

- (127) Walnut
- (128) Fog
- (139) Light Ash
- (140) Warm Ash
- (141) Whitened Ash
- (142) Grey Ash
- (143) Classic Oak
- (144) Graphite Pear
- (145) Zebra
- (147) Silverwood
- (148) Smokewood
- (149) Barnwood

Legacy finishes are not available.

Monolithic Laminate Insert Construction

Surface material: laminate on front and back surface

Edge material: .5mm edgeband

Core material: particle board

Thickness: 7/16 inches

Monolithic Laminate Insert Attachment


Laminate tiles are installed on one side or both sides of a panel frame, or attach to wall mount tracks. Mounting clips are attached to laminate inserts for connection to the panel frame or vertical wall mount tracks.

Note: Insert dimensions are nominal. Insert configurations shown below are for one side only.

Note: Laminate inserts are not compatible with the slotted standard coat hook (DP2CHTP).

Note: Worksurface height monolithic tiles are to be used with worksurface height panel frames only.

Monolithic Laminate Insert



Monolithic Laminate Insert Configurations



Worksurface Height

- One worksurface height monolithic insert



36"H Panel Frames

- One 28"H monolithic insert



42"H Panel Frames

- One 35"H monolithic insert



50"H Panel Frames

- One 42"H monolithic insert



57"H Panel Frames

- One 49"H monolithic insert

Monolithic Laminate Inserts

For Worksurface Height, 36" and 42" High Panel Frames

Base Raceway or Open Base

description	w *	w	h	d	pattern no.	List
 Worksurface Height Individual Monolithic Laminate Insert Base Raceway or Open Base (For worksurface height panel frame only)	15"	14 ⁵ / ₈ "	22 ¹ / ₂ "	⁷ / ₁₆ "	DP3L1WH15	\$218.
	18"	17 ⁵ / ₈ "	22 ¹ / ₂ "	⁷ / ₁₆ "	DP3L1WH18	230.
	24"	23 ⁵ / ₈ "	22 ¹ / ₂ "	⁷ / ₁₆ "	DP3L1WH24	262.
	30"	29 ⁵ / ₈ "	22 ¹ / ₂ "	⁷ / ₁₆ "	DP3L1WH30	305.
	36"	35 ⁵ / ₈ "	22 ¹ / ₂ "	⁷ / ₁₆ "	DP3L1WH36	331.
	42"	41 ⁵ / ₈ "	22 ¹ / ₂ "	⁷ / ₁₆ "	DP3L1WH42	395.
	48"	47 ⁵ / ₈ "	22 ¹ / ₂ "	⁷ / ₁₆ "	DP3L1WH48	401.
 28" High Individual Monolithic Laminate Insert Base Raceway or Open Base (For 36"H Panel Frame)	15"	14 ⁵ / ₈ "	29"	⁷ / ₁₆ "	DP3L12815	218.
	18"	17 ⁵ / ₈ "	29"	⁷ / ₁₆ "	DP3L12818	230.
	24"	23 ⁵ / ₈ "	29"	⁷ / ₁₆ "	DP3L12824	262.
	30"	29 ⁵ / ₈ "	29"	⁷ / ₁₆ "	DP3L12830	305.
	36"	35 ⁵ / ₈ "	29"	⁷ / ₁₆ "	DP3L12836	331.
	42"	41 ⁵ / ₈ "	29"	⁷ / ₁₆ "	DP3L12842	395.
	48"	47 ⁵ / ₈ "	29"	⁷ / ₁₆ "	DP3L12848	401.
 35" High Individual Monolithic Laminate Insert Base Raceway or Open Base (For 42"H Panel Frame)	15"	14 ⁵ / ₈ "	36 ³ / ₈ "	⁷ / ₁₆ "	DP3L14215	261.
	18"	17 ⁵ / ₈ "	36 ³ / ₈ "	⁷ / ₁₆ "	DP3L14218	287.
	24"	23 ⁵ / ₈ "	36 ³ / ₈ "	⁷ / ₁₆ "	DP3L14224	325.
	30"	29 ⁵ / ₈ "	36 ³ / ₈ "	⁷ / ₁₆ "	DP3L14230	391.
	36"	35 ⁵ / ₈ "	36 ³ / ₈ "	⁷ / ₁₆ "	DP3L14236	530.
	42"	41 ⁵ / ₈ "	36 ³ / ₈ "	⁷ / ₁₆ "	DP3L14242	557.
	48"	47 ⁵ / ₈ "	36 ³ / ₈ "	⁷ / ₁₆ "	DP3L14248	561.

w* = nominal width

Dimensions listed under w h d are actual to the nearest ¹/₁₆"**Ordering Information****Monolithic Laminate Inserts**

1. Pattern Number
2. Laminate Finish
3. Edgeband Finish

Order Code**Monolithic Laminate Inserts***Example:* **DP3L14224****DP3L1** Pattern Number
4224**118** Bright White Laminate**118** Bright White Edgeband**Included with:****Monolithic Laminate Inserts**

- Attachment clips

Note: Worksurface height monolithic tiles are to be used with worksurface height panel frames only.

Monolithic Laminate Inserts

For Worksurface Height, 36" and 42" High Panel Frames

Tile To Floor

description	w *	w	d	pattern no.	List
Worksurface Height Individual Monolithic Laminate Insert Tile To Floor (For worksurface height panel frame only) 	15"	14 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L1WH15F	\$218.
	18"	17 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L1WH18F	230.
	24"	23 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L1WH24F	262.
	30"	29 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L1WH30F	305.
	36"	35 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L1WH36F	331.
	42"	41 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L1WH42F	395.
	48"	47 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L1WH48F	401.
36" High Individual Monolithic Laminate Insert Tile To Floor (For 36"H panel frame) 	15"	14 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L12815F	218.
	18"	17 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L12818F	230.
	24"	23 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L12824F	262.
	30"	29 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L12830F	305.
	36"	35 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L12836F	331.
	42"	41 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L12842F	395.
	48"	47 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L12848F	401.
42" High Individual Monolithic Laminate Insert Tile To Floor (For 42"H panel frame) 	15"	14 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L14215F	264.
	18"	17 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L14218F	305.
	24"	23 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L14224F	341.
	30"	29 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L14230F	395.
	36"	35 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L14236F	534.
	42"	41 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L14242F	561.
	48"	47 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L14248F	567.

w* = nominal width

Dimensions listed under w h d are actual to the nearest ¹/₁₆"**Ordering Information****Monolithic Laminate Inserts**

1. Pattern Number
2. Laminate Finish
3. Edgeband Finish

Order Code**Monolithic Laminate Inserts***Example:* **DP3L14224F****DP3L1** Pattern Number**4224F****118** Bright White Laminate**118** Bright White Edgeband**Included with:****Monolithic Laminate Inserts**

- Attachment clips

Note: Worksurface height monolithic tiles are to be used with worksurface height panel frames only.

Monolithic Laminate Inserts

For 50" and 57" High Panel Frames

Base Raceway or Open Base

description	w *	w	h	d	pattern no.	List
42" High Individual Monolithic Laminate Insert Base Raceway or Open Base (For 50"H Panel Frame)	15"	14 ⁵ / ₈ "	43 ¹¹ / ₁₆ "	⁷ / ₁₆ "	DP3L15015	\$266.
	18"	17 ⁵ / ₈ "	43 ¹¹ / ₁₆ "	⁷ / ₁₆ "	DP3L15018	308.
	24"	23 ⁵ / ₈ "	43 ¹¹ / ₁₆ "	⁷ / ₁₆ "	DP3L15024	343.
	30"	29 ⁵ / ₈ "	43 ¹¹ / ₁₆ "	⁷ / ₁₆ "	DP3L15030	398.
	36"	35 ⁵ / ₈ "	43 ¹¹ / ₁₆ "	⁷ / ₁₆ "	DP3L15036	536.
	42"	41 ⁵ / ₈ "	43 ¹¹ / ₁₆ "	⁷ / ₁₆ "	DP3L15042	564.
	48"	47 ⁵ / ₈ "	43 ¹¹ / ₁₆ "	⁷ / ₁₆ "	DP3L15048	569.
49" High Individual Monolithic Laminate Insert Base Raceway or Open Base (For 57"H Panel Frame)	15"	14 ⁵ / ₈ "	50 ¹ / ₁₆ "	⁷ / ₁₆ "	DP3L15715	311.
	18"	17 ⁵ / ₈ "	50 ¹ / ₁₆ "	⁷ / ₁₆ "	DP3L15718	335.
	24"	23 ⁵ / ₈ "	50 ¹ / ₁₆ "	⁷ / ₁₆ "	DP3L15724	399.
	30"	29 ⁵ / ₈ "	50 ¹ / ₁₆ "	⁷ / ₁₆ "	DP3L15730	501.
	36"	35 ⁵ / ₈ "	50 ¹ / ₁₆ "	⁷ / ₁₆ "	DP3L15736	544.
	42"	41 ⁵ / ₈ "	50 ¹ / ₁₆ "	⁷ / ₁₆ "	DP3L15742	664.
	48"	47 ⁵ / ₈ "	50 ¹ / ₁₆ "	⁷ / ₁₆ "	DP3L15748	670.

w* = nominal width

Dimensions listed under w h d are actual to the nearest ¹/₁₆"**Ordering Information****Monolithic Laminate Inserts**

1. Pattern Number
2. Laminate Finish
3. Edgeband Finish

Order Code**Monolithic Laminate Inserts***Example:* **DP3L15024****DP3L1** Pattern Number**118** Bright White Laminate**118** Bright White Edgeband**Included with:****Monolithic Laminate Inserts**

- Attachment clips

Note: Worksurface height monolithic tiles are to be used with worksurface height panel frames only.

Monolithic Laminate Inserts

For 50" and 57" High Panel Frames

Tile To Floor

description	w *	w	d	pattern no.	List
50" High Individual Monolithic Laminate Insert Tile To Floor (For 50"H panel frame) 	15"	14 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L15015F	\$310.
	18"	17 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L15018F	332.
	24"	23 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L15024F	397.
	30"	29 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L15030F	498.
	36"	35 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L15036F	540.
	42"	41 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L15042F	661.
	48"	47 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L15048F	667.
57" High Individual Monolithic Laminate Insert Tile To Floor (for 57"H panel frame) 	15"	14 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L15715F	316.
	18"	17 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L15718F	339.
	24"	23 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L15724F	403.
	30"	29 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L15730F	505.
	36"	35 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L15736F	548.
	42"	41 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L15742F	668.
	48"	47 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L15748F	673.

w* = nominal width

Dimensions listed under w h d are actual to the nearest ¹/₁₆"**Ordering Information****Monolithic Laminate Inserts**

1. Pattern Number
2. Laminate Finish
3. Edgeband Finish

Order Code**Monolithic Laminate Inserts***Example:* **DP3L15024F****DP3L1** Pattern Number**5024F****118** Bright White Laminate**118** Bright White Edgeband**Included with:****Monolithic Laminate Inserts**

- Attachment clips

Note: Worksurface height monolithic tiles are to be used with worksurface height panel frames only.

This page intentionally left blank

Tiled Inserts

Dividends Horizon tiled inserts are available by component for use with panel frames or wall mount tracks for "Build-to-Spec" applications. These applications include when inserts are only required on one panel side, when fabrics are mixed tile-to-tile or side-to-side, or when wall mount tracks are being used.

Tiled inserts are also included in "Preconfigured" tiled panel assemblies. For railroaded fabric, running horizontally vs. vertically, add "RR" to the end of the pattern number.

Tiled Insert Construction

Fabric laminated with web adhesive, heat-cured to 7/16" thick tackable acoustical board.

Tiled Insert Supports

All Dividends Horizon panel frames and wall mount tracks are pre-punched to accept tiled panel insert supports which span horizontally across the panel frame.

Tiled panel insert supports are mounted above each tiled insert with the exception of the uppermost insert which attaches to the upper panel frame. D1 style insert supports are trim finish to match top caps and raceway covers.

D2 Tile Support Mounting Brackets

D2 tile supports require the use of D2 tile support mounting brackets. One pair of mounting brackets can be used to attach D2 tile supports on one or both sides of a panel at the installed height.


Tiled Insert Attachment

Tiled inserts attach to the troughs in the horizontal panel frame and tiled insert supports or to the bottom tile channel in a wall mount track application. Mounting clips are attached to inserts for connection to the vertical frame or wall mount tracks for additional support. No tools are required for insert attachment.

Note: When attaching cantilevers to tiled panels, they can only be hung at the 28 1/2" worksurface height.

Note: Insert dimensions are nominal. Inserts and tiled supports are for one side only.


Note: Overheads can only be attached to the uppermost position of tiled panels. On 78" H panels the overhead may be positioned on the 4th or 5th tile location from the bottom, but not both locations of a single panel.




Tiled Insert Configurations

	36"H Panels • Two 14"H tiled inserts • One tile support		64"H Panels • Four 14"H tiled inserts • Three tile supports
	42"H Panels • One 7"H tiled insert • Two 14"H tiled inserts • Two tile supports		78"H Panels • Five 14"H tiled inserts • Four tile supports
	57"H Panels • One 7"H tiled insert • Three 14"H tiled inserts • Three tile supports		

Tiled Insert Attachment (D1 Style)



Tiled Insert Attachment (D2 Style)



Tiled Fabric Inserts 7", 10" and 14" High

Dividends Horizon

description	w *	w	h	d	pattern no.	grade 10	20	30	40
7" High Individual Tiled Fabric Insert 	15"	14 ³ / ₈ "	7 ³ / ₁₆ "	⁷ / ₁₆ "	DP1SO715	\$69.	\$81.	\$98.	\$104.
	18"	17 ³ / ₈ "	7 ³ / ₁₆ "	⁷ / ₁₆ "	DP1SO718	69.	81.	98.	104.
	24"	23 ³ / ₈ "	7 ³ / ₁₆ "	⁷ / ₁₆ "	DP1SO724	73.	94.	101.	110.
	30"	29 ³ / ₈ "	7 ³ / ₁₆ "	⁷ / ₁₆ "	DP1SO730	84.	104.	113.	120.
	36"	35 ³ / ₈ "	7 ³ / ₁₆ "	⁷ / ₁₆ "	DP1SO736	98.	113.	120.	126.
	42"	41 ³ / ₈ "	7 ³ / ₁₆ "	⁷ / ₁₆ "	DP1SO742	104.	119.	130.	135.
	48"	47 ³ / ₈ "	7 ³ / ₁₆ "	⁷ / ₁₆ "	DP1SO748	111.	124.	135.	157.
	60"	59 ³ / ₈ "	7 ³ / ₁₆ "	⁷ / ₁₆ "	DP1SO760	120.	132.	136.	141.
10" High Individual Tiled Fabric Insert 	15"	14 ³ / ₈ "	10 ⁷ / ₈ "	⁷ / ₁₆ "	DP1SO1015	89.	100.	106.	109.
	18"	17 ³ / ₈ "	10 ⁷ / ₈ "	⁷ / ₁₆ "	DP1SO1018	89.	100.	106.	109.
	24"	23 ³ / ₈ "	10 ⁷ / ₈ "	⁷ / ₁₆ "	DP1SO1024	97.	107.	110.	117.
	30"	29 ³ / ₈ "	10 ⁷ / ₈ "	⁷ / ₁₆ "	DP1SO1030	100.	109.	116.	121.
	36"	35 ³ / ₈ "	10 ⁷ / ₈ "	⁷ / ₁₆ "	DP1SO1036	106.	116.	125.	144.
	42"	41 ³ / ₈ "	10 ⁷ / ₈ "	⁷ / ₁₆ "	DP1SO1042	109.	121.	141.	148.
	48"	47 ³ / ₈ "	10 ⁷ / ₈ "	⁷ / ₁₆ "	DP1SO1048	116.	134.	148.	152.
	60"	59 ³ / ₈ "	10 ⁷ / ₈ "	⁷ / ₁₆ "	DP1SO1060	121.	135.	142.	146.
14" High Individual Tiled Fabric Insert 	15"	14 ³ / ₈ "	14 ³ / ₁₆ "	⁷ / ₁₆ "	DP1SO1415	108.	120.	129.	134.
	18"	17 ³ / ₈ "	14 ³ / ₁₆ "	⁷ / ₁₆ "	DP1SO1418	108.	120.	129.	134.
	24"	23 ³ / ₈ "	14 ³ / ₁₆ "	⁷ / ₁₆ "	DP1SO1424	118.	132.	135.	144.
	30"	29 ³ / ₈ "	14 ³ / ₁₆ "	⁷ / ₁₆ "	DP1SO1430	120.	134.	141.	150.
	36"	35 ³ / ₈ "	14 ³ / ₁₆ "	⁷ / ₁₆ "	DP1SO1436	129.	141.	153.	174.
	42"	41 ³ / ₈ "	14 ³ / ₁₆ "	⁷ / ₁₆ "	DP1SO1442	134.	150.	171.	179.
	48"	47 ³ / ₈ "	14 ³ / ₁₆ "	⁷ / ₁₆ "	DP1SO1448	141.	164.	179.	186.
	60"	59 ³ / ₈ "	14 ³ / ₁₆ "	⁷ / ₁₆ "	DP1SO1460	150.	166.	172.	178.



w* = nominal width

Dimensions listed under w h d are actual to the nearest ¹/₁₆"

Ordering Information	Order Code	Included with:	Options
Tiled Inserts	Tiled Inserts	Tiled Inserts	Tiled Inserts
1. Pattern Number	<i>Example:</i> DP1 SO1436, W234-5	• Attachment clips	Tile to Floor Option:
2. Fabric	DP1 Pattern Number	Note: Tiled insert supports must be ordered separately (see opposite page for quantities required).	To specify tile to floor for use with panel frames, add an "F" suffix to the pattern number and add \$11 to the list price.
	SO1436		Railroading fabric option:
	W234-5 Peano Sand fabric		To specify railroaded fabric, add "RR" to the suffix of the pattern number.
			Note: Tile to floor option available for 14" and 28" High inserts.

Tiled Fabric Inserts 21" and 28" High

Dividends Horizon

description	w *	w	h	d	pattern no.	grade 10	20	30	40
21" High Individual Tiled Fabric Insert 	15"	14 ⁵ / ₈ "	21 ³ / ₁₆ "	⁷ / ₁₆ "	DP1SO2115	\$129.	\$149.	\$162.	\$177.
	18"	17 ⁵ / ₈ "	21 ³ / ₁₆ "	⁷ / ₁₆ "	DP1SO2118	129.	149.	162.	177.
	24"	23 ⁵ / ₈ "	21 ³ / ₁₆ "	⁷ / ₁₆ "	DP1SO2124	159.	185.	201.	210.
	30"	29 ⁵ / ₈ "	21 ³ / ₁₆ "	⁷ / ₁₆ "	DP1SO2130	172.	201.	215.	232.
	36"	35 ⁵ / ₈ "	21 ³ / ₁₆ "	⁷ / ₁₆ "	DP1SO2136	190.	215.	242.	259.
	42"	41 ⁵ / ₈ "	21 ³ / ₁₆ "	⁷ / ₁₆ "	DP1SO2142	197.	218.	246.	263.
	48"	47 ⁵ / ₈ "	21 ³ / ₁₆ "	⁷ / ₁₆ "	DP1SO2148	207.	232.	257.	278.
	60"	59 ⁵ / ₈ "	21 ³ / ₁₆ "	⁷ / ₁₆ "	DP1SO2160	227.	246.	258.	264.
28" High Individual Tiled Fabric Insert 	15"	14 ⁵ / ₈ "	29"	⁷ / ₁₆ "	DP1SO2815	135.	143.	154.	170.
	18"	17 ⁵ / ₈ "	29"	⁷ / ₁₆ "	DP1SO2818	135.	143.	154.	170.
	24"	23 ⁵ / ₈ "	29"	⁷ / ₁₆ "	DP1SO2824	153.	177.	194.	203.
	30"	29 ⁵ / ₈ "	29"	⁷ / ₁₆ "	DP1SO2830	169.	194.	207.	225.
	36"	35 ⁵ / ₈ "	29"	⁷ / ₁₆ "	DP1SO2836	183.	207.	235.	249.
	42"	42 ⁵ / ₈ "	29"	⁷ / ₁₆ "	DP1SO2842	191.	208.	237.	253.
	48"	47 ⁵ / ₈ "	29"	⁷ / ₁₆ "	DP1SO2848	198.	225.	246.	264.
	60"	59 ⁵ / ₈ "	29"	⁷ / ₁₆ "	DP1SO2860	235.	251.	261.	276.

w* = nominal width




Dimensions listed under w h d are actual to the nearest 1/16

Ordering Information	Order Code	Included With:	Options
Tiled Inserts	Tiled Inserts	Tiled Inserts	Tiled Inserts
1. Pattern Number	<i>Example:</i> DP1 SO1436, W234-5	• Attachment clips	Tile to Floor Option:
2. Fabric	DP1 Pattern Number	Note: Tiled insert supports must be ordered separately (see opposite page for quantities required).	To specify tile to floor for use with panel frames, add an "F" suffix to the pattern number and add \$11 to the list price.
	SO1436		Railroading fabric option:
	W234-5 Peano Sand fabric		To specify railroaded fabric, add "RR" to the suffix of the pattern number.
			Note: Tile to floor option available for 14" and 28" High inserts.

Tiled Fabric Inserts

Tile Supports

Dividends Horizon

description	w *	d	pattern no.	list
 D1 Tile Support/ External Reveal	15"	5/8"	DP1SOS15	\$39.
	18"	5/8"	DP1SOS18	39.
	24"	5/8"	DP1SOS24	40.
	30"	5/8"	DP1SOS30	45.
	36"	5/8"	DP1SOS36	46.
	42"	5/8"	DP1SOS42	48.
	48"	5/8"	DP1SOS48	48.
	60"	5/8"	DP1SOS60	52.
 D2 Tile Support/ Recessed Reveal	15"		DP2SOS15	35.
	18"		DP2SOS18	35.
	24"		DP2SOS24	36.
	30"		DP2SOS30	39.
	36"		DP2SOS36	40.
	42"		DP2SOS42	45.
	48"		DP2SOS48	45.
	60"		DP2SOS60	48.
 D2 Tile Support Mounting Brackets (pair)			DP2SOSC	0.

Panels, Build-To-Spec

w* = nominal width
Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
D1 Tile Support / External Reveal 1. Pattern Number 2. Trim Finish	D1 Tile Support / External Reveal Supports <i>Example:</i> DP1 SOS18, 117	Note: D2 insert supports require mounting brackets.	Tiled Insert Supports
D2 Tile Support / Recessed Reveal 1. Pattern Number	DP1 Pattern Number SOS18		
	117 Soft Grey trim finish		

Tiled Laminate Inserts

Dividends Horizon tiled laminate inserts provide another material option for Dividends Horizon panels and wall mount applications. Tiled sizes are for use with frames from 36" to 78" high, and widths of up to 48" in tile to raceway, open base and tile to floor applications. Tiled laminate inserts may also be wall mounted using wall mount tracks. Tiled laminate inserts with matching surface and edge are available in the following finishes:

- (114) Folkstone Grey
- (115) Medium Grey
- (117) Soft Grey
- (118) Bright White
- (119) Pumice
- (124) Medium Cherry
- (125) Natural Maple
- (126) Natural Cherry
- (127) Walnut
- (128) Fog
- (139) Light Ash
- (140) Warm Ash
- (141) Whitened Ash

- (142) Grey Ash
- (143) Classic Oak
- (144) Graphite Pear
- (145) Zebra
- (147) Silverwood
- (148) Smokewood
- (149) Barnwood

Legacy finishes are not available.

Tiled Laminate Insert Construction

- Surface material: laminate on front and back surface
- Edge material: .5 mm edgeband
- Core material: particle board
- Thickness: 7/16"

Tiled Insert Supports

All Dividends Horizon panel frames are pre-punched to accept tiled panel insert supports, which span horizontally across the panel frame. Tiled panel insert supports are mounted above each tiled insert with the exception of the uppermost insert which attaches to the upper panel frame. D1 style insert supports are trim finish to match top caps and raceway covers.

D2 Tile Support Mounting Brackets


D2 tile supports require the use of D2 tile support mounting brackets. One pair of mounting brackets can be used to attach D2 tile supports on one or both sides of a panel at the installed height.

Tiled Laminate Insert Attachment

Laminate tiles are installed on one side or both sides of a panel frame or attached to wall mount tracks. Mounting clips are attached to laminate inserts for connection to the panel frame or vertical wall mount tracks.

Tiled Laminate Insert Planning Guidelines

Insert dimensions are nominal. Insert configurations shown below are for one side only. Laminate inserts are not compatible with the slotted standard coat hook (DP2CHTP). When attaching cantilevers to tiled panels, they can only be hung at 28-1/2" worksurface height. Overheads can only be attached to the uppermost position of tiled panels. On 78"-high panels the overhead may be positioned on the 4th or 5th tile location from the bottom, but not both locations of a single panel.




Tiled Insert Configurations




- 36\"H Panels**
- Two 14\"H tiled inserts
 - One tile support



- 42\"H Panels**
- One 7\"H tiled insert
 - Two 14\"H tiled inserts
 - Two tile supports



- 50\"H Panels**
- Three 14\"H tiled inserts
 - Two tile supports



- 57\"H Panels**
- One 7\"H tiled insert
 - Three 14\"H tiled inserts
 - Three tile supports



- 64\"H Panels**
- Four 14\"H tiled inserts
 - Three tile supports



- 78\"H Panels**
- Five 14\"H tiled inserts
 - Four tile supports

Tiled Laminate Inserts

7", 10", 14", 21" and 28" High

Base Raceway or Open Base

description	w*	w	h	d	pattern no.	list
7" High Individual Tiled Laminate Insert Base Raceway or Open Base 	15"	14 ⁵ / ₈ "	7 ³ / ₁₆ "	⁷ / ₁₆ "	DP3L10715	\$144.
	18"	17 ⁵ / ₈ "	7 ³ / ₁₆ "	⁷ / ₁₆ "	DP3L10718	146.
	24"	23 ⁵ / ₈ "	7 ³ / ₁₆ "	⁷ / ₁₆ "	DP3L10724	152.
	30"	29 ⁵ / ₈ "	7 ³ / ₁₆ "	⁷ / ₁₆ "	DP3L10730	157.
	36"	35 ⁵ / ₈ "	7 ³ / ₁₆ "	⁷ / ₁₆ "	DP3L10736	178.
	42"	41 ⁵ / ₈ "	7 ³ / ₁₆ "	⁷ / ₁₆ "	DP3L10742	183.
	48"	47 ⁵ / ₈ "	7 ³ / ₁₆ "	⁷ / ₁₆ "	DP3L10748	189.
10" High Individual Tiled Laminate Insert Base Raceway or Open Base 	15"	14 ⁵ / ₈ "	10 ³ / ₁₆ "	⁷ / ₁₆ "	DP3L11015	148.
	18"	17 ⁵ / ₈ "	10 ³ / ₁₆ "	⁷ / ₁₆ "	DP3L11018	152.
	24"	23 ⁵ / ₈ "	10 ³ / ₁₆ "	⁷ / ₁₆ "	DP3L11024	157.
	30"	29 ⁵ / ₈ "	10 ³ / ₁₆ "	⁷ / ₁₆ "	DP3L11030	173.
	36"	35 ⁵ / ₈ "	10 ³ / ₁₆ "	⁷ / ₁₆ "	DP3L11036	197.
	42"	41 ⁵ / ₈ "	10 ³ / ₁₆ "	⁷ / ₁₆ "	DP3L11042	204.
	48"	47 ⁵ / ₈ "	10 ³ / ₁₆ "	⁷ / ₁₆ "	DP3L11048	210.
14" High Individual Tiled Laminate Insert Base Raceway or Open Base 	15"	14 ⁵ / ₈ "	14 ³ / ₁₆ "	⁷ / ₁₆ "	DP3L11415	152.
	18"	17 ⁵ / ₈ "	14 ³ / ₁₆ "	⁷ / ₁₆ "	DP3L11418	154.
	24"	23 ⁵ / ₈ "	14 ³ / ₁₆ "	⁷ / ₁₆ "	DP3L11424	169.
	30"	29 ⁵ / ₈ "	14 ³ / ₁₆ "	⁷ / ₁₆ "	DP3L11430	187.
	36"	35 ⁵ / ₈ "	14 ³ / ₁₆ "	⁷ / ₁₆ "	DP3L11436	220.
	42"	41 ⁵ / ₈ "	14 ³ / ₁₆ "	⁷ / ₁₆ "	DP3L11442	226.
	48"	47 ⁵ / ₈ "	14 ³ / ₁₆ "	⁷ / ₁₆ "	DP3L11448	230.
21" High Individual Tiled Laminate Insert Base Raceway or Open Base 	15"	14 ⁵ / ₈ "	21 ³ / ₁₆ "	⁷ / ₁₆ "	DP3L12115	167.
	18"	17 ⁵ / ₈ "	21 ³ / ₁₆ "	⁷ / ₁₆ "	DP3L12118	183.
	24"	23 ⁵ / ₈ "	21 ³ / ₁₆ "	⁷ / ₁₆ "	DP3L12124	217.
	30"	29 ⁵ / ₈ "	21 ³ / ₁₆ "	⁷ / ₁₆ "	DP3L12130	221.
	36"	35 ⁵ / ₈ "	21 ³ / ₁₆ "	⁷ / ₁₆ "	DP3L12136	316.
	42"	41 ⁵ / ₈ "	21 ³ / ₁₆ "	⁷ / ₁₆ "	DP3L12142	320.
	48"	47 ⁵ / ₈ "	21 ³ / ₁₆ "	⁷ / ₁₆ "	DP3L12148	325.
28" High Individual Tiled Laminate Insert Base Raceway or Open Base 	15"	14 ⁵ / ₈ "	29"	⁷ / ₁₆ "	DP3L12815	218.
	18"	17 ⁵ / ₈ "	29"	⁷ / ₁₆ "	DP3L12818	230.
	24"	23 ⁵ / ₈ "	29"	⁷ / ₁₆ "	DP3L12824	262.
	30"	29 ⁵ / ₈ "	29"	⁷ / ₁₆ "	DP3L12830	305.
	36"	35 ⁵ / ₈ "	29"	⁷ / ₁₆ "	DP3L12836	331.
	42"	41 ⁵ / ₈ "	29"	⁷ / ₁₆ "	DP3L12842	395.
	48"	47 ⁵ / ₈ "	29"	⁷ / ₁₆ "	DP3L12848	401.

w* = nominal width

Dimensions listed under w h d are actual to the nearest ¹/₁₆"**Ordering Information****Tiled Laminate Inserts**

1. Pattern Number
2. Laminate Finish
3. Edgeband Finish

Order Code**Tiled Laminate Inserts***Example:* **DP3L10724****DP3L1** Pattern Number**0724****118** Bright White Laminate**118** Bright White Edgeband**Included with:****Tiled Laminate Inserts**

- Attachment clips


Note: Tiled insert supports must be ordered separately (see opposite page for quantities required)

Tiled Laminate Inserts

14" and 28" High

Tile To Floor

Dividends Horizon

description	w*	w	d	pattern no.	list
14" High Individual Tiled Laminate Insert Tile to Floor 	15"	14 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L11415F	\$160.
	18"	17 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L11418F	170.
	24"	23 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L11424F	186.
	30"	29 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L11430F	208.
	36"	35 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L11436F	247.
	42"	41 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L11442F	265.
	48"	47 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L11448F	270.
28" High Individual Tiled Laminate Insert Tile to Floor 	15"	14 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L12815F	218.
	18"	17 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L12818F	230.
	24"	23 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L12824F	262.
	30"	29 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L12830F	305.
	36"	35 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L12836F	331.
	42"	41 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L12842F	395.
	48"	47 ⁵ / ₈ "	⁷ / ₁₆ "	DP3L12848F	401.

w* = nominal width

Dimensions listed under w h d are actual to the nearest ¹/₁₆"

Ordering Information

Tiled Laminate Inserts

1. Pattern Number
2. Laminate Finish
3. Edgeband Finish

Order Code

Tiled Laminate Inserts

Example: **DP3L11424F**

DP3L1 Pattern Number
1424F

118 Bright White Laminate

118 Bright White Edgeband

Included with:

Tiled Laminate Inserts

- Attachment clips

Note: Tiled insert supports must be ordered separately (see opposite page for quantities required)

This page intentionally left blank

Beltway Inserts

Lower Inserts

Specifications

Dividends Horizon

Beltway Inserts

Dividends Horizon beltway panel inserts are available by component for use with panel frames for "build-to-spec" applications. These applications include when inserts are only required on one panel side and when fabrics or materials are mixed insert-to-insert or side-to-side.

Beltway inserts are also included in "Preconfigured" beltway panel assemblies.

Beltway Insert Construction

Fabric inserts are constructed of fabric laminated with web adhesive and heat-cured to $\frac{7}{16}$ " thick acoustical board. Laminate inserts are constructed of a particle laminate on the front and back. Steel tiles are constructed of formed steel that is painted in any Knoll core paint finish. 24" high inserts are to only be used below beltways.

Beltway Insert Attachment

Beltway panel inserts attach to the troughs in the upper and lower horizontal frame supports and beltway insert supports. Beltway top and bottom panel inserts require beltway cover and insert supports. Mounting clips attach to panel inserts and connect to vertical frame for additional support. No tools are required for insert attachment.

Note: Slatwall tiles may not be specified or installed with beltway.

Beltway Cover

Beltway covers snap into the beltway supports and are constructed of painted steel. Beltway covers include knockouts with covers for duplex receptacles centered 12" from each panel end (except for 18 and 24" wide). A single communications knockout cover in the center of the beltway is included on all beltways except for 30" wide. Electrical knockouts are the same size as communications

knockouts and can be used for communications cables and data ports if terminal blocks are not installed within the beltway.

Beltway covers and insert supports can be installed on one or both sides of panels. Beltway cover and insert supports require top and bottom beltway panel inserts.

Beltway Cover Construction

Steel painted in knoll core paint colors.

Electrical


Beltways 30" and wider accept two duplex receptacles per beltway. 18" and 24" wide beltways provide pass-through electrical only. All electrical components are ordered separately and must be field-installed.

One-Sided Beltway Panel


Beltway panels are available with one beltway per panel or per panel side.

Note: Insert dimensions are nominal. Inserts and beltway cover/supports are for one side only.


Beltway Insert Locations



Beltway Insert Locations




Beltway Insert Attachment



Beltway Insert Configurations


42"H Panels

- One 7"H upper insert
- One 4"H beltway cover and insert support
- One 24"H lower insert




50"H Panels

- One 14"H upper panel insert
- One 4"H beltway cover and insert support
- One 24"H lower insert




57"H Panels

- One 21"H upper insert
- One 4"H beltway cover and insert support
- One 24"H lower insert




78"H Panels

- One 50"H upper insert
- One 4"H beltway cover and insert support
- One 24"H lower panel insert



64"H Panels

- One 28"H upper insert
- One 4"H beltway cover and insert support
- One 24"H lower insert





Beltway Inserts

Lower Fabric Inserts

Beltway Cover and Insert Supports

Dividends Horizon

description	w*	w	h	d	pattern no.	grade 10	20	30	40
 8" High Fabric Beltway Lower Insert, (For Worksurface Height Below Worksurface Beltway Panels)	18"	17 5/8"	7 7/8"	7/16"	DP1SO0818	\$63.	\$73.	\$89.	\$94.
	24"	23 3/8"	7 7/8"	7/16"	DP1SO0824	66.	86.	92.	101.
	30"	29 3/8"	7 7/8"	7/16"	DP1SO0830	76.	94.	104.	110.
	36"	35 3/8"	7 7/8"	7/16"	DP1SO0836	89.	104.	110.	116.
	42"	41 5/8"	7 7/8"	7/16"	DP1SO0842	94.	109.	118.	122.
	48"	47 5/8"	7 7/8"	7/16"	DP1SO0848	102.	113.	122.	143.
	60"	59 5/8"	7 7/8"	7/16"	DP1SO0860	110.	119.	123.	129.
 24" High Fabric Beltway Lower Insert, (For Beltway Panels only)	18"	17 5/8"	25 1/2"	7/16"	DP1SO2418	119.	136.	149.	162.
	24"	23 3/8"	25 1/2"	7/16"	DP1SO2424	147.	168.	183.	194.
	30"	29 3/8"	25 1/2"	7/16"	DP1SO2430	160.	183.	199.	216.
	36"	35 3/8"	25 1/2"	7/16"	DP1SO2436	175.	199.	225.	235.
	42"	41 5/8"	25 1/2"	7/16"	DP1SO2442	182.	202.	227.	240.
	48"	47 5/8"	25 1/2"	7/16"	DP1SO2448	190.	216.	233.	255.
	60"	59 5/8"	25 1/2"	7/16"	DP1SO2460	217.	232.	245.	261.
 Beltway Cover and Insert Supports	18"			7/16"	DP8BC18K	131.	n/a	n/a	n/a
	24"			7/16"	DP8BC24K	149.	n/a	n/a	n/a
	30"			7/16"	DP8BC30K	166.	n/a	n/a	n/a
	36"			7/16"	DP8BC36K	182.	n/a	n/a	n/a
	42"			7/16"	DP8BC42K	202.	n/a	n/a	n/a
	48"			7/16"	DP8BC48K	227.	n/a	n/a	n/a
	60"			7/16"	DP8BC60K	262.	n/a	n/a	n/a
 Beltway Knockout Replacement Cover for Electrical and Data	Pkg of 10				DE2KC10	92.	n/a	n/a	n/a

w* = nominal width

Dimensions listed under w h d are actual to the nearest 1/16"


Ordering Information	Order Code	Included with:	Options
Beltway Cover/Insert Supports 1. Pattern Number 2. Beltway Cover/Trim Finish Beltway Inserts 1. Pattern Number 2. Fabric	Beltway Inserts <i>Example:</i> DP1 SO2442, W257-6 DP1 Pattern Number SO2442 W257-6 Solid Crepe Blue Pine fabric Beltway Cover/Insert Supports <i>Example:</i> DP2 BC42K, 117 DP2 Pattern Number BC42K 117 Soft Grey Beltway Cover Trim	Beltway Inserts Beltway Cover/Insert Supports - Individual beltway cover - Insert supports (top and bottom rail) - Attachment hardware - Beltway knockout covers Note: 24"H inserts are to only be used below beltways.	Beltway Panel Inserts Beltway Cover/Insert Supports Beltway cover has a smooth finish Title to Floor Option: To specify tile to floor, add an "F" suffix to the pattern number and add \$11 to the list price. Note: Tile to floor option available for 24" high inserts.

Panels, Build-To-Spec

Beltway Inserts
Lower Fabric Inserts
Beltway Cover and Insert Supports

Dividends Horizon

description	w*	w	h	d	pattern no.	grade 10	20	30	40
10" High Fabric Beltway Lower Insert, (For Below Worksurface Beltway Panels with Tile to Floor)	18"	17 ⁵ / ₈ "	15 ⁵ / ₈ "	7 ¹ / ₁₆ "	DP1SO1018F	\$82.	\$90.	\$96.	\$100.
	24"	23 ⁵ / ₈ "	15 ⁵ / ₈ "	7 ¹ / ₁₆ "	DP1SO1024F	88.	97.	101.	107.
	30"	29 ⁵ / ₈ "	15 ⁵ / ₈ "	7 ¹ / ₁₆ "	DP1SO1030F	90.	100.	106.	111.
	36"	35 ⁵ / ₈ "	15 ⁵ / ₈ "	7 ¹ / ₁₆ "	DP1SO1036F	96.	104.	114.	132.
	42"	41 ⁵ / ₈ "	15 ⁵ / ₈ "	7 ¹ / ₁₆ "	DP1SO1042F	100.	111.	129.	135.
	48"	47 ⁵ / ₈ "	15 ⁵ / ₈ "	7 ¹ / ₁₆ "	DP1SO1048F	106.	121.	135.	138.
	60"	59 ⁵ / ₈ "	15 ⁵ / ₈ "	7 ¹ / ₁₆ "	DP1SO1060F	111.	122.	138.	145.



w* = nominal width




Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Beltway Cover/Insert Supports 1. Pattern Number 2. Beltway Cover/Trim Finish	Beltway Inserts <i>Example:</i> DP1 SO2442, W257-6 DP1 Pattern Number SO2442 W257-6 Solid Crepe Blue Pine fabric	Beltway Inserts Beltway Cover/Insert Supports - Individual beltway cover - Insert supports (top and bottom rail) - Attachment hardware - Beltway knockout covers Note: 24"H inserts are to only be used below beltways.	Beltway Panel Inserts Beltway Cover/Insert Supports Beltway cover has a smooth finish Tile to Floor Option: To specify tile to floor, add an "F" suffix to the pattern number and add \$11 to the list price. Note: Tile to floor option available for 24" high inserts.
Beltway Inserts 1. Pattern Number 2. Fabric	Beltway Cover/Insert Supports <i>Example:</i> DP2 BC42K, 117 DP2 Pattern Number BC42K 117 Soft Grey Beltway Cover Trim		

Beltway Inserts

Lower Steel Inserts

Dividends Horizon

description	w*	w	h	d	pattern no.	1 pack P1	1 pack P2	1 pack P3	2 pack P1	2 pack P2	2 pack P3
24" High Solid Steel Insert 	18"	17 5/8"	25 1/2"	7/16"	DP3SS()2418	\$138.	\$166.	\$177.	\$239.	\$280.	\$306.
	24"	23 5/8"	25 1/2"	7/16"	DP3SS()2424	171.	196.	214.	300.	342.	372.
	30"	29 5/8"	25 1/2"	7/16"	DP3SS()2430	181.	211.	231.	317.	372.	403.
	36"	35 5/8"	25 1/2"	7/16"	DP3SS()2436	204.	232.	258.	355.	403.	450.
	42"	41 5/8"	25 1/2"	7/16"	DP3SS()2442	210.	233.	259.	370.	410.	455.
	48"	47 5/8"	25 1/2"	7/16"	DP3SS()2448	217.	247.	271.	380.	437.	477.
24" High Perforated Steel Insert 	18"	17 5/8"	25 1/2"	7/16"	DP3PSB()2418	207.	246.	270.	360.	422.	459.
	24"	23 5/8"	25 1/2"	7/16"	DP3PSB()2424	256.	293.	319.	450.	513.	562.
	30"	29 5/8"	25 1/2"	7/16"	DP3PSB()2430	276.	317.	344.	480.	562.	606.
	36"	35 5/8"	25 1/2"	7/16"	DP3PSB()2436	307.	347.	387.	532.	606.	671.
	42"	41 5/8"	25 1/2"	7/16"	DP3PSB()2442	316.	350.	388.	555.	616.	681.
	48"	47 5/8"	25 1/2"	7/16"	DP3PSB()2448	323.	371.	404.	577.	657.	715.
24" High Embossed Steel Insert 	18"	17 5/8"	25 1/2"	7/16"	DP3ESB()2418	207.	246.	270.	360.	422.	459.
	24"	23 5/8"	25 1/2"	7/16"	DP3ESB()2424	256.	293.	319.	450.	513.	562.
	30"	29 5/8"	25 1/2"	7/16"	DP3ESB()2430	276.	317.	344.	480.	562.	606.
	36"	35 5/8"	25 1/2"	7/16"	DP3ESB()2436	307.	347.	387.	532.	606.	671.
	42"	41 5/8"	25 1/2"	7/16"	DP3ESB()2442	316.	350.	388.	555.	616.	681.
	48"	47 5/8"	25 1/2"	7/16"	DP3ESB()2448	323.	371.	404.	577.	657.	715.

Panels, Build-To-Spec



w* = nominal width
Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Steel Insert 1. Pattern number 2. Paint finish	Steel Insert Example: DP3SS()2418 115 DP3 Pattern number SS22418 115 Medium Grey paint	Steel Insert Note: 24"H inserts are to only be used below beltways.	Steel Insert Insert pack quantity into parenthesis in pattern number Title to Floor Option: To specify tile to floor, add an 'F' suffix to the pattern number and add \$17 for a single pack or \$33 for a double pack. Note: Tile to Floor option available for 24" high inserts.

Beltway Inserts

Lower Laminate Inserts

Dividends Horizon

description	w*	w	d	pattern no.	list
24" High Laminate Beltway Lower Insert Base Raceway or Open Base 	15"	14 5/8"	7/16"	DP3L12415	\$180.
	18"	17 5/8"	7/16"	DP3L12418	191.
	24"	23 5/8"	7/16"	DP3L12424	215.
	30"	29 5/8"	7/16"	DP3L12430	255.
	36"	35 5/8"	7/16"	DP3L12436	313.
	42"	41 5/8"	7/16"	DP3L12442	318.
	48"	47 5/8"	7/16"	DP3L12448	323.
24" High Laminate Beltway Lower Insert Tile to Floor 	15"	14 5/8"	7/16"	DP3L12415F	180.
	18"	17 5/8"	7/16"	DP3L12418F	191.
	24"	23 5/8"	7/16"	DP3L12424F	215.
	30"	29 5/8"	7/16"	DP3L12430F	255.
	36"	35 5/8"	7/16"	DP3L12436F	313.
	42"	41 5/8"	7/16"	DP3L12442F	318.
	48"	47 5/8"	7/16"	DP3L12448F	323.

w* = nominal width

Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information

Beltway Laminate Inserts

1. Pattern Number
2. Laminate Finish
3. Edgeband Finish

Order Code

Beltway Laminate Inserts

Example: **DP3L12436**

DP3L1 Pattern Number

2436

118 Bright White Laminate

118 Bright White Edgeband

Included with:

Beltway Laminate Inserts

- Attachment clips

Note: 24"H inserts are to only be used below beltways.

This page intentionally left blank

High Acoustic Core Inserts and Sound Transmission Septum Inserts

Optional high acoustic core inserts or sound transmission septum inserts combine with tiles to provide enhanced acoustics.

High acoustic core inserts can be installed in monolithic and tiled panels but must be field-cut to be installed in beltway panels.

Sound transmission septum inserts can be installed in monolithic and tiled panels and single-sided beltway panels.

High Acoustic Core Insert Construction

1 1/2" thick, three-ply insert with an inner septum and outer fiberglass with polywrap.

Sound Transmission Septum Insert Construction

1/16" thick black asphalt paper.

Core Insert Attachment

High acoustic core inserts and sound transmission septum inserts are inserted into the center of the panel frame. Core inserts are sized to fit into the panel frame without the use of fasteners. In-field installation is required.

High Acoustic Core Insert Panel Ratings

Noise Reduction Coefficient (NRC) rating: .80 when combined with tiles.

Sound Transmission Class (STC) rating: 26 when combined with tiles.

Sound Transmission Septum Insert Panel Ratings

Noise Reduction Coefficient (NRC) rating: .60 when combined with tiles.

Sound Transmission Class (STC) rating: 17 when combined with tiles.

Available Sizes


High acoustic core inserts and sound transmission septum inserts are available for all widths of 50", 64" and 78" high monolithic and tiled panels.

Beltway electrical panels require the high acoustic core inserts or the sound transmission septum inserts to be field-cut prior to installation.


Packaging

High acoustic cores and sound transmission septum inserts are shipped in separate containers.


High Acoustic Core Insert



High Acoustic Core Insert Construction






Sound Transmission Septum Insert Construction



High Acoustic Core Inserts

Sound Transmission Septum Inserts

Dividends Horizon

description	type	pattern no.	High Acoustic Core Insert	Sound Transmission Septum Insert
 50" High	For 18" panel width	DP1() 5018	\$152.	\$58.
	For 24" panel width	DP1() 5024	165.	58.
	For 30" panel width	DP1() 5030	177.	58.
	For 36" panel width	DP1() 5036	191.	89.
	For 42" panel width	DP1() 5042	207.	89.
	For 48" panel width	DP1() 5048	239.	89.
 64" High	For 18" panel width	DP1() 6418	177.	58.
	For 24" panel width	DP1() 6424	191.	58.
	For 30" panel width	DP1() 6430	201.	58.
	For 36" panel width	DP1() 6436	234.	89.
	For 42" panel width	DP1() 6442	269.	89.
	For 48" panel width	DP1() 6448	295.	89.
 78" High	For 18" panel width	DP1() 7818	204.	95.
	For 24" panel width	DP1() 7824	233.	95.
	For 30" panel width	DP1() 7830	261.	95.
	For 36" panel width	DP1() 7836	282.	108.
	For 42" panel width	DP1() 7842	301.	108.
	For 48" panel width	DP1() 7848	364.	108.

Panels, Build-To-Spec

Ordering Information	Order Code	Included with:	Options
Inserts	Inserts	Inserts	Inserts
1. Pattern Number	<i>Example:</i> DP1(AC) 6448 DP1(AC) Pattern Number 6448	- High Acoustic Core Insert - Sound Transmission Septum Insert	Insert the appropriate letters for insert required within the parentheses of the pattern number. (AC) = High Acoustic (ST) = Sound Transmission

Single Pane Window Insert Kit

Single pane windows are available for three applications:

- Top position, with topway - for use in the top position of panels and D1 style stack frame with a topway trough.
- Top position, full view - for use in the top position of full view panels and D1 style stack frames (use with D2 tile supports)
- Middle position - for use in the middle positions of topway and full view panels.

Note: Window insert kits may not be specified in the bottom position of panels. Specify D2 tile supports and insert support mounting brackets separately.

Note: Single window insert kits are not compatible with the D2 style stack frame. Use D1 style stack frames with top position single or double pane window insert kits.

Construction

Single pane windows are shipped in two components - an "open" frame, and a "window" frame. Each frame snaps onto a Dividends Horizon panel frame. Both frames are constructed of extruded, then robotically-welded aluminum. Single pane windows have 1/4" tempered glass inserts with PVC glazing strip.

Single Pane Window Insert Kit

Available Sizes


- Heights: 14", 21" and 28"
- Widths: 24", 30", 36", 42", and 48"

Attachment

Window insert kits are installed on each side of a panel frame. Glazed insert kits consist of two inserts. Individual tile support rails must be ordered separately.

Note: Window types are aesthetically different, and are not designed to be mixed together within a single installation.

Single Pane Window Insert Kit



Window Insert Kits

Single Pane Windows

Dividends Horizon

description	h	w	pattern no.	P1	P2	P3
 Window, top position with topway	14"	24"	D2P1()T1424	\$547.	\$580.	\$606.
	14"	30"	D2P1()T1430	637.	665.	700.
	14"	36"	D2P1()T1436	668.	702.	737.
	14"	42"	D2P1()T1442	794.	833.	874.
	14"	48"	D2P1()T1448	811.	852.	896.
	21"	24"	D2P1()T2124	596.	625.	654.
	21"	30"	D2P1()T2130	702.	738.	773.
	21"	36"	D2P1()T2136	755.	794.	829.
	21"	42"	D2P1()T2142	901.	947.	990.
	21"	48"	D2P1()T2148	1,003.	1,056.	1,105.
	28"	24"	D2P1()T2824	654.	688.	724.
	28"	30"	D2P1()T2830	773.	811.	851.
	28"	36"	D2P1()T2836	829.	874.	913.
	28"	42"	D2P1()T2842	990.	1,043.	1,093.
	28"	48"	D2P1()T2848	1,105.	1,161.	1,216.
 Window, top position full view	14"	24"	D2P1()VT1424	510.	540.	564.
	14"	30"	D2P1()VT1430	594.	620.	651.
	14"	36"	D2P1()VT1436	668.	702.	737.
	14"	42"	D2P1()VT1442	794.	833.	874.
	14"	48"	D2P1()VT1448	811.	852.	896.
	21"	24"	D2P1()VT2124	596.	625.	654.
	21"	30"	D2P1()VT2130	702.	738.	773.
	21"	36"	D2P1()VT2136	755.	794.	829.
	21"	42"	D2P1()VT2142	901.	947.	990.
	21"	48"	D2P1()VT2148	1,003.	1,056.	1,105.
	28"	24"	D2P1()VT2824	654.	688.	724.
	28"	30"	D2P1()VT2830	773.	811.	851.
	28"	36"	D2P1()VT2836	829.	874.	913.
	28"	42"	D2P1()VT2842	990.	1,043.	1,093.
	28"	48"	D2P1()VT2848	1,105.	1,161.	1,216.
 Window, middle position	14"	24"	D2P1()VL1424	510.	540.	564.
	14"	30"	D2P1()VL1430	594.	620.	651.
	14"	36"	D2P1()VL1436	668.	702.	737.
	14"	42"	D2P1()VL1442	794.	833.	874.
	14"	48"	D2P1()VL1448	811.	852.	896.

Panels, Build-To-Spec

Ordering Information

Single Pane Window Kit

1. Pattern number
2. Paint finish

Order Code

Single Pane Window Kit

Example:	D2P1GT1448, 117
D2P1	Single Pane Window w/
GT1448	Clear Glass
117	Soft Grey Paint

Included with:

Single Pane Window Kit

Note: The single pane window insert kit is not compatible with the D2 style stack frame. Use D1 style stack frames with single pane window insert kits.

Note: Use top position window insert kits when using with D1 style stack frames.

Options

Single Pane Window Kit

Note: Single Pane Window Kit must be used with D2 Style Supports

Glass Options:
(G) = Clear Tempered Glass
(F) = Powder Glass

Markerboard Tiles

Markerboard tiles may be attached to any Dividends Horizon universal panel frame or wall mount tracks.

Construction

Markerboard tiles are constructed of 20 gauge steel, powder coated with paint suitable for use with standard dry erase markers.

Available Sizes

- Heights: 7", 10", 14", 21", 24" and 28"
- Widths: 18", 24", 30", 36", 42", and 48"

Attachment

Markerboard tiles are installed on one side or both sides of a panel frame or attached to wall mount tracks. Individual D1 or D2 tile support rails must be ordered separately.



Markerboard Trays

Markerboard trays are positioned directly below markerboard tiles, and are designed to hold dry erase markers and erasers. Trays mount to the outside of tile frames, and replace a D1 or D2 tile support.

Markerboard trays may not be positioned directly above or below a beltway raceway and may not be used with stack frames.

Note: Markerboard tiles can use D1 or D2 tile supports. Legacy D1 and D2 Markerboard tiles use D1 tile supports only.

Markerboard Tile



DP8 Stack Frame/Steel Tile Planning Note

When planning steel or markerboard tiles in the lower of two stack frames, or the upper position of full view panels with stack frames above them, different attachment clips are required. Specify pattern number DP8 SSTK (\$10 list) for each steel or markerboard tile used in these applications. This hardware kit is not required for any other tiles, or for steel and markerboard tiles in other locations.

Proper use and regular cleaning of your markerboard surface is essential for preventing permanent stains and/or ghosting typically associated with dry erase markers. By following the care and use instructions below, you will minimize the possibility of permanent stains and ghosting.

Initial Cleaning of Markerboards Before First Use:

- Using a clean, dry cloth and a nonabrasive cleaner, gently clean the entire board to loosen any residue
- Using a dry cloth, wipe the entire surface to remove all dirt and residue from the prior step
- Rinse the entire board with clean water
- Using a dry cloth, wipe dry the entire surface

Daily Use, Care and Maintenance:





- *Use the proper markers.* All dry erase markers will write legibly on the marker board surface, but not all will erase properly due to their composition. Do not use low odor dry erase markers or permanent (indelible) markers. Use of these markers will lead to staining or ghosting, even with regular cleaning.
- *Clean the markerboard regularly.* It is recommended that markerboards be erased daily using an eraser designated for use with dry erase markers. If the markerboard is used daily, we recommend that a complete cleaning is performed at least 2-3 times a week using EXPO® whiteboard cleaner.
- *Remove ghosting.* Using EXPO® whiteboard cleaner and a paper towel, wipe the entire surface and let dry. Mix Joy® dishwashing detergent with warm water and apply to the board using a paper towel, then wipe dry with a clean cloth. Repeat as necessary.
- *Remove permanent marker.* Using a dry erase marker, write on top of the permanent marker, erase with a dry eraser, and then clean with EXPO® whiteboard cleaner.

Note: Do not use other painted tiles as markerboards or product damage will occur and the tile warranty will be voided.

Markerboard Tiles

7", 10", 14" and 21" High

Dividends Horizon

description	h	w	pattern no.	1 pack	6 pack
D3 7" Markerboard tile 	7"	18"	DP3MB()718	\$97.	\$433.
	7"	24"	DP3MB()724	102.	459.
	7"	30"	DP3MB()730	110.	508.
	7"	36"	DP3MB()736	135.	593.
	7"	42"	DP3MB()742	145.	632.
	7"	48"	DP3MB()748	150.	670.
D3 10" Markerboard tile 	10"	18"	DP3MB()1018	135.	603.
	10"	24"	DP3MB()1024	145.	643.
	10"	30"	DP3MB()1030	146.	670.
	10"	36"	DP3MB()1036	164.	711.
	10"	42"	DP3MB()1042	169.	753.
	10"	48"	DP3MB()1048	179.	802.
D3 14" Markerboard tile 	14"	18"	DP3MB()1418	135.	603.
	14"	24"	DP3MB()1424	145.	643.
	14"	30"	DP3MB()1430	146.	670.
	14"	36"	DP3MB()1436	164.	711.
	14"	42"	DP3MB()1442	169.	753.
	14"	48"	DP3MB()1448	179.	802.
D3 21" Markerboard tile 	21"	18"	DP3MB()2118	173.	900.
	21"	24"	DP3MB()2124	217.	1,127.
	21"	30"	DP3MB()2130	232.	1,211.
	21"	36"	DP3MB()2136	261.	1,343.
	21"	42"	DP3MB()2142	266.	1,393.
	21"	48"	DP3MB()2148	275.	1,450.

Ordering Information

Markerboard Tiles

1. Pattern Number

Order Code

Markerboard Tiles

Example: **DP3MB(1) 1436**

DP3MB(1) Pattern Number
1436

Included with:

Markerboard Tiles

Options

Markerboard Tiles




(1) = 1 Pack

(6) = 6 Pack

Markerboard Tiles

24" and 28" High and Markerboard Tray

Dividends Horizon

description	height	width	pattern number	1 pack	2 pack	P1	P2	P3
D3 24" Markerboard tile 	24"	18"	DP3MB()2418	\$173.	\$300.			
	24"	24"	DP3MB()2424	217.	374.			
	24"	30"	DP3MB()2430	232.	402.			
	24"	36"	DP3MB()2436	261.	449.			
	24"	42"	DP3MB()2442	266.	464.			
	24"	48"	DP3MB()2448	275.	483.			
D3 28" Markerboard tile 	28"	18"	DP3MB()2818	189.	327.			
	28"	24"	DP3MB()2824	219.	380.			
	28"	30"	DP3MB()2830	233.	409.			
	28"	36"	DP3MB()2836	261.	457.			
	28"	42"	DP3MB()2842	266.	470.			
	28"	48"	DP3MB()2848	275.	485.			
Markerboard Tray 		24"	DP1MBT24			150.	159.	166.
		30"	DP1MBT30			154.	161.	169.
		36"	DP1MBT36			157.	166.	171.
		42"	DP1MBT42			160.	168.	174.
		48"	DP1MBT48			164.	170.	179.

Panels, Build-To-Spec

Ordering Information	Order Code	Included with:	Options
Markerboard Tiles 1. Pattern Number	Markerboard Tiles <i>Example:</i> DP3MB(1) 1436	Markerboard Tiles	Markerboard Tiles (1) = 1 Pack (2) = 2 Pack
Markerboard Tray 1. Pattern Number 2. Paint Finish	DP3MB(1) Pattern Number 1436		

Solid Steel Inserts

Solid steel tiles are painted solid steel formed inserts that may be inserted into any Dividends Horizon universal panel frame or attached to wall mount tracks.

Construction

Steel tiles are made of 20-gauge formed steel that is painted in any Dividends Horizon paint color.

Embossed Steel Inserts

Embossed steel tiles are painted embossed steel formed inserts that may be inserted into any Dividends Horizon universal panel frame or attached to wall mount tracks.

Construction

Embossed steel tiles are made of 18-gauge formed steel that is painted in any Dividends Horizon paint color

Perforated Steel Inserts

Perforated steel tiles are painted perforated steel formed inserts that may be inserted into any Dividends Horizon universal panel frame or attached to wall mount tracks.

Construction

Perforated steel tiles are made of 18-gauge formed steel that is painted in any Dividends Horizon paint color.

Available Sizes

- Height: 7", 10", 14", 21", 24" and 28"
- Widths: 15", 18", 24", 30", 36", 42" and 48"

Attachment

Steel tiles are installed on one side or both sides of a panel frame or attached to wall mount tracks. Individual D1 or D2 tile support rails must be ordered separately.


One-sided Attachment

For applications with perforated inserts on one side of panel only, specify sound transmission septums.


Tile-to-Floor Option

14" and 28" high steel tiles are available to be specified Tile-to-Floor.

Solid Steel Tile Insert



Perforated and Embossed Steel Tile Inserts



Lower of two DP8 stack frames






Top position of full view frames with stack frame above



DP8 Stack Frame/Steel Tile Planning Note

When planning steel or markerboard tiles in the lower of two stack frames, or the upper position of full view panels with stack frames above them, different attachment clips are required. Specify pattern number DP8 SSTK (\$10 list) for each steel or markerboard tile used in these applications. This hardware kit is not required for any other tiles, or for steel and markerboard tiles in other locations.

7", 8", 10", 14" and 21" High Solid Steel Insert

description	w*	w	h	d	pattern no.	1 pack P1	1 pack P2	1 pack P3	6 pack P1	6 pack P2	6 pack P3
D3 7" High Solid Steel Insert 	15"	14 5/8"	7 3/16"	7/16"	DP3SS()715	\$78.	\$93.	\$108.	\$349.	\$403.	\$482.
	18"	17 5/8"	7 3/16"	7/16"	DP3SS()718	78.	93.	108.	349.	403.	482.
	24"	23 5/8"	7 3/16"	7/16"	DP3SS()724	83.	102.	110.	371.	458.	499.
	30"	29 5/8"	7 3/16"	7/16"	DP3SS()730	95.	112.	125.	415.	510.	554.
	36"	35 5/8"	7 3/16"	7/16"	DP3SS()736	109.	131.	138.	482.	554.	597.
	42"	41 5/8"	7 3/16"	7/16"	DP3SS()742	116.	136.	146.	510.	589.	639.
	48"	47 5/8"	7 3/16"	7/16"	DP3SS()748	122.	140.	148.	542.	622.	674.
D3 8" High Solid Steel Insert 	18"	17 5/8"	8 3/16"	7/16"	DP3SS()0818	85.	98.	113.	351.	409.	484.
	24"	23 5/8"	8 3/16"	7/16"	DP3SS()0824	88.	108.	117.	374.	461.	500.
	30"	29 5/8"	8 3/16"	7/16"	DP3SS()0830	101.	118.	131.	421.	513.	559.
	36"	35 5/8"	8 3/16"	7/16"	DP3SS()0836	114.	135.	143.	485.	557.	602.
	42"	41 5/8"	8 3/16"	7/16"	DP3SS()0842	120.	141.	149.	513.	591.	641.
	48"	47 5/8"	8 3/16"	7/16"	DP3SS()0848	126.	144.	153.	545.	625.	685.
D3 10" High Solid Steel Insert 	15"	14 5/8"	10 3/16"	7/16"	DP3SS()1015	109.	126.	133.	488.	554.	579.
	18"	17 5/8"	10 3/16"	7/16"	DP3SS()1018	109.	126.	133.	488.	554.	579.
	24"	23 5/8"	10 3/16"	7/16"	DP3SS()1024	116.	135.	138.	523.	597.	622.
	30"	29 5/8"	10 3/16"	7/16"	DP3SS()1030	117.	138.	143.	542.	630.	652.
	36"	35 5/8"	10 3/16"	7/16"	DP3SS()1036	133.	148.	160.	579.	663.	695.
	42"	41 5/8"	10 3/16"	7/16"	DP3SS()1042	137.	154.	173.	608.	695.	762.
	48"	47 5/8"	10 3/16"	7/16"	DP3SS()1048	143.	174.	179.	652.	783.	816.

Order information

Freestanding Foot

1. Pattern number
2. Finish

Order Code

Freestanding Foot

Example: **DFFEUS()****DFFEUS** Pattern number**115** Medium Grey paint

Included with:

Solid Steel Insert



Solid Steel Insert

Insert pack quantity into parenthesis in pattern number

Tile to Floor Option:

Tile to Floor available in heights of 14", Worksurface Height, 24" and 28". To specify tile to floor, add an 'F' suffix to the pattern number and add \$17 for a single pack, \$33 for a double pack and \$99 for a 6 pack to the list price.

7", 8", 10", 14" and 21" High Solid Steel Insert

description	w*	w	h	d	pattern no.	1 pack P1	1 pack P2	1 pack P3	6 pack P1	6 pack P2	6 pack P3
D3 14" High Solid Steel Insert 	15"	14 5/8"	14 3/16"	7/16"	DP3SS()1415	\$109.	\$126.	\$133.	\$488.	\$554.	\$579.
	18"	17 5/8"	14 3/16"	7/16"	DP3SS()1418	109.	126.	133.	488.	554.	579.
	24"	23 5/8"	14 3/16"	7/16"	DP3SS()1424	116.	135.	138.	523.	597.	622.
	30"	29 5/8"	14 3/16"	7/16"	DP3SS()1430	117.	138.	143.	542.	630.	652.
	36"	35 5/8"	14 3/16"	7/16"	DP3SS()1436	133.	148.	160.	579.	663.	695.
	42"	41 5/8"	14 3/16"	7/16"	DP3SS()1442	137.	154.	173.	608.	695.	762.
	48"	47 5/8"	14 3/16"	7/16"	DP3SS()1448	143.	174.	179.	652.	783.	816.
D3 21" High Solid Steel Insert 	15	14 5/8"	21 3/16"	7/16"	DP3SS()2115	141.	169.	180.	730.	860.	936.
	18"	17 5/8"	21 3/16"	7/16"	DP3SS()2118	141.	169.	180.	730.	860.	936.
	24"	23 5/8"	21 3/16"	7/16"	DP3SS()2124	175.	199.	218.	912.	1,041.	1,141.
	30"	29 5/8"	21 3/16"	7/16"	DP3SS()2130	185.	217.	235.	979.	1,141.	1,228.
	36"	35 5/8"	21 3/16"	7/16"	DP3SS()2136	207.	237.	263.	1,087.	1,228.	1,371.
	42"	41 5/8"	21 3/16"	7/16"	DP3SS()2142	216.	238.	264.	1,131.	1,251.	1,392.
	48"	47 5/8"	21 3/16"	7/16"	DP3SS()2148	220.	252.	276.	1,174.	1,336.	1,456.

Order information

Freestanding Foot

1. Pattern number
2. Finish

Order Code

Freestanding Foot

Example: **DFFEUS()****DFFEUS** Pattern number**115** Medium Grey paint

Included with:

Solid Steel Insert

Solid Steel Insert

Insert pack quantity into parenthesis in pattern number

Tile to Floor Option:

Tile to Floor available in heights of 14", Worksurface Height, 24" and 28". To specify tile to floor, add an 'F' suffix to the pattern number and add \$17 for a single pack, \$33 for a double pack and \$99 for a 6 pack to the list price.




Worksurface Height and 28" High Solid Steel Insert

description	w*	w	h	d	pattern no.	1 pack P1	1 pack P2	1 pack P3	2 pack P1	2 pack P2	2 pack P3
D3 Worksurface Height Solid Steel Insert	15"	14 5/8"	22 1/2"	7/16"	DP3SS()WH15	\$141.	\$169.	\$180.	\$245.	\$287.	\$313.
	18"	17 5/8"	22 1/2"	7/16"	DP3SS()WH18	141.	169.	180.	245.	287.	313.
	24"	23 5/8"	22 1/2"	7/16"	DP3SS()WH24	175.	199.	218.	305.	349.	378.
	30"	29 5/8"	22 1/2"	7/16"	DP3SS()WH30	185.	217.	235.	323.	378.	413.
	36"	35 5/8"	22 1/2"	7/16"	DP3SS()WH36	207.	237.	263.	362.	413.	458.
	42"	41 5/8"	22 1/2"	7/16"	DP3SS()WH42	216.	238.	264.	376.	419.	463.
	48"	47 5/8"	22 1/2"	7/16"	DP3SS()WH48	220.	252.	276.	388.	446.	486.

D3 28" High Solid Steel Insert	15"	14 5/8"	29"	7/16"	DP3SS()2815	152.	152.	179.	264.	289.	313.
	18"	17 5/8"	29"	7/16"	DP3SS()2818	152.	152.	179.	264.	289.	313.
	24"	23 5/8"	29"	7/16"	DP3SS()2824	177.	177.	218.	307.	351.	382.
	30"	29 5/8"	29"	7/16"	DP3SS()2830	190.	217.	237.	332.	382.	419.
	36"	35 5/8"	29"	7/16"	DP3SS()2836	207.	237.	263.	367.	419.	463.
	42"	41 5/8"	29"	7/16"	DP3SS()2842	216.	240.	263.	378.	422.	469.
	48"	47 5/8"	29"	7/16"	DP3SS()2848	220.	252.	277.	395.	448.	488.

Ordering Information	Order Code	Included with:	Options
Solid Steel Insert	Solid Steel Insert	Solid Steel Insert	Solid Steel Insert
1. Pattern number	Example: DP3SS()2118 115		Insert pack quantity into parenthesis in pattern number
2. Paint finish	DP3 Pattern number		
	SS22118		Tile to Floor Option:
	115 Medium Grey paint		Tile to Floor available in heights of 14", Worksurface Height, 24" and 28". To specify tile to floor, add an 'F' suffix to the pattern number and add \$17 for a single pack, \$33 for a double pack and \$99 for a 6 pack to the list price.

7", 10", 14" and 21" High Perforated Steel Insert

description	w*	w	h	d	pattern no.	1 pack P1	1 pack P2	1 pack P3	6 pack P1	6 pack P2	6 pack P3
D3 7" High Perforated Steel Insert 	15"	14 ⁵ / ₈ "	7 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()715	\$117.	\$137.	\$166.	\$523.	\$608.	\$716.
	18"	17 ⁵ / ₈ "	7 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()718	117.	137.	166.	523.	608.	716.
	24"	23 ⁵ / ₈ "	7 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()724	126.	154.	170.	554.	685.	749.
	30"	29 ⁵ / ₈ "	7 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()730	140.	174.	183.	622.	773.	838.
	36"	35 ⁵ / ₈ "	7 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()736	169.	195.	206.	716.	838.	901.
	42"	41 ⁵ / ₈ "	7 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()742	178.	202.	220.	773.	881.	966.
	48"	47 ⁵ / ₈ "	7 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()748	182.	208.	227.	816.	936.	1,008.
D3 8" High Perforated Steel Insert 	18"	17 ⁵ / ₈ "	8 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()0818	121.	142.	170.	528.	614.	716.
	24"	23 ⁵ / ₈ "	8 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()0824	132.	159.	174.	557.	687.	752.
	30"	29 ⁵ / ₈ "	8 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()0830	144.	179.	189.	625.	775.	752.
	36"	35 ⁵ / ₈ "	8 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()0836	173.	199.	211.	718.	839.	903.
	42"	41 ⁵ / ₈ "	8 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()0842	182.	206.	227.	775.	883.	967.
	48"	47 ⁵ / ₈ "	8 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()0848	187.	215.	231.	818.	937.	1,009.
D3 10" High Perforated Steel Insert 	15"	14 ⁵ / ₈ "	10 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()1015	169.	190.	197.	739.	838.	870.
	18"	17 ⁵ / ₈ "	10 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()1018	169.	190.	197.	739.	838.	870.
	24"	23 ⁵ / ₈ "	10 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()1024	178.	199.	206.	783.	901.	936.
	30"	29 ⁵ / ₈ "	10 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()1030	179.	206.	217.	816.	946.	979.
	36"	35 ⁵ / ₈ "	10 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()1036	197.	227.	238.	870.	998.	1,041.
	42"	41 ⁵ / ₈ "	10 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()1042	205.	235.	254.	912.	1,041.	1,141.
	48"	47 ⁵ / ₈ "	10 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()1048	217.	257.	274.	979.	1,174.	1,228.

Ordering Information

Perforated Steel Insert

1. Pattern number
2. Paint finish

Order Code

Perforated Steel Insert

Example: **DP3PBS21430 117****DP3** Pattern number**PSB21430****117** Soft Grey paint

Included with:

Perforated Steel Insert

Options

Perforated Steel Insert



Insert pack quantity into parenthesis in pattern number

Tile to Floor Option:

Tile to Floor available in heights of 14", Worksurface Height, 24" and 28". To specify tile to floor, add an 'F' suffix to the pattern number and add \$17 for a single pack, \$33 for a double pack and \$99 for a 6 pack to the list price.



Tile to Floor Option not available on DP2 perforated steel tile insert.

7", 10", 14" and 21" High Perforated Steel Insert

description	w*	w	h	d	pattern no.	1 pack P1	1 pack P2	1 pack P3	6 pack P1	6 pack P2	6 pack P3
D3 14" High Perforated Steel Insert 	15"	14 ⁵ / ₈ "	14 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()1415	\$169.	\$190.	\$197.	\$739.	\$838.	\$870.
	18"	17 ⁵ / ₈ "	14 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()1418	169.	190.	197.	739.	838.	870.
	24"	23 ⁵ / ₈ "	14 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()1424	178.	199.	206.	783.	901.	936.
	30"	29 ⁵ / ₈ "	14 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()1430	179.	206.	217.	816.	946.	979.
	36"	35 ⁵ / ₈ "	14 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()1436	197.	227.	238.	870.	998.	1,041.
	42"	41 ⁵ / ₈ "	14 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()1442	205.	235.	254.	912.	1,041.	1,141.
	48"	47 ⁵ / ₈ "	14 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()1448	217.	257.	274.	979.	1,174.	1,228.
D3 21" High Perforated Steel Insert 	15"	14 ⁵ / ₈ "	21 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()2115	210.	251.	275.	1,099.	1,292.	1,405.
	18"	17 ⁵ / ₈ "	21 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()2118	210.	251.	275.	1,099.	1,292.	1,405.
	24"	23 ⁵ / ₈ "	21 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()2124	261.	301.	327.	1,371.	1,565.	1,717.
	30"	29 ⁵ / ₈ "	21 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()2130	280.	323.	351.	1,465.	1,717.	1,850.
	36"	35 ⁵ / ₈ "	21 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()2136	314.	355.	395.	1,628.	1,850.	2,056.
	42"	41 ⁵ / ₈ "	21 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()2142	322.	359.	396.	1,698.	1,879.	2,087.
	48"	47 ⁵ / ₈ "	21 ³ / ₁₆ "	⁷ / ₁₆ "	DP3PSB()2148	330.	377.	414.	1,763.	2,012.	2,187.




Ordering Information	Order Code	Included with:	Options
Perforated Steel Insert 1. Pattern number 2. Paint finish	Perforated Steel Insert Example: DP3PBS21430 117 DP3 Pattern number PSB21430 117 Soft Grey paint 	Perforated Steel Insert	Perforated Steel Insert Insert pack quantity into parenthesis in pattern number Tile to Floor Option: Tile to Floor available in heights of 14", Worksurface Height, 24" and 28". To specify tile to floor, add an 'F' suffix to the pattern number and add \$17 for a single pack, \$33 for a double pack and \$99 for a 6 pack to the list price. Tile to Floor Option not available on DP2 perforated steel tile insert.

14", Worksurface Height and 28" High Perforated Steel Insert

description	w*	w	h	d	pattern no.	1 pack P1	1 pack P2	1 pack P3	2 pack P1	2 pack P2	2 pack P3
D3 Worksurface Height Perforated Steel Insert 	15"	14 5/8"	22 1/2"	7/16"	DP3PSB()WH15	\$210.	\$251.	\$275.	\$367.	\$429.	\$469.
	18"	17 5/8"	22 1/2"	7/16"	DP3PSB()WH18	210.	251.	275.	367.	429.	469.
	24"	23 5/8"	22 1/2"	7/16"	DP3PSB()WH24	261.	301.	327.	458.	523.	574.
	30"	29 5/8"	22 1/2"	7/16"	DP3PSB()WH30	280.	323.	351.	488.	574.	619.
	36"	35 5/8"	22 1/2"	7/16"	DP3PSB()WH36	314.	355.	395.	542.	619.	685.
	42"	41 5/8"	22 1/2"	7/16"	DP3PSB()WH42	322.	359.	396.	566.	627.	695.
	48"	47 5/8"	22 1/2"	7/16"	DP3PSB()WH48	330.	377.	414.	589.	671.	730.
D3 28" High Perforated Steel Insert 	15"	14 5/8"	29"	7/16"	DP3PSB()2815	230.	230.	274.	397.	436.	469.
	18"	17 5/8"	29"	7/16"	DP3PSB()2818	230.	230.	274.	397.	436.	469.
	24"	24 5/8"	29"	7/16"	DP3PSB()2824	264.	264.	327.	463.	529.	579.
	30"	29 5/8"	29"	7/16"	DP3PSB()2830	281.	323.	355.	499.	579.	627.
	36"	35 5/8"	29"	7/16"	DP3PSB()2836	314.	355.	395.	550.	627.	695.
	42"	41 5/8"	29"	7/16"	DP3PSB()2842	322.	360.	395.	574.	630.	703.
	48"	47 5/8"	29"	7/16"	DP3PSB()2848	330.	377.	415.	594.	674.	735.

Ordering Information	Order Code	Included with:	Options
Perforated Steel Insert 1. Pattern number 2. Paint finish	Perforated Steel Insert Example: DP3PSB21430 117 DP3 Pattern number PSB21430 117 Soft Grey paint	Perforated Steel Insert	Perforated Steel Insert Insert pack quantity into parenthesis in pattern number Tile to Floor Option: Tile to Floor available in heights of 14", Worksurface Height, 24" and 28". To specify tile to floor, add an 'F' suffix to the pattern number and add \$17 for a single pack, \$33 for a double pack and \$99 for a 6 pack to the list price. Tile to Floor Option not available on DP2 perforated steel tile insert.

7", 10", 14" and 21" High Embossed Steel Insert

description	w*	w	h	d	pattern no.	1 pack P1	1 pack P2	1 pack P3	6 pack P1	6 pack P2	6 pack P3
D3 7" High Embossed Steel Insert 	15"	14 5/8"	7 3/16"	7/16"	DP3ESB()715	\$117.	\$137.	\$166.	\$523.	\$608.	\$716.
	18"	17 5/8"	7 3/16"	7/16"	DP3ESB()718	117.	137.	166.	523.	608.	716.
	24"	23 5/8"	7 3/16"	7/16"	DP3ESB()724	126.	154.	170.	554.	685.	749.
	30"	30 3/8"	7 3/16"	7/16"	DP3ESB()730	140.	174.	183.	622.	773.	838.
	36"	35 5/8"	7 3/16"	7/16"	DP3ESB()736	169.	195.	206.	716.	838.	901.
	42"	41 5/8"	7 3/16"	7/16"	DP3ESB()742	178.	202.	220.	773.	881.	966.
	48"	47 5/8"	7 3/16"	7/16"	DP3ESB()748	182.	208.	227.	816.	936.	1,008.
D3 8" High Embossed Steel Insert 	18"	17 5/8"	8 3/16"	7/16"	DP3ESB()0818	121.	142.	170.	528.	611.	718.
	24"	23 5/8"	8 3/16"	7/16"	DP3ESB()0824	132.	159.	174.	557.	687.	749.
	30"	29 5/8"	8 3/16"	7/16"	DP3ESB()0830	145.	179.	189.	625.	775.	839.
	36"	35 5/8"	8 3/16"	7/16"	DP3ESB()0836	173.	199.	210.	718.	839.	888.
	42"	41 5/8"	8 3/16"	7/16"	DP3ESB()0842	182.	206.	226.	706.	888.	967.
	48"	47 5/8"	8 3/16"	7/16"	DP3ESB()0848	187.	215.	231.	818.	937.	1,009.
D3 10" High Embossed Steel Insert 	15"	14 5/8"	10 3/16"	7/16"	DP3ESB()1015	169.	190.	197.	739.	838.	870.
	18"	17 5/8"	10 3/16"	7/16"	DP3ESB()1018	169.	190.	197.	739.	838.	870.
	24"	23 5/8"	10 3/16"	7/16"	DP3ESB()1024	178.	199.	206.	783.	901.	936.
	30"	29 5/8"	10 3/16"	7/16"	DP3ESB()1030	179.	206.	217.	816.	946.	979.
	36"	35 5/8"	10 3/16"	7/16"	DP3ESB()1036	197.	227.	238.	870.	998.	1,041.
	42"	41 5/8"	10 3/16"	7/16"	DP3ESB()1042	205.	235.	254.	912.	1,041.	1,141.
	48"	47 5/8"	10 3/16"	7/16"	DP3ESB()1048	217.	257.	274.	979.	1,174.	1,228.

Ordering Information

Embossed Steel Insert

1. Pattern number
2. Paint finish

Order Code

Embossed Steel Insert

Example: **DP3ESB21430 117****DP3** Pattern number**ESB21430****117** Soft Grey paint

Included with:

Embossed Steel Insert

Options



Embossed Steel Insert

Insert pack quantity into parenthesis in pattern number

Tile to Floor Option:



Tile to Floor available in heights of 14", Worksurface Height, 24" and 28". To specify tile to floor, add an 'F' suffix to the pattern number and add \$17 for a single pack, \$33 for a double pack and \$99 for a 6 pack to the list price.

7", 10", 14" and 21" High Embossed Steel Insert

description	w*	w	h	d	pattern no.	1 pack P1	1 pack P2	1 pack P3	6 pack P1	6 pack P2	6 pack P3
D3 14" High Embossed Steel Insert 	15"	14 ⁵ / ₈ "	14 ³ / ₁₆ "	⁷ / ₁₆ "	DP3ESB()1415	\$169.	\$190.	\$197.	\$739.	\$838.	\$870.
	18"	17 ⁵ / ₈ "	14 ³ / ₁₆ "	⁷ / ₁₆ "	DP3ESB()1418	169.	190.	197.	739.	838.	870.
	24"	23 ⁵ / ₈ "	14 ³ / ₁₆ "	⁷ / ₁₆ "	DP3ESB()1424	178.	199.	206.	783.	901.	936.
	30"	29 ⁵ / ₈ "	14 ³ / ₁₆ "	⁷ / ₁₆ "	DP3ESB()1430	179.	206.	217.	816.	946.	979.
	36"	35 ⁵ / ₈ "	14 ³ / ₁₆ "	⁷ / ₁₆ "	DP3ESB()1436	197.	227.	238.	870.	998.	1,041.
	42"	41 ⁵ / ₈ "	14 ³ / ₁₆ "	⁷ / ₁₆ "	DP3ESB()1442	205.	235.	254.	912.	1,041.	1,141.
	48"	47 ⁵ / ₈ "	14 ³ / ₁₆ "	⁷ / ₁₆ "	DP3ESB()1448	217.	257.	274.	979.	1,174.	1,228.
D3 21" Embossed Steel Insert 	15"	14 ⁵ / ₈ "	21"	⁷ / ₁₆ "	DP3ESB()2115	210.	251.	275.	1,099.	1,292.	1,405.
	18"	17 ⁵ / ₈ "	21"	⁷ / ₁₆ "	DP3ESB()2118	210.	251.	275.	1,099.	1,292.	1,405.
	24"	23 ⁵ / ₈ "	21"	⁷ / ₁₆ "	DP3ESB()2124	261.	301.	327.	1,371.	1,565.	1,717.
	30"	29 ⁵ / ₈ "	21"	⁷ / ₁₆ "	DP3ESB()2130	280.	323.	351.	1,465.	1,717.	1,850.
	36"	35 ⁵ / ₈ "	21"	⁷ / ₁₆ "	DP3ESB()2136	314.	355.	395.	1,628.	1,850.	2,056.
	42"	41 ⁵ / ₈ "	21"	⁷ / ₁₆ "	DP3ESB()2142	322.	359.	396.	1,698.	1,879.	2,087.
	48"	47 ⁵ / ₈ "	21"	⁷ / ₁₆ "	DP3ESB()2148	330.	377.	414.	1,763.	2,012.	2,187.

Ordering Information	Order Code	Included with:	Options
Embossed Steel Insert	Embossed Steel Insert	Embossed Steel Insert	Embossed Steel Insert
1. Pattern number	Example: DP3ESB21430 117		Insert pack quantity into parenthesis in pattern number
2. Paint finish	DP3 Pattern number		
	ESB21430		Tile to Floor Option:
	117 Soft Grey paint		Tile to Floor available in heights of 14", Worksurface Height, 24" and 28". To specify tile to floor, add an 'F' suffix to the pattern number and add \$17 for a single pack, \$33 for a double pack and \$99 for a 6 pack to the list price.

Worksurface Height and 28" High Embossed Steel Insert

description	w*	w	h	d	pattern no.	1 pack P1	1 pack P2	1 pack P3	2 pack P1	2 pack P2	2 pack P3
D3 Worksurface Height Embossed Steel Insert 	15"	14 5/8"	22 1/2"	7/16"	DP3ESB()WH15	\$210.	\$251.	\$275.	\$367.	\$429.	\$469.
	18"	17 5/8"	22 1/2"	7/16"	DP3ESB()WH18	210.	251.	275.	367.	429.	469.
	24"	23 5/8"	22 1/2"	7/16"	DP3ESB()WH24	261.	301.	327.	458.	523.	574.
	30"	39 5/8"	22 1/2"	7/16"	DP3ESB()WH30	280.	323.	351.	488.	574.	619.
	36"	35 5/8"	22 1/2"	7/16"	DP3ESB()WH36	314.	355.	395.	542.	619.	685.
	42"	41 5/8"	22 1/2"	7/16"	DP3ESB()WH42	322.	359.	396.	566.	627.	695.
	48"	47 5/8"	22 1/2"	7/16"	DP3ESB()WH48	330.	377.	414.	589.	671.	730.
D3 28" High Embossed Steel Insert 	15"	14 5/8"	29"	7/16"	DP3ESB()2815	230.	230.	274.	397.	436.	469.
	18"	17 5/8"	29"	7/16"	DP3ESB()2818	230.	230.	274.	397.	436.	469.
	24"	23 5/8"	29"	7/16"	DP3ESB()2824	264.	264.	327.	463.	529.	579.
	30"	29 5/8"	29"	7/16"	DP3ESB()2830	281.	323.	355.	499.	579.	627.
	36"	35 5/8"	29"	7/16"	DP3ESB()2836	314.	355.	395.	550.	627.	695.
	42"	41 5/8"	29"	7/16"	DP3ESB()2842	322.	360.	395.	574.	630.	703.
	48"	47 5/8"	29"	7/16"	DP3ESB()2848	330.	377.	415.	594.	674.	735.

Ordering Information**Embossed Steel Insert**

1. Pattern number
2. Paint finish

Order Code**Embossed Steel Insert**Example: **DP3ESB22130 117****DP3** Pattern number**ESB22130****117** Soft Grey paint**Included with:****Embossed Steel Insert****Options****Embossed Steel Insert**

Insert pack quantity into parenthesis in pattern number

Tile to Floor Option:

Tile to Floor available in heights of 14", Worksurface Height, 24" and 28". To specify tile to floor, add an 'F' suffix to the pattern number and add \$17 for a single pack, \$33 for a double pack and \$99 for a 6 pack to the list price.

Slatwall Tiles

Slatwall tiles are designed to support KnollExtra Orchestra work tools. Slatwall tiles will support flat panel monitor arms with varying weight limitations based on mounting and application. Please refer to the KnollExtra price list for comprehensive mounting and weight limitation information by application. Slatwall kits include all mounting brackets and hardware for installation, and are fully assembled. SLATWALL TILES INCLUDE INTEGRAL TILE SUPPORT(S).

Slatwall tiles are field installed on Dividends Horizon DP8 panel frames or attached to wall mount tracks. To specify, select the slatwall width to match the width of the panel frame, in either top or middle position locations.

Specify slatwall tiles along with built-to-spec panel frames or wall mount tracks and other tiles for a complete installation. Slatwall tiles may not be specified directly above or below other slatwall tiles, beltway, stack frames, or stacking screens. Slatwall tiles may not be specified on stack frames.

Construction

Slatwall is constructed of heat treated extruded aluminum, powder coated in any Knoll Core paint color. 16 gauge steel reinforcements with integral hooks and tri-lobular screws on the back of slatwall provide reinforcement for heavy loads.

Note: Due to design improvements with the slatwall tile, monitor arm reinforcements are no longer required when hanging monitor arms from Dividends Horizon slatwall.

Note: When using stacking or add up components, slatwall must be installed first. It is not recommended to use stacking or add up components when slatwall is installed on both sides in the top position as this significantly limits the access to the fasteners needed to secure stacking or add up components.

Top Position Slatwall Tiles

Top position slatwall tiles may be installed at the top of any Dividends Horizon DP8 panel frame or attached to wall mount tracks, and includes all required hardware. Top position slatwall is available in heights of 7, 14, 21 and 28 inches.

TOP POSITION SLATWALL TILES FEATURE AN INTEGRAL TILE SUPPORT AT THE BOTTOM, REPLACING THE SEPARATE D1 OR D2 TILE SUPPORT TYPICALLY REQUIRED BETWEEN TILES.


Middle Position Slatwall Tiles

Middle position slatwall tiles may be installed at the middle of any Dividends Horizon DP8 panel frame or attached to wall mount tracks, and includes all necessary hardware. Middle position slatwall is available in heights of 7, 14 and 21 inches.


MIDDLE POSITION SLATWALL TILES FEATURE AN INTEGRAL TILE SUPPORT AT THE TOP AND BOTTOM, REPLACING D1 OR D2 TILE SUPPORT TYPICALLY REQUIRED BETWEEN TILES.

Note: due to the canted design of the slatwall tile, a variable reveal exists in applications where slatwall tiles meet in a corner of a 90 degree configuration.

Top Position Slatwall



Middle Position Slatwall



Slatwall Tiles

7", 14", 21" and 28" High

Dividends Horizon

description	w	h	d	pattern no.	P1	P2	P3
7" High Slatwall Tile 	24"	7"	7/16"	DP1SW0724()	\$280.	\$305.	\$318.
	30"	7"	7/16"	DP1SW0730()	296.	329.	341.
	36"	7"	7/16"	DP1SW0736()	318.	351.	364.
	42"	7"	7/16"	DP1SW0742()	337.	368.	387.
	48"	7"	7/16"	DP1SW0748()	358.	392.	407.
14" High Slatwall Tile 	24"	14"	7/16"	DP1SW1424()	373.	412.	452.
	30"	14"	7/16"	DP1SW1430()	440.	484.	526.
	36"	14"	7/16"	DP1SW1436()	505.	555.	605.
	42"	14"	7/16"	DP1SW1442()	550.	605.	658.
	48"	14"	7/16"	DP1SW1448()	597.	656.	718.
21" High Slatwall Tile 	24"	21"	7/16"	DP1SW2124()	495.	545.	595.
	30"	21"	7/16"	DP1SW2130()	596.	653.	712.
	36"	21"	7/16"	DP1SW2136()	695.	765.	833.
	42"	21"	7/16"	DP1SW2142()	767.	845.	920.
	48"	21"	7/16"	DP1SW2148()	838.	922.	1,007.
28" Top Position Slatwall Tile 	24"	28"	7/16"	DP1SW2824()	615.	678.	739.
	30"	28"	7/16"	DP1SW2830()	749.	823.	898.
	36"	28"	7/16"	DP1SW2836()	884.	969.	1,057.
	42"	28"	7/16"	DP1SW2842()	980.	1,076.	1,173.
	48"	28"	7/16"	DP1SW2848()	1,075.	1,182.	1,288.

Panels, Build-To-Spec

Ordering Information

Post Assemblies

1. Pattern Number
2. Paint Finish

Order Code

Post Assemblies

Example: **DP1 S2824T, 111**
DP1 S2824Pattern Number
T
111 Jet Black Paint

Included with:

Note: Middle position slatwall tiles are able to be used on topway or full view panels.

Options

Panel Options:

(T) = for topway panel top position
(F) = for full view panel top position
(M) = for middle position

Technology Tile

Dividends Horizon technology tiles are 14", worksurface height or 28" high fabric or painted steel tiles with a factory installed technology port for above worksurface power and/or data access. Technology ports may be specified on the left, right, or both sides of technology tiles.

Each technology port has two openings: duplex power receptacles are positioned to the outside of the panel, while data ports may be positioned in either of the two positions. For applications where only one of the two openings is used, a knockout filler is included with each data port to fill this opening.

Technology tiles with one port accommodate one power and one data or two data outlets. Technology tiles with two ports accommodate up to two power receptacles and two data outlets, or four data outlets.

Specify vertical power modules, power receptacles, and data components separately.

Construction

Steel inserts are made of 20-gauge formed painted steel. Fabric inserts are made with a roll-coat adhesive, heat-cured to $\frac{7}{16}$ " thick tackable acoustical board.


Available Sizes

Heights: 14", worksurface height, 28"
Widths: 18", 24", 30", 42", 48" and 60"


Note: Steel technology tiles are only available in Knoll Core finishes

Note: Technology tiles are not able to be specified in the top position of 36" high topway panel.


14" High Technology Tile






Worksurface Height Technology Tile






28" High Technology Tile



description	h	w	pattern no.	grade 10	20	30	40
14" High, Technology Tile Fabric 	14"	18"	DP6TF()1418	\$206.	\$221.	\$227.	\$232.
	14"	24"	DP6TF()1424	218.	229.	233.	242.
	14"	30"	DP6TF()1430	221.	232.	240.	250.
	14"	36"	DP6TF()1436	227.	240.	251.	270.
	14"	42"	DP6TF()1442	232.	250.	265.	277.
	14"	48"	DP6TF()1448	240.	261.	277.	283.
	14"	60"	DP6TF()1460	250.	262.	266.	275.
Worksurface Height, Technology Tile Fabric 	22 1/2"	18"	DP6TF()WH18	274.	287.	300.	317.
	22 1/2"	24"	DP6TF()WH24	296.	325.	348.	361.
	22 1/2"	30"	DP6TF()WH30	316.	348.	366.	387.
	22 1/2"	36"	DP6TF()WH36	334.	366.	398.	415.
	22 1/2"	42"	DP6TF()WH42	342.	368.	401.	421.
	22 1/2"	48"	DP6TF()WH48	355.	387.	412.	438.
	22 1/2"	60"	DP6TF()WH60	373.	404.	425.	460.
28" High, Technology Tile Fabric 	28"	18"	DP6TF()2818	274.	287.	300.	317.
	28"	24"	DP6TF()2824	296.	325.	348.	361.
	28"	30"	DP6TF()2830	316.	348.	366.	387.
	28"	36"	DP6TF()2836	334.	366.	398.	415.
	28"	42"	DP6TF()2842	342.	368.	401.	421.
	28"	48"	DP6TF()2848	355.	387.	412.	438.
	28"	60"	DP6TF()2860	398.	420.	435.	450.

Ordering Information	Order Code	Included with:	Options
Technology Tile Fabric: 1. Pattern Number 2. Fabric 3. Bezel location	Technology Tile Fabric <i>Example:</i> DP3TFL1418/ W352-4 DP3TF Technology Tile Fabric L Left Hand Bezel Location 14 Height 18 Width W352-4 Labrynth Sage Fabric	Technology Tile Fabric • Fabric Technology Tile • Bezel	Technology Tile Fabric Bezel Location Options: (L) = Left Hand Bezel (R) = Right Hand Bezel (D) = Double Bezel - add \$45 Tile to Floor Options: Tile to Floor available in heights of 14", Worksurface Height, and 28". To specify tile to floor, add an "F" suffix to the pattern number and add \$11 to the list price.

description	h	w	pattern no.	P1	P2	P3
14" High, Technology Tile Steel 	14"	18"	DP6TS()1418	\$182.	\$193.	\$196.
	14"	24"	DP6TS()1424	190.	198.	205.
	14"	30"	DP6TS()1430	191.	201.	206.
	14"	36"	DP6TS()1436	201.	216.	223.
	14"	42"	DP6TS()1442	205.	221.	227.
	14"	48"	DP6TS()1448	216.	230.	234.
	14"	60"	DP6TS()1460	229.	240.	245.
Worksurface Height, Technology Tile Steel 	22 1/2"	18"	DP6TS()WH18	223.	234.	240.
	22 1/2"	24"	DP6TS()WH24	242.	262.	267.
	22 1/2"	30"	DP6TS()WH30	254.	274.	282.
	22 1/2"	36"	DP6TS()WH36	276.	295.	304.
	22 1/2"	42"	DP6TS()WH42	282.	301.	311.
	22 1/2"	48"	DP6TS()WH48	287.	305.	316.
	22 1/2"	60"	DP6TS()WH60	287.	305.	316.
28" High, Technology Tile Steel 	28"	18"	DP6TS()2818	223.	234.	240.
	28"	24"	DP6TS()2824	242.	262.	267.
	28"	30"	DP6TS()2830	254.	274.	282.
	28"	36"	DP6TS()2836	276.	295.	304.
	28"	42"	DP6TS()2842	282.	301.	311.
	28"	48"	DP6TS()2848	287.	305.	316.

Ordering Information	Order Code	Included with:	Options
Technology Tile Steel 1. Pattern Number 2. Paint 3. Bezel location	Technology Tile Steel <i>Example:</i> DP3TSL1418/ 113 DPSTS Technology Tile Steel L Left Hand Bezel Location 14 Height 18 Width 113 Dark Grey Paint Finish	Technology Tile Steel - Steel Technology Tile - Bezel Note: Steel technology tiles are only available in Knoll core finishes.	Technology Tile Steel Bezel Location Options: (L) = Left Hand Bezel (R) = Right Hand Bezel (D) = Double Bezel - add \$45 Tile to Floor Options: Tile to Floor available in heights of 14", Worksurface Height, and 28". To specify tile to floor, add an "F" suffix to the pattern number and add \$17 to the list price.

This page intentionally left blank

Freestanding Foot

This painted metal structural foot is used at the either end of a panel(s) or the attachment point of two adjacent panels to provide stability. Multiple feet can be used to support a freestanding panel run.

The foot provides up to 1 1/4" of adjustment for leveling and can be retrofitted to DP8 panels installed after 04.01.2014 attaching to the existing frame foot. Attachment hardware is included.

In a freestanding application, freestanding feet are required on each end of the panel run (maximum 50" panel height). In longer, straight runs of panels, a freestanding foot is required a minimum of every 8'. Center feet can only be located at a panel joint and should be used to provide added stability.

Freestanding foot is not to be used in 2-way, 3-way or 4-way post intersections. In these configurations, a stabilizing foot can be used at an end of a panel run application when additional panel support is required.

Single sided feet are designed to be used in applications where an obstruction limits the foot from being on both sides of the panel such as hallways or corridors.

Freestanding feet are designed to work with base raceway and tile to the floor panels. They do not work with open base panels.

Construction

1/4" Steel, welded assembly available in all Dividends Horizon standard paint finishes.


Available Sizes

End foot: height .25", width 5", depth 7.5" and 15"

Center foot: height .25", width 7", depth 7.5" and 15"

Note: Freestanding feet can only be used where the standard panel foot is located.





Note: Panel mounted overheads cannot be used on panels with freestanding feet.



Freestanding Foot

Freestanding Foot

Dividends Horizon

description	type	pattern no.	list
End Universal 	2 per pack	DFFEUD	\$375.
	single pack	DFFEUS	190.
Center Universal 	single pack	DFFCUS	200.
Center Single Sided 	Single pack	DFFSSS	220.
End SingleSided 	left, single pack	DFFELS	185.
	right, single pack	DFFERS	185.

Right hand shown

Panels, Build-To-Spec

Order information	Order Code	Included with:
Freestanding Foot	Freestanding Foot	Freestanding Foot
1. Pattern number	Example: DFFEUS()	
2. Finish	DFFEUS Pattern number	
	115 Medium Grey paint	

Dividends Horizon rolling doors were developed for clients desiring increased privacy for focused work.

Rolling doors are available in 57, 64 and 78" overall heights, and widths to accommodate panel openings of 36, 42 and 48 inches.

Planning

Rolling doors must be mounted to the end of an equal height Dividends Horizon panel or run of panels of equal or greater width. Doors may not be mounted to Dividends Horizon screens or universal posts.

Door jamb may be mounted directly to DP8 series universal posts – specify jamb to post attachment kit separately.

When fully open, the door will extend 2" beyond the end of the panel end trim on a panel of corresponding width.

Thresholds are included with door pattern number, and are required in all installations. The Dividends Horizon rolling door meets ADA 5 lb pull test requirements when used with the supplied threshold.

42" and 48" wide meet ADA access requirements with openings of 36.4"W and 42.4"W respectively.

Specifying 57" and 64" Rolling Doors

57" and 64" rolling doors include:

- Rolling door
- Mounting brackets
- Door jamb (for door side opposite to mounting brackets)
- Threshold

To complete the specification, specify an DP5 end trim for the panel to which the door is mounted, and a jamb-compatible top cap for the panel to which the door jamb is attached.

Specifying 78" Rolling Doors

78" rolling doors include:

- Rolling door
- Header
- Mounting brackets,
- Door jamb (for door side opposite to mounting brackets)
- Panel end trim
- Threshold

78" high doors include a header, with vertical clearance of 76 1/2" from height of finished floor. Specify a top cap for the header separately. Extended length top caps are recommended in this application.

No additional end trim is required for 78" high doors, as it is included in the door pattern number.

Construction

Rolling door and door jamb are constructed of extruded aluminum, powder coated in any Knoll Core paint finish. Threshold is anodized extruded aluminum.

Door inserts are available in clear, powder or bronze frosted glass.

Locks are optional, and engage with door jamb. Standard KnollKey system keying guidelines apply.


Opening Clearance

36"W door = 30.4"W

42"W door = 36.4"W

48"W door = 42.4W


42"W and 48"W doors are ADA compliant.



Rolling Door

57", 64" and 78" High

Dividends Horizon

description	type	w	d	h	pattern no.	Temp	GL13 GL25 GL35	Metal P1	Metal P2	Metal P3	Plastic
 right hand shown	57" High with lock	36"	3"	57"	DPRD15736(L/R)L	\$3,108.	\$3,204.				
		42"	3"	57"	DPRD15742(L/R)L	3,377.	3,470.				
		48"	3"	57"	DPRD15748(L/R)L	3,717.	3,817.				
	57" High no lock	36"	3"	57"	DPRD15736(L/R)N	3,012.	3,104.				
		42"	3"	57"	DPRD15742(L/R)N	3,279.	3,372.				
		48"	3"	57"	DPRD15748(L/R)N	3,606.	3,710.				
	64" High with lock	36"	3"	64"	DPRD16436(L/R)L	3,234.	3,352.				
		42"	3"	64"	DPRD16442(L/R)L	3,504.	3,618.				
		48"	3"	64"	DPRD16448(L/R)L	3,854.	3,979.				
	64" High no lock	36"	3"	64"	DPRD16436(L/R)N	3,138.	3,255.				
		42"	3"	64"	DPRD16442(L/R)N	3,406.	3,520.				
		48"	3"	64"	DPRD16448(L/R)N	3,746.	3,874.				
	78" High with lock	36"	3"	78"	DPRD17836(L/R)L	3,762.	3,920.				
		42"	3"	78"	DPRD17842(L/R)L	4,029.	4,185.				
		48"	3"	78"	DPRD17848(L/R)L	4,433.	4,604.				
	78" High no lock	36"	3"	78"	DPRD17836(L/R)N	3,663.	3,821.				
		42"	3"	78"	DPRD17842(L/R)N	3,931.	4,089.				
		48"	3"	78"	DPRD17848(L/R)N	4,324.	4,498.				
Panel Top Caps for Jamb Side		18"			DP()PT18RD			79.	81.	83.	0.
		24"			DP()PT24RD			79.	81.	83.	0.
		30"			DP()PT30RD			79.	81.	83.	0.
		36"			DP()PT36RD			79.	81.	83.	0.
		42"			DP()PT42RD			79.	81.	83.	0.
		48"			DP()PT48RD			79.	81.	83.	0.
		54"			DP()PT54RD			83.	86.	88.	0.
		60"			DP()PT60RD			87.	89.	91.	0.
		66"			DP()PT66RD			91.	95.	98.	0.
		72"			DP()PT72RD			97.	101.	108.	0.
	78"			DP()PT78RD			105.	112.	116.	0.	

Ordering Information

Rolling Door

1. Pattern Number
2. Glass type

Top Cap

1. Pattern Number
2. Paint finish

Application Notes:

Stacking screen header bracket is for use on 78"h doors (connection side) when connecting door header to top of 14"h stacking screen positioned on top of a 64"h panel.

Order Code

Rolling Door

Example: DPRD1 5736 RL

DPRD1 Rolling Door

57 Height

36 Width

R Right

L Lock

118T Bright White Textured

GL13 Frosted Glass

Included With:

Rolling Door

57" and 64" High

- Rolling Door
- Mounting Brackets
- Door jamb
- Threshold

78" High

- Rolling Door
- Header
- Mounting Brackets
- Door jamb
- Panel end trim
- Threshold

Top Cap

- Top Cap
- End Plug

Options

Rolling Door

Mounting Options:

L = Left Hand
R = Right Hand

Paint Finish:

All Core paint finishes

Glass Type:

Temp = Clear Glass
GL13 = Frosted Glass
GL25 = Bronze Glass
GL35 = Grey Glass

Top Cap

Top Cap Options:

(4) = Radius Metal
(5) = Flat Metal

Rolling Door

57", 64" and 78" High

Dividends Horizon

description	type	w	d	h	pattern no.	Temp	GL13 GL25 GL35	Metal P1	Metal P2	Metal P3	Plastic
Panel Top Caps for Jamb Side		84"			DP()PT84RD			\$114.	\$120.	\$124.	\$0.
		90"			DP()PT90RD			123.	128.	131.	0.
		96"			DP()PT96RD			129.	134.	139.	0.
Door Jamb Kit to mount to DP8 Post					DPRD1JPM			0.	0.	0.	29.
Stacking screen header bracket					DPRD1SSB			0.	0.	0.	27.

Ordering Information	Order Code	Included With:	Options
Rolling Door 1. Pattern Number 2. Glass type Top Cap 1. Pattern Number 2. Paint finish Application Notes: Stacking screen header bracket is for use on 78"h doors (connection side) when connecting door header to top of 14"h stacking screen positioned on top of a 64"h panel.	Rolling Door <i>Example:</i> DPRD1 5736 RL DPRD1 Rolling Door 57 Height 36 Width R Right L Lock 118T Bright White Textured GL13 Frosted Glass	Rolling Door 57" and 64" High - Rolling Door - Mounting Brackets - Door jamb - Threshold 78" High - Rolling Door - Header - Mounting Brackets - Door jamb - Panel end trim - Threshold Top Cap - Top Cap - End Plug	Rolling Door Mounting Options: L = Left Hand R = Right Hand Paint Finish: All Core paint finishes Glass Type: Temp = Clear Glass GL13 = Frosted Glass GL25 = Bronze Glass GL35 = Grey Glass Top Cap <i>Top Cap Options:</i> (4) = Radius Metal (5) = Flat Metal

This page intentionally left blank

Glass Screens

Glass Screens, available in both triangular and rectangular profile frames, provide territorial privacy, while transmitting light into the office.

Glass Screen Construction

Glass screens are available in both triangular and rectangular frame profiles, made from extruded aluminum frame members, powder coated in any Knoll Core paint finish. Glass is 4mm thick tempered glass.

Glass Screen Dimensions

Widths: 24, 30, 36, 42 and 48 inches

Heights: 42, 50, 57 and 64 inches


Thickness: 3 inches

Planning With Screens

Dividends Horizon glass screens are primarily designed to divide space and let light into the office. Screens do not have a slotted standard, and do not support overhead storage components. Screens feature slots to allow use of a mid-span worksurface support at the standard 28 1/2" H worksurface height.

Screens attach to Dividends Horizon panels or connecting posts of the same or greater height, or other screens of the same height. In a "high/low" situation, screens do not attach to higher or lower screens, or lower panels. Screens ship with attachment hardware and topcap, if specified.

**Glass Screen with Rectangular
Frame and Open Base Option**



Screen Base Options

Triangular frame glass screens are available with three base options: base raceway, open base, or frame to floor. Rectangular frame glass screens are available with two base options: base raceway or open base. All bases feature leveling glides with 2" of vertical travel. Raceway covers are standard without knockouts. Screens support electrical pass-thru's, but do not support power modules or electrical receptacles.

Note: 36"H screen may not be connected to a Legacy post.

Note: 64" open weave screen "L" or "U" configurations require minimum 36" wide panel return(s).

Note: Raceway covers are not available with knockouts.

Note: Screens are only available in Knoll core finishes.

Note: Freestanding screen kits are finished with textured paint, including 613 silver.

Screen Kit Dimensions

Flat Steel Feet


Width: 4 inches

Thickness: 7/16 inches

Depth: 20 inches

Open Weave Screens

64" High and Freestanding Open Weave Screen Kits

description	type	h	w	d	pattern no.	P1	P2	P3
 (single screen kit shown)	For use with 2 open weave screens				DP7SWTFKD	\$551.	\$605.	\$630.
	For use with 24" wide open weave screen				DP7SWTFK24	514.	565.	587.
	For use with 30" wide open weave screen				DP7SWTFK30	521.	573.	593.
	For use with 36" wide open weave screen				DP7SWTFK36	534.	587.	609.
	For use with 42" wide open weave screen				DP7SWTFK42	551.	605.	630.
	For use with 48" wide open weave screen				DP7SWTFK48	551.	605.	630.

Ordering Information

Open Weave Screen:

1. Pattern number
2. Frame finish
3. Top cap style
4. Top cap finish
5. Base finish
6. Fabric finish

Freestanding Open Weave Screen Kits

1. Pattern number
2. Paint finish

Order Code

Open Weave Screen:

Example: **DP7SWTFF3636**
117/4/117/117/W1113-1

DP7SWT	Triangular open weave screen
FF	Screen to Floor
117	Frame finish
4	Radius metal top cap
117	Top cap finish
117	Raceway finish
W1113-1	Warp Net White

Included with:

Open Weave Screen

Note: Freestanding open weave screen kits are finished with textured paint, including 613 Silver.

Note: Freestanding open weave screen kits only work with open weave screens with frame-to-floor (FF) base option.

Options:

Open Weave Screen

Top Cap Options:

No Top Cap - Deduct \$40;
 Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4

Raceway Type:

(FF) = Frame to the Floor both sides
 (RR) = Raceway covers no knockouts
 (LL) = Open base



Note: Raceway covers are not available with knockouts.

Glass Screens

Triangular Frame Screen with Glass

42" and 50" High

Dividends Horizon

description	h	w	t	pattern no.	P1	P2	P3
42" High Triangular Frame Screen with Glass 	42"	24"	3"	DP7S()T()4224	\$1,265.	\$1,290.	\$1,314.
	42"	30"	3"	DP7S()T()4230	1,335.	1,363.	1,385.
	42"	36"	3"	DP7S()T()4236	1,412.	1,437.	1,463.
	42"	42"	3"	DP7S()T()4242	1,438.	1,466.	1,494.
	42"	48"	3"	DP7S()T()4248	1,466.	1,494.	1,521.
50" High Triangular Frame Screen with Glass 	50"	24"	3"	DP7S()T()5024	1,356.	1,381.	1,411.
	50"	30"	3"	DP7S()T()5030	1,387.	1,417.	1,442.
	50"	36"	3"	DP7S()T()5036	1,423.	1,450.	1,477.
	50"	42"	3"	DP7S()T()5042	1,539.	1,566.	1,595.
	50"	48"	3"	DP7S()T()5048	1,647.	1,681.	1,715.

Panels, Build-To-Spec

*Note: Frame with raceway covers shown

Ordering Information	Order Code	Included with:	Options
Triangular Frame Screen with Glass: 1. Pattern number 2. Frame finish 3. Glass type 4. Top cap style 5. Top cap finish 6. Raceway finish	Triangular Frame with Glass: <i>Example:</i> DP7SGTRR4236 117/4/117/117 DP7SGT Triangular frame with clear glass RR Raceway type 117 Frame finish 4 Radius metal top cap 117 Top cap finish 117 Raceway finish	Triangular Frame with Glass - Topcap (when specified) - Connecting hardware Note: Screens are only available in Knoll core finishes.	Glass Options: (G) = Clear Tempered Glass (F) = Powder Glass Top Cap Options: No Top Cap - Deduct \$40; Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4 Raceway Type: (FF) = Frame to the Floor both sides (RR) = Raceway covers no knockouts (LL) = Open base Frame to floor option not available on Triangular glass screens. Note: Raceway covers are not available with knockouts.


Glass Screens

Triangular Frame Screen with Glass

57" and 64" High

Dividends Horizon

description	h	w	t	pattern no.	P1	P2	P3
57" High Triangular Frame Screen with Glass	57"	24"	3"	DP7S()T()5724	\$1,387.	\$1,417.	\$1,442.
	57"	30"	3"	DP7S()T()5730	1,463.	1,491.	1,518.
	57"	36"	3"	DP7S()T()5736	1,540.	1,569.	1,597.
	57"	42"	3"	DP7S()T()5742	1,597.	1,630.	1,660.
	57"	48"	3"	DP7S()T()5748	1,653.	1,689.	1,721.



64" High Triangular Frame Screen with Glass	64"	24"	3"	DP7S()T()6424	1,422.	1,449.	1,476.
	64"	30"	3"	DP7S()T()6430	1,539.	1,566.	1,595.
	64"	36"	3"	DP7S()T()6436	1,649.	1,685.	1,718.
	64"	42"	3"	DP7S()T()6442	1,656.	1,690.	1,723.
	64"	48"	3"	DP7S()T()6448	1,664.	1,694.	1,728.



*Note: Frame to the floor shown

Ordering Information	Order Code	Included with:	Options
Triangular Frame Screen with Glass: 1. Pattern number 2. Frame finish 3. Glass type 4. Top cap style 5. Top cap finish 6. Raceway finish	Triangular Frame with Glass: <i>Example:</i> DP7SGTRR5736 117/4/117/117 DP7SGT Triangular frame with clear glass RR Raceway type 117 Frame finish 4 Radius metal top cap 117 Top cap finish 117 Raceway finish	Triangular Frame with Glass • Topcap (when specified) • Connecting hardware Note: Screens are only available in Knoll core finishes.	Glass Options: (G) = Clear Tempered Glass (F) = Powder Glass Top Cap Options: No Top Cap - Deduct \$40; Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4 Raceway Type: (FF) = Frame to the Floor both sides (RR) = Raceway covers no knockouts (LL) = Open base Note: Raceway covers are not available with knockouts.


Glass Screens

Rectangular Frame Screen with Glass


42" and 50" High

Dividends Horizon

description	h	w	t	pattern no.	P1	P2	P3
42" High Rectangular Frame Screen with Glass	42"	24"	3"	DP7S()R()4224	\$1,271.	\$1,295.	\$1,322.
	42"	30"	3"	DP7S()R()4230	1,345.	1,371.	1,397.
	42"	36"	3"	DP7S()R()4236	1,421.	1,448.	1,475.
	42"	42"	3"	DP7S()R()4242	1,449.	1,476.	1,503.
	42"	48"	3"	DP7S()R()4248	1,477.	1,507.	1,538.



50" High Rectangular Frame Screen with Glass	50"	24"	3"	DP7S()R()5024	1,367.	1,391.	1,421.
	50"	30"	3"	DP7S()R()5030	1,401.	1,429.	1,457.
	50"	36"	3"	DP7S()R()5036	1,436.	1,463.	1,491.
	50"	42"	3"	DP7S()R()5042	1,550.	1,583.	1,608.
	50"	48"	3"	DP7S()R()5048	1,666.	1,697.	1,730.



Panels, Build-To-Spec

Ordering Information	Order Code	Included with:	Options
Rectangular Frame Screen with Glass: 1. Pattern number 2. Frame finish 3. Glass type 4. Top cap style 5. Top cap finish 6. Raceway finish	Rectangular Frame with Glass: <i>Example:</i> DP7SGRRR4236 117/4/117/117 DP7SGR Rectangular frame screen with clear glass RR Raceway type 117 Frame finish 4 Radius metal top cap 117 Top cap finish 117 Raceway finish	Rectangular Frame Glass • Topcap (when specified) • Connecting hardware Note: Screens are only available in Knoll core finishes.	Glass Options: (G) = Clear Tempered Glass (F) = Powder Glass Top Cap Options: No Top Cap - Deduct \$40; Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4 Raceway Type: (RR) = Raceway covers no knockouts (LL) = Open base Frame to floor option not available on Rectangular glass screens. Note: Raceway covers are not available with knockouts.


Glass Screens

Rectangular Frame Screen with Glass

57" and 64" High

Dividends Horizon

description	h	w	t	pattern no.	P1	P2	P3
57" High Rectangular Frame Screen with Glass	57"	24"	3"	DP7S()R()5724	\$1,398.	\$1,426.	\$1,454.
	57"	30"	3"	DP7S()R()5730	1,476.	1,506.	1,537.
	57"	36"	3"	DP7S()R()5736	1,552.	1,585.	1,609.
	57"	42"	3"	DP7S()R()5742	1,609.	1,642.	1,677.
	57"	48"	3"	DP7S()R()5748	1,674.	1,702.	1,736.



64" High Rectangular Frame Screen with Glass	64"	24"	3"	DP7S()R()6424	1,430.	1,459.	1,484.
	64"	30"	3"	DP7S()R()6430	1,549.	1,582.	1,607.
	64"	36"	3"	DP7S()R()6436	1,667.	1,698.	1,731.
	64"	42"	3"	DP7S()R()6442	1,674.	1,702.	1,736.
	64"	48"	3"	DP7S()R()6448	1,678.	1,710.	1,741.



Ordering Information	Order Code	Included with:	Options
Rectangular Frame Screen with Glass: 1. Pattern number 2. Frame finish 3. Glass type 4. Top cap style 5. Top cap finish 6. Raceway finish	Rectangular Frame with Glass: <i>Example:</i> DP7SGRRR5736 117/4/117/117 DP7SGR Rectangular frame screen with clear glass RR Raceway type 117 Frame finish 4 Radius metal top cap 117 Top cap finish 117 Raceway finish	Rectangular Frame Glass - Topcap (when specified) - Connecting hardware Note: Screens are only available in Knoll core finishes.	Glass Options: (G) = Clear Tempered Glass (F) = Powder Glass Top Cap Options: No Top Cap - Deduct \$40; Radius and Flat Metal P1 as standard; P2 \$2, P3 \$4 Raceway Type: (RR) = Raceway covers no knockouts (LL) = Open base Frame to floor option not available on Rectangular glass screens. Note: Raceway covers are not available with knockouts.

This page intentionally left blank

Stacking Glass Screens

Stacking glass screens, available in both triangular and rectangular profile frames, provide territorial privacy, while transmitting light into the office.

Stacking Glass Screen

Construction

Stacking glass screens are constructed of extruded aluminum frame members, powder coated in any Knoll Core paint finish. Clear glass is 4mm tempered glass.

Stacking Screen Dimensions:

Widths: 24, 30, 36, 42, and 48 inches

Heights: 14, 21 and 28 inches

Thickness: 3 inches

Planning With Stacking Screens

Dividends Horizon glass screens are primarily designed to divide space and let light into the office. Screens do not have a slotted standard, and do not support overhead storage components.

Stacking screens attach to any Dividends Horizon full view panel frame, and may be stacked one tier high. Stacking screens do not stack on topway panel frames.

Stacking screens attach to Dividends Horizon panels or connecting posts of the same or greater height, or other screens of the same height.


Note: Stacking screens may be used with DP8 full view panel frames only.

Note: Screens are only available in Knoll core finishes.

Note: Knoll's three window types are aesthetically and functionally different, and are not designed to be mixed together within a single installation.

Note: Reveal strips for stacking screens 60" or wider must be specified separately to ensure the correct length of reveal strip is provided.

Rectangular Stack Panel Screen with Glass insert



Glass Stacking Screens

Triangular Frame Stacking Screen with Glass

Dividends Horizon

description	h	w	t	pattern no.	P1	P2	P3
14" High Triangular Frame Stacking Screen with Glass 	14"	24"	3"	DP7SS()T1424	\$747.	\$761.	\$776.
	14"	30"	3"	DP7SS()T1430	784.	798.	813.
	14"	36"	3"	DP7SS()T1436	820.	839.	856.
	14"	42"	3"	DP7SS()T1442	859.	875.	894.
	14"	48"	3"	DP7SS()T1448	896.	912.	932.
	14"	54"	3"	DP7SS()T1454	940.	971.	999.
	14"	60"	3"	DP7SS()T1460	988.	1,017.	1,047.
	14"	66"	3"	DP7SS()T1466	1,042.	1,069.	1,105.
	14"	72"	3"	DP7SS()T1472	1,090.	1,122.	1,156.
	14"	78"	3"	DP7SS()T1478	1,146.	1,179.	1,215.
	14"	84"	3"	DP7SS()T1484	1,204.	1,240.	1,275.
	14"	90"	3"	DP7SS()T1490	1,265.	1,303.	1,340.
	14"	96"	3"	DP7SS()T1496	1,327.	1,368.	1,408.
21" High Triangular Frame Stacking Screen with Glass 	21"	24"	3"	DP7SS()T2124	750.	765.	783.
	21"	30"	3"	DP7SS()T2130	793.	808.	826.
	21"	36"	3"	DP7SS()T2136	833.	850.	868.
	21"	42"	3"	DP7SS()T2142	875.	893.	910.
	21"	48"	3"	DP7SS()T2148	917.	938.	956.
	21"	54"	3"	DP7SS()T2154	963.	990.	1,017.
	21"	60"	3"	DP7SS()T2160	1,010.	1,039.	1,070.
	21"	66"	3"	DP7SS()T2166	1,061.	1,091.	1,124.
	21"	72"	3"	DP7SS()T2172	1,114.	1,145.	1,181.
	21"	78"	3"	DP7SS()T2178	1,168.	1,205.	1,239.
	21"	84"	3"	DP7SS()T2184	1,226.	1,266.	1,301.
	21"	90"	3"	DP7SS()T2190	1,289.	1,327.	1,367.
	21"	96"	3"	DP7SS()T2196	1,354.	1,395.	1,433.
28" High Triangular Frame Stacking Screen with Glass 	28"	24"	3"	DP7SS()T2824	805.	822.	839.
	28"	30"	3"	DP7SS()T2830	854.	873.	886.
	28"	36"	3"	DP7SS()T2836	903.	918.	940.
	28"	42"	3"	DP7SS()T2842	954.	973.	991.
	28"	48"	3"	DP7SS()T2848	1,002.	1,022.	1,041.
	28"	54"	3"	DP7SS()T2854	1,052.	1,084.	1,115.
	28"	60"	3"	DP7SS()T2860	1,104.	1,136.	1,171.
	28"	66"	3"	DP7SS()T2866	1,159.	1,193.	1,227.
	28"	72"	3"	DP7SS()T2872	1,218.	1,252.	1,290.
	28"	78"	3"	DP7SS()T2878	1,277.	1,316.	1,355.
	28"	84"	3"	DP7SS()T2884	1,341.	1,379.	1,423.
	28"	90"	3"	DP7SS()T2890	1,410.	1,452.	1,493.
	28"	96"	3"	DP7SS()T2896	1,480.	1,523.	1,570.

Panels, Build-To-Spec

Ordering Information	Order Code	Included with:	Options
Triangular Frame Stacking Screen 1. Pattern number 2. Frame finish 3. Glass	Triangular Frame Stacking Screen <i>Example:</i> DP7SSGT1424 / 117 DP7SSGT Stack, Triangular Frame, w/ clear tempered glass 117 Frame finish	Triangular Frame Stacking Screen • Attachment hardware Note: Screens are only available in Knoll core finishes. Note: Reveal strips for stacking screens 60" or wider must be specified separately.	NOTE: Stacking screens are compatible with DP8 Full View panels only. Glass Options: (G) = Clear Tempered Glass (F) = Powder Glass

Glass Stacking Screen Reveal Filler Strips

description	h	w	t	pattern no.	P1	P2	P3
Stacking Screen Reveal Filler	2"	24"	2"	DP8PRFN24	n/c	n/c	n/c
	2"	30"	2"	DP8PRFN30	n/c	n/c	n/c
	2"	36"	2"	DP8PRFN36	n/c	n/c	n/c
	2"	42"	2"	DP8PRFN42	n/c	n/c	n/c
	2"	48"	2"	DP8PRFN48	n/c	n/c	n/c
	2"	60"	2"	DP8PRFN60	n/c	n/c	n/c

Ordering Information	Order Code	Included with:	Options
Triangular Frame Stacking Screen	Triangular Frame Stacking Screen	Triangular Frame Stacking Screen	NOTE: Stacking screens are compatible with DP8 Full View panels only.
1. Pattern number	<i>Example:</i> DP7SSGT1424 / 117	• Attachment hardware	Glass Options:
2. Frame finish	DP7SSGT Stack, Triangular Frame,	Note: Screens are only available in Knoll core finishes.	(G) = Clear Tempered Glass
3. Glass	w/ clear tempered glass	Note: Reveal strips for stacking screens 60" or wider must be specified separately.	(F) = Powder Glass
	117 Frame finish		

Glass Stacking Screens

Rectangular Frame Stacking Screen with Glass

Dividends Horizon

description	h*	w	t	pattern no.	P1	P2	P3
14" High Rectangular Frame Stacking Screen with Glass 	14"	24"	3"	DP7SS()R1424	\$685.	\$697.	\$711.
	14"	30"	3"	DP7SS()R1430	720.	736.	749.
	14"	36"	3"	DP7SS()R1436	757.	768.	787.
	14"	42"	3"	DP7SS()R1442	792.	807.	823.
	14"	48"	3"	DP7SS()R1448	828.	844.	861.
	14"	54"	3"	DP7SS()R1454	871.	895.	922.
	14"	60"	3"	DP7SS()R1460	914.	938.	967.
	14"	66"	3"	DP7SS()R1466	958.	987.	1,015.
	14"	72"	3"	DP7SS()R1472	1,006.	1,035.	1,067.
	14"	78"	3"	DP7SS()R1478	1,057.	1,089.	1,121.
	14"	84"	3"	DP7SS()R1484	1,109.	1,142.	1,177.
	14"	90"	3"	DP7SS()R1490	1,165.	1,201.	1,235.
	14"	96"	3"	DP7SS()R1496	1,223.	1,261.	1,297.
21" High Rectangular Frame Stacking Screen with Glass 	21"	24"	3"	DP7SS()R2124	830.	848.	863.
	21"	30"	3"	DP7SS()R2130	879.	897.	912.
	21"	36"	3"	DP7SS()R2136	926.	945.	964.
	21"	42"	3"	DP7SS()R2142	976.	993.	1,014.
	21"	48"	3"	DP7SS()R2148	1,019.	1,041.	1,065.
	21"	54"	3"	DP7SS()R2154	1,070.	1,104.	1,136.
	21"	60"	3"	DP7SS()R2160	1,124.	1,159.	1,193.
	21"	66"	3"	DP7SS()R2166	1,181.	1,217.	1,253.
	21"	72"	3"	DP7SS()R2172	1,239.	1,276.	1,315.
	21"	78"	3"	DP7SS()R2178	1,303.	1,342.	1,378.
	21"	84"	3"	DP7SS()R2184	1,368.	1,410.	1,450.
	21"	90"	3"	DP7SS()R2190	1,436.	1,480.	1,521.
	21"	96"	3"	DP7SS()R2196	1,508.	1,553.	1,596.
28" High Rectangular Frame Stacking Screen with Glass 	28"	24"	3"	DP7SS()R2824	798.	812.	830.
	28"	30"	3"	DP7SS()R2830	847.	864.	878.
	28"	36"	3"	DP7SS()R2836	895.	911.	933.
	28"	42"	3"	DP7SS()R2842	948.	965.	986.
	28"	48"	3"	DP7SS()R2848	998.	1,016.	1,033.
	28"	54"	3"	DP7SS()R2854	1,046.	1,078.	1,109.
	28"	60"	3"	DP7SS()R2860	1,097.	1,132.	1,163.
	28"	66"	3"	DP7SS()R2866	1,153.	1,188.	1,222.
	28"	72"	3"	DP7SS()R2872	1,212.	1,246.	1,283.
	28"	78"	3"	DP7SS()R2878	1,271.	1,310.	1,347.
	28"	84"	3"	DP7SS()R2884	1,335.	1,374.	1,415.
	28"	90"	3"	DP7SS()R2890	1,404.	1,444.	1,487.
	28"	96"	3"	DP7SS()R2896	1,469.	1,515.	1,559.

Panels, Build-To-Spec

Ordering Information	Order Code	Included with:	Options
Rectangular Frame Stacking Screen: 1. Pattern number 2. Frame finish 3. Glass	Rectangular Frame Stacking Screen: <i>Example:</i> DP7SSGR1424 /117 DP7SSGR Stack, Rectangular Frame, w/clear tempered glass 117 Raceway finish	Rectangular Frame Stacking Screen: • Attachment hardware Note: Screens are only available in Knoll core finishes. Note: Reveal strips for stacking screens 60" or wider must be specified separately.	NOTE: Stacking screens are compatible with DP8 Full View panels only. Glass Options: (G) = Clear Tempered Glass (F) = Powder Glass

Frameless Add Up

Frameless add ups provide additional privacy between workstations, while creating a lighter and more transparent space. Combining frameless glass add ups with Dividends Horizon panels provides a clean, light aesthetic.

Frameless add ups are available in either a standard mount or recessed into the frame. 7" and 14" heights are available, which is consistent with Dividends Horizon panel frame height increments.

Frameless add ups replace flat top caps on panels, bolting onto the panel frame. Add ups are not available in radius profile.

Frameless Glass Add Up Construction

Frameless glass add ups feature an extruded aluminum base and are available in any Knoll Core paint finish. Legacy finishes are not available.

Glass options range by thickness; 1/2" tempered glass is available in clear, acid etch, grey and bronze glass; 3/8" tempered glass in clear and frosted laminated; 1/4" tempered glass in clear and acid etch. 3/8" and 1/4" only available in recessed version.

Frameless Glass Add Up Dimensions

- Widths: 15, 18, 24, 30, 36, 42, 48, 54, 60, 66, 72, 78, 84, and 96 inches
- Heights: 7 and 14 inches
- Thickness: 3 inches

Planning with Frameless Add Ups

Standard frameless add ups attach to the top of any height Dividends or Dividends Horizon topway or full view panel frame or stack frame, regardless of production date. **Recessed add ups can only be attached to the top of topway panels.**

Frameless add ups replace the panel top cap and can span over one or more panels up to 96" wide.

Dividends Horizon frameless add ups are designed for use in same-height panel applications, and also support change of height applications involving a post connection.

Use shortened frameless add ups in change of height applications with DP5 end trims. Frameless add ups are not compatible with DP6 thin profile end trims.

End caps for standard add ups are specified for each end of a run of add ups. End caps must be specified separately and are available in packages of ten.

Note: Frameless add ups should not be used with worksurface height panels in a high-low condition. The glass will not line up with the higher panel.

Note: Recessed add up glass requires special post top caps, DP5 end trim and high low trim modified to accept glass within the frame.


Frameless Add Up Alignment Clip

A clear polycarbonate alignment clip maintains alignment between frameless add up inserts. One alignment clip is included with every frameless add up. Alignment clips do not need to be specified separately.


Shortened Frameless Glass Add Up

Use Shortened Frameless Glass Add Up in change of height applications with DP5 Hi-Lo Panel End Trim. The glass add up width is 1" shorter than the panel width. Frameless add ups are not compatible with DP6 thin profile end trims.


Standard Framless Add Up



Standard Frameless Add Up End Cap




Recessed Frameless Add Up



Shortened Frameless Glass Add Up


"Shortened" for Straight, In-Line, Hi-Lo Condition (for Hi-Lo conditions with a Post, specify Full Width Frameless Glass)




Standard Frameless Add Up

1/2" Clear, Powder, Bronze and Grey Glass

Dividends Horizon

description	w	d	h	pattern no.	list	Clear (TEMP)	Powder (GL13) Bronze (GL25) Grey (GL35)
 Frameless Add Up, 7" High	15"	1/2"	7"	DP1AU0715()G		\$278.	\$295.
	18"	1/2"	7"	DP1AU0718()G		306.	332.
	24"	1/2"	7"	DP1AU0724()G		337.	371.
	30"	1/2"	7"	DP1AU0730()G		367.	407.
	36"	1/2"	7"	DP1AU0736()G		415.	462.
	42"	1/2"	7"	DP1AU0742()G		462.	520.
	48"	1/2"	7"	DP1AU0748()G		512.	573.
	54"	1/2"	7"	DP1AU0754()G		555.	628.
	60"	1/2"	7"	DP1AU0760()G		601.	679.
	66"	1/2"	7"	DP1AU0766()G		644.	731.
	72"	1/2"	7"	DP1AU0772()G		689.	785.
	78"	1/2"	7"	DP1AU0778()G		746.	847.
	84"	1/2"	7"	DP1AU0784()G		801.	915.
	90"	1/2"	7"	DP1AU0790()G		868.	990.
	96"	1/2"	7"	DP1AU0796()G		937.	1,069.



 Shortened Frameless Add Up, 7" High	14"	1/2"	7"	DP1AU0714()G		278.	295.
	17"	1/2"	7"	DP1AU0717()G		306.	332.
	23"	1/2"	7"	DP1AU0723()G		337.	371.
	29"	1/2"	7"	DP1AU0729()G		367.	407.
	35"	1/2"	7"	DP1AU0735()G		415.	462.
	41"	1/2"	7"	DP1AU0741()G		462.	520.
	47"	1/2"	7"	DP1AU0747()G		512.	573.
	53"	1/2"	7"	DP1AU0753()G		555.	628.
	59"	1/2"	7"	DP1AU0759()G		601.	679.
	65"	1/2"	7"	DP1AU0765()G		644.	731.
	71"	1/2"	7"	DP1AU0771()G		689.	785.
	77"	1/2"	7"	DP1AU0777()G		746.	847.
	83"	1/2"	7"	DP1AU0783()G		801.	915.
	89"	1/2"	7"	DP1AU0789()G		868.	990.
	95"	1/2"	7"	DP1AU0795()G		937.	1,069.

Ordering Information	Order Code	Included with:	Options
Frameless Add Up with Clear Glass 1. Pattern number 2. Frame finish 3. Glass finish End Cap 1. Pattern number 2. Frame finish	Recessed Frameless Add Up with Clear Glass <i>Example:</i> DP1AU0736VG DP1AU Standard Frameless Add Up 07 7" High 36 36" Wide V Full view G Glass 117 Frame finish TEMP Clear glass finish	Recessed Frameless Add Up with Clear Glass - Attachment hardware - Topway Trough Spacer (Topway only) - Alignment Clip	Frame Options: (V) = Full view (C) = Topway Glass Options: (TEMP) = Clear (GL13) = Powder (GL25) = Bronze (GL35) = Grey

Standard Frameless Add Up

1/2" Clear, Powder, Bronze and Grey Glass

Dividends Horizon

description	w	d	h	pattern no.	list	Clear	Powder
						(TEMP)	(GL13)
Frameless Add Up, 14" High 	15"	1/2"	14"	DP1AU1415()G		\$340.	\$379.
	18"	1/2"	14"	DP1AU1418()G		395.	448.
	24"	1/2"	14"	DP1AU1424()G		449.	512.
	30"	1/2"	14"	DP1AU1430()G		498.	579.
	36"	1/2"	14"	DP1AU1436()G		572.	667.
	42"	1/2"	14"	DP1AU1442()G		644.	755.
	48"	1/2"	14"	DP1AU1448()G		719.	845.
	54"	1/2"	14"	DP1AU1454()G		790.	931.
	60"	1/2"	14"	DP1AU1460()G		859.	1,017.
	66"	1/2"	14"	DP1AU1466()G		932.	1,103.
	72"	1/2"	14"	DP1AU1472()G		1,003.	1,190.
	78"	1/2"	14"	DP1AU1478()G		1,082.	1,285.
	84"	1/2"	14"	DP1AU1484()G		1,170.	1,388.
	90"	1/2"	14"	DP1AU1490()G		1,263.	1,500.
	96"	1/2"	14"	DP1AU1496()G		1,366.	1,618.
Shortened Frameless Add Up, 14" High 	14"	1/2"	14"	DP1AU1414()G		340.	379.
	17"	1/2"	14"	DP1AU1417()G		395.	448.
	23"	1/2"	14"	DP1AU1423()G		449.	512.
	29"	1/2"	14"	DP1AU1429()G		498.	579.
	35"	1/2"	14"	DP1AU1435()G		572.	667.
	41"	1/2"	14"	DP1AU1441()G		644.	755.
	47"	1/2"	14"	DP1AU1447()G		719.	845.
	53"	1/2"	14"	DP1AU1453()G		790.	931.
	59"	1/2"	14"	DP1AU1459()G		859.	1,017.
	65"	1/2"	14"	DP1AU1465()G		932.	1,103.
	71"	1/2"	14"	DP1AU1471()G		1,003.	1,190.
	77"	1/2"	14"	DP1AU1477()G		1,082.	1,285.
	83"	1/2"	14"	DP1AU1483()G		1,170.	1,388.
	89"	1/2"	14"	DP1AU1489()G		1,263.	1,500.
	95"	1/2"	14"	DP1AU1495()G		1,366.	1,618.
End Cap				DP1AUECTP	53.		





Ordering Information	Order Code	Included with:	Options
Frameless Add Up with Clear Glass 1. Pattern number 2. Frame finish 3. Glass finish End Cap 1. Pattern number 2. Frame finish	Recessed Frameless Add Up with Clear Glass <i>Example:</i> DP1AU1436VG DP1AU Standard Frameless Add Up 14 14" High 36 36" Wide V Full view G Glass 117 Frame finish TEMP Clear glass finish	Recessed Frameless Add Up with Clear Glass - Attachment hardware - Topway Trough Spacer (Topway only) - Alignment Clip	Frame Options: (V) = Full view (C) = Topway Glass Options: (TEMP) = Clear (GL13) = Powder (GL25) = Bronze (GL35) = Grey

Recessed Frameless Add Up

1/2" Clear, Powder, Bronze and Grey Glass

Dividends Horizon

description	w	d	h	pattern no.	list	Clear (TEMP)	Powder (GL70)	Bronze (GL25) Grey (GL35)
Recessed Frameless Add Up, 7" High 	15"	1/2"	7"	DP1AR0715H()		\$268.	\$345.	\$425.
	18"	1/2"	7"	DP1AR0718H()		290.	355.	440.
	24"	1/2"	7"	DP1AR0724H()		314.	378.	460.
	30"	1/2"	7"	DP1AR0730H()		338.	400.	480.
	36"	1/2"	7"	DP1AR0736H()		375.	439.	533.
	42"	1/2"	7"	DP1AR0742H()		418.	494.	610.
	48"	1/2"	7"	DP1AR0748H()		460.	556.	677.
	54"	1/2"	7"	DP1AR0754H()		533.	660.	795.
	60"	1/2"	7"	DP1AR0760H()		575.	715.	870.
	66"	1/2"	7"	DP1AR0766H()		620.	764.	934.
	72"	1/2"	7"	DP1AR0772H()		659.	815.	1,007.
	78"	1/2"	7"	DP1AR0778H()		703.	848.	1,073.
	84"	1/2"	7"	DP1AR0784H()		743.	915.	1,140.
	90"	1/2"	7"	DP1AR0790H()		792.	958.	1,188.
	96"	1/2"	7"	DP1AR0796H()		840.	1,018.	1,258.

Recessed Shortened Frameless Add Up, 7" High 	14"	1/2"	7"	DP1AR0714H()		277.	345.	425.
	17"	1/2"	7"	DP1AR0717H()		285.	355.	440.
	23"	1/2"	7"	DP1AR0723H()		313.	378.	460.
	29"	1/2"	7"	DP1AR0729H()		335.	400.	480.
	35"	1/2"	7"	DP1AR0735H()		373.	439.	533.
	41"	1/2"	7"	DP1AR0741H()		415.	494.	610.
	47"	1/2"	7"	DP1AR0747H()		459.	549.	670.
	53"	1/2"	7"	DP1AR0753H()		533.	635.	770.
	59"	1/2"	7"	DP1AR0759H()		573.	688.	843.
	65"	1/2"	7"	DP1AR0765H()		613.	738.	908.
	71"	1/2"	7"	DP1AR0771H()		652.	778.	970.
	77"	1/2"	7"	DP1AR0777H()		692.	795.	1,045.
	83"	1/2"	7"	DP1AR0783H()		737.	890.	1,125.
	89"	1/2"	7"	DP1AR0789H()		788.	940.	1,170.
	95"	1/2"	7"	DP1AR0795H()		829.	999.	1,258.


Ordering Information	Order Code	Included with:	Options
Frameless Add Up with Clear Glass 1. Pattern number 2. Frame finish 3. Glass finish	Recessed Frameless Add Up with Clear Glass <i>Example:</i> DP1AR0736HTEMP117 DP1AR Recessed Frameless Add Up 07 7" High 36 36" Wide H 1/2" Thick TEMP Clear glass finish 117 Frame finish	Recessed Frameless Add Up with Clear Glass - Attachment hardware - Alignment Clip	Frame Options: Glass Options: (TEMP) = Clear (GL70) = Powder (GL25) = Bronze (GL35) = Grey

Recessed Frameless Add Up


1/2" Clear, Powder, Bronze and Grey Glass

Dividends Horizon

description	w	d	h	pattern no.	list	Clear (TEMP)	Powder (GL70)	Bronze (GL25) Grey (GL35)
Recessed Frameless Add Up, 14" High	15"	1/2"	14"	DP1AR1415H()		\$300.	\$335.	\$440.
	18"	1/2"	14"	DP1AR1418H()		348.	395.	455.
	24"	1/2"	14"	DP1AR1424H()		396.	452.	555.
	30"	1/2"	14"	DP1AR1430H()		439.	511.	660.
	36"	1/2"	14"	DP1AR1436H()		505.	588.	770.
	42"	1/2"	14"	DP1AR1442H()		567.	666.	880.
	48"	1/2"	14"	DP1AR1448H()		635.	735.	960.
	54"	1/2"	14"	DP1AR1454H()		697.	813.	1,100.
	60"	1/2"	14"	DP1AR1460H()		758.	883.	1,193.
	66"	1/2"	14"	DP1AR1466H()		822.	958.	1,318.
	72"	1/2"	14"	DP1AR1472H()		885.	1,045.	1,440.
	78"	1/2"	14"	DP1AR1478H()		955.	1,110.	1,520.
	84"	1/2"	14"	DP1AR1484H()		1,032.	1,200.	1,625.
	90"	1/2"	14"	DP1AR1490H()		1,114.	1,328.	1,788.
	96"	1/2"	14"	DP1AR1496H()		1,205.	1,433.	1,878.



Recessed Shortened Frameless Add Up, 14" High	14"	1/2"	14"	DP1AR1414H()		299.	335.	440.
	17"	1/2"	14"	DP1AR1417H()		348.	395.	455.
	23"	1/2"	14"	DP1AR1423H()		395.	452.	555.
	29"	1/2"	14"	DP1AR1429H()		440.	511.	660.
	35"	1/2"	14"	DP1AR1435H()		505.	588.	770.
	41"	1/2"	14"	DP1AR1441H()		568.	666.	880.
	47"	1/2"	14"	DP1AR1447H()		635.	735.	970.
	53"	1/2"	14"	DP1AR1453H()		697.	813.	1,115.
	59"	1/2"	14"	DP1AR1459H()		758.	883.	1,198.
	65"	1/2"	14"	DP1AR1465H()		822.	953.	1,318.
	71"	1/2"	14"	DP1AR1471H()		885.	1,045.	1,440.
	77"	1/2"	14"	DP1AR1477H()		955.	1,115.	1,525.
	83"	1/2"	14"	DP1AR1483H()		1,032.	1,200.	1,650.
	89"	1/2"	14"	DP1AR1489H()		1,114.	1,310.	1,770.
	95"	1/2"	14"	DP1AR1495H()		1,205.	1,433.	1,886.





Ordering Information	Order Code	Included with:	Options
Frameless Add Up with Clear Glass 1. Pattern number 2. Frame finish 3. Glass finish	Recessed Frameless Add Up with Clear Glass <i>Example:</i> DP1AR1436HTEMP117 DP1AR Recessed Frameless Add Up 14 14" High 36 36" Wide H 1/2" Thick TEMP Clear glass finish 117 Frame finish	Recessed Frameless Add Up with Clear Glass - Attachment hardware - Alignment Clip	Frame Options: Glass Options: (TEMP) = Clear (GL70) = Powder (GL25) = Bronze (GL35) = Grey

Recessed Frameless Add Up

3/8" Clear and Laminate Frosted

Dividends Horizon

description	w	d	h	pattern no.	Clear (TEMP)	laminate Frosted (GL60)
Recessed Frameless Add Up, 7" high 	15"	3/8"	7"	DP1AR0715W()	\$241.	\$311.
	18"	3/8"	7"	DP1AR0718W()	261.	320.
	24"	3/8"	7"	DP1AR0724W()	283.	340.
	30"	3/8"	7"	DP1AR0730W()	304.	360.
	36"	3/8"	7"	DP1AR0736W()	338.	395.
	42"	3/8"	7"	DP1AR0742W()	376.	445.
	48"	3/8"	7"	DP1AR0748W()	414.	494.
	54"	3/8"	7"	DP1AR0754W()	480.	572.
	60"	3/8"	7"	DP1AR0760W()	518.	619.
	66"	3/8"	7"	DP1AR0766W()	558.	664.
	72"	3/8"	7"	DP1AR0772W()	593.	714.
	78"	3/8"	7"	DP1AR0778W()	633.	743.
	84"	3/8"	7"	DP1AR0784W()	669.	801.
	90"	3/8"	7"	DP1AR0790W()	713.	862.
	96"	3/8"	7"	DP1AR0796W()	756.	899.
Recessed Shortened Frameless Add Up, 7" high 	14"	3/8"	7"	DP1AR0714W()	249.	311.
	17"	3/8"	7"	DP1AR0717W()	257.	320.
	23"	3/8"	7"	DP1AR0723W()	282.	340.
	29"	3/8"	7"	DP1AR0729W()	302.	360.
	35"	3/8"	7"	DP1AR0735W()	336.	395.
	41"	3/8"	7"	DP1AR0741W()	374.	445.
	47"	3/8"	7"	DP1AR0747W()	413.	503.
	53"	3/8"	7"	DP1AR0753W()	480.	579.
	59"	3/8"	7"	DP1AR0759W()	516.	633.
	65"	3/8"	7"	DP1AR0765W()	552.	666.
	71"	3/8"	7"	DP1AR0771W()	587.	714.
	77"	3/8"	7"	DP1AR0777W()	623.	743.
	83"	3/8"	7"	DP1AR0783W()	663.	810.
	89"	3/8"	7"	DP1AR0789W()	709.	862.
	95"	3/8"	7"	DP1AR0795W()	746.	899.



Panels, Build-To-Spec

Ordering Information	Order Code	Included with:	Options
Frameless Add Up with Clear Glass 1. Pattern number 2. Frame finish 3. Glass finish	Recessed Frameless Add Up with Clear Glass <i>Example:</i> DP1AR0736WTEMP117 DP1AR Recessed Frameless Add Up 07 7" High 36 36" Wide W 3/8" Thick TEMP Clear glass finish 117 Frame finish	Recessed Frameless Add Up with Clear Glass - Attachment hardware - Alignment clip	Frame Options: Glass Options: (TEMP) = Clear (GL60) = Laminated Frosted

Recessed Frameless Add Up

3/8" Clear and Laminate Frosted

Dividends Horizon

description	w	d	h	pattern no.	Clear (TEMP)	laminate Frosted (GL60)
Recessed Frameless Add Up, 14" high 	15"	3/8"	14"	DP1AR1415W()	\$270.	\$330.
	18"	3/8"	14"	DP1AR1418W()	313.	356.
	24"	3/8"	14"	DP1AR1424W()	356.	407.
	30"	3/8"	14"	DP1AR1430W()	395.	460.
	36"	3/8"	14"	DP1AR1436W()	455.	529.
	42"	3/8"	14"	DP1AR1442W()	510.	599.
	48"	3/8"	14"	DP1AR1448W()	572.	671.
	54"	3/8"	14"	DP1AR1454W()	627.	739.
	60"	3/8"	14"	DP1AR1460W()	682.	808.
	66"	3/8"	14"	DP1AR1466W()	740.	873.
	72"	3/8"	14"	DP1AR1472W()	797.	945.
	78"	3/8"	14"	DP1AR1478W()	860.	1,026.
	84"	3/8"	14"	DP1AR1484W()	929.	1,105.
	90"	3/8"	14"	DP1AR1490W()	1,003.	1,195.
	96"	3/8"	14"	DP1AR1496W()	1,085.	1,290.
Recessed Shortened Frameless Add Up, 14" high 	14"	3/8"	14"	DP1AR1414W()	269.	330.
	17"	3/8"	14"	DP1AR1417W()	313.	356.
	23"	3/8"	14"	DP1AR1423W()	356.	407.
	29"	3/8"	14"	DP1AR1429W()	396.	460.
	35"	3/8"	14"	DP1AR1435W()	455.	529.
	41"	3/8"	14"	DP1AR1441W()	511.	599.
	47"	3/8"	14"	DP1AR1447W()	572.	671.
	53"	3/8"	14"	DP1AR1453W()	627.	739.
	59"	3/8"	14"	DP1AR1459W()	682.	808.
	65"	3/8"	14"	DP1AR1465W()	740.	873.
	71"	3/8"	14"	DP1AR1471W()	797.	950.
	77"	3/8"	14"	DP1AR1477W()	860.	1,026.
	83"	3/8"	14"	DP1AR1483W()	929.	1,089.
	89"	3/8"	14"	DP1AR1489W()	1,003.	1,195.
	95"	3/8"	14"	DP1AR1495W()	1,085.	1,290.

Ordering Information

Frameless Add Up with Clear Glass

1. Pattern number
2. Frame finish
3. Glass finish

Order Code

Recessed Frameless Add Up with Clear Glass

Example: DP1AR1436WTEMP117

DP1AR Recessed Frameless Add Up

14 7" High

36 36" Wide

W 3/8" Thick

TEMP Clear glass finish

117 Frame finish

Included with:

Recessed Frameless Add Up with Clear Glass

- Attachment hardware
- Alignment Clip

Options

Frame Options:

Glass Options:



(TEMP) = Clear

(GL60) = Laminated Frosted

Recessed Frameless Add Up

1/4" Clear and Powder Glass

Dividends Horizon

description	w	d	h	pattern no.	Clear (TEMP)	Powder (GL70)
Recessed Frameless Add Up, 7" High 	15"	1/4"	7"	DP1AR0715E()	\$217.	\$264.
	18"	1/4"	7"	DP1AR0718E()	235.	272.
	24"	1/4"	7"	DP1AR0724E()	254.	289.
	30"	1/4"	7"	DP1AR0730E()	274.	306.
	36"	1/4"	7"	DP1AR0736E()	304.	336.
	42"	1/4"	7"	DP1AR0742E()	320.	378.
	48"	1/4"	7"	DP1AR0748E()	352.	420.
	54"	1/4"	7"	DP1AR0754E()	408.	486.
	60"	1/4"	7"	DP1AR0760E()	440.	526.
	66"	1/4"	7"	DP1AR0766E()	474.	565.
	72"	1/4"	7"	DP1AR0772E()	504.	607.
	78"	1/4"	7"	DP1AR0778E()	538.	646.
	84"	1/4"	7"	DP1AR0784E()	568.	681.
	90"	1/4"	7"	DP1AR0790E()	606.	733.
	96"	1/4"	7"	DP1AR0796E()	643.	764.
Recessed Shortened Frameless Add Up, 7" High 	14"	1/4"	7"	DP1AR0714E()	212.	264.
	17"	1/4"	7"	DP1AR0717E()	218.	272.
	23"	1/4"	7"	DP1AR0723E()	239.	289.
	29"	1/4"	7"	DP1AR0729E()	271.	306.
	35"	1/4"	7"	DP1AR0735E()	302.	336.
	41"	1/4"	7"	DP1AR0741E()	317.	378.
	47"	1/4"	7"	DP1AR0747E()	351.	428.
	53"	1/4"	7"	DP1AR0753E()	408.	492.
	59"	1/4"	7"	DP1AR0759E()	438.	538.
	65"	1/4"	7"	DP1AR0765E()	469.	566.
	71"	1/4"	7"	DP1AR0771E()	499.	607.
	77"	1/4"	7"	DP1AR0777E()	529.	663.
	83"	1/4"	7"	DP1AR0783E()	564.	689.
	89"	1/4"	7"	DP1AR0789E()	603.	733.
	95"	1/4"	7"	DP1AR0795E()	634.	764.



Panels, Build-To-Spec

Ordering Information	Order Code	Included with	Options
Frameless Add Up with Clear Glass 1. Pattern number 2. Frame finish 3. Glass finish	Recessed Frameless Add Up with Clear Glass <i>Example:</i> DP1AR0736ETEMP117 DP1AR Recessed Frameless Add Up 07 7" High 36 36" Wide E 1/4" Thick TEMP Clear glass finish 117 Frame finish	Recessed Frameless Add Up with Clear Glass • Attachment hardware • Topway Trough Spacer • Alignment Clip	Frame Options: Glass Options: (TEMP) = Clear (GL70) = Powder

Recessed Frameless Add Up

1/4" Clear and Powder Glass

Dividends Horizon

description	w	d	h	pattern no.	Clear (TEMP)	Powder (GL70)
Recessed Frameless Add Up, 14" High 	15"	1/4"	14"	DP1AR1415E()	\$230.	\$256.
	18"	1/4"	14"	DP1AR1418E()	266.	302.
	24"	1/4"	14"	DP1AR1424E()	303.	346.
	30"	1/4"	14"	DP1AR1430E()	336.	391.
	36"	1/4"	14"	DP1AR1436E()	386.	450.
	42"	1/4"	14"	DP1AR1442E()	434.	509.
	48"	1/4"	14"	DP1AR1448E()	486.	570.
	54"	1/4"	14"	DP1AR1454E()	533.	628.
	60"	1/4"	14"	DP1AR1460E()	580.	687.
	66"	1/4"	14"	DP1AR1466E()	629.	742.
	72"	1/4"	14"	DP1AR1472E()	677.	803.
	78"	1/4"	14"	DP1AR1478E()	731.	872.
	84"	1/4"	14"	DP1AR1484E()	789.	939.
	90"	1/4"	14"	DP1AR1490E()	852.	1,016.
	96"	1/4"	14"	DP1AR1496E()	922.	1,096.
Recessed Shortened Frameless Add Up, 14" high 	14"	1/4"	14"	DP1AR1414E()	229.	256.
	17"	1/4"	14"	DP1AR1417E()	266.	302.
	23"	1/4"	14"	DP1AR1423E()	302.	346.
	29"	1/4"	14"	DP1AR1429E()	337.	391.
	35"	1/4"	14"	DP1AR1435E()	386.	450.
	41"	1/4"	14"	DP1AR1441E()	435.	509.
	47"	1/4"	14"	DP1AR1447E()	486.	570.
	53"	1/4"	14"	DP1AR1453E()	533.	628.
	59"	1/4"	14"	DP1AR1459E()	580.	687.
	65"	1/4"	14"	DP1AR1465E()	629.	742.
	71"	1/4"	14"	DP1AR1471E()	677.	807.
	77"	1/4"	14"	DP1AR1477E()	731.	872.
	83"	1/4"	14"	DP1AR1483E()	789.	926.
	89"	1/4"	14"	DP1AR1489E()	852.	1,016.
	95"	1/4"	14"	DP1AR1495E()	922.	1,096.

Ordering Information	Order Code	Included with	Options
Frameless Add Up with Clear Glass 1. Pattern number 2. Frame finish 3. Glass finish	Recessed Frameless Add Up with Clear Glass <i>Example:</i> DP1AR0736ETEMP117 DP1AR Recessed Frameless Add Up 07 7" High 36 36" Wide E 1/4" Thick TEMP Clear glass finish 117 Frame finish	Recessed Frameless Add Up with Clear Glass • Attachment hardware • Topway Trough Spacer • Alignment clip	Frame Options: Glass Options: (TEMP) = Clear (GL70) = Powder

This page intentionally left blank

Dividends Horizon DP8 Post Assemblies

Post assemblies are required for all "L", "T", and "X" applications involving same-height panels. Included with post assemblies are the appropriate post, post cover, top cap and inside corner raceway filler.

Posts use the universal panel connection hardware, which is included with the post, for attachment.

For high-low and post-to-panel applications, posts and covers must be ordered separately by component.

Dividends Horizon Post and Trim Construction

Posts are 3" square extruded aluminum construction. Post covers are powder-coated 20 gauge steel.

Posts have cut-outs for electrical and data access that match the wire and cable channels provided by panel frames. This allows cables to be routed through the post at the topway and base raceway. Refer to the Beltway Electrical Specification page for cable routing information.

The illustrations that follow are common same-height post assembly configurations. Choose the post assembly that matches the required application.

Note: Worksurface height panels do not attach to any other panel height.

Post "L" Configuration

"L" post assembly includes:

- Universal post
- Two-way top cap
- Corner post cover
- Inside corner raceway filler
- "L" Post/Panel Top Connector

Post "T" Configuration

"T" post assembly includes:

- Universal post
- Three-way top cap
- Straight post cover
- Inside corner raceway filler
- T Post/Panel Top Connector

Post "X" Configuration

"X" post assembly includes:


- Universal post
- Four-way top cap
- Inside corner raceway filler
- X Post/Panel Top Connector

Post "X" Configuration


Trim options available:

- Radius
- Flat


Two-way Post Connection




Post and Cover Plan Views




Post "L" Configuration



Post "T" Configuration



Post "X" Configuration



Dividends Horizon DP8 Post Assemblies

L, T and X Configurations

Dividends Horizon

description	h	w	d	pattern no.	Metal P1	Metal P2	Metal P3	Veneer
Dividends Horizon Two-Way Post Assembly ("L") 	28 1/2"	3"	3"	DP8(C/V/U)PAWH2()	\$181.	\$190.	\$201.	\$575.
	36"	3"	3"	DP8(C/V/U)PA362()	181.	190.	201.	577.
	42"	3"	3"	DP8(C/V/U)PA422()	181.	190.	201.	594.
	50"	3"	3"	DP8(C/V/U)PA502()	195.	208.	216.	648.
	57"	3"	3"	DP8(C/V/U)PA572()	231.	244.	254.	752.
	64"	3"	3"	DP8(C/V/U)PA642()	231.	244.	254.	781.
	78"	3"	3"	DP8(C/V/U)PA782()	334.	354.	369.	938.

Dividends Horizon Three-Way Post Assembly ("T") 	28 1/2"	3"	3"	DP8(C/V/U)PAWH3()	188.	198.	208.	547.
	36"	3"	3"	DP8(C/V/U)PA363()	188.	198.	208.	580.
	42"	3"	3"	DP8(C/V/U)PA423()	188.	198.	208.	592.
	50"	3"	3"	DP8(C/V/U)PA503()	201.	211.	219.	619.
	57"	3"	3"	DP8(C/V/U)PA573()	231.	245.	254.	668.
	64"	3"	3"	DP8(C/V/U)PA643()	231.	245.	254.	731.
	78"	3"	3"	DP8(C/V/U)PA783()	330.	346.	367.	840.

Dividends Horizon Four-Way Post Assembly ("X") 	28 1/2"	3"	3"	DP8(C/V/U)PAWH4()	174.	183.	191.	319.
	36"	3"	3"	DP8(C/V/U)PA364()	174.	183.	191.	324.
	42"	3"	3"	DP8(C/V/U)PA424()	174.	183.	191.	325.
	50"	3"	3"	DP8(C/V/U)PA504()	183.	194.	206.	339.
	57"	3"	3"	DP8(C/V/U)PA574()	211.	220.	232.	357.
	64"	3"	3"	DP8(C/V/U)PA644()	211.	220.	232.	369.
	78"	3"	3"	DP8(C/V/U)PA784()	303.	317.	334.	429.

Post Connectors/End Trim

Ordering Information	Order Code	Included with:	Options
Post Assemblies 1. Pattern Number 2. Finish	Post Assemblies <i>Example:</i> DP8A362,5,113 613 Silver Paint Finish	Post Assemblies - Post - Post top cap - Post cover - Connecting hardware	Post Assemblies (4) = Radius Metal (5) = Flat Metal (V4) = Radius Veneer (V5) = Flat Veneer

Note: Plastic versions not available.

Dividends Horizon DP8 Post Assemblies

Recessed Add Up Glass L, T and X Configurationa

Dividends Horizon

description	h	w	d	pattern no.	Metal P1	Metal P2	Metal P3
Dividends Horizon Two-Way Post Assembly ("L") for Recessed Glass 	28 1/2"	3"	3"	DP8CPAGWH25	\$181.	\$190.	\$201.
	36"	3"	3"	DP8CPAG3625	181.	190.	201.
	42"	3"	3"	DP8CPAG4225	181.	190.	201.
	50"	3"	3"	DP8CPAG5025	195.	208.	216.
	57"	3"	3"	DP8CPAG5725	231.	244.	254.
	64"	3"	3"	DP8CPAG6425	231.	244.	254.
	78"	3"	3"	DP8CPAG7825	334.	354.	369.

Dividends Horizon Three-Way Post Assembly ("T") for Recessed Glass 	28 1/2"	3"	3"	DP8CPAGWH35	188.	198.	208.
	36"	3"	3"	DP8CPAG3635	188.	198.	208.
	42"	3"	3"	DP8CPAG4235	188.	198.	208.
	50"	3"	3"	DP8CPAG5035	201.	211.	219.
	57"	3"	3"	DP8CPAG5735	231.	245.	254.
	64"	3"	3"	DP8CPAG6435	231.	245.	254.
	78"	3"	3"	DP8CPAG7835	330.	346.	367.

Dividends Horizon Four-Way Post Assembly ("X") for Recessed Glass 	28 1/2"	3"	3"	DP8CPAGWH45	174.	183.	191.
	36"	3"	3"	DP8CPAG3645	174.	183.	191.
	42"	3"	3"	DP8CPAG4245	174.	183.	191.
	50"	3"	3"	DP8CPAG5045	183.	194.	206.
	57"	3"	3"	DP8CPAG5745	211.	220.	232.
	64"	3"	3"	DP8CPAG6445	211.	220.	232.
	78"	3"	3"	DP8CPAG7845	303.	317.	334.

Ordering Information

Post Assemblies

1. Pattern Number
2. Finish

Order Code

Post Assemblies

Example: **DP8CPAG3625,613**

DP8CPAG Pattern Number

36 Height

2 Assembly Type

5 Flat End Trim

613 Silver Paint Finish

Included with:

Post Assemblies

- Post
- Post top cap
- Post cover
- Connecting hardware

This page intentionally left blank

High-Low Post Components

High-Low panel-to-post configurations require ordering the post covers by components.

Shown are common high-low panel-to-post configurations. Choose the high-low panel-to-post configuration that matches the required application.

Posts use the universal panel connection hardware for attachment, which is included with the post.

Change of height kit is required for every WH panel connecting to taller panel or taller post.

NOTE: 28½"H panels do not attach to 36"H posts in a high-low application.

Panel-to-panel high-low applications require DP8HLCWH Change of Height Kit.

High-Low "L" Post Connector Configuration (see Figure 1)

High-Low "L" components required:

- 1 One, universal post that matches height of tallest panel DP8PO(64)
- 2 One, "one-way" post top cap DP8PT1(5)
- 3 One corner post covers that match height of tallest panel. DP8PC(64)2
- 4 One, high-low right hand post cover that matches high-low panel-to-post dimension. DP8PC(14)(R)H - Mirrored configuration would require left hand cover DP8PC(14)(L)H

High-Low "T" Post Connector Configuration A (see Figure 2)

High-Low "T" components required:

- 1 One, universal post that matches height of tallest panel DP8PO(64)
- 2 One, "two-way" top cap DP8PT2(5)
- 3 One, straight post cover that matches height of tallest panel DP8PC(64)
- 4 One, high-low right hand post cover that matches high-low panel-to-post dimension DP8PC(14)(R)H - Mirrored configuration would require a left hand cover DP8PC(14)(L)H

High-Low "T" Post Connector Configuration B (see Figure 3)

High-Low "T" components required:

- 1 One, universal post that matches height of tallest panel DP8PO(64)
- 2 One, "in-line" top cap DP8PTS(5)
- 3 One, straight post cover that matches height of tallest panel DP8PC(64)
- 4 One, high-low straight post cover that matches high-low panel-to-post dimension DP8PC(14)H

Hi-Low "T" Post Connector Configuration C (see Figure 4)

High-Low "T" components required:

- 1 One, universal post that matches height of tallest panel DP8PC(64)
- 2 One, "one-way" top cap DP8PT1(5)
- 3 One, straight post cover that matches height of tallest panel DP8PC(64)
- 4 Two, high-low right hand post covers that match high-low panel-to-post dimension DP8PC(14)(R)H - Mirrored configuration would require left hand covers DP8PC(14)(L)H

Figure 1




Figure 2




Figure 3







Figure 4




Post Top Caps




One-Way




Two-Way



Three-Way



Four-Way



Inline

High-Low "X" Post Connector Configuration A (see Figure 5)

High-Low "X" components required (best method of various options):

- 1 One universal post that matches height of tallest panel DP8PO(64)
- 2 One, "one-way" top cap assembly DP8(C/V/U)PT1(5)
- 3 One, high-low straight post cover assembly that matches high-low panel-to-post dimensions DP8PC(14)H
- 4 Two, high-low right hand post covers that match high-low panel-to-post dimensions DP8PC(14)(R)H - Mirrored configuration would require left hand covers DP8PC(14)(L)H

High-Low "X" Post Connector Configuration B (see Figure 6)

High-Low "X" components required:

- 1 One, universal post that matches height of tallest panel DP8PO(64)
- 2 One, "in-line" top cap assembly DP8(C/V/U)PTS(5)
- 3 Two, high-low straight post covers assemblies that match high-low panel-to-post dimensions DP8PC(14)H

High-Low "X" Post Connector Configuration C (see Figure 7)

High-Low "X" components required:

- 1 One, universal post that matches height of tallest panel DP8PO(64)
- 2 One, "two-way" top cap assembly DP8(C/V/U)PT2(5)
- 3 One, high-low straight post cover assembly that matches high-low panel-to-post dimension. DP8PC(14)H
- 4 One, high-low right hand post cover assembly that matches high-low panel-to-post dimension. DP8PC(14)(R)H - Mirrored configuration would require left hand cover DP8PC(14)(L)H

High-Low "X" Post Connector Configuration D (see Figure 8)

High-Low "X" components required:

- 1 One, universal post that matches height of tallest panel DP8PO(64)
- 2 One, "three-way" top cap assembly DP8(C/V/U)PT3(5)
- 3 One, high-low straight post cover assembly that matches high-low panel-to-post dimension DP8PC(14)H

Note: Change of height kit is required for every WH panel connecting to a taller panel or taller post.

Figure 5




Figure 6




Figure 7






Figure 8



Post Plan View



Post, Stack Panel Post, Post Top Caps and Inside Corner Raceway Filler

description	type	h	w	d	pattern no.	list price	P1	P2	P3	Veneer
Dividends Horizon Universal Post 		28 1/2"	3"	3"	DP8POWH	\$95.				
		36"	3"	3"	DP8PO36	95.				
		42"	3"	3"	DP8PO42	95.				
		42"	3"	3"	DP8PO50	110.				
		57"	3"	3"	DP8PO57	132.				
		64"	3"	3"	DP8PO64	132.				
		78"	3"	3"	DP8PO78	226.				

Dividends Horizon Universal Post-Four-Way High-Low 		28 1/2"	3"	3"	DP8(C/V/U)POWH4	103.				
		36"	3"	3"	DP8(C/V/U)PO364	103.				
		42"	3"	3"	DP8(C/V/U)PO424	105.				
		50"	3"	3"	DP8(C/V/U)PO504	120.				
		57"	3"	3"	DP8(C/V/U)PO574	141.				
		64"	3"	3"	DP8(C/V/U)PO644	141.				
		78"	3"	3"	DP8(C/V/U)PO784	235.				

Dividends Horizon Universal Post-Three-Way High-Low 		28 1/2"	3"	3"	DP8(C/V/U)POWH3	103.				
		36"	3"	3"	DP8(C/V/U)PO363	103.				
		42"	3"	3"	DP8(C/V/U)PO423	105.				
		50"	3"	3"	DP8(C/V/U)PO503	120.				
		57"	3"	3"	DP8(C/V/U)PO573	141.				
		64"	3"	3"	DP8(C/V/U)PO643	141.				
		78"	3"	3"	DP8(C/V/U)PO783	235.				

Ordering Information	Order Code	Included with:	Options
Post Top Cap 1. Pattern number 2. Finish	Post Top Caps <i>Example:</i> DP8PTG45 DP8PTG Pattern Number 4 Configuration 5 Flat End Trim 613 Silver Paint Finish 		Post Top Caps Options (5) = Flat Metal (V5) = Flat Veneer An inside corner raceway filler is used to block the light leak created when two raceway covers meet at a 90° connection.

Post, Stack Panel Post, Post Top Caps and Inside Corner Raceway Filler

description	type	h	w	d	pattern no.	list price	P1	P2	P3	Veneer
Dividends Horizon Universal Post-Two-Way High-Low 		28 1/2"	3"	3"	DP8(C/V/U)POWH2	\$103.				
		36"	3"	3"	DP8(C/V/U)PO362	103.				
		42"	3"	3"	DP8(C/V/U)PO422	105.				
		50"	3"	3"	DP8(C/V/U)PO502	120.				
		57"	3"	3"	DP8(C/V/U)PO572	141.				
		64"	3"	3"	DP8(C/V/U)PO642	141.				
		78"	3"	3"	DP8(C/V/U)PO782	235.				

Dividends Horizon Universal Post-Straight High-Low 		28 1/2"	3"	3"	DP8(C/V/U)POWHS	103.				
		36"	3"	3"	DP8(C/V/U)PO36S	103.				
		42"	3"	3"	DP8(C/V/U)PO42S	105.				
		42"	3"	3"	DP8(C/V/U)PO50S	120.				
		57"	3"	3"	DP8(C/V/U)PO57S	141.				
		64"	3"	3"	DP8(C/V/U)PO64S	141.				
		78"	3"	3"	DP8(C/V/U)PO78S	235.				

14" High Dividends Horizon Stack Panel Post		14 5/8"	3"	3"	DP8SPO14	98.				
---	--	---------	----	----	-----------------	-----	--	--	--	--



21" High Dividends Horizon Stack Panel Post		21 15/16"	3"	3"	DP8SPO21	99.				
---	--	-----------	----	----	-----------------	-----	--	--	--	--



Ordering Information	Order Code	Included with:	Options
Post Top Cap 1. Pattern number 2. Finish	Post Top Caps <i>Example:</i> DP8PTG45 DP8PTG Pattern Number 4 Configuration 5 Flat End Trim 613 Silver Paint Finish 		Post Top Caps Options (5) = Flat Metal (V5) = Flat Veneer An inside corner raceway filler is used to block the light leak created when two raceway covers meet at a 90° connection.


Post, Stack Panel Post, Post Top Caps and Inside Corner Raceway Filler

description	type	h	w	d	pattern no.	list price	P1	P2	P3	Veneer
28" High Dividends Horizon Stack Panel Post		29 1/4"	3"	3"	DP8SPO28	\$114.				



Worksurface Height Panel Change of Height Kit	DP7HLCWH	73.
--	-----------------	-----

Dividends Horizon
Post Top Cap Assemblies



Four-Way	1/2"	3"	3"	DP8(C/V/U)PT4()	8.	9.	9.	125.
In-line Straght	1/2"	3"	3"	DP8(C/V/U)PTS()	8.	9.	9.	121.
One-Way	1/2"	3"	3"	DP8(C/V/U)PT1()	8.	9.	9.	108.
Three-Way	1/2"	3"	3"	DP8(C/V/U)PT3()	8.	9.	9.	122.
Two-Way	1/2"	3"	3"	DP8(C/V/U)PT2()	8.	9.	9.	123.



Ordering Information	Order Code	Included with:	Options
Post Top Cap 1. Pattern number 2. Finish	Post Top Caps <i>Example:</i> DP8PTG45 DP8PTG Pattern Number 4 Configuration 5 Flat End Trim 613 Silver Paint Finish		Post Top Caps Options (5) = Flat Metal (V5) = Flat Veneer An inside corner raceway filler is used to block the light leak created when two raceway covers meet at a 90° connection.


Dividends Horizon DP8 Post Components

Post Top Caps for Recessed Glass, Filler, Connectors

Dividends Horizon

description	type	h	w	d	pattern no.	list price	P1	P2	P3
Dividends Horizon Post Top Cap Assemblies for Recessed Glass	Four-Way	1/2"	3"	3"	DP8CPTG45	\$8.	\$9.	\$9.	
	In-line Straight	1/2"	3"	3"	DP8CPTGS5	8.	9.	9.	
	One-Way	1/2"	3"	3"	DP8CPTG15	8.	9.	9.	
	Three-Way	1/2"	3"	3"	DP8CPTG35	8.	9.	9.	
	Two-Way	1/2"	3"	3"	DP8CPTG25	8.	9.	9.	






Inside Corner Raceway Filler	DP7BF	10.
------------------------------	--------------	-----



Panel to Panel Connectors	High-low (10 qty)	1 1/2"	1/2"	1/2"	DP8HLC	29.
	In Line (10 qty)	6 1/2"	3/4"	1/4"	DP8PPC	22.



Post Connectors/End Trim

Ordering Information	Order Code	Included with:	Options
Post Top Cap	Post Top Caps		Post Top Caps Options
1. Pattern number	<i>Example:</i> DP8CPTG45		(4) = Radius Metal
2. Finish	613 Silver Paint Finish		(5) = Flat Metal
			(V4) = Radius Veneer
			(V5) = Flat Veneer

An inside corner raceway filler is used to block the light leak created when two raceway covers meet at a 90° connection.

Dividends Horizon DP8 Post Components

Post Covers and High Low Post Covers

Dividends Horizon

description	h	pattern no.	Metal P1	Metal P2	Metal P3	Veneer
Dividends Horizon Post Covers Full Height "T" 	36"	DP8PC36	\$60.	\$63.	\$83.	\$273.
	42"	DP8PC42	60.	63.	83.	286.
	50"	DP8PC50	61.	67.	71.	297.
	57"	DP8PC57	70.	74.	79.	335.
	64"	DP8PC64	70.	74.	79.	386.
	78"	DP8PC78	79.	87.	90.	436.
	28 1/2"	DP8PCWH	60.	63.	83.	239.
	28 1/2" + 14"	DP8PCWHS14	126.	141.	147.	n/a
	28 1/2" + 21"	DP8PCWHS21	140.	154.	160.	n/a
	28 1/2" + 28"	DP8PCWHS28	148.	162.	168.	n/a
Dividends Horizon Post Covers Full Height "L" 	36"	DP8PC362	94.	97.	101.	327.
	42"	DP8PC422	94.	97.	101.	345.
	50"	DP8PC502	97.	102.	106.	388.
	57"	DP8PC572	104.	110.	121.	482.
	64"	DP8PC642	104.	110.	121.	498.
	78"	DP8PC782	121.	129.	132.	600.
	28 1/2"	DP8PCWH2	94.	97.	101.	329.
	28 1/2" + 14"	DP8PCWHS142	133.	147.	152.	n/a
	28 1/2" + 21"	DP8PCWHS212	142.	156.	163.	n/a
	28 1/2" + 28"	DP8PCWHS282	150.	163.	169.	n/a
Dividends Horizon High Low Post Covers 	36" - 42"	DP8PC07()	10.	12.	12.	187.
	57" - 64"	DP8PC07()	10.	12.	12.	187.
	50" - 57"	DP8PC07()	10.	12.	12.	187.
	42" - 50"	DP8PC07()	10.	12.	12.	187.
	42" - 57"	DP8PC14()	18.	28.	31.	211.
	50" - 64"	DP8PC14()	18.	28.	31.	211.
	36" - 50"	DP8PC14()	18.	28.	31.	211.
	64" - 78"	DP8PC14()	18.	28.	31.	211.
	36" - 57"	DP8PC21()	33.	34.	35.	231.
	42" - 64"	DP8PC21()	33.	34.	35.	231.
	57" - 78"	DP8PC21()	33.	34.	35.	231.
	50" - 78"	DP8PC28()	49.	53.	54.	250.
	36" - 64"	DP8PC28()	49.	53.	54.	250.
	42" - 78"	DP8PC36()	63.	70.	74.	299.
	36" - 78"	DP8PC42()	71.	78.	80.	327.
	28 1/2" - 36"	DP8PCWH36()	104.	115.	118.	n/a
	28 1/2" - 42"	DP8PCWH42()	109.	120.	124.	n/a
	28 1/2" - 50"	DP8PCWH50()	124.	139.	143.	n/a

Ordering Information

Post Covers

1. Pattern number
2. Finish

Order Code

Post Top Caps

Example: **DP8PT45**

613 Silver Paint Finish

Included with:

Options

Post Covers

Add a "V" suffix to the base pattern number for a veneer finish.

High Low Post Covers Options

(H) = Straight Condition

(RH) = Right Hand Condition

(LH) = Left Hand Condition

Two DP8HLC - Panel to Panel Connectors High-low (a.k.a utility connector assembly) ship with the hi-lo post cover.

Dividends Horizon DP8 Post Components

Post Covers and High Low Post Covers

Dividends Horizon

description	h	pattern no.	Metal P1	Metal P2	Metal P3	Veneer
Dividends Horizon	28½" - 57"	DP8PCWH57()	\$125.	\$140.	\$145.	n/a
High Low Post Covers	28½" - 64"	DP8PCWH64()	126.	141.	147.	n/a
	28½" - 78"	DP8PCWH78()	132.	145.	151.	n/a
Dividends Horizon Post	36"	DP8PC36U	147.	160.	167.	308.
Covers Full Height	42"	DP8PC42U	151.	164.	170.	335.
Double Underlap	50"	DP8PC50U	166.	182.	191.	379.
	57"	DP8PC57U	167.	184.	193.	413.
	64"	DP8PC64U	182.	202.	210.	457.
	78"	DP8PC78U	250.	274.	286.	584.
	28½"	DP8PCWHU	140.	154.	160.	284.
Dividends Horizon High Low Post Covers Double	57"-64"	DP8PC07UH	109.	120.	124.	221.
Underlap	36"-42"	DP8PC07UH	109.	120.	124.	221.
	42"-50"	DP8PC07UH	109.	120.	124.	221.
	50"-57"	DP8PC07UH	109.	120.	124.	221.
	36"-50"	DP8PC14UH	114.	125.	132.	256.
	42"-57"	DP8PC14UH	114.	125.	132.	256.
	50"-64"	DP8PC14UH	114.	125.	132.	256.
	64"-78"	DP8PC14UH	114.	125.	132.	256.
	36"-57"	DP8PC21UH	113.	124.	129.	267.
	57"-78"	DP8PC21UH	113.	124.	129.	267.
	36"-64"	DP8PC28UH	122.	134.	140.	294.
	42"-64"	DP8PC28UH	122.	134.	140.	294.
	50"-78"	DP8PC28UH	122.	134.	140.	294.

Post Connectors/End Trim

Ordering Information	Order Code	Included with:	Options
Post Covers	Post Top Caps		Post Covers
1. Pattern number	<i>Example:</i> DP8PT45		Add a "V" suffix to the base pattern number for a veneer finish.
2. Finish	613 Silver Paint Finish		High Low Post Covers Options
			(H) = Straight Condition
			(RH) = Right Hand Condition
			(LH) = Left Hand Condition
			Two DP8HLC - Panel to Panel Connectors High-low (a.k.a utility connector assembly) ship with the hi-lo post cover.

Panel End Trim

Panel end trim in one of three trim types ends a panel run.

Trim options available:

- Metal Radius
- Metal Flat

Metal trim is constructed of extruded aluminum, powder coated.

End trim includes the appropriate attachment hardware and the panel end cap for transition to panel top trim.

Thin Profile Panel End Trim

The thin profile panel end trim is an extruded aluminum end cover that is designed to attach to panel ends to provide a smooth end condition for the end of panel runs. The thin profile end trim and high low end trims are constructed of extruded aluminum with a powder coated finish. Thin profile panel end trim may only be used with panels that have been selected with the number 5 (flat metal) trim option.

High-Low Panel-to-Panel End Trim

High-low panel-to-panel end trim is used to complete straight, high-low panel-to-panel connections.

Construction and attachment is identical to panel end trim and includes attachment hardware and top/bottom end caps.

Up to ten, category 5 cables can be laid-in to carry data from the upper panel topway to the lower panel topway.

High-Low Thin Profile End Trim

High-low panel to panel end trim is used to complete straight, high-low panel to panel connections. Construction and attachment is identical to the thin profile panel end trim and includes attachment hardware. High-low thin profile end trim may only be used with panels that have been selected with the number 5 (flat metal) trim option.

Note: When using the high-low thin profile end trim, the higher and lower panels continue to use the standard full-width top cap.

Panel Top Caps

Radius and flat metal top caps are available in all panel widths.

Construction: All panel top caps are powder coated metal.


Top caps with retainer clips must be ordered when using top caps on full view panels.

Shortened High-Low Panel Top Caps


When specifying the enhanced smooth or metal panel trim for a high-low panel end trim condition, the top cap on the lower panel must be shortened by 1 inch. Panel top caps can be field cut to the new length, or shortened top caps may be ordered separately.

Note: Thin profile end trim and high low end trim are available in Knoll core finishes only.


Panel End Trim



Enhanced High-Low Panel End Trim




Thin Profile End Trim



Panel End Trim and Panel Top Caps

Panel End and High-Low Panel End

Dividends Horizon

description	type	h *	w	d	pattern no.	Metal P1	Metal P2	Metal P3	Veneer
 Panel End	28 1/2"	28 1/2"	3"	5/8"	DP()PEWH	\$73.	\$81.	\$84.	\$254.
	36"	36"	3"	5/8"	DP()PE36F	73.	81.	84.	266.
	42"	42"	3"	5/8"	DP()PE42	77.	83.	85.	284.
	28 1/2" + 14"	42 1/2"	3"	5/8"	DP()PEWHS14	84.	90.	94.	226.
	28 1/2" + 21"	49 1/2"	3"	5/8"	DP()PEWHS21	87.	95.	98.	240.
	50"	50"	3"	5/8"	DP()PE50	80.	84.	86.	319.
	28 1/2" + 28"	56 1/2"	3"	5/8"	DP()PEWHS28	89.	97.	100.	250.
	57"	57"	3"	5/8"	DP()PE57	83.	86.	88.	357.
	64"	64"	3"	5/8"	DP()PE64	83.	86.	88.	386.
	78"	78"	3"	5/8"	DP()PE78	88.	92.	96.	421.
 Panel End for Recessed Glass	28 1/2"	28 1/2"	3"	5/8"	DP5PEGWH	73.	81.	84.	
	36"	36"	3"	5/8"	DP5PEG36F	73.	81.	84.	
	42"	42"	3"	5/8"	DP5PEG42	77.	83.	85.	
	28 1/2" + 14"	42 1/2"	3"	5/8"	DP5PEGWHS14	84.	90.	94.	
	28 1/2" + 21"	49 1/2"	3"	5/8"	DP5PEGWHS21	87.	95.	98.	
	50"	50"	3"	5/8"	DP5PEG50	80.	84.	86.	
	28 1/2" + 28"	56 1/2"	3"	5/8"	DP5PEGWHS28	89.	97.	100.	
	57"	57"	3"	5/8"	DP5PEG57	83.	86.	88.	
	64"	64"	3"	5/8"	DP5PG64	83.	86.	88.	
	78"	78"	3"	5/8"	DP5PEG78	88.	92.	96.	
 Panel End, High-Low	28 1/2" - 42"	13 1/2"	3"	3/8"	DP()PEWH42	64.	72.	74.	284.
	64" - 78"	14"	3"	3/8"	DP()PE14	49.	51.	52.	226.
	36" - 50"	14"	3"	3/8"	DP()PE14	49.	51.	52.	226.
	50" - 64"	14"	3"	3/8"	DP()PE14	49.	51.	52.	226.
	42" - 57"	15"	3"	3/8"	DP()PE14	49.	51.	52.	226.
	36" - 57"	21"	3"	3/8"	DP()PE22	51.	54.	56.	240.
	57" - 78"	21"	3"	3/8"	DP()PE22	51.	54.	56.	240.
	28 1/2" - 50"	21 1/2"	3"	3/8"	DP()PEWH50	70.	77.	80.	319.
	42" - 64"	22"	3"	3/8"	DP()PE22	51.	54.	56.	240.
	50" - 78"	28"	3"	3/8"	DP()PE28	61.	65.	71.	250.
	36" - 64"	28"	3"	3/8"	DP()PE28	61.	65.	71.	250.
	28 1/2" - 57"	28 1/2"	3"	3/8"	DP()PEWH57	73.	83.	85.	357.
	28 1/2" - 64"	35 1/2"	3"	3/8"	DP()PEWH64	77.	85.	88.	387.

h* = Nominal height


Dimensions listed under h w d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Panel End 1. Pattern Number 2. Trim Finish	Panel End <i>Example:</i> DP2A PE42, 117 DP2A Pattern Number PE42 117 Soft grey	Panel End • Panel end cover • Connecting hardware	Panel End, High-Low Panel End and Top Caps Trim options (4) = Radius Metal (5) = Flat Metal (V5) = Flat Veneer
High-Low Panel End 1. Pattern Number 2. Trim Finish	High-Low Panel End <i>Example:</i> DP2A PE42 117 DP2A Pattern Number PE42 117 Soft Grey	High-Low Panel End • Panel end cover • Connecting hardware • Lower transition cap	

Panel End Trim and Panel Top Caps

Panel End and High-Low Panel End

Dividends Horizon

description	type	h *	w	d	pattern no.	Metal P1	Metal P2	Metal P3	Veneer	
	Panel End, High-Low	42" - 78"	36"	3"	3/8"	DP()PE36	\$73.	\$81.	\$84.	\$269.
		36" - 78"	42"	3"	3/8"	DP()PE42H	77.	83.	85.	289.
		28½" - 78"	49½"	3"	3/8"	DP()PEWH78	85.	91.	95.	421.
		36" - 42"	6"	3"	3/8"	DP()PE08	45.	49.	50.	197.
		50" - 57"	7"	3"	3/8"	DP()PE08	45.	49.	50.	197.
		57" - 64"	7"	3"	3/8"	DP()PE08	45.	49.	50.	197.
		28½" - 36"	7½"	3"	3/8"	DP()PEWH36	59.	68.	71.	266.
		42" - 50"	8"	3"	3/8"	DP()PE08	45.	49.	50.	197.



h* = Nominal height

Dimensions listed under h w d are actual to the nearest $\frac{1}{16}"$

Ordering Information	Order Code	Included with:	Options
Panel End 1. Pattern Number 2. Trim Finish	Panel End <i>Example:</i> DP2A PE42, 117 DP2A Pattern Number PE42 117 Soft grey High-Low Panel End <i>Example:</i> DP2A PE42 117 DP2A Pattern Number PE42 117 Soft Grey 	Panel End • Panel end cover • Connecting hardware High-Low Panel End • Panel end cover • Connecting hardware • Lower transition cap	Panel End, High-Low Panel End and Top Caps Trim options (4) = Radius Metal (5) = Flat Metal (V5) = Flat Veneer

High-Low Panel End Trim for Recessed Add Up Glass

description	type	h *	w	d	pattern no.	Metal P1	Metal P2	Metal P3
Panel End, High-Low Glass Lower Panel/ No Glass Upper	28 1/2" - 36"	7 1/2"	3"	3/8"	DP5PEGNWH36	\$59.	\$68.	\$71.
	28 1/2" - 42"	13 1/2"	3"	3/8"	DP5PEGNWH42	64.	72.	74.
	28 1/2" - 50"	21 1/2"	3"	3/8"	DP5PEGNWH50	70.	77.	80.
	28 1/2" - 57"	28 1/2"	3"	3/8"	DP5PEGNWH57	73.	83.	85.
	28 1/2" - 64"	35 1/2"	3"	3/8"	DP5PEGNWH64	77.	85.	88.
	28 1/2" - 78"	49 1/2"	3"	3/8"	DP5PEGNWH78	85.	91.	95.
	36" - 42"	6"	3"	3/8"	DP5PEGN08	45.	49.	52.
	36" - 50"	14"	3"	3/8"	DP5PEGN14	49.	51.	52.
	36" - 57"	21"	3"	3/8"	DP5PEGN22	51.	54.	56.
	36" - 64"	28"	3"	3/8"	DP5PEGN28	61.	65.	71.
	36" - 78"	42"	3"	3/8"	DP5PEGN42H	77.	83.	85.
	42" - 50"	8"	3"	3/8"	DP5PEGN08	45.	49.	52.
	42" - 57"	15"	3"	3/8"	DP5PEGN14	49.	51.	52.
	42" - 64"	22"	3"	3/8"	DP5PEGN22	51.	54.	56.
	42" - 78"	36"	3"	3/8"	DP5PEGN36	73.	81.	84.
	50" - 57"	7"	3"	3/8"	DP5PEGN08	45.	49.	52.
	50" - 64"	14"	3"	3/8"	DP5PEGN14	49.	51.	52.
	50" - 78"	28"	3"	3/8"	DP5PEGN28	61.	65.	71.
	57" - 64"	7"	3"	3/8"	DP5PEGN08	45.	49.	52.
	57" - 78"	21"	3"	3/8"	DP5PEGN22	51.	54.	56.
	64" - 78"	14"	3"	3/8"	DP5PEGN14	49.	51.	52.





h* = Nominal height

Dimensions listed under h w d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
High-Low Panel End	High-Low Panel End	High-Low Panel End	Panel End, High-Low Panel End and Top Caps
1. Pattern Number		• Panel end cover	
2. Trim Finish		• Connecting hardware	
	<i>Example:</i> DP5PEGG42H 117		Trim options
	DP5PE Pattern Number		
	GG Configuration		
	42 Height		
	117 Soft Grey		

High-Low Panel End Trim for Recessed Add Up Glass

description	type	h *	w	d	pattern no.	Metal P1	Metal P2	Metal P3
Panel End, High-Low Glass Lower Panel/ Glass Upper Panel	28 1/2" - 36"	7 1/2"	3"	3/8"	DP5PEGGWH36	\$59.	\$68.	\$71.
	28 1/2" - 42"	13 1/2"	3"	3/8"	DP5PEGGWH42	64.	72.	74.
	28 1/2" - 50"	21 1/2"	3"	3/8"	DP5PEGGWH50	70.	77.	80.
	28 1/2" - 57"	28 1/2"	3"	3/8"	DP5PEGGWH57	73.	83.	85.
	28 1/2" - 64"	35 1/2"	3"	3/8"	DP5PEGGWH64	77.	85.	88.
	28 1/2" - 78"	49 1/2"	3"	3/8"	DP5PEGGWH78	85.	91.	95.
	36" - 42"	6"	3"	3/8"	DP5PEGG08	45.	49.	52.
	36" - 50"	14"	3"	3/8"	DP5PEGG14	49.	51.	52.
	36" - 57"	21"	3"	3/8"	DP5PEGG22	51.	54.	56.
	36" - 64"	28"	3"	3/8"	DP5PEGG28	61.	65.	71.
	36" - 78"	42"	3"	3/8"	DP5PEGG42H	77.	83.	85.
	42" - 50"	8"	3"	3/8"	DP5PEGG08	45.	49.	52.
	42" - 57"	15"	3"	3/8"	DP5PEGG14	49.	51.	52.
	42" - 64"	22"	3"	3/8"	DP5PEGG22	51.	54.	56.
	42" - 78"	36"	3"	3/8"	DP5PEGG36	73.	81.	84.
	50" - 57"	7"	3"	3/8"	DP5PEGG08	45.	49.	52.
	50" - 64"	14"	3"	3/8"	DP5PEGG14	49.	51.	52.
	50" - 78"	28"	3"	3/8"	DP5PEGG28	61.	65.	71.
	57" - 64"	7"	3"	3/8"	DP5PEGG08	45.	49.	52.
	57" - 78"	21"	3"	3/8"	DP5PEGG22	51.	54.	56.
	64" - 78"	14"	3"	3/8"	DP5PEGG14	49.	51.	52.

h* = Nominal height

Dimensions listed under h w d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
High-Low Panel End	High-Low Panel End	High-Low Panel End	Panel End, High-Low Panel End and Top Caps
1. Pattern Number		• Panel end cover	
2. Trim Finish		• Connecting hardware	
	<i>Example:</i> DP5PEGG42H 117		Trim options
	DP5PE Pattern Number		
	GG Configuration		
	42 Height		
	117 Soft Grey		

High-Low Panel End Trim for Recessed Add Up Glass

description	type	h *	w	d	pattern no.	Metal P1	Metal P2	Metal P3
Panel End, High-Low No Glass Lower Panel/ Glass Upper Panel	28 1/2" - 36"	7 1/2"	3"	3/8"	DP5PENGWH36	\$59.	\$68.	\$71.
	28 1/2" - 42"	13 1/2"	3"	3/8"	DP5PENGWH42	64.	72.	74.
	28 1/2" - 50"	21 1/2"	3"	3/8"	DP5PENGWH50	70.	77.	80.
	28 1/2" - 57"	28 1/2"	3"	3/8"	DP5PENGWH57	73.	83.	85.
	28 1/2" - 64"	35 1/2"	3"	3/8"	DP5PENGWH64	77.	85.	88.
	28 1/2" - 78"	49 1/2"	3"	3/8"	DP5PENGWH78	85.	91.	95.
	36" - 42"	6"	3"	3/8"	DP5PENG08	45.	49.	52.
	36" - 50"	14"	3"	3/8"	DP5PENG14	49.	51.	52.
	36" - 57"	21"	3"	3/8"	DP5PENG22	51.	54.	56.
	36" - 64"	28"	3"	3/8"	DP5PENG28	61.	65.	71.
	36" - 78"	42"	3"	3/8"	DP5PENG42H	77.	83.	85.
	42" - 50"	8"	3"	3/8"	DP5PENG08	45.	49.	52.
	42" - 57"	15"	3"	3/8"	DP5PENG14	49.	51.	52.
	42" - 64"	22"	3"	3/8"	DP5PENG22	51.	54.	56.
	42" - 78"	36"	3"	3/8"	DP5PENGG36	73.	81.	84.
	50" - 57"	7"	3"	3/8"	DP5PENG08	45.	49.	52.
	50" - 64"	14"	3"	3/8"	DP5PENG14	49.	51.	52.
	50" - 78"	28"	3"	3/8"	DP5PENG28	61.	65.	71.
	57" - 64"	7"	3"	3/8"	DP5PENG08	45.	49.	52.
	57" - 78"	21"	3"	3/8"	DP5PENG22	51.	54.	56.
	64" - 78"	14"	3"	3/8"	DP5PENG14	49.	51.	52.

* Lower Transition Cap is included with the products on this page.

h* = Nominal height

Dimensions listed under h w d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
High-Low Panel End	High-Low Panel End	High-Low Panel End	Panel End, High-Low Panel End and Top Caps
1. Pattern Number		• Panel end cover	
2. Trim Finish		• Connecting hardware	
	<i>Example:</i> DP5PEGG42H 117		Trim options
	DP5PE Pattern Number		
	GG Configuration		
	42 Height		
	117 Soft Grey		

Thin Profile Panel End Trim and High-Low Panel End

description	type	h*	w	d	pattern no.	P1	P2	P3
Thin Profile Panel End 	28 1/2"	28 1/2"	3"	5/8"	DP6PEWH	\$114.	\$114.	\$114.
	28 1/2" + 14"	42 1/2"	3"	5/8"	DP6PEWHS14	134.	148.	153.
	28 1/2" + 21"	49 1/2"	3"	5/8"	DP6PEWHS21	145.	159.	166.
	28 1/2" + 28"	56 1/2"	3"	5/8"	DP6PEWHS28	155.	170.	176.
	36"	36"	3"	5/8"	DP6PE36F	114.	114.	114.
	42"	42"	3"	5/8"	DP6PE42	123.	123.	123.
	50"	50"	3"	5/8"	DP6PE50	136.	136.	136.
	57"	57"	3"	5/8"	DP6PE57	148.	148.	148.
	64"	64"	3"	5/8"	DP6PE64	159.	159.	159.
	78"	78"	3"	5/8"	DP6PE78	186.	186.	186.
Thin Profile Panel End High-Low 	28 1/2"-36"	36"	3"	5/8"	DP6PEWH36	82.	88.	91.
	28 1/2"-42"	42"	3"	5/8"	DP6PEWH42	90.	99.	102.
	28 1/2"-50"	50"	3"	5/8"	DP6PEWH50	99.	111.	115.
	28 1/2"-57"	57"	3"	5/8"	DP6PEWH57	110.	121.	125.
	28 1/2"-64"	64"	3"	5/8"	DP6PEWH64	122.	135.	140.
	28 1/2"-78"	78"	3"	5/8"	DP6PEWH78	145.	161.	167.
	36"-42"	6"	3"	5/8"	DP6PE08	57.	59.	59.
	36"-50"	14"	3"	5/8"	DP6PE14	74.	79.	79.
	36"-57"	21"	3"	5/8"	DP6PE22	88.	92.	92.
	36"-64"	28"	3"	5/8"	DP6PE28	101.	108.	108.
	36"-78"	42"	3"	5/8"	DP6PE42H	125.	135.	135.
	42"-50"	8"	3"	5/8"	DP6PE08	57.	59.	59.
	42"-57"	15"	3"	5/8"	DP6PE14	74.	79.	79.
	42"-64"	22"	3"	5/8"	DP6PE22	88.	92.	92.
	42"-78"	36"	3"	5/8"	DP6PE36	116.	122.	122.
	50"-57"	7"	3"	5/8"	DP6PE08	57.	59.	59.
	50"-64"	14"	3"	5/8"	DP6PE14	74.	79.	79.
	50"-78"	28"	3"	5/8"	DP6PE28	101.	108.	108.
	57"-64"	7"	3"	5/8"	DP6PE08	57.	59.	59.
	57"-78"	21"	3"	5/8"	DP6PE22	88.	92.	92.
	64"-78"	14"	3"	5/8"	DP6PE14	74.	79.	79.

h* = Nominal height


Dimensions listed under h w d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Thin Profile End Trim	Thin Profile End Trim	Thin Panel End Trim	
1. Pattern Number	<i>Example:</i> DP6PE42 117	Attachment hardware	
2. Finish	DP Dividends Panel	Note: Thin profile end trim is only available in Knoll core paint finishes.	
	6 Thin Profile		
	PE Panel End		
	42 Height		
	117 Finish		

Panel End Trim and Panel Top Caps

Topway and Full View Frame Top Caps

Dividends Horizon

description	w	pattern no.	Metal P1	Metal P2	Metal P3	Veneer
Panel Top Caps 	15"	DP()PT15	\$49.	\$51.	\$53.	\$99.
	18"	DP()PT18	49.	51.	53.	111.
	24"	DP()PT24	49.	51.	53.	126.
	30"	DP()PT30	49.	51.	53.	144.
	36"	DP()PT36	49.	51.	53.	161.
	42"	DP()PT42	49.	51.	53.	180.
	48"	DP()PT48	49.	51.	53.	205.
	54"	DP()PT54	53.	55.	57.	227.
	60"	DP()PT60	56.	58.	62.	256.
	66"	DP()PT66	62.	67.	71.	280.
	72"	DP()PT72	70.	75.	79.	296.
	78"	DP()PT78	78.	82.	85.	313.
	84"	DP()PT84	84.	87.	92.	329.
	90"	DP()PT90	90.	95.	98.	350.
	96"	DP()PT96	96.	103.	109.	370.

Post Connectors/End Trim

Ordering Information

Panel Top Cap

1. Pattern Number
2. Trim Finish

Order Code

Panel Top Cap

Example: **DP5PT18, 117**

DP5PT18 Pattern number

117 Soft Grey trim finish

Included with:

Panel Top Cap

- Panel Top Cap

Options

Panel Top Caps

Trim options


- (4) = Radius Metal
- (5) = Flat Metal
- (V4) = Radius Veneer
- (V5) = Flat Veneer

Panel End Trim and Panel Top Caps

Shortened Panel Top Caps

Dividends Horizon

description	w	pattern no.	Metal P1	Metal P2	Metal P3	Veneer
Shortened Panel Top Caps (for lower panel on high-low panel to panel application) Not for use with DP6 Thin profile panel ends	14"	DP()PT14	\$49.	\$51.	\$53.	\$99.
	17"	DP()PT17	49.	51.	53.	111.
	23"	DP()PT23	49.	51.	53.	126.
	29"	DP()PT29	49.	51.	53.	144.
	35"	DP()PT35	49.	51.	53.	161.
	41"	DP()PT41	49.	51.	53.	180.
	47"	DP()PT47	49.	51.	53.	205.
	53"	DP()PT53	53.	55.	57.	227.
	59"	DP()PT59	56.	58.	62.	256.
	65"	DP()PT65	62.	67.	71.	280.
	71"	DP()PT71	70.	75.	79.	296.
	77"	DP()PT77	78.	82.	85.	313.
	83"	DP()PT83	84.	87.	92.	329.
	89"	DP()PT89	90.	95.	98.	350.
	95"	DP()PT95	96.	103.	109.	370.



h* = Nominal height

Dimensions listed under h w d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Panel Top Cap	Panel Top Cap	Panel Top Cap	Panel Top Caps
1. Pattern Number	<i>Example:</i> DP5PT18, 117	• Panel Top Cap	Trim options
2. Trim Finish	DP5PT18 Pattern number		(4) = Radius Metal
Panel-to-Panel Top Cap Transition	117 Soft Grey trim finish		(5) = Flat Metal
1. Pattern Number			
2. Trim Finish			

This page intentionally left blank

Panel Wall Starter, Panel-to-Panel Top Cap Transition

Off-Module Panel Connector

Specifications

Dividends Horizon

Panel Wall Starter

Panel wall starters mount to reinforced building walls to begin a perpendicular topway or full view panel run. Wall starters consist of a wall bracket and upper and lower panel-mounting brackets. Wall fasteners are not included or supplied by Knoll. Choice of wall fasteners is critical and must be selected to match the wall construction, wall surface and loading conditions.

Wall starters are available in all Dividends Horizon panel heights. Black finish only.

NOTE: KNOLL, INC. ASSUMES NO RESPONSIBILITY FOR WALL CONSTRUCTION OR PERFORMANCE OF FASTENERS USED.

Off-Module Panel Connector

The off-module connector allows for panel attachment anywhere along the width of the perpendicular panel. The off-module connector can be used with same height topway or full view panels only. The connector consists of a height specific connector and attaching hardware. The 3-way (DP1PT3) or 4-way (DP1PT4) post top cap must be ordered separately when radius metal top caps are being used. Specify connector height to match panel height. Black finish only.

When using the off-module panel connector, the attached connector will deface the perpendicular fabric panel insert.

Electrical components and data cables cannot be routed through the off-module panel.


Panel-to-Panel Top Cap Transition

Top cap transitions fill the gap between panel top cap sections in straight panel-to-panel configurations.


- Construction: Trim-colored, softly-radiused molded plastic
- Size: 1" wide by 3" deep
- Attachment: Snaps between top cap sections in straight, same-height panel configurations

NOTE: PANEL-TO-PANEL TOP CAP TRANSITIONS ARE ORDERED SEPARATELY FROM PANELS.


Panel Wall Starter Connection



Off-Module Panel Connector




Panel-To-Panel Transition for Enhanced Smooth Panel Trim



Panel Wall Starter, Panel-to-Panel Top Cap Transition and Off-Module Panel Connector

Dividends Horizon

description	type	h *	h	w	d	pattern no.	Single pack list	10 pack list
 Panel/Screen Wall Starter		36"	28"	2"	3/4"	DP3PWS36	\$121.	n/a
		42"	35 3/8"	2"	3/4"	DP3PWS42	125.	n/a
		50"	42 11/16"	2"	3/4"	DP3PWS50	130.	n/a
		57"	50"	2"	3/4"	DP3PWS57	133.	n/a
		64"	57 1/4"	2"	3/4"	DP3PWS64	141.	n/a
		78"	71 7/8"	2"	3/4"	DP3PWS78	147.	n/a
Panel-to-Panel Top Cap Transition		3/4"	1"	3"		DP() TCT()	7.	74.
 Off-Module Panel Connector		36"	28"	2"	3/4"	DP2PMS36	79.	n/a
		42"	35 3/8"	2"	3/4"	DP2PMS42	79.	n/a
		50"	42 11/16"	2"	3/4"	DP2PMS50	88.	n/a
		57"	50"	2"	3/4"	DP2PMS57	91.	n/a
		64"	57 1/4"	2"	3/4"	DP2PMS64	94.	n/a
		78"	71 7/8"	2"	3/4"	DP2PMS78	113.	n/a
Radius Post Top Cap (for use with off-module panel connector when radius metal top caps are used)	three-way		1/2"	3"	3"	DP1PT3	5.	n/a
	four-way		1/2"	3"	3"	DP1PT4	5.	n/a

h* = nominal height

Dimensions listed under h w d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Panel Wall Starter	Panel Wall Starter	Panel Wall Starter	Panel Wall Starter
1. Pattern Number	<i>Example:</i> DP1 PWS 64	Off-Module Panel Connector	Off-Module Panel Connector
Off-Module Panel Connector	DP1 PW Pattern Number	Panel-to-Panel Top Cap Transition	Panel-to-Panel Top Cap Transition
1. Pattern Number	64	Note: Three-way or four-way post top cap must be ordered separately when radius metal panel top caps are being used.	Trim Option:
Panel-to-Panel Top Cap Transition	Off-Module Panel Connector		(4) = Radius Metal
1. Pattern Number	<i>Example:</i> DP1 PMS50		(5) = Flat Metal
2. Trim Finish	DP1 Pattern Number		(V4) = Radius Veneer
	PMS50		(V5) = Flat Veneer
	Panel-to-Panel Top Cap Transition		Panel-to-Panel Top Cap Transition
	<i>Example:</i> DP1 TCT, 117		Add an 'SP' suffix to the base pattern number for single pack or 'TP' suffix for a 10 pack.
	DP1 TCT Pattern Number		
	117 Soft Grey		

Dividends Horizon Wall System

The Dividends Horizon Wall System allows designers to transform the aesthetic and function of private offices.

With the use of vertical wall tracks, building walls can support worksurfaces and storage, while fabric, slatwall, and marker board tiles improve aesthetic and function.

Wall System Dimensions

The Dividends Horizon wall system is available in heights of 57, 64, 71 and 78" from the finished floor. Wall tracks are designed to be positioned 5" from top of finished floor to accommodate building base molding and uneven floors.

Horizontal elements like bottom trim channels and top trims are available on 6" increments, from 24" to 48" wide. The maximum distance between wall tracks is 48".

Wall Tracks

Wall tracks work like the vertical elements of a Dividends Horizon panel frame, and are shipped in pairs which include a left and right track. Tracks feature slotted standards on the standard Dividends Horizon 1 1/2" increment.

Wall tracks are attached to building walls at 7" height increments. Available in all Knoll Core paint finishes.

End Trim


While wall tracks are painted, end trims are available for applications where a finished end is desired. Match end trim height to wall track height.

Top Cap

Top caps are available for applications with a lower horizon height, and are optional. Top caps conceal the space between tiles and the finished wall, and the top of the wall tracks.

Bottom Channel

The bottom channel is a "J" shaped channel that supports the bottom of the lowest tile. Bottom channels are also used during the installation process to accurately set the width between left and right wall tracks.



Tile Supports

Tile supports are specified in the same manner as with Dividends Horizon panels, and are not required at the top or bottom of wall tracks, or with Slatwall. Specify Wall Track tile support mounting brackets for each tile support.

Tiles

Standard Dividends Horizon tiles are specified with Wall Tracks.

Wall tracks support monolithic or tiled applications, using standard fabric, steel, or Slatwall tiles. Specify bottom channels at the bottom of the lowest tile.

Unlike panels, Wall Tracks accommodate tile supports at 7" inch increments, increasing design flexibility. Both D1 and D2 tile supports may be used with Wall Tracks.

For tiled applications, specify standard tile supports, and DP1WTTSB tile support mounting brackets for D2 tile supports.

Worksurface Planning


Dividends Horizon worksurfaces up to 24" deep may be mounted to wall tracks, using the same cantilevers, end supports and end panels used in panel planning, and follow the same planning rules.

Wall Track Planning


Wall tracks may be positioned on 6" width increments, from 24" to a maximum of 48".

Worksurfaces are supported with standard supports, including cantilevers, end supports, and end panels. Maximum worksurface depth when cantilever supported is 24".

One overhead may be mounted on each wall track section or multiple wall mount frames can be used to support shelves and overhangs exceeding 48" w.




Post Connectors/End Trim



Wall Mount Tracks and Components

57", 64", 71" and 78" High

Dividends Horizon

description	w	h	d	pattern no.	NA Black	P1	P2	P3
 Wall Mount Tracks (pair)	1 1/2"	57"	1 1/2"	DP1WT57	\$270.	\$270.	\$297.	\$310.
	1 1/2"	64"	1 1/2"	DP1WT64	281.	281.	310.	320.
	1 1/2"	71"	1 1/2"	DP1WT71	291.	291.	320.	336.
	1 1/2"	78"	1 1/2"	DP1WT78	302.	302.	335.	345.
 End Trim for Wall Mount Tracks	1 1/2"	57"	5/8"	DP1WTET57	n/a	98.	108.	113.
	1 1/2"	64"	5/8"	DP1WTET64	n/a	108.	121.	125.
	1 1/2"	71"	5/8"	DP1WTET71	n/a	108.	121.	125.
	1 1/2"	78"	5/8"	DP1WTET78	n/a	108.	121.	125.
 Top Cap for Wall Mount Tracks	15"	3/4"	1 1/2"	DP1WTTC15	n/a	80.	88.	91.
	18"	3/4"	1 1/2"	DP1WTTC18	n/a	85.	91.	95.
	24"	3/4"	1 1/2"	DP1WTTC24	n/a	88.	96.	99.
	30"	3/4"	1 1/2"	DP1WTTC30	n/a	97.	105.	112.
	36"	3/4"	1 1/2"	DP1WTTC36	n/a	111.	122.	126.
	42"	3/4"	1 1/2"	DP1WTTC42	n/a	121.	131.	137.
	48"	3/4"	1 1/2"	DP1WTTC48	n/a	121.	131.	137.
	54"	3/4"	1 1/2"	DP1WTTC54	n/a	142.	157.	163.
	60"	3/4"	1 1/2"	DP1WTTC60	n/a	143.	158.	164.
	66"	3/4"	1 1/2"	DP1WTTC66	n/a	143.	158.	164.
	72"	3/4"	1 1/2"	DP1WTTC72	n/a	143.	158.	164.
	78"	3/4"	1 1/2"	DP1WTTC78	n/a	150.	164.	171.
	84"	3/4"	1 1/2"	DP1WTTC84	n/a	203.	220.	228.
	90"	3/4"	1 1/2"	DP1WTTC90	n/a	207.	224.	235.
	96"	3/4"	1 1/2"	DP1WTTC96	n/a	212.	232.	243.
 Bottom Tile Channel for Wall Mount Tracks	15"			DP1WTBTC15	n/a	56.	60.	64.
	18"			DP1WTBTC18	n/a	57.	62.	67.
	24"			DP1WTBTC24	n/a	60.	70.	73.
	30"			DP1WTBTC30	n/a	64.	73.	75.
	36"			DP1WTBTC36	n/a	80.	88.	91.
	42"			DP1WTBTC42	n/a	90.	98.	101.
	48"			DP1WTBTC48	n/a	101.	114.	120.

Ordering Information	Order Code	Included with:	Options
Wall Mount Tracks 1. Pattern Number 2. Paint Finish	Wall Mount Tracks <i>Example:</i> DP1WT57613 DP1WT57 Pattern Number 613 Paint Finish	Wall Mount Tracks Wall fasteners are not included or supplied by Knoll.	
End Trim for Wall Mount Tracks 1. Pattern Number 2. Paint Finish	Tile Support Brackets <i>Example:</i> DP1WTTSB DP1WT Pattern Number TSB	Bottom Tile Channel for Wall Mount Tracks • Hardware	
Top Cap for Wall Mount Tracks 1. Pattern Number 2. Paint Finish		Tile Support Brackets for Wall Mount Tracks • Hardware	
Bottom Tile Channel for Wall Mount Tracks 1. Pattern Number 2. Paint Finish			
Tile Support Brackets 1. Pattern Number			

Wall Mount Tracks and Components 57", 64", 71" and 78" High

description	w	h	d	pattern no.	NA Black	P1	P2	P3
Tile Support Brackets for Wall Mount Tracks (pair)				DP1WTTSB	\$11.	n/a	n/a	n/a



Ordering Information	Order Code	Included with:	Options
Wall Mount Tracks 1. Pattern Number 2. Paint Finish	Wall Mount Tracks <i>Example:</i> DP1WT57613 DP1WT57 Pattern Number 613 Paint Finish	Wall Mount Tracks Wall fasteners are not included or supplied by Knoll.	
End Trim for Wall Mount Tracks 1. Pattern Number 2. Paint Finish	Tile Support Brackets <i>Example:</i> DP1WTTSB DP1WT Pattern Number TSB	Bottom Tile Channel for Wall Mount Tracks • Hardware	
Top Cap for Wall Mount Tracks 1. Pattern Number 2. Paint Finish		Tile Support Brackets for Wall Mount Tracks • Hardware	
Bottom Tile Channel for Wall Mount Tracks 1. Pattern Number 2. Paint Finish			
Tile Support Brackets 1. Pattern Number			

Carpet Grippers

Carpet grippers should be specified to increase rigidity of unsupported panel runs. The carpet grippers snap onto leveling glides to prevent panel runs from shifting on carpet. The glides rotate in carpet grippers to permit leveling. Available in black finish only.

Panel-Mounted Coat Hook

The Dividends Horizon panel-mounted coat hook is made of extruded aluminum and is available in an anodized black finish or matte aluminum finish. The coat hook attaches to any Dividends Horizon panel by connecting over the top of the Dividends Horizon metal panel top caps only.

Slotted Standard Coat Hook

Independent of the top cap, the slotted standard coat hook attaches to the left or right vertical slotted standard of any Dividends Horizon panel. The die cast slotted standard coat hook is available in any of the Knoll Core paint finishes. The slotted standard coat hook is sold in packages of ten and is not compatible with laminate tiles or screens.

Panel Reveal Fillers

Panel reveal filler strips are used to cover unused vertical panel slots. Panel reveal fillers are designed to only be used with Legacy post panel applications. Panel reveal fillers should not be used with panel applications that are using DP8 posts. Panel reveal fillers are available in two thickness:

- 1/2" for panel-to-panel and panel to end trim attachment.
- 1/4" for panel-to-post attachment.


Panel reveal fillers are offered in a 74" length and are field cut to install into any Dividends Horizon panel height.

To determine the correct amount of reveal fillers to be specified, use the following formulas: For panels and end trim-2 x the number of straight panel connections plus the number of panel end trims. For panel to post connections, 4x the number of posts.


Carpet Gripper




Panel-Mounted Coat Hook
(for radius plastic and metal trim only)




Panel Reveal Fillers



Slotted Standard Coat Hook Application






Slotted Standard Coat Hook



Coat Hooks and Reveal Fillers

Carpet Grippers

Dividends Horizon

description	type	h	w	d	pattern no.	list	P1	P2	P3
Carpet Grippers 	Package of 10				DP1 CG	\$15.			
Coat Hook (For Panel Slotted Standard) 	Package of 10				DP2CHTP		176.	176.	176.
Coat Hook (For radius metal and plastic trim only) (Package of 4) 	Anodized Black Finish				DP1 CHB	153.			
	Matte Aluminum Finish				DP1 CHP	145.			
Wide Panel Reveal Filler (for panel-to-panel, panel-to-DP2/4/5 end trim or between laminate inserts) 	15 Fillers		74"		DP2PRFW15 ()	73.			
Narrow Panel Reveal Filler (for panel-to-post attachment and panel-to-DP6 end trim) 	15 Fillers		74"		DP2PRFN15 ()	55.			
Corner Panel Reveal Filler (for inside corner of DP8 post) 	15 Fillers		74"		DP2PRFIC15	210.			

Ordering Information	Order Code	Included with:	Options
Panel Rigidizer Bracket 1. Pattern Number	Panel Rigidizer Bracket <i>Example:</i> DP1 PRBL	Panel Rigidizer Bracket • Rigidizer Bracket • Set Screws	Panel Rigidizer Bracket
Panel Reveal Filler 1. Pattern Number	Panel Reveal Filler <i>Example:</i> DP1PRF N15	Panel Reveal Filler • Reveal Fillers (15 qty)	Panel Reveal Filler Note: Two narrow panel reveal fillers are required for inside corner on DP2/4/5 posts. They are used only on the outside of DP8 posts.
Slotted Standard Coat Hook 1. Pattern Number 2. Paint Finish	Slotted Standard Coat Hook <i>Example:</i> DP2CH 118 Bright White		Panel Reveal Option: (B) = Black (W) = White (G) = Grey

Coat Hooks and Reveal Fillers

Accessories

Dividends Horizon

description	type	w	d	h	pattern no.	list	lam.	V1	V2
Pencil drawer		14 1/2"	15"	1 1/4"	MM1-PD-()	\$373.	\$0.	\$0.	\$0.
Coathooks (10)					MM2-CH	112.	0.	0.	0.
Stabilizer foot		2"	13"	14"	MM1-SF-()	425.	0.	0.	0.
Carpet grips (10)	Panel				MM2-CG	34.	0.	0.	0.
	Pedestal or desk support				MM2-NCG	33.	0.	0.	0.
Replacement grommets (10)	Thick surface	3"	3"	1 3/4"	MM1WG	153.	0.	0.	0.
	Thin surface	3"	3"	1 1/4"	MM1UG	153.	0.	0.	0.
Privacy screen alignment clips, set of 10	Corner				MZ1-LS	52.	0.	0.	0.
	Straight				MZ1-SS	52.	0.	0.	0.
Sample Worksurface	Dividends Horizon Post Formed	16"	16"	1 1/4"	MSAMP1616	0.	126.	163.	338.

Order Code	Specification Information	Application Notes
Example: MM1-PD-612	<i>Specify paint finishes:</i>	Stabilizer foot attaches to connector track to stabilize panel runs.
MM1 Accessory	Pencil tray is molded plastic and available in black or clear.	Carpet grips snap under panel glides to prevent panel runs from sliding. Glide rotates in carpet grip to permit leveling.Coathooks engage below the top cap at any point on the vertical panel.
PD Height	Black: N	Pencil drawer secures underneath a worksurface.
612 Medium Grey	Clear: C	

This page intentionally left blank

Universal Gallery Panels

Dividends Horizon Universal Gallery Panels are an extensive series of laminate and veneer partitions with applications that delineate space and provide a planning alternative when the need to carry data and utilities is not required.

Universal Gallery Panel Dimensions

- Height: Worksurface Height, 36", 42", 50"
- Width: 16", 19", 20", 24", 30", 36", 42", 48", 54", 60", 66", 72", 78", 84", 90", 96"
- Thickness: 1 3/16"

Construction

Laminate

- Surface Material: .028 laminate, front and back
- Edge Material: 2mm ABS on top and bottom sides; .8mm ABS on right and left sides
- Core Material: 45lb. density, FSC Certified particle board
- Thickness: 1 3/16"

Techwood and Natural Veneer

- Surface Material: .6mm veneer, front and back
- Edge Material: .8mm ABS on top bottom, left and right sides
- Core Material: 45lb. density, FSC Certified particle board
- Thickness: 1 3/16"

Leveling Glides/ Carpet Gripper

- 1" wide x 2" long, provides 1" of vertical adjustment. Polished finish
- DPGPCG, Carpet Grippers, 10 pack, specified separately

Note: Woodgrain laminate can be specified in horizontal or vertical grain direction.

Note: Grain matching is not available with woodgrain laminate in Shared T and Extension/Return Gallery Panel applications.

Applications

Covered L: A single panel specified as either right or left-handed, Covered L applications plan as a return panel without the need for a Universal Post. Maximum overall width is 99" which includes the width of the adjacent Dividends Horizon Panel. Extensions can be added for longer runs. All hardware is included.

Covered T: A single panel specified at the end of a panel run, Covered T adds stability to a spine application with widths that are specified independently. Maximum overall width is 99" which includes the width of the adjacent Dividends Horizon Panel. Extensions can be added for longer runs. All hardware is included.

Shared T: Specified as an assembly of two gallery panels, the Shared T offers greater planning flexibility where each panel can be specified up to 96" wide and where the joint bisects the adjacent Dividends Panel. Extensions can be added for longer runs. All hardware is included.

Extensions and Returns:

Extensions are gallery panels that are added, *in-line*, to the end of an existing gallery panel to add length to a run. Maximum width is 78".

Returns are gallery panels that are added to the *face* of an existing gallery panel to add stability to a panel run or privacy to a workstation.

Intermediate:

Freestanding Intermediate Gallery

Panels are specified as an off-module divider between workstations and are not connected to the slotted standard of the spine panel run. Maximum width is 78". Extensions/ Returns cannot be added.

Panel Mounted Intermediate Gallery Panels

are specified as a divider between workstations and are connected to the Dividends Horizon Panel slotted standard to either the left or right side of the connection. Maximum width is 78". Extensions/ Returns cannot be added.

Maximum Overall Widths by Finish

(Includes width of adjacent Dividends Horizon Panel)

- 99" max. for solid color laminate
- 99" max. for horizontal woodgrain laminate
- 60" max. for vertical woodgrain laminate
- 99" max. for horizontal grain veneer
- 99" max for vertical grain veneer

Available Finishes:

Laminate

Folkstone Grey (114)
Soft Grey (117)
Bright White (118)
Pumice (119)
Natural Maple (125)
Walnut (127)
Whitened Ash (141)
Grey Ash (142)
Classic Oak (143)
Warm Ash (140)
Light Ash (139)
Graphite Pear (144)
Natural Cherry (126)

Techwood and Natural Veneer:

Techwood (V1)

Black Oak (641)
Blonde Maple (638)
Cherry (509)
Dark Mahogany (628)
Dove Grey (645)
Espresso (514)
Light Cherry (639)
Light Walnut (644)
Maple (506)
Medium Teak (513)
Medium Walnut (512)
Natural (637)

Natural Veneer (V2)

Birch with Birch Edge (037E)
Bronze Cherry (002)
Ebony (640)
Grigio (642)
Light Walnut (017)
Maple (006)
Natural Oak (020)
Old English Walnut (022)
Peacock Green Walnut (021)
Rustic Walnut (038)
White Pine (647)

Note: All laminate gallery panels may be specified with any ABS edge band including SPLY.

Note: All veneer gallery panels are offered with synthetic matching edge only.

Covered L Specification

The Covered L Gallery Panel attaches directly to the end of a Dividends Horizon Panel as a return without the need for a Universal Post. Covered L applications are specified as either right or left handed and have a maximum overall width of 99". Extension can be added to create longer runs. Returns can be added to enclose a space or provide additional stability. All hardware is included.

Follow the steps below to complete a Covered L Gallery Panel specification:

- 1. Application:** Covered L (L).
- 2. Plus Dimension:** In applications where a Return is required, choose the plus dimension: left, right or none (L, R or N). L and R add 1 $\frac{3}{16}$ " to the overall width and preserves the on-module width inside the workstation.

3. Height: Worksurface Height, 36" 42", 50"

4. Width: 16", 19", 20", 24", 30", 36", 42", 48", 54", 60", 66", 72", 78", 84", 90", 96"

Note: Widths above are the usable, on-module dimension inside the workstation, not overall dimension.

5. Handed: Choose either left or right (L or R). handedness is determined from the user's perspective within the workstation. See below.

Note: If a Plus Dimension is chosen (L or R), the handedness must match (L or R).

6. Adjacent Panel Height: Choose the height of the adjacent Dividends Horizon (50, 42, 36 or WH).

Note: Hi Lo applications with WH Dividends Panels are not supported.

7. Finish: Choose the appropriate laminate or veneer finish.

8. Laminate Grain Direction: Choose vertical or horizontal grain direction (V or H) or (~) for solid color laminate.

Note: No grain direction choice is required for solid color laminate.

Note: Woodgrain laminate is not available with grain matching in Shared T and Extension/Return Gallery Panel applications.



Note: See width limitations by finish option as referenced on the Dividends Horizon Gallery Panel Specification page.

9. Edgeband: Choose any standard synthetic edge option.


Length of Run Restriction: No Covered L Gallery Panel run can exceed 96" (usable), including extensions without lateral support for stability i.e. attaching to freestanding storage or using a Gallery Panel Return.

Product Line	Category	Application (1)	Plus Dimensions (2)	Height (3)	Width 1 (4)	Handed (5)	Adjacent Panel (6)	Finish (7)	Grain Direction (8)	Edgeband (9)
DP	GP	L	R	WH	16	R	WH	118	~	118
DP= Dividend Panel	GP= Gallery Panel	L= Covered L	R= Add 1 $\frac{3}{16}$ " to the right side L= Add 1 $\frac{3}{16}$ " to the left side N= No Added dimensions	WH= Work surface height 36= 36" Height 42= 42" Height 50= 50" Height	16= 16" Wide 19= 19" Wide 20= 20" Wide 24= 24" Wide 30= 30" Wide 36= 36" Wide 42= 42" Wide 48= 48" Wide 54= 54" Wide 60= 60" Wide 66= 66" Wide 72= 72" Wide 78= 78" Wide 84= 84" Wide 90= 90" Wide 96= 96" Wide	R= Right Handed L= Left Handed	WH: WH 36: 36" 42: 42" or 36" 50: 50", 42" or 36"	Select Finish	V= Vertical H= Horizontal ~ = Solid color lam	Select Edge Band


Gallery Panel to Dividends Horizon Panel Alignment



Covered L, Left Hand



Covered L, Right Hand



Covered L, Attachment

Covered T Specification

The Covered T Gallery Panel attaches to the end of a Dividends Horizon Panel run as a dual return without the need for a universal post. Covered T applications have widths that are specified independently and cannot exceed an overall width of 99". Extension can be added to create longer runs. Returns can be added to enclose a space or provide additional stability. All hardware included.

Follow the steps below to complete a Covered T Gallery Panel Specification:

- Application:** Covered T (T).
- Plus Dimension:** In applications where a Return(s) are required, choose the plus dimension: left, right, both or none (L, R, B or N). L and R add 1 $\frac{3}{16}$ " to the left or right sides, B adds 1 $\frac{3}{16}$ " to both left and right sides and preserves the on-module width inside the workstation.

3. Height: Worksurface Height, 36" 42", 50"

4. Width 1: 16", 19", 20", 24", 30", 36", 42", 48", 54", 60", 66", 72", 78", 84", 90", 96"

5. Width 2: 16", 19", 20", 24", 30", 36", 42", 48", 54", 60", 66", 72", 78", 84", 90", 96"

Note: Widths above are the usable, on-module dimension inside the workstation, not overall dimension.

Note: No combination of Width 1 and Width 2 can exceed 96".

6. Adjacent Panel Height: Choose the height of the adjacent Dividends Horizon (50, 42, 36 or WH).

Note: Hi Lo applications with WH Dividends Panels are not supported.

7. Finish: Choose the appropriate laminate or veneer finish.

8. Laminate Grain Direction: Choose vertical or horizontal grain direction (V or H) or (~) for solid color laminate.



Note: See width limitations by finish option as referenced on the Dividends Horizon Gallery Panel Specification page.

9. Edgeband: Choose any standard synthetic edge option.


Length of Run Restriction: No Covered T Gallery Panel run can exceed 96" (usable), including extensions without lateral support for stability i.e. attaching to freestanding storage or using a Gallery Panel Return.

Product Line	Category	Application (1)	Plus Dimensions (2)	Height (3)	Width 1 (4)	Width 2 (5)	Adjacent Panel (6)	Finish (7)	Grain Direction (8)	Edgeband (9)
DP	GP	T	R	WH	16	16	WH	118	~	118
DP= Dividend Panel	GP= Gallery Panel	T= Covered T	R= Add 1 $\frac{3}{16}$ " to the right side L= Add 1 $\frac{3}{16}$ " to the left side N= No Added dimensions	WH= Work surface height 36= 36" Height 42= 42" Height 50= 50" Height	16= 16" Wide 19= 19" Wide 20= 20" Wide 24= 24" Wide 30= 30" Wide 36= 36" Wide 42= 42" Wide 48= 48" Wide 54= 54" Wide 60= 60" Wide 66= 66" Wide 72= 72" Wide 78= 78" Wide	16= 16" Wide 19= 19" Wide 20= 20" Wide 24= 24" Wide 30= 30" Wide 36= 36" Wide 42= 42" Wide 48= 48" Wide 54= 54" Wide 60= 60" Wide 66= 66" Wide 72= 72" Wide 78= 78" Wide	WH: WH 36: 36" 42: 42" or 36" 50: 50", 42" or 36"	Select Finish	V= Vertical H= Horizontal ~ = Solid color lam	Select Edge Band


Gallery Panel to Dividends Horizon Panel Alignment




Covered T: Combination of W1 and W2 not to exceed 96"



Covered T: Overall width not to exceed 99"



50"H Covered T with 42"H Adjacent Dividends Horizon Panel



Covered T Attachment

Shared T Specification

The Shared T Gallery Panel application attaches to the end of a Dividends Horizon Panel run and specified as an assembly of two gallery panels without the need for a universal post. Shared T applications have widths that are specified independently up to 96" for greater planning flexibility and where the joints bisects the adjacent Dividends Horizon Panel. Extension can be added to create longer runs. Returns can be added to enclose a space or provide additional stability. All hardware is included.

Follow the steps below to complete a Shared T Gallery Panel specification:

- 1. Application:** Shared T (S).
- 2. Plus Dimension:** In applications where a Return(s) are required, choose the plus dimension: left, right, both or none (L, R, B or N). L and R add 1 3/16" to the left or right sides, B adds 1 3/16" to both left and right sides and preserves the on-module width inside the workstation.

3. Height: Worksurface Height, 36" 42", 50"

4. Width 1: 16", 19", 20", 24", 30", 36", 42", 48", 54", 60", 66", 72", 78", 84", 90", 96"

5. Width 2: 16", 19", 20", 24", 30", 36", 42", 48", 54", 60", 66", 72", 78", 84", 90", 96"

Note: Widths above are the usable, on-module dimension inside the workstation, not overall dimension.

6. Adjacent Panel Height: Choose the height of the adjacent Dividends Horizon (50, 42, 36 or WH)

Note: Hi Lo applications with WH Dividends Panels are not supported.

7. Finish: Choose the appropriate laminate or veneer finish.



8. Laminiate Grain Direction: Choose vertical or horizontal grain direction (V or H) or (~) for solid color laminate.

Note: See width limitations by finish option as referenced on the Dividends Horizon Gallery Panel Specification page.

9. Edgeband: Choose any standard synthetic edge option.



Length of Run Restriction: No Shared T Gallery Panel run can exceed 96" (usable), including extensions without lateral support for stability i.e. attaching to freestanding storage or using a Gallery Panel Return.

Product Line	Category	Application (1)	Plus Dimensions (2)	Height (3)	Width 1 (4)	Width 2 (5)	Adjacent Panel (6)	Finish (7)	Grain Direction (8)	Edgeband (9)
DP	GP	S	R	WH	16	16	WH	118	~	118
DP= Dividend Panel GP= Gallery Panel S= Shared T			R= Add 1 3/16" to the right side L= Add 1 3/16" to the left side N= No Added dimensions	WH= Work surface height 36= 36" Height 42= 42" Height 50= 50" Height	16= 16" Wide 19= 19" Wide 20= 20" Wide 24= 24" Wide 30= 30" Wide 36= 36" Wide 42= 42" Wide 48= 48" Wide 54= 54" Wide 60= 60" Wide 66= 66" Wide 72= 72" Wide 78= 78" Wide 84= 84" Wide 90= 90" Wide 96= 96" Wide	16= 16" Wide 19= 19" Wide 20= 20" Wide 24= 24" Wide 30= 30" Wide 36= 36" Wide 42= 42" Wide 48= 48" Wide 54= 54" Wide 60= 60" Wide 66= 66" Wide 72= 72" Wide 78= 78" Wide 84= 84" Wide 90= 90" Wide 96= 96" Wide	WH: WH 36= 36" 42= 42" or 36" 50= 50", 42" or 36"	Select Finish	V= Vertical H= Horizontal ~ = Solid color lam	Select Edge Band




Gallery Panel to Dividends Horizon Panel alignment

Shared T: W1 or W2 can exceed 96"



50"H Shared T with 42"H Adjacent Dividends Horizon Panel



Shared T Gallery Panel Connection

Extension/ Return Specification

The **Extension Gallery Panel** application attaches, in-line, to the end of an existing gallery panel to add length to a run. Maximum width is 78". All hardware is included.

The **Return Gallery Panels** application attaches the face of an existing gallery panel to add stability to a panel run or privacy to a workstation. Maximum width is 78". All hardware is included.

Note: Extensions and Returns are identical except for where the attach to an existing gallery panel.

Extension can be added to create longer runs. Returns can be added to enclose a space or provide additional stability.

Follow the steps below to complete an Extension/ Return Gallery Panel Specification:

- 1. Application:** Extension/ Return (E).
- 2. Plus Dimension:** In applications where a Return(s) are required, choose the plus dimension: left, right, both or none (L, R, B or N). L and R add 1 $\frac{3}{16}$ " to the left or right sides, B adds 1 $\frac{3}{16}$ " to both left and right sides and preserves the on-module width inside the workstation.
- 3. Height:** Worksurface Height, 36" 42", 50"
- 4. Width 1:** 16", 19", 20", 24", 30", 36", 42", 48", 54", 60", 66", 72", 78"

5. Finish: Choose the appropriate laminate or veneer finish.


6. Laminate Grain Direction: Choose vertical or horizontal grain direction (V or H) or (~) for solid color laminate.

Note: See width limitations by finish option as referenced on the Dividends Horizon Gallery Panel Specification page.



7. Edgeband: Choose any standard synthetic edge option.

Length of Run Restriction: No Shared T Gallery Panel run can exceed 96" (usable), including extensions without lateral support for stability i.e. attaching to freestanding storage or using a Gallery Panel Return.

Product Line	Category	Application (1)	Plus Dimensions (2)	Height (3)	Width 1 (4)	Finish (5)	Grain Direction (6)	Edgeband (7)
DP	GP	E	R	WH	16	118	~	118
DP= Dividend Panel	GP= Gallery Panel	E= Extension	R= Add 1 $\frac{3}{16}$ " to the right side L= Add 1 $\frac{3}{16}$ " to the left side N= No Added dimensions	WH= Work surface height 36= 36" Height 42= 42" Height 50= 50" Height	16= 16" Wide 19= 19" Wide 20= 20" Wide 24= 24" Wide 30= 30" Wide 36= 36" Wide 42= 42" Wide 48= 48" Wide 54= 54" Wide 60= 60" Wide 66= 66" Wide 72= 72" Wide 78= 78" Wide	Select Finish	V= Vertical H= Horizontal ~ = Solid color lam	Select Edge Band



Covered T with an Extension Gallery Panel to create a longer run



Attached storage or Return Gallery Panel for stability on ALL runs that exceed 96"

Intermediate Specification

The Intermediate Gallery Panel application can be specified as either Freestanding or Panel Mounted.

Freestanding Intermediate Gallery Panels are specified as an off-module divider between workstations and are not connected to the Dividends Horizon slotted standard. Maximum width is 78". Extensions/ Returns cannot be added.

Dividends Horizon Freestanding Feet (DPGPFF) are offered in pairs. Two (2) pairs are required to complete the assembly and are ordered separately.

Note: Freestanding Intermediate applications are best suited for 42" and wider Gallery Panels.

Panel Mounted Intermediate Gallery Panels are specified as a divider between workstations and are connected to the Dividends Horizon Panel slotted standard. Maximum width is 78". Extensions/Returns cannot be added to intermediate gallery panels.


Dividends Horizon Gallery Panel Brackets (DPGPPB) are offered in pairs, either left or right handed. One (1) pair is required to complete the assembly and are ordered separately.

Note: Panel Mounted Intermediate applications are best suited for 16"-36" wide Gallery Panels.


Follow the steps below to complete an Extension/ Return Gallery Panel Specification:

- 1. **Application:** Intermediate (I).
- 2. **Height:** Worksurface Height, 36" 42", 50"
- 3. **Width 1:** 16", 19", 20", 24", 30", 36", 42", 48", 54", 60", 66", 72", 78"
- Note:** Widths above are the usable, on-module dimension inside the workstation, not overall dimension.
- 4. **Finish:** Choose the appropriate laminate or veneer finish.
- 5. **Laminate Grain Direction:** Choose vertical or horizontal grain direction (V or H) or (~) for solid color laminate.
- Note:** See width limitations by finish option as referenced on the Dividends Horizon Gallery Panel Specification page.
- 6. **Edgeband:** Choose any standard synthetic edge option.



Product Line	Category	Application (1)	Height (2)	Width 1 (3)	Finish (4)	Grain Direction (5)	Edgeband (6)
DP	GP	I	WH	16	118	~	118
DP= Dividend Panel	GP= Gallery Panel	I= Intermediate	WH= Work surface height 36= 36" Height 42= 42" Height 50= 50" Height	16= 16" Wide 19= 19" Wide 20= 20" Wide 24= 24" Wide 30= 30" Wide 36= 36" Wide 42= 42" Wide 48= 48" Wide 54= 54" Wide 60= 60" Wide 66= 66" Wide 72= 72" Wide 78= 78" Wide	Select Finish	V= Vertical H= Horizontal ~ = Solid color lam	Select Edge Band




Intermediate Gallery Panel with Freestanding Feet




Gallery Panel, Freestanding Feet, DPGPFF




Left-Hand Panel Bracket DPGPPBL



Right-Hand Panel Bracket DPGPPBR



Intermediate Gallery Panel with Left-Hand Panel Bracket




Intermediate Gallery Panel with Right-Hand Bracket

Universal Gallery Panels


Gallery Panel Components

Dividends Horizon

description	w	h	d	pattern no.	list	P1	P2	P3
Gallery Panel Freestanding Feet (Pair)	4"	3"	5"	DPGPFF		\$239.	\$247.	\$250.



Gallery Panel Panel Brackets (Pair)	1"	3"		DPGPPB(L/R)	65.	0.	0.	0.
Available in black only.								



Gallery Panel Carpet Grippers (10 per pack)	3/4"	1/8"	3/4"	DPGPCG	14.	0.	0.	0.
Available in black only.								



Ordering Information	Order Code	Included with:	Options:
Concealed Post 1. Pattern Number 2. Paint Finish Code	Concealed Post <i>Example:</i> DP8PO42CPF DP8PO42 Pattern Number CPF	Concealed Post • Tile to floor filler	Post Top Cap Option: (4) = Radius Profile (5) = Flat Profile
Concealed Post Top Caps 1. Pattern Number 2. Paint Finish Code	Concealed Post Top Caps <i>Example:</i> DP8PTCP5 DP8PTCP Pattern Number 5 Flat profile 613 Silver paint finish	Concealed Post Top Caps	

This page intentionally left blank

Concealed Post Planning Guidelines Specifications

Dividends Horizon

Concealed Post

Concealed posts eliminate visible post covers, creating a seamless aesthetic at three-way post connections. Larger widths of fabric or laminate tile-to-floor tiles are used to hide the concealed post. Panel top caps, up to 99" long, span concealed posts, which eliminate the need for post top caps. Concealed post applications are specified by individual components through "Build-to-Spec".

Planning with Concealed Posts

Concealed posts are to be used in three-way post conditions where straight post covers want to be eliminated. The concealed post should be specified in place of a standard Dividends Horizon DP8 post. Concealed post fabric or laminate tiles must be specified in the tile location that is covering the post. (See illustration below) Concealed post, half post or centered fabric and laminate tiles are designed to cover the concealed post with the edge

of the tile ending in the center of the concealed post. Only concealed post fabric and laminate tile sizes are compatible with concealed posts.


A high low condition may be created by having a perpendicular panel at a lower height than the concealed post. Specify the height of the concealed post to be at the same height as the higher panels. A concealed post high low top cap must be specified in this situation. Panel top caps that span concealed posts are not designed for use in high-low concealed post applications, standard width panel top caps and a concealed post high low top cap should be used instead. A DP8 straight high low post cover should be specified in a concealed post high low application.

The two panels on the straight side of the three-way concealed post intersection must always be the same height. The concealed post is not designed to change height on the concealed post side of the three-way connection.


Concealed post panel top caps and frameless add ups are 3" wider than standard sizes, for applications that span the concealed post. Panel top caps are available in lengths up to 99". Any concealed post application requiring panel top caps longer than 99" must specify panel top caps equal to the width of a panel or combination of panels and a concealed post same height top cap. Concealed post fabric and laminate tiles, post top caps, panel top caps, and frameless add ups are designed for use with the concealed post only.

Note: Concealed posts and corresponding components are not compatible with Dividends Horizon DP8 posts, Legacy posts, standard post top caps, or standard fabric or laminate tile sizes.

Concealed Post Connection Plan View



Concealed Post Application



Concealed Post Construction

Concealed posts are a square extruded aluminum construction. They have cut-outs for electrical and data access that match the wire and cable channels provided by panel frames. This allows cables to be routed through the post at the topway and base raceway.

Concealed Post Same Height Top Cap

When all three panels in a concealed post application are the same height and standard length panel top caps are used, a concealed post same height top cap must be specified. A concealed post same height top cap covers the top of a concealed post and connects three panel top caps at the same height. (See illustration below)

Concealed Post High Low Top Cap

When the perpendicular panel in a three-way concealed post application is a lower height than the concealed post, a concealed post high low top cap must be specified. A concealed post high low top

cap covers the top of the concealed post and connects the two same height panel top caps. (See illustration below) A DP8 high low straight post cover should be specified in a concealed post high low application.

Concealed Post Top Cap Construction

Concealed post flat and radius profile top caps are constructed of cast aluminum and powder coated in all core paint finishes.

Concealed Post Panel Top Caps

Concealed post panel top caps are 3" longer than standard panel top cap widths, so they can span over a concealed post. Concealed post panel top caps are available in flat profile metal. Concealed post panel top caps that span a concealed post must be used in same height applications only. High low concealed post conditions must use concealed post high low top caps. (See illustration below)


Concealed Post Shortened Panel Top Caps

Concealed post shortened panel tops are 3" longer than standard shortened panel top cap widths, so they can span over a concealed post. A concealed post shortened panel top cap must be specified for the lower panel in a high low panel-to-panel condition when the panel top cap of the lower panel is spanning over the concealed post. (See illustration below) When the lower panel top cap is not spanning over the concealed post because a concealed post top cap is being used, specify standard shortened panel top cap widths. Standard DP5 high low panel end trim should be specified with concealed post shortened panel top caps in high low panel-to-panel applications.


Concealed Post Panel Top Cap Construction

Concealed post panel top caps are constructed of roll-formed steel.


Concealed Post




Concealed Post Same Height Top Cap




Concealed Post High Low Top Cap



Concealed Post Panel Top Cap



Concealed Post Shortened Panel Top Cap



Concealed Post

Post Components

Post and Post Top Caps Assemblies

Dividends Horizon

description	w	h	d	pattern no.	P1	P2	P3
Concealed Post	3"	28 1/2"	3"	DP8(C/V/U)POWHCPF	\$156.	\$156.	\$156.
	3"	36"	3"	DP8(C/V/U)PO36CPF	177.	177.	177.
	3"	42"	3"	DP8(C/V/U)PO42CPF	191.	191.	191.
	3"	50"	3"	DP8(C/V/U)PO50CPF	208.	208.	208.
	3"	57"	3"	DP8(C/V/U)PO57CPF	222.	222.	222.
	3"	64"	3"	DP8(C/V/U)PO64CPF	248.	248.	248.
Concealed Post Same Height Top Caps	3"	1/2"	3"	DP8(C/V/U)PTCP()	12.	15.	16.
							
Concealed Post High Low Top Caps	3"	1/2"	3"	DP8(C/V/U)PTCPH()	12.	15.	16.
							
Concealed Post Same Height Top Caps for Recessed Add Up Glass	3"	1/2"	3"	DP8CPTCPG5	12.	15.	16.
							
Concealed Post High Low Top Caps for Recessed Add Up Glass	3"	1/2"	3"	DP8CPTCPHG5	12.	15.	16.
							

Ordering Information

Concealed Post

1. Pattern Number
2. Paint Finish Code

Concealed Post Top Caps

1. Pattern Number
2. Paint Finish Code

Order Code

Concealed Post

Example: **DP8PO42CPF**

DP8PO42 Pattern Number

CPF

U Panel Type

PO36CPF Pattern number

613 Silver Paint finish

Concealed Post Top Caps

Example: **DP8PTCP5613**

DP8PTCP Pattern Number

5 Flat profile

613 Silver paint finish

Included with:

Concealed Post

- Tile to floor filler

Concealed Post Top Caps

Options:

Concealed Post Option:



- C** = Topway panel
- V** = Full view panel
- U** = Universal panel

Post Top Cap Option:

- (4)** = Radius Profile
- (5)** = Flat Profile

Concealed Post Post Components Panel Top Caps

Dividends Horizon

description	w	h	d	pattern no.	P1	P2	P3
Concealed Post Panel Top Caps 	33"	1/2"	3"	DP5(C/V/U)PT30CP	\$85.	\$93.	\$96.
	39"	1/2"	3"	DP5(C/V/U)PT36CP	86.	94.	97.
	51"	1/2"	3"	DP5(C/V/U)PT48CP	88.	95.	98.
	63"	1/2"	3"	DP5(C/V/U)PT60CP	89.	96.	99.
	75"	1/2"	3"	DP5(C/V/U)PT72CP	92.	98.	102.
	87"	1/2"	3"	DP5(C/V/U)PT84CP	94.	102.	105.
	99"	1/2"	3"	DP5(C/V/U)PT96CP	95.	103.	106.
Concealed Post Shortened Panel Top Caps 	32"	1/2"	3"	DP5(C/V/U)PT29CP	85.	93.	96.
	38"	1/2"	3"	DP5(C/V/U)PT35CP	86.	94.	97.
	50"	1/2"	3"	DP5(C/V/U)PT47CP	88.	95.	98.
	62"	1/2"	3"	DP5(C/V/U)PT59CP	89.	96.	99.
	74"	1/2"	3"	DP5(C/V/U)PT71CP	92.	98.	102.
	86"	1/2"	3"	DP5(C/V/U)PT83CP	94.	102.	105.
	98"	1/2"	3"	DP5(C/V/U)PT95CP	95.	103.	106.

Ordering Information	Order Code	Included with:	Options:
Concealed Post Panel Top Caps 1. Pattern Number 2. Paint Finish Code	Concealed Post Panel Top Caps <i>Example:</i> DP5PT48CP DP5PT48 Pattern Number CP 117 Soft Grey paint finish	Concealed Post Panel Top Caps • Panel Top Caps	Trim Option: (5) = Metal, Flat

Concealed Post Monolithic Panel Inserts Specifications

Concealed Post Monolithic Inserts

Concealed post monolithic inserts are designed to cover a concealed post and eliminate the need for a post cover. Concealed post monolithic tile-to-floor fabric inserts create a seamless aesthetic at a three-way connection. There are three types of concealed post monolithic tiles: half post, centered, and double with post. Concealed post monolithic inserts can be fabric or laminate and are only available tile-to-floor. Concealed post applications are specified by individual components through "Build-to-Spec".

Concealed Post Monolithic Insert Construction

Fabric Tiles

Fabric laminated with adhesive and heat-cured to 7/18" thick acoustical board.

Laminate Tiles

The surface material is laminate on the front and back of a particle board core. Overall thickness is 7/16" with a 0.5 edgeband.

Concealed Post Monolithic Insert Attachment

Fabric Tiles

Panel inserts flex to attach to the troughs in the upper and lower horizontal frame supports. Mounting clips are attached to panel inserts for connection to the vertical frame for additional support. No tools are required for insert attachment.

Laminate Tiles

Laminate tiles are installed one side or both sides of a panel frame. Mounting clips are attached to laminate inserts for connection to the panel frame.


Planning with Concealed Post Half Post Tiles

Half post tiles attach to a panel frame or combination of panel frames that are connected to a concealed post. This type of tile covers the entire width of the panel frame(s) and half of the concealed post. Half post tiles are 1-1/2" wider than standard tile widths


to cover half of the concealed post. Half post tiles are handed, either left or right.

The left edge of a left half post tile ends in the middle of a concealed post and the right edge of the tile ends on the furthest right edge of the panel(s). The right edge of a right half post tile ends in the middle of a concealed post and the left edge of the tile ends on the left side of the panel(s). (See illustration below) A half post tile must be used with either another half post tile or a centered tile, so the other half of the post is concealed by a tile.

Half Post Tile Application



Half Post Tile Plan View



Concealed Post

Monolithic Panel Inserts and Frameless Add Ups

Specifications

Dividends Horizon

Planning with Concealed Post Centered Tiles

Centered tiles attach to a panel frame or combination of panel frames that are connected to concealed posts. Centered tiles are centered on a panel frame(s) between two concealed posts. The left and right edge of the tile ends in the center of a concealed post. A centered tile is 3" wider than standard tile widths. Centered tiles must be centered on the panel frame(s) between the concealed posts. Neither the right nor left edge of a centered tile is able to end anywhere other than the center of a concealed post. (See illustration below) A centered tile must be used with either a half post tile or another centered tile, so the other half of the post is concealed by a tile.

Planning with Concealed Post Double with Post Tiles


A double with post tile attaches to two panel frames that are connected by a concealed post. The tile attaches to the panels and hides the concealed post connection. The concealed post must be between the panel frames. Double with post tiles are 3" wider than standard tile widths, so that they are able to cover a concealed post. (See illustration below) Neither the right nor left edge of a double with post tile is able to end anywhere other than the right or left edge of a panel frame.

Concealed Post Frameless Add Ups


Concealed post frameless add ups are 3" longer than standard frameless add up lengths, so they can span over a concealed post. Concealed post frameless add ups are not compatible with Dividends Horizon DP8 or Legacy posts.

Note: Concealed posts and corresponding components are not compatible with Dividends Horizon DP8 posts, Legacy posts, standard post top caps, or standard fabric or laminate tile sizes.


Double With Post Tile Application




Centered Tile Application



Double With Post Tile Plan View



Centered Tile Plan View



*Monolithic Panel Half Post Fabric Inserts**Worksurface Height, 28" and 42" High*

description	w *	w	h	d	pattern no.	10	20	30	40
Worksurface Height Concealed Post	15"	16 1/2"	27 1/4"	7/16"	DP1SOWH15()F	\$135.	\$145.	\$152.	\$157.
Monolithic Panel Half Post	18"	19 1/2"	27 1/4"	7/16"	DP1SOWH18()F	152.	164.	169.	175.
Fabric Inserts	24"	25 1/2"	27 1/4"	7/16"	DP1SOWH24()F	167.	179.	187.	193.
	30"	31 1/2"	27 1/4"	7/16"	DP1SOWH30()F	182.	195.	204.	214.
	36"	37 1/2"	27 1/4"	7/16"	DP1SOWH36()F	196.	216.	223.	231.
	42"	43 1/2"	27 1/4"	7/16"	DP1SOWH42()F	214.	230.	239.	245.
	48"	49 1/2"	27 1/4"	7/16"	DP1SOWH48()F	229.	244.	256.	265.
	60"	61 1/2"	27 1/4"	7/16"	DP1SOWH60()F	239.	259.	274.	282.
28" High Concealed Post	15"	16 1/2"	33 13/16"	7/16"	DP1SO2815()F	136.	119.	125.	130.
Monolithic Panel Half Post	18"	19 1/2"	33 13/16"	7/16"	DP1SO2818()F	155.	148.	157.	161.
Fabric Inserts	24"	25 1/2"	33 13/16"	7/16"	DP1SO2824()F	175.	180.	189.	194.
(For 36"H Panel Frame)	30"	31 1/2"	33 13/16"	7/16"	DP1SO2830()F	194.	210.	221.	229.
	36"	37 1/2"	33 13/16"	7/16"	DP1SO2836()F	216.	239.	251.	261.
	42"	43 1/2"	33 13/16"	7/16"	DP1SO2842()F	233.	274.	284.	292.
	48"	49 1/2"	33 13/16"	7/16"	DP1SO2848()F	251.	274.	286.	294.
	60"	61 1/2"	33 13/16"	7/16"	DP1SO2860()F	266.	289.	301.	311.
42" High Concealed Post	15"	16 1/2"	41 3/16"	7/16"	DP1SO4215()F	140.	153.	160.	167.
Monolithic Panel Half Post	18"	19 1/2"	41 3/16"	7/16"	DP1SO4218()F	166.	178.	186.	193.
Fabric Inserts	24"	25 1/2"	41 3/16"	7/16"	DP1SO4224()F	187.	203.	214.	220.
	30"	31 1/2"	41 3/16"	7/16"	DP1SO4230()F	210.	229.	237.	244.
	36"	37 1/2"	41 3/16"	7/16"	DP1SO4236()F	233.	251.	263.	275.
	42"	43 1/2"	41 3/16"	7/16"	DP1SO4242()F	254.	278.	289.	299.
	48"	49 1/2"	41 3/16"	7/16"	DP1SO4248()F	280.	301.	314.	325.
	60"	61 1/2"	41 3/16"	7/16"	DP1SO4260()F	296.	322.	336.	350.

w* = nominal width

Dimensions listed under w h d are actual to the nearest 1/16

Ordering Information	Order Code	Included with:	Options
Concealed Post Monolithic Panel Fabric Inserts	Concealed Post Monolithic Panel Fabric Inserts	Concealed Post Monolithic Panel Fabric Inserts	Concealed Post Monolithic Panel Fabric Inserts
1. Pattern Number	<i>Example:</i> DP1SO2818CE	• Attachment Clips	Configuration:
2. Fabric	DP1SO Pattern Number		(CE) = Left Half Post: Tile ends in the center of the post on the left and at the right side of the panel frame.
	2818		(EC) = Right Half Post: Tile ends in the center of the post on the right and at the left side of the panel frame.
	CE Center left, End Right		
	F Tile to Floor		
	W1077 Element		

Concealed Post

Monolithic Panel Half Post Fabric Inserts

50", 57" and 64" High

Dividends Horizon

description	w *	w	h	d	pattern no.	10	20	30	40
50" High Concealed Post Monolithic Panel Half Post Fabric Inserts 	15"	16 1/2"	48 1/2"	7/16"	DP1SO5015()F	\$145.	\$155.	\$164.	\$169.
	18"	19 1/2"	48 1/2"	7/16"	DP1SO5018()F	173.	185.	193.	198.
	24"	25 1/2"	48 1/2"	7/16"	DP1SO5024()F	197.	217.	226.	232.
	30"	31 1/2"	48 1/2"	7/16"	DP1SO5030()F	227.	242.	253.	263.
	36"	37 1/2"	48 1/2"	7/16"	DP1SO5036()F	252.	274.	286.	294.
	42"	43 1/2"	48 1/2"	7/16"	DP1SO5042()F	280.	301.	316.	325.
	48"	49 1/2"	48 1/2"	7/16"	DP1SO5048()F	305.	331.	347.	359.
	60"	61 1/2"	48 1/2"	7/16"	DP1SO5060()F	329.	356.	368.	384.
57" High Concealed Post Monolithic Panel Half Post Fabric Inserts 	15"	16 1/2"	55 3/8"	7/16"	DP1SO5715()F	150.	161.	168.	174.
	18"	19 1/2"	55 3/8"	7/16"	DP1SO5718()F	180.	194.	201.	210.
	24"	25 1/2"	55 3/8"	7/16"	DP1SO5724()F	214.	229.	237.	244.
	30"	31 1/2"	55 3/8"	7/16"	DP1SO5730()F	240.	261.	274.	283.
	36"	37 1/2"	55 3/8"	7/16"	DP1SO5736()F	274.	292.	305.	317.
	42"	43 1/2"	55 3/8"	7/16"	DP1SO5742()F	303.	325.	341.	355.
	48"	49 1/2"	55 3/8"	7/16"	DP1SO5748()F	334.	360.	375.	389.
	60"	61 1/2"	55 3/8"	7/16"	DP1SO5760()F	360.	388.	404.	417.
64" High Concealed Post Monolithic Panel Half Post Fabric Inserts 	15"	16 1/2"	63 1/16"	7/16"	DP1SO6415()F	152.	164.	170.	175.
	18"	19 1/2"	63 1/16"	7/16"	DP1SO6418()F	186.	198.	210.	219.
	24"	25 1/2"	63 1/16"	7/16"	DP1SO6424()F	223.	238.	247.	256.
	30"	31 1/2"	63 1/16"	7/16"	DP1SO6430()F	254.	277.	289.	299.
	36"	37 1/2"	63 1/16"	7/16"	DP1SO6436()F	290.	313.	329.	340.
	42"	43 1/2"	63 1/16"	7/16"	DP1SO6442()F	325.	352.	366.	380.
	48"	49 1/2"	63 1/16"	7/16"	DP1SO6448()F	361.	389.	407.	421.
	60"	61 1/2"	63 1/16"	7/16"	DP1SO6460()F	391.	420.	443.	458.

w* = nominal width

Dimensions listed under w h d are actual to the nearest 1/16

Ordering Information	Order Code	Included with:	Options
Concealed Post Monolithic Panel Fabric Inserts 1. Pattern Number 2. Fabric	Concealed Post Monolithic Panel Fabric Inserts <i>Example:</i> DP1SO5718CEF DP1SO Pattern Number 5718 CE Center left, End Right F Tile to Floor W1077 Element	Concealed Post Monolithic Panel Fabric Inserts • Attachment Clips	Concealed Post Monolithic Panel Fabric Inserts Configuration: (CE) = Left Half Post: Tile ends in the center of the post on the left and at the right side of the panel frame. (EC) = Right Half Post: Tile ends in the center of the post on the right and at the left side of the panel frame.

Monolithic Panel Half Post Laminate Inserts
Worksurface Height, 28" and 42" High

description	w *	w	h	d	pattern no.	list
Worksurface Height Concealed Post	15"	16 1/2"	27 1/4"	7/16"	DP3L1WH15()F	\$230.
Monolithic Panel Half Post	18"	19 1/2"	27 1/4"	7/16"	DP3L1WH18()F	262.
Laminate Inserts	24"	25 1/2"	27 1/4"	7/16"	DP3L1WH24()F	305.
	30"	31 1/2"	27 1/4"	7/16"	DP3L1WH30()F	331.
	36"	37 1/2"	27 1/4"	7/16"	DP3L1WH36()F	395.
	42"	43 1/2"	27 1/4"	7/16"	DP3L1WH42()F	401.
	48"	49 1/2"	27 1/4"	7/16"	DP3L1WH48()F	529.
28" High Concealed Post	15"	16 1/2"	33 13/16"	7/16"	DP3L12815()F	230.
Monolithic Panel Half Post	18"	19 1/2"	33 13/16"	7/16"	DP3L12818()F	262.
Laminate Inserts	24"	25 1/2"	33 13/16"	7/16"	DP3L12824()F	305.
(For 36"H Panel Frame)	30"	31 1/2"	33 13/16"	7/16"	DP3L12830()F	331.
	36"	37 1/2"	33 13/16"	7/16"	DP3L12836()F	395.
	42"	43 1/2"	33 13/16"	7/16"	DP3L12842()F	401.
	48"	49 1/2"	33 13/16"	7/16"	DP3L12848()F	529.
42" High Concealed Post	15"	16 1/2"	41 3/16"	7/16"	DP3L14215()F	305.
Monolithic Panel Half Post	18"	19 1/2"	41 3/16"	7/16"	DP3L14218()F	341.
Laminate Inserts	24"	25 1/2"	41 3/16"	7/16"	DP3L14224()F	395.
	30"	31 1/2"	41 3/16"	7/16"	DP3L14230()F	534.
	36"	37 1/2"	41 3/16"	7/16"	DP3L14236()F	561.
	42"	43 1/2"	41 3/16"	7/16"	DP3L14242()F	567.
	48"	49 1/2"	41 3/16"	7/16"	DP3L14248()F	623.

w* = nominal width

Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Concealed Post Monolithic Panel Laminate Inserts	Concealed Post Monolithic Panel Laminate Inserts	Concealed Post Monolithic Panel Laminate Inserts	Concealed Post Monolithic Panel Laminate Inserts
1. Pattern Number	<i>Example:</i> DP3L14236CEF	• Attachment Clips	Configuration:
2. Laminate Finish	DP3L1 Pattern Number		(CE) = Left Half Post: Tile ends in the center of the post on the left and at the right side of the panel frame.
3. Edgeband Finish	4236		(EC) = Right Half Post: Tile ends in the center of the post on the right and at the left side of the panel frame.
	CE Center left, End Right		
	F Tile to Floor		
	118 Bright White Laminate		
	118 Bright White Edgeband		

Concealed Post

Monolithic Panel Half Post Laminate Inserts

50" and 57" High

Dividends Horizon

description	w *	w	h	d	pattern no.	list
 50" High Concealed Post Monolithic Panel Half Post Laminate Inserts	15"	16 1/2"	48 1/2"	7/16"	DP3L15015()F	\$332.
	18"	19 1/2"	48 1/2"	7/16"	DP3L15018()F	397.
	24"	25 1/2"	48 1/2"	7/16"	DP3L15024()F	498.
	30"	31 1/2"	48 1/2"	7/16"	DP3L15030()F	540.
	36"	37 1/2"	48 1/2"	7/16"	DP3L15036()F	661.
	42"	43 1/2"	48 1/2"	7/16"	DP3L15042()F	667.
	48"	49 1/2"	48 1/2"	7/16"	DP3L15048()F	860.
 57" High Concealed Post Monolithic Panel Half Post Laminate Inserts	15"	16 1/2"	55 3/8"	7/16"	DP3L15715()F	339.
	18"	19 1/2"	55 3/8"	7/16"	DP3L15718()F	403.
	24"	25 1/2"	55 3/8"	7/16"	DP3L15724()F	505.
	30"	31 1/2"	55 3/8"	7/16"	DP3L15730()F	548.
	36"	37 1/2"	55 3/8"	7/16"	DP3L15736()F	668.
	42"	43 1/2"	55 3/8"	7/16"	DP3L15742()F	673.
	48"	49 1/2"	55 3/8"	7/16"	DP3L15748()F	867.

w* = nominal width

Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Concealed Post Monolithic Panel Laminate Inserts 1. Pattern Number 2. Laminate Finish 3. Edgeband Finish	Concealed Post Monolithic Panel Laminate Inserts <i>Example:</i> DP3L15736CEF DP3L1 Pattern Number 5736 CE Center left, End Right F Tile to Floor 118 Bright White Laminate 118 Bright White Edgeband	Concealed Post Monolithic Panel Laminate Inserts Attachment Clips	Concealed Post Monolithic Panel Fabric Inserts Configuration: (CE) = Left Half Post: Tile ends in the center of the post on the left and at the right side of the panel frame. (EC) = Right Half Post: Tile ends in the center of the post on the right and at the left side of the panel frame.

*Monolithic Panel Centered Fabric Inserts**Worksurface Height, 28" and 42" High*

description	w *	w	d	h	pattern no.	10	20	30	40
Worksurface Height Concealed Post	15"	18"	7/16"	27 1/4"	DP1SOWH15CCF	\$189.	\$204.	\$217.	\$223.
Monolithic Panel Centered Fabric Insert	18"	21"	7/16"	27 1/4"	DP1SOWH18CCF	194.	214.	223.	230.
	24"	27"	7/16"	27 1/4"	DP1SOWH24CCF	201.	219.	229.	235.
	30"	33"	7/16"	27 1/4"	DP1SOWH30CCF	206.	226.	234.	242.
	36"	39"	7/16"	27 1/4"	DP1SOWH36CCF	216.	232.	240.	250.
	42"	45"	7/16"	27 1/4"	DP1SOWH42CCF	221.	237.	245.	256.
	48"	51"	7/16"	27 1/4"	DP1SOWH48CCF	227.	243.	253.	264.
	60"	63"	7/16"	27 1/4"	DP1SOWH60CCF	238.	256.	270.	280.
28" High Concealed Post	15"	18"	7/16"	33 13/16"	DP1SO2815CCF	203.	223.	232.	238.
Monolithic Panel Centered Fabric Insert	18"	21"	7/16"	33 13/16"	DP1SO2818CCF	214.	231.	239.	245.
(For 36"H Panel Frame)	24"	27"	7/16"	33 13/16"	DP1SO2824CCF	220.	237.	247.	256.
	30"	33"	7/16"	33 13/16"	DP1SO2830CCF	229.	244.	256.	265.
	36"	39"	7/16"	33 13/16"	DP1SO2836CCF	235.	253.	265.	276.
	42"	45"	7/16"	33 13/16"	DP1SO2842CCF	242.	262.	276.	286.
	48"	51"	7/16"	33 13/16"	DP1SO2848CCF	251.	270.	284.	292.
	60"	63"	7/16"	33 13/16"	DP1SO2860CCF	265.	288.	300.	311.
42" High Concealed Post	15"	18"	7/16"	41 3/16"	DP1SO4215CCF	223.	238.	247.	256.
Monolithic Panel Centered Fabric Insert	18"	21"	7/16"	41 3/16"	DP1SO4218CCF	232.	247.	261.	267.
	24"	27"	7/16"	41 3/16"	DP1SO4224CCF	239.	261.	270.	282.
	30"	33"	7/16"	41 3/16"	DP1SO4230CCF	250.	270.	283.	291.
	36"	39"	7/16"	41 3/16"	DP1SO4236CCF	261.	282.	292.	303.
	42"	45"	7/16"	41 3/16"	DP1SO4242CCF	267.	291.	303.	314.
	48"	51"	7/16"	41 3/16"	DP1SO4248CCF	280.	301.	314.	325.
	60"	63"	7/16"	41 3/16"	DP1SO4260CCF	296.	322.	336.	350.

w* = nominal width

Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Concealed Post Monolithic Panel Fabric Inserts	Concealed Post Monolithic Panel Fabric Inserts	Concealed Post Monolithic Panel Fabric Inserts	Concealed Post Monolithic Panel Fabric Inserts
1. Pattern Number	<i>Example:</i> DP1SO2818CCF	• Attachment Clips	
2. Fabric	DP1SO Pattern Number		
	2818		
	CC Center Left, Center Right		
	F Tile to Floor		
	W1077 Element		

Concealed Post

Monolithic Panel Centered Fabric Inserts

50", 57" and 64" High

Dividends Horizon

description	w *	w	h	d	pattern no.	10	20	30	40
50" High Concealed Post	15"	18"	48 1/2"	7/16"	DP1SO5015CCF	\$239.	\$259.	\$267.	\$280.
Monolithic Panel Centered Fabric Insert	18"	21"	48 1/2"	7/16"	DP1SO5018CCF	251.	270.	283.	291.
	24"	27"	48 1/2"	7/16"	DP1SO5024CCF	262.	284.	294.	305.
	30"	33"	48 1/2"	7/16"	DP1SO5030CCF	275.	294.	307.	318.
	36"	39"	48 1/2"	7/16"	DP1SO5036CCF	286.	305.	320.	332.
	42"	45"	48 1/2"	7/16"	DP1SO5042CCF	294.	318.	334.	347.
	48"	45"	48 1/2"	7/16"	DP1SO5048CCF	305.	331.	347.	360.
	60"	63"	48 1/2"	7/16"	DP1SO5060CCF	329.	356.	371.	386.
57" High Concealed Post	15"	18"	55 3/8"	7/16"	DP1SO5715CCF	253.	278.	289.	299.
Monolithic Panel Centered Fabric Insert	18"	21"	55 3/8"	7/16"	DP1SO5718CCF	266.	291.	303.	314.
	24"	27"	55 3/8"	7/16"	DP1SO5724CCF	283.	304.	318.	329.
	30"	33"	55 3/8"	7/16"	DP1SO5730CCF	294.	318.	334.	343.
	36"	39"	55 3/8"	7/16"	DP1SO5736CCF	307.	334.	348.	361.
	42"	45"	55 3/8"	7/16"	DP1SO5742CCF	322.	347.	363.	374.
	48"	51"	55 3/8"	7/16"	DP1SO5748CCF	335.	361.	376.	391.
	60"	63"	55 3/8"	7/16"	DP1SO5760CCF	361.	389.	405.	420.
64" High Concealed Post	15"	18"	63 1/16"	7/16"	DP1SO6415CCF	277.	295.	308.	320.
Monolithic Panel Centered Fabric Insert	18"	21"	63 1/16"	7/16"	DP1SO6418CCF	290.	311.	325.	337.
	24"	27"	63 1/16"	7/16"	DP1SO6424CCF	304.	327.	341.	356.
	30"	33"	63 1/16"	7/16"	DP1SO6430CCF	318.	342.	360.	371.
	36"	39"	63 1/16"	7/16"	DP1SO6436CCF	334.	360.	375.	389.
	42"	45"	63 1/16"	7/16"	DP1SO6442CCF	348.	374.	392.	405.
	48"	51"	63 1/16"	7/16"	DP1SO6448CCF	362.	391.	408.	423.
	60"	63"	63 1/16"	7/16"	DP1SO6460CCF	391.	421.	445.	459.

w* = nominal width
Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Concealed Post Monolithic Panel Fabric Inserts	Concealed Post Monolithic Panel Fabric Inserts	Concealed Post Monolithic Panel Fabric Inserts	Concealed Post Monolithic Panel Fabric Inserts
1. Pattern Number	<i>Example:</i> DP1SO5718CCF	• Attachment Clips	
2. Fabric	DP1SO Pattern Number		
	5718		
	CC Center Left, Center Right		
	F Tile to Floor		
	W1077 Element		

Alternative Planning

Concealed Post

Monolithic Panel Centered Laminate Inserts

Worksurface Height, 28" and 42" High

description	w *	w	h	d	pattern no.	list
Worksurface Height Concealed Post	15"	18"	27 1/4"	7/16"	DP3L1WH15CCF	\$230.
Monolithic Panel Centered Laminate Insert	18"	21"	27 1/4"	7/16"	DP3L1WH18CCF	262.
	24"	27"	27 1/4"	7/16"	DP3L1WH24CCF	305.
	30"	33"	27 1/4"	7/16"	DP3L1WH30CCF	331.
	36"	39"	27 1/4"	7/16"	DP3L1WH36CCF	395.
	42"	45"	27 1/4"	7/16"	DP3L1WH42CCF	401.
	48"	51"	27 1/4"	7/16"	DP3L1WH48CCF	529.
28" High Concealed Post	15"	18"	33 13/16"	7/16"	DP3L12815CCF	230.
Monolithic Panel Centered Laminate Insert	18"	21"	33 13/16"	7/16"	DP3L12818CCF	262.
(For 36"H Panel Frame)	24"	27"	33 13/16"	7/16"	DP3L12824CCF	305.
	30"	33"	33 13/16"	7/16"	DP3L12830CCF	331.
	36"	39"	33 13/16"	7/16"	DP3L12836CCF	395.
	42"	45"	33 13/16"	7/16"	DP3L12842CCF	401.
	48"	51"	33 13/16"	7/16"	DP3L12848CCF	529.
42" High Concealed Post	15"	18"	41 3/16"	7/16"	DP3L14215CCF	305.
Monolithic Panel Centered Laminate Insert	18"	21"	41 3/16"	7/16"	DP3L14218CCF	341.
	24"	27"	41 3/16"	7/16"	DP3L14224CCF	395.
	30"	33"	41 3/16"	7/16"	DP3L14230CCF	534.
	36"	39"	41 3/16"	7/16"	DP3L14236CCF	561.
	42"	45"	41 3/16"	7/16"	DP3L14242CCF	567.
	48"	51"	41 3/16"	7/16"	DP3L14248CCF	623.

w* = nominal width

Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Concealed Post Monolithic Panel Laminate Inserts	Concealed Post Monolithic Panel Laminate Inserts	Concealed Post Monolithic Panel Laminate Inserts	
1. Pattern Number	<i>Example:</i> DP3L14236CCF	• Attachment Clips	
2. Laminate Finish	DP3L1 Pattern Number		
3. Edgeband Finish	4236		
	CC Center Left, Center Right		
	F Tile to Floor		
	118 Bright White Laminate		
	118 Bright White Edgeband		

Concealed Post

Monolithic Panel Centered Laminate Inserts

50" and 57" High

Dividends Horizon

description	w *	w	h	d	pattern no.	list
50" High Concealed Post	15"	18"	48 1/2"	7/16"	DP3L15015CCF	\$332.
Monolithic Panel Centered Laminate Insert	18"	21"	48 1/2"	7/16"	DP3L15018CCF	397.
	24"	27"	48 1/2"	7/16"	DP3L15024CCF	498.
	30"	33"	48 1/2"	7/16"	DP3L15030CCF	540.
	36"	39"	48 1/2"	7/16"	DP3L15036CCF	661.
	42"	45"	48 1/2"	7/16"	DP3L15042CCF	667.
	48"	51"	48 1/2"	7/16"	DP3L15048CCF	860.
57" High Concealed Post	15"	18"	55 3/8"	7/16"	DP3L15715CCF	339.
Monolithic Panel Centered Laminate Insert	18"	21"	55 3/8"	7/16"	DP3L15718CCF	403.
	24"	27"	55 3/8"	7/16"	DP3L15724CCF	505.
	30"	33"	55 3/8"	7/16"	DP3L15730CCF	548.
	36"	39"	55 3/8"	7/16"	DP3L15736CCF	668.
	42"	45"	55 3/8"	7/16"	DP3L15742CCF	673.
	48"	51"	55 3/8"	7/16"	DP3L15748CCF	867.

w* = nominal width

Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Concealed Post Monolithic Panel Laminate Inserts	Concealed Post Monolithic Panel Laminate Inserts	Concealed Post Monolithic Panel Laminate Inserts	
1. Pattern Number	<i>Example:</i> DP3L15736CCF		
2. Laminate Finish	DP3L1 Pattern Number		
3. Edgeband Finish	5736	• Attachment Clips	
	CC Center Left, Center Right		
	F Tile to Floor		
	118 Bright White Laminate		
	118 Bright White Edgeband		

Concealed Post

Dividends Horizon

Monolithic Panel Double with Post Fabric Inserts

Worksurface Height, 28" and 42" High

description	w *	w	h	d	pattern no.	10	20	30	40
Worksurface Height Concealed Post	30"	33"	27 1/4"	7/16"	DP1SOWH30EPEF	\$189.	\$204.	\$217.	\$221.
Monolithic Panel Double with	36"	39"	27 1/4"	7/16"	DP1SOWH36EPEF	210.	229.	237.	243.
Post Fabric Insert	48"	51"	27 1/4"	7/16"	DP1SOWH48EPEF	231.	247.	261.	267.
	60"	63"	27 1/4"	7/16"	DP1SOWH60EPEF	251.	274.	284.	292.



28" High Concealed Post	30"	33"	33 13/16"	7/16"	DP1SO2830EPEF	148.	160.	168.	173.
Monolithic Panel Double with	36"	39"	33 13/16"	7/16"	DP1SO2836EPEF	201.	219.	229.	234.
Post Fabric Insert	48"	51"	33 13/16"	7/16"	DP1SO2848EPEF	252.	275.	287.	295.
(For 36"h panel frame)	60"	63"	33 13/16"	7/16"	DP1SO2860EPEF	305.	331.	347.	359.



42" High Concealed Post	30"	33"	41 3/16"	7/16"	DP1SO4230EPEF	185.	198.	206.	217.
Monolithic Panel Double with	36"	39"	41 3/16"	7/16"	DP1SO4236EPEF	234.	252.	263.	275.
Post Fabric Insert	48"	51"	41 3/16"	7/16"	DP1SO4248EPEF	284.	305.	318.	331.
	60"	63"	41 3/16"	7/16"	DP1SO4260EPEF	334.	360.	374.	389.



w* = nominal width

Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Concealed Post Monolithic Panel Fabric Inserts	Concealed Post Monolithic Panel Fabric Inserts	Concealed Post Monolithic Panel Fabric Inserts	Concealed Post Monolithic Panel Fabric Inserts
1. Pattern Number	<i>Example:</i> DP1SO2836EPEF	• Attachment Clips	
2. Fabric	DP1SO Pattern Number		
	2836		
	EPE End, Post, End		
	F Tile to Floor		
	W1077 Element		

Concealed Post

Monolithic Panel Double with Post Fabric Inserts

50", 57" and 64" High

Dividends Horizon

description	w *	w	h	d	pattern no.	10	20	30	40
50" High Concealed Post	30"	33"	48 1/2"	7/16"	DP1SO5030EPEF	\$220.	\$234.	\$244.	\$254.
Monolithic Panel Double with	36"	39"	48 1/2"	7/16"	DP1SO5036EPEF	264.	286.	299.	310.
Post Fabric Insert	48"	51"	48 1/2"	7/16"	DP1SO5048EPEF	310.	335.	351.	363.
	60"	63"	48 1/2"	7/16"	DP1SO5060EPEF	358.	386.	403.	416.



57" High Concealed Post	30"	33"	55 3/8"	7/16"	DP1SO5730EPEF	252.	275.	287.	295.
Monolithic Panel Double with	36"	39"	55 3/8"	7/16"	DP1SO5736EPEF	295.	318.	335.	347.
Post Fabric Insert	48"	51"	55 3/8"	7/16"	DP1SO5748EPEF	337.	364.	382.	395.
	60"	51"	55 3/8"	7/16"	DP1SO5760EPEF	380.	409.	433.	447.



64" High Concealed Post	30"	33"	63 1/16"	7/16"	DP1SO6430EPEF	322.	348.	363.	375.
Monolithic Panel Double with	36"	39"	63 1/16"	7/16"	DP1SO6436EPEF	342.	371.	389.	402.
Post Fabric Insert	48"	51"	63 1/16"	7/16"	DP1SO6448EPEF	364.	395.	413.	426.



Alternative Planning

w* = nominal width

Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Concealed Post Monolithic Panel Fabric Inserts	Concealed Post Monolithic Panel Fabric Inserts	Concealed Post Monolithic Panel Fabric Inserts	Concealed Post Monolithic Panel Fabric Inserts
1. Pattern Number	<i>Example:</i> DP1SO5736EPEF	• Attachment Clips	
2. Fabric	DP1SO Pattern Number		
	5736		
	EPE End, Post, End		
	F Tile to Floor		
	W1077 Element		

Concealed Post

Monolithic Panel Double with Post Laminate Inserts

Worksurface Height, 28" and 42" High

description	w *	w	h	d	pattern no.	list
Worksurface Height Concealed Post	30"	33"	27 1/4"	7/16"	DP3L1WH30EPEF	\$331.
Monolithic Panel Double with	36"	39"	27 1/4"	7/16"	DP3L1WH36EPEF	395.
Post Laminate Insert	48"	51"	27 1/4"	7/16"	DP3L1WH48EPEF	405.
	60"	63"	27 1/4"	7/16"	DP3L1WH60EPEF	533.
	72"	75"	27 1/4"	7/16"	DP3L1WH72EPEF	545.
	84"	87"	27 1/4"	7/16"	DP3L1WH84EPEF	555.



28" High Concealed Post	30"	33"	33 13/16"	7/16"	DP3L12830EPEF	493.
Monolithic Panel Double with	36"	39"	33 13/16"	7/16"	DP3L12836EPEF	500.
Post Laminate Insert	48"	51"	33 13/16"	7/16"	DP3L12848EPEF	529.
(For 36"h panel frame)	60"	63"	33 13/16"	7/16"	DP3L12860EPEF	857.
	72"	75"	33 13/16"	7/16"	DP3L12872EPEF	869.
	84"	87"	33 13/16"	7/16"	DP3L12884EPEF	881.



42" High Concealed Post	30"	33"	41 3/16"	7/16"	DP3L14230EPEF	534.
Monolithic Panel Double with	36"	39"	41 3/16"	7/16"	DP3L14236EPEF	561.
Post Laminate Insert	48"	51"	41 3/16"	7/16"	DP3L14248EPEF	584.
	60"	63"	41 3/16"	7/16"	DP3L14260EPEF	865.
	72"	75"	41 3/16"	7/16"	DP3L14272EPEF	876.
	84"	87"	41 3/16"	7/16"	DP3L14284EPEF	888.



w* = nominal width

Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Concealed Post Monolithic Panel Laminate Inserts	Concealed Post Monolithic Panel Laminate Inserts	Concealed Post Monolithic Panel Laminate Inserts	Concealed Post Monolithic Panel Laminate Inserts
1. Pattern Number	<i>Example:</i> DP3L14236EPEF	• Attachment Clips	
2. Laminate Finish	DP3L1 Pattern Number		
3. Edgeband Finish	4236		
	EPE End, Post, End		
	F Tile to Floor		
	118 Bright White Laminate		
	118 Bright White Edgeband		

Concealed Post

Monolithic Panel Double with Post Laminate Inserts

50" and 57" High

Dividends Horizon

description	w *	w	h	d	pattern no.	list
50" High Concealed Post Monolithic Panel Double with Post Laminate Insert 	30"	33"	48 1/2"	7/16"	DP3L15030EPEF	\$540.
	36"	39"	48 1/2"	7/16"	DP3L15036EPEF	661.
	48"	51"	48 1/2"	7/16"	DP3L15048EPEF	860.
	60"	63"	48 1/2"	7/16"	DP3L15060EPEF	873.
	72"	75"	48 1/2"	7/16"	DP3L15072EPEF	884.
	84"	87"	48 1/2"	7/16"	DP3L15084EPEF	895.

57" High Concealed Post Monolithic Panel Double with Post Laminate Insert 	30"	33"	55 3/8"	7/16"	DP3L15730EPEF	548.
	36"	39"	55 3/8"	7/16"	DP3L15736EPEF	668.
	48"	51"	55 3/8"	7/16"	DP3L15748EPEF	867.
	60"	63"	55 3/8"	7/16"	DP3L15760EPEF	879.
	72"	75"	55 3/8"	7/16"	DP3L15772EPEF	889.
	84"	87"	55 3/8"	7/16"	DP3L15784EPEF	900.

Alternative Planning



w* = nominal width

Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Concealed Post Monolithic Panel Laminate Inserts 1. Pattern Number 2. Laminate Finish 3. Edgeband Finish	Concealed Post Monolithic Panel Laminate Inserts <i>Example:</i> DP3L15736EPEF DP3L1 Pattern Number 5736 EPE End, Post, End F Tile to Floor 118 Bright White Laminate 118 Bright White Edgeband	Concealed Post Monolithic Panel Laminate Inserts • Attachment Clips	Concealed Post Monolithic Panel Laminate Inserts

Concealed Post
Standard Frameless Add Up
1/2" Clear, Powder, Bronze and Grey Glass


Dividends Horizon


description	w	d	h	pattern no.	list	Clear (TEMP)	Powder (GL70) Bronze (GL25) Grey (GL35)
Frameless Add Up, 7" High (For use with concealed post only) 	51"	1/2"	7"	DP1AU0751()G		\$535.	\$600.
	57"	1/2"	7"	DP1AU0757()G		580.	651.
	63"	1/2"	7"	DP1AU0763()G		622.	704.
	69"	1/2"	7"	DP1AU0769()G		670.	756.
	75"	1/2"	7"	DP1AU0775()G		714.	811.
	81"	1/2"	7"	DP1AU0781()G		773.	881.
	87"	1/2"	7"	DP1AU0787()G		837.	950.
	93"	1/2"	7"	DP1AU0793()G		903.	1,029.
	99"	1/2"	7"	DP1AU0799()G		974.	1,111.
Shortened Frameless Add Up, 7" High (For use with concealed post only) 	50"	1/2"	7"	DP1AU0750()G		535.	600.
	56"	1/2"	7"	DP1AU0756()G		580.	651.
	62"	1/2"	7"	DP1AU0762()G		622.	704.
	68"	1/2"	7"	DP1AU0768()G		670.	756.
	74"	1/2"	7"	DP1AU0774()G		714.	811.
	80"	1/2"	7"	DP1AU0780()G		773.	881.
	86"	1/2"	7"	DP1AU0786()G		837.	950.
	92"	1/2"	7"	DP1AU0792()G		903.	1,029.
	98"	1/2"	7"	DP1AU0798()G		974.	1,111.

Ordering Information	Order Code	Included with:	Options
Frameless Add Up with Glass 1. Pattern number 2. Frame finish 3. Glass finish End Cap 1. Pattern number 2. Paint finish	Frameless Add Up with Glass <i>Example:</i> DP1AU0757VG DP1AU Frameless Add Up 07 7" High 57 57" Wide V Glass 117 Frame finish TEMP Clear glass finish 	Frameless Add Up with Glass - Attachment hardware - Topway Trough Spacer (Topway only) - Alignment Clip	Frame Options: (V) = Full view (C) = Topway Glass Options: (TEMP) = Clear (GL70) = Powder (GL25) = Bronze (GL35) = Grey

Concealed Post
Standard Frameless Add Up
1/2" Clear, Powder, Bronze and Grey Glass

Dividends Horizon

description	w	d	h	pattern no.	list	Clear (TEMP)	Powder (GL70) Bronze (GL25) Grey (GL35)
 Frameless Add Up, 14" High (For use with concealed post only)	51"	1/2"	14"	DP1AU1451()G		\$755.	\$887.
	57"	1/2"	14"	DP1AU1457()G		825.	972.
	63"	1/2"	14"	DP1AU1463()G		897.	1,062.
	69"	1/2"	14"	DP1AU1469()G		966.	1,146.
	75"	1/2"	14"	DP1AU1475()G		1,038.	1,234.
	81"	1/2"	14"	DP1AU1481()G		1,127.	1,334.
	87"	1/2"	14"	DP1AU1487()G		1,216.	1,443.
	93"	1/2"	14"	DP1AU1493()G		1,313.	1,559.
	99"	1/2"	14"	DP1AU1499()G		1,420.	1,683.

 Shortened Frameless Add Up, 14" High (For use with concealed post only)	50"	1/2"	14"	DP1AU1450()G		755.	887.
	56"	1/2"	14"	DP1AU1456()G		825.	972.
	62"	1/2"	14"	DP1AU1462()G		897.	1,062.
	68"	1/2"	14"	DP1AU1468()G		966.	1,146.
	74"	1/2"	14"	DP1AU1474()G		1,038.	1,234.
	80"	1/2"	14"	DP1AU1480()G		1,127.	1,334.
	86"	1/2"	14"	DP1AU1486()G		1,216.	1,443.
	92"	1/2"	14"	DP1AU1492()G		1,313.	1,559.
	98"	1/2"	14"	DP1AU1498()G		1,420.	1,683.



End Cap				DP1AUECTP	53.		
---------	--	--	--	-----------	-----	--	--



Alternative Planning

Ordering Information	Order Code	Included with:	Options
Frameless Add Up with Glass 1. Pattern number 2. Frame finish 3. Glass finish End Cap 1. Pattern number 2. Paint finish	Frameless Add Up with Glass <i>Example:</i> DP1AU0757VG DP1AU Frameless Add Up 14 14" High 57 57" Wide V Glass 117 Frame finish TEMP Clear glass finish	Frameless Add Up with Glass - Attachment hardware - Topway Trough Spacer (Topway only) - Alignment Clip	Frame Option: (V) = Full view (C) = Topway Glass Options: (TEMP) = Clear (GL70) = Powder (GL25) = Bronze (GL35) = Grey

*Recessed Frameless Add Up**1/2" Clear, Powder, Bronze and Grey Glass*

description	w	d	h	pattern no.	list	Clear (TEMP)	Powder (GL70)	Bronze (GL25) Grey (GL35)
Recessed Frameless Add Up, 7" High (For use with concealed post only) 	51"	1/2"	7"	DP1AR0751H()		\$519.	\$635.	\$735.
	57"	1/2"	7"	DP1AR0757H()		561.	688.	813.
	63"	1/2"	7"	DP1AR0763H()		602.	723.	863.
	69"	1/2"	7"	DP1AR0769H()		643.	783.	945.
	75"	1/2"	7"	DP1AR0775H()		677.	825.	1,010.
	81"	1/2"	7"	DP1AR0781H()		728.	865.	1,070.
	87"	1/2"	7"	DP1AR0787H()		774.	930.	1,145.
	93"	1/2"	7"	DP1AR0793H()		822.	999.	1,248.
	99"	1/2"	7"	DP1AR0799H()		952.	1,185.	1,220.
Recessed Shortened Frameless Add Up, 7" High (For use with concealed post only) 	50"	1/2"	7"	DP1AR0750H()		517.	635.	735.
	56"	1/2"	7"	DP1AR0756H()		559.	688.	813.
	62"	1/2"	7"	DP1AR0762H()		593.	723.	863.
	68"	1/2"	7"	DP1AR0768H()		640.	783.	945.
	74"	1/2"	7"	DP1AR0774H()		673.	825.	1,010.
	80"	1/2"	7"	DP1AR0780H()		725.	865.	1,070.
	86"	1/2"	7"	DP1AR0786H()		772.	930.	1,145.
	92"	1/2"	7"	DP1AR0792H()		818.	999.	1,248.
	98"	1/2"	7"	DP1AR0798H()		942.	1,230.	1,500.

Ordering Information**Frameless Add Up with Glass**

1. Pattern number
2. Frame finish
3. Glass finish

End Cap

1. Pattern number
2. Paint finish

Order Code**Frameless Add Up with Glass***Example:* **DP1AR0757H****DP1AR** Frameless Add Up**07** 7" High**57** 57" Wide**H** 1/2" Thick**117** Frame finish**TEMP** Clear glass finish**Included with:****Frameless Add Up with Glass**



- Attachment hardware
- Topway Trough Spacer
- Allignment Clip

Options**Glass Options:**

(TEMP)= Clear
 (GL70)= Powder
 (GL25)= Bronze
 (GL35)= Grey

Concealed Post
Recessed Frameless Add Up
1/2" Clear, Powder, Bronze and Grey Glass



Dividends Horizon

description	w	d	h	pattern no.	list	Clear (TEMP)	Powder (GL70) Bronze (GL25) Grey (GL35)	Bronze (GL25) Grey (GL35)
Recessed Frameless Add Up, 14" High (For use with concealed post only) 	51"	1/2"	7"	DP1AR1451H()		\$666.	\$813.	\$1,065.
	57"	1/2"	7"	DP1AR1457H()		728.	883.	1,163.
	63"	1/2"	7"	DP1AR1463H()		791.	938.	1,268.
	69"	1/2"	7"	DP1AR1469H()		852.	1,035.	1,385.
	75"	1/2"	7"	DP1AR1475H()		915.	1,105.	1,490.
	81"	1/2"	7"	DP1AR1481H()		995.	1,175.	1,585.
	87"	1/2"	7"	DP1AR1487H()		1,073.	1,300.	1,700.
	93"	1/2"	7"	DP1AR1493H()		1,159.	1,433.	1,838.
	99"	1/2"	7"	DP1AR1499H()		1,335.	1,560.	2,020.
Recessed Shortened Frameless Add Up, 14" High (For use with concealed post only) 	50"	1/2"	14"	DP1AR1450H()		666.	813.	1,065.
	56"	1/2"	14"	DP1AR1456H()		728.	883.	1,163.
	62"	1/2"	14"	DP1AR1462H()		791.	938.	1,268.
	68"	1/2"	14"	DP1AR1468H()		852.	1,035.	1,385.
	74"	1/2"	14"	DP1AR1474H()		915.	1,105.	1,490.
	80"	1/2"	14"	DP1AR1480H()		994.	1,175.	1,585.
	86"	1/2"	14"	DP1AR1486H()		1,073.	1,300.	1,700.
	92"	1/2"	14"	DP1AR1492H()		1,159.	1,433.	1,838.
	98"	1/2"	14"	DP1AR1498H()		1,336.	1,560.	2,020.

Alternative Planning

Ordering Information	Order Code	Included with:	Options
Frameless Add Up with Glass 1. Pattern number 2. Frame finish 3. Glass finish End Cap 1. Pattern number 2. Paint finish	Frameless Add Up with Glass <i>Example:</i> DP1AR0757H DP1AR Frameless Add Up 07 7" High 57 57" Wide H 1/2" Thick 117 Frame finish TEMP Clear glass finish	Frameless Add Up with Glass - Attachment hardware - Topway Trough Spacer (Topway only) - Alignment Clip	Glass Options: (TEMP)= Clear (GL70)= Powder (GL25)= Bronze (GL35)= Grey

*Recessed Frameless Add Up**3/8" Clear and Laminated Frosted Glass*

description	w	d	h	pattern no.	list	Clear (TEMP)	Frosted Laminated (GL60)
Recessed Frameless Add Up, 7" high (For use with concealed post only) 	51"	3/8"	7"	DP1AR0751W()		\$467.	\$579.
	57"	3/8"	7"	DP1AR0757W()		505.	619.
	63"	3/8"	7"	DP1AR0763W()		542.	671.
	69"	3/8"	7"	DP1AR0769W()		579.	714.
	75"	3/8"	7"	DP1AR0775W()		609.	761.
	81"	3/4"	7"	DP1AR0781W()		655.	801.
	87"	3/4"	7"	DP1AR0787W()		697.	862.
	93"	3/4"	7"	DP1AR0793W()		740.	899.
	99"	3/4"	7"	DP1AR0799W()		774.	984.
Recessed Shortened Frameless Add Up, 7" high (For use with concealed post only) 	50"	3/8"	7"	DP1AR0750W()		465.	579.
	56"	3/8"	7"	DP1AR0756W()		503.	619.
	62"	3/8"	7"	DP1AR0762W()		534.	671.
	68"	3/8"	7"	DP1AR0768W()		576.	714.
	74"	3/8"	7"	DP1AR0774W()		606.	743.
	80"	3/4"	7"	DP1AR0786W()		653.	801.
	86"	3/4"	7"	DP1AR0780W()		695.	862.
	92"	3/4"	7"	DP1AR0792W()		736.	899.
	98"	3/4"	7"	DP1AR0798W()		774.	941.

Ordering Information**Recessed Frameless Add Up
with Clear Glass**


1. Pattern number
2. Glass finish


Order Code**Frameless Add Up with Glass***Example:* **DP1AR0736W TEMP****DP1AR** Frameless Add Up**07** 7" High**36** 36" Wide**W** 3/8" Thick**TEMP** Clear glass finish**Included with:****Recessed Frameless Add Up
with Clear Glass**

- Attachment hardware
- Alignment Clip

Options**Glass Options:**(TEMP)= Clear
(GL60)= Laminated Frosted

*Recessed Frameless Add Up**3/8" Clear and Laminated Frosted Glass*



description	w	d	h	pattern no.	list	Clear (TEMP)	Frosted Laminated (GL60)
Recessed Frameless Add Up, 14" high (For use with concealed post only) 	51"	3/8"	14"	DP1AR1451W()		\$599.	\$739.
	57"	3/8"	14"	DP1AR1457W()		655.	795.
	63"	3/8"	14"	DP1AR1463W()		712.	864.
	69"	3/8"	14"	DP1AR1469W()		767.	941.
	75"	3/8"	14"	DP1AR1475W()		824.	1,004.
	81"	3/8"	14"	DP1AR1481W()		896.	1,080.
	87"	3/8"	14"	DP1AR1487W()		966.	1,195.
	93"	3/8"	14"	DP1AR1493W()		1,043.	1,290.
	99"	3/8"	14"	DP1AR1499W()		1,128.	1,330.

Recessed Shortened Frameless Add Up, 14" high (For use with concealed post only) 	50"	3/8"	14"	DP1AR1450W()		599.	739.
	56"	3/8"	14"	DP1AR1456W()		655.	795.
	62"	3/8"	14"	DP1AR1462W()		712.	864.
	68"	3/8"	14"	DP1AR1468W()		767.	941.
	74"	3/8"	14"	DP1AR1474W()		824.	1,004.
	80"	3/8"	14"	DP1AR1480W()		895.	1,080.
	86"	3/8"	14"	DP1AR1486W()		966.	1,195.
	92"	3/8"	14"	DP1AR1492W()		1,043.	1,290.
	98"	3/8"	14"	DP1AR1498W()		1,129.	1,332.

Ordering Information	Order Code	Included with:	Options
Recessed Frameless Add Up with Clear Glass 1. Pattern number 2. Glass finish	Frameless Add Up with Glass <i>Example:</i> DP1AR0736W TEMP DP1AR Frameless Add Up 07 7" High 36 36" Wide W 3/8" Thick TEMP Clear glass finish	Recessed Frameless Add Up with Clear Glass - Attachment hardware - Alignment Clip	Glass Options: (TEMP)= Clear (GL60) = Laminated Frosted

Concealed Post
 Recessed Frameless Add Up
 1/4" Clear and Powder Glass


Dividends Horizon


description	w	d	h	pattern no.	list	Clear (TEMP)	Powder (GL70)
Recessed Frameless Add Up, 7" high (For use with concealed post only) 	51"	1/4"	7"	DP1AR0751E()		\$397.	\$492.
	54"	1/4"	7"	DP1AR0757E()		429.	526.
	63"	1/4"	7"	DP1AR0763E()		461.	570.
	69"	1/4"	7"	DP1AR0769E()		492.	607.
	75"	1/4"	7"	DP1AR0775E()		518.	646.
	81"	1/4"	7"	DP1AR0781E()		557.	681.
	87"	1/4"	7"	DP1AR0787E()		592.	733.
	93"	1/4"	7"	DP1AR0793E()		629.	764.
	99"	1/4"	7"	DP1AR0799E()		658.	855.
Recessed Shortened Frameless Add Up, 7" high (For use with concealed post only) 	50"	1/4"	7"	DP1AR0750E()		396.	492.
	56"	1/4"	7"	DP1AR0756E()		428.	526.
	62"	1/4"	7"	DP1AR0762E()		454.	570.
	68"	1/4"	7"	DP1AR0768E()		490.	607.
	74"	1/4"	7"	DP1AR0774E()		515.	662.
	80"	1/4"	7"	DP1AR0780E()		555.	681.
	86"	1/4"	7"	DP1AR0786E()		591.	733.
	92"	1/4"	7"	DP1AR0792E()		626.	764.
	98"	1/4"	7"	DP1AR0798E()		658.	799.

Ordering Information	Order Code	Included with:	Options
Frameless Add Up with Glass 1. Pattern number 2. Frame finish 3. Glass finish	Recessed Frameless Add Up with Glass <i>Example:</i> DP1AR0736E TEMP DP1AR Frameless Add Up 07 7" High 36 36" Wide E 1/4" Thick 117 Frame finish TEMP Clear glass finish	Recessed Frameless Add Up with Clear Glass - Attachment hardware - Alignment Clip	Glass Options: (TEMP)= Clear (GL60) = Powder

Concealed Post
Recessed Frameless Add Up
1/4" Clear and Powder Glass

Dividends Horizon


description	w	d	h	pattern no.	list	Clear (TEMP)	Powder (GL70)
Recessed Frameless Add Up, 14" high (For use with concealed post only) 	51"	1/4"	14"	DP1AR1451E()		\$509.	\$628.
	57"	1/4"	14"	DP1AR1457E()		557.	675.
	63"	1/4"	14"	DP1AR1463E()		605.	734.
	69"	1/4"	14"	DP1AR1469E()		652.	799.
	75"	1/4"	14"	DP1AR1475E()		700.	853.
	81"	1/4"	14"	DP1AR1481E()		761.	918.
	87"	1/4"	14"	DP1AR1487E()		821.	1,016.
	93"	1/4"	14"	DP1AR1493E()		887.	1,096.
	99"	1/4"	14"	DP1AR1499E()		959.	1,131.

Recessed Shortened Frameless Add Up, 14" high (For use with concealed post only) 	50"	1/4"	14"	DP1AR1450E()		509.	628.
	56"	1/4"	14"	DP1AR1456E()		557.	675.
	62"	1/4"	14"	DP1AR1462E()		605.	734.
	68"	1/4"	14"	DP1AR1468E()		652.	799.
	74"	1/4"	14"	DP1AR1474E()		700.	853.
	80"	1/4"	14"	DP1AR1480E()		760.	918.
	86"	1/4"	14"	DP1AR1486E()		821.	1,016.
	92"	1/4"	14"	DP1AR1492E()		887.	1,096.
	98"	1/4"	14"	DP1AR1498E()		959.	1,132.


Alternative Planning

Ordering Information	Order Code	Included with:	Options
Frameless Add Up with Glass 1. Pattern number 2. Frame finish 3. Glass finish	Recessed Frameless Add Up with Glass <i>Example:</i> DP1AR0736E TEMP DP1AR Frameless Add Up 07 7" High 36 36" Wide E 1/4" Thick 117 Frame finish TEMP Clear glass finish	Recessed Frameless Add Up with Clear Glass - Attachment hardware - Alignment Clip	Glass Options: (TEMP)= Clear (GL60)= Powder


The 120-degree planning model provides comparable or greater square footage per workstation than typical cubicle layouts (comparisons are illustrated on this page). At the same time, Dividends Horizon 120° allows for a more natural space, creating a more comfortable place to work. Maintaining a consistent 48" module promotes improved asset management and a reduction of reconfiguration costs.




Big House
Sq. Feet = 69.8'
7 Panels




8' x 8'
Sq. Feet = 64'
7 Panels




Full House
Sq. Feet = 42.1'
5 Panels



6' x 7'
Sq. Feet = 42'
7 Panels




Open House
Sq. Feet = 35.5'
4 Panels




6' x 6'
Sq. Feet = 36'
6 Panels




Townhouse
Sq. Feet = 34.1'
3 Panels




6' x 6'
Sq. Feet = 36'
6 Panels




Apartment
Sq. Feet = 32.1'
2 Panels



4' x 6'
Sq. Feet = 24'
4 Panels



8 Open House Stations
Sq. Feet = 284'
19 Panels




8 Station Cluster
Each station 6' x 6'
Sq. Feet = 288'
28 Panels


These workspaces are designed specifically for Dividends Horizon 120. The (L/R) suffix at the end of a pattern number indicates a defined pedestal location. If the workspace has no defined pedestal location, the (L/R) represents the curved side of the top. All tops and tables are available with 2mm edge band or a 1" ergonomic edge.

Workspace: W3


This workspace, combined with the T3 Transition top, works best with the "apartment" layout. This application allows for stations on both sides of the spine, and is ideal for high density layouts. Available in extended versions for placement directly next to another workspace.



Workspace: W3



Workspace: W4



Workspace: W5 (L/R)

Workspace: W4


This top works well in the "open house," "full house," and "big house" layouts for call center, professional, and managerial applications.

Workspace: W5 (L/R)


With transition top T5 and this workspace, teaming is made easy using the "townhouse" or "open house" layout. The shared space allows for call center, professional, or technical applications.

Workspace: W6 (L/R)


In the "big house," "full house" or "open house", this workspace allows for a pedestal on one side (determined by the L/R). Applications for this top include a call center with the "open house," technical applications with the "full house," and managerial layouts with the "big house."



Workspace: W6 (L/R)



Workspace: W7 (L/R)



Workspace: W11 / W1118 (L/R)

Workspace: W7 (L/R)

Used in conjunction with a T4 transition top, the W7 workspace provides a great teaming space when the "townhouse" layout is used. The "open house" layout incorporates the T2 transition top for professional or technical stations with shared space for conferencing. Available in extended versions for placement directly next to another workspace.

Workspace: W11 / W1118 (L/R)

This top is a spacious option for a technical station in the "open house" layout. Adding a T2 transition top provides additional teaming space. The W11 surface also fits nicely in a private managerial office or a "full house" professional application.

Worksurface: W12 / W1218 (L/R)

This top, with the T5/T518 transition top provides a technical office with shared conferencing space in the “open house” layout. The 18" return allows ample space in the supervisory application of the “full house.”

Worksurface: W13 / W1318 (L/R)

This surface provides a teaming space with the T2/T218 transition in the “open house” layout. The W13/W1318 creates generous worksurface space in the “full house” as well as the management layout of the “big house.”


Transition Tops

Transition tops require columns (not included) for support. Flat brackets (not included) are required to attach transition tops to adjacent worksurfaces.

Application Notes


Dividends Horizon 120 worksurfaces use cantilevers as their main form of support. A cantilever must be used at each post location to support worksurfaces properly. A pedestal may be used for support, where applicable, in conjunction with cantilevers.

Worksurface: W12 / W1218 (L/R)




left

right




Worksurface: W13 / W1318 (L/R)



left

right




Transition Tops




Transition top: T2



Transition top: T218



Transition top: T3



Transition top: T4



Transition top: T5



Transition top: T518

120° Planning

120° Post Assemblies

Dividends Horizon

description	h*	w	d	pattern no.	Black	Metal P1	Metal P2	Metal P3
 120°Two-Way Post Assembly	36"	3"	3"	DP8(C/V/U)120PA362()		\$340.	\$348.	\$360.
	42"	3"	3"	DP8(C/V/U)120PA422()		340.	348.	360.
	50"	3"	3"	DP8(C/V/U)120PA502()		353.	367.	377.
	57"	3"	3"	DP8(C/V/U)120PA572()		392.	405.	418.
	64"	3"	3"	DP8(C/V/U)120PA642()		392.	405.	418.
	78"	3"	3"	DP8(C/V/U)120PA782()		500.	521.	537.
 120°Three-Way Post Assembly	36"	3"	3"	DP8(C/V/U)120PA363()		346.	356.	367.
	42"	3"	3"	DP8(C/V/U)120PA423()		346.	356.	367.
	50"	3"	3"	DP8(C/V/U)120PA503()		360.	371.	383.
	57"	3"	3"	DP8(C/V/U)120PA573()		392.	405.	418.
	64"	3"	3"	DP8(C/V/U)120PA643()		392.	405.	418.
	78"	3"	3"	DP8(C/V/U)120PA783()		497.	516.	533.
 120°Two-Way Post Assembly for Recessed Add Up Glass	36"	3"	3"	DP8(C/V/U)120PAG362()		340.	348.	360.
	42"	3"	3"	DP8(C/V/U)120PAG422()		340.	348.	360.
	50"	3"	3"	DP8(C/V/U)120PAG502()		353.	367.	377.
	57"	3"	3"	DP8(C/V/U)120PAG572()		392.	405.	418.
	64"	3"	3"	DP8(C/V/U)120PAG642()		392.	405.	418.
	78"	3"	3"	DP8(C/V/U)120PAG782()		500.	521.	537.
 120°Three-Way Post Assembly for Recessed Add Up Glass	36"	3"	3"	DP8(C/V/U)120PAG363()		346.	356.	367.
	42"	3"	3"	DP8(C/V/U)120PAG423()		346.	356.	367.
	50"	3"	3"	DP8(C/V/U)120PAG503()		360.	371.	383.
	57"	3"	3"	DP8(C/V/U)120PAG573()		392.	405.	418.
	64"	3"	3"	DP8(C/V/U)120PAG643()		392.	405.	418.
	78"	3"	3"	DP8(C/V/U)120PAG783()		497.	516.	533.

Alternative Planning

h = nominal height

Ordering Information	Order Code	Included with:	Options
Post Assemblies 1. Pattern Number 2. Trim Finish	Post Assemblies <i>Example:</i> DP(4)120PA 642, 113 DP(4)120 Pattern Number PA 642 113 Dark grey trim finish	Post Assemblies • Post assemblies • Post top cap • Post cover • Connecting hardware	Post assembly trim options (4) = Metal, Radius (5) = Metal, Flat

120° Planning
120° Post Assemblies

Dividends Horizon

description	h*	w	d	pattern no.	Black	Metal P1	Metal P2	Metal P3
14" High 120° Stack Panel Posts	14 ^{5/8"}	3"	3"	DP8120SPO 14	\$136.			
								
21" High 120° Stack Panel Posts	21 ^{15/16"}	3"	3"	DP8120SPO 21	153.			
								
28" High 120° Stack Panel Posts	29 ^{1/4"}	3"	3"	DP8120SPO 28	159.			
								

h = nominal height

Ordering Information	Order Code	Included with:	Options
Post Assemblies 1. Pattern Number 2. Trim Finish	Post Assemblies <i>Example:</i> DP(4)120PA 642, 113 DP(4)120 Pattern Number PA 642 113 Dark grey trim finish	Post Assemblies • Post assemblies • Post top cap • Post cover • Connecting hardware	Post assembly trim options (4) = Metal, Radius (5) = Metal, Flat

120° Planning

120° High Low Planning

Dividends Horizon

description	type	h	w	d	pattern no.	Metal P1	Metal P2	Metal P3
 Post Covers (Straight) High-Low Connection	36" - 42"	8"			DP8120PC08S	\$10.	\$12.	\$12.
	36" - 50"	14"			DP8120PC14S	18.	28.	31.
	36" - 64"	28"			DP8120PC28S	49.	53.	54.
	36" - 78"	42"			DP8120PC42SH	71.	78.	80.
	42" - 50"	8"			DP8120PC08S	10.	12.	12.
	42" - 64"	22"			DP8120PC22S	33.	34.	35.
	42" - 78"	36"			DP8120PC36S	63.	70.	74.
	50" - 64"	14"			DP8120PC14S	18.	28.	31.
	50" - 78"	28"			DP8120PC28S	49.	53.	54.
	64" - 78"	14"			DP8120PC14S	18.	28.	31.
 Post Top Caps	One-Way	1/2"	3"	3"	DP8(C/V/U)120PT1	8.	9.	9.
	Three-Way	1/2"	3"	3"	DP8(C/V/U)120PT3	8.	9.	9.
	Two-Way	1/2"	3"	3"	DP8(C/V/U)120PT2	8.	9.	9.
 Post Top Caps for Recessed Add Up Glass	One-Way	1/2"	3"	3"	DP8(C/V/U)120PTG1	8.	9.	9.
	Three-Way	1/2"	3"	3"	DP8(C/V/U)120PTG3	8.	9.	9.
	Two-Way	1/2"	3"	3"	DP8(C/V/U)120PTG2	8.	9.	9.
 Post Covers (Straight)	36"				DP8120PC36SF	55.	58.	64.
	42"				DP8120PC42S	55.	58.	64.
	50"				DP8120PC50S	56.	61.	65.
	57"				DP8120PC57S	64.	68.	72.
	64"				DP8120PC64S	64.	68.	72.
	78"				DP8120PC78S	72.	80.	83.
 Universal Post (Post Only)	36"	3"	3"		DP8120PO36	240.		
	42"	3"	3"		DP8120PO42	240.		
	50"	3"	3"		DP8120PO50	254.		
	57"	3"	3"		DP8120PO57	274.		
	64"	3"	3"		DP8120PO64	274.		
	78"	3"	3"		DP8120PO78	370.		


Alternative Planning

Ordering Information	Order Code	Included with:	Options
Universal Post	Universal Post	Universal Post	120° Post
1. Pattern Number	<i>Example:</i> DP2A P050	Connecting hardware	Panel Top Cap and Post Covers
Panel Top Cap	DP2A Pattern Number	Panel Top Cap	(4) = Metal, Radius
1. Pattern Number	P050	Post Covers	(5) = Metal, Flat
2. Trim finish	Panel Top Cap		
Post Covers	<i>Example:</i> DPV1 PT4, V04		
1. Pattern Number	DPV1 PT4 Pattern Number		
2. Trim finish	V04 Maple trim finish		
	Post Covers		
	<i>Example:</i> DP2A PC50S, 117		
	DP(2A) Pattern Number		
	PC50S		
	117 Soft grey trim finish		

120° Planning
120° Worksurface and Transition Tops
Grain Direction

Dividends Horizon

Grain Direction



120° Planning

120° Worksurface and Transition Tops

Dividends Horizon

description	top name	w	return depth	d	pattern no.	2 mm	woodgrain edge	metal edge
Worksurface	W11L	48"	18"L-24"R		D1WW11481824	\$1,311.	\$1,440.	\$1,572.
	W11L	48"	24"L-18"R		D1WW11482418	1,311.	1,440.	1,572.
	W12L	48"	24"		D1WW124824L	1,368.	1,510.	1,644.
	W12R	48"	24"		D1WW124824R	1,368.	1,510.	1,644.
	W1318L	48"	24"L-18"R		D1WW13482418	1,311.	1,440.	1,572.
	W1318R	48"	18"L-24"R		D1WW13481824	1,311.	1,440.	1,572.
	W13L	48"	24"		D1WW134824L	1,311.	1,440.	1,572.
	W13R	48"	24"		D1WW134824R	1,311.	1,440.	1,572.
	W218L	48"	24"L-18"R		D1WW12482418	1,368.	1,510.	1,644.
	W218R	48"	18"L-24"R		D1WW12481824	1,368.	1,510.	1,644.
	W3	48"	24"		D1WW34824	1,002.	1,098.	1,194.
	W4	48"	24"		D1WW44824	1,026.	1,132.	1,232.
	W5L	48"	24"		D1WW54824L	827.	911.	998.
	W5R	48"	24"		D1WW54824R	827.	911.	998.
	W6L	48"	24"		D1WW64824L	1,110.	1,222.	1,332.
	W6R	48"	24"		D1WW64824R	1,110.	1,222.	1,332.
	W7L	48"	24"		D1WW74824L	1,106.	1,220.	1,327.
	W7R	48"	24"		D1WW74824R	1,106.	1,220.	1,327.
Transition tops	T2	50"	24"		D1WT224	665.	734.	800.
	T218	37 1/2"	18"		D1WT218	624.	690.	748.
	T3	26"	24"		D1WT324	634.	701.	766.
	T4	26"	24"		D1WT424	765.	840.	916.
	T5	50"	24"		D1WT524	773.	851.	924.
	T518	37 1/2"	18"		D1WT518	694.	761.	829.

Alternative Planning

Ordering Information	Order Code	Included with:	Options
Worksurface	Example: D1WW134824L, 118, 118	Worksurface	Refer to the worksurface planning page for worksurface drawings and applications.
1. Pattern number	D1W Dividends 120 w/s 2mm edge	• Worksurface	
2. Finish	W13 Worksurface #13	Worksurface supports must be ordered separately.	
	4824 Side width/return depth	For all tops, specify laminate and edge color.	Note: W3 worksurfaces have a grain direction option. Specify left, right or diagonal. Add \$26 to the list price when specifying diagonal.
	L Pedestal on left side	Transition and peninsula tops require a column base for support.	
	118 Bright White laminate	Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.	
	118 Bright White edge		

3+1 Circuit Electrical

The Dividends Horizon 3+1 electrical system is designed for areas where power usage is significant and sensitive electronic equipment requiring a single isolated circuit is required.

The wire configuration of the 8-wire/4 circuit electrical system is (see chart):

- Hot "A" (black)
- Hot "B" (red)
- Hot "C" (blue)
- Shared neutral "N1" (white/black) for circuits #1, 2 and 3
- Shared ground "G1" (green or bare copper) for circuits #1, 2 and 3
- Hot "X" (pink)
- Isolated neutral "N2" (white/red) for circuit 4
- Isolated ground "G2" (green/yellow) for circuit 4

For convenience power, Circuits 1, 2 and 3 share a common neutral and ground (N1 & G1). Circuit 4 is electrically isolated with its own neutral and ground (N2 & G2).

As the ground conductor of Circuit 4 (green-yellow insulated wire) is truly isolated, touching no bare metal back to the open end of the Power Infeed, 4-conductor ISOLATED GROUND RECEPTACLES (2G, 1N, 1P are unnecessary for uninterrupted power supply (UPS) applications.

Compatibility

All Dividends Horizon power systems use components that appear similar. However, components from the three different power systems are not functionally, fully interchangeable. 3+1 components can be connected to 3+3 wire systems however only 3+1 will function.

3+1 Duplex Receptacles

Duplex receptacles used in 3+1 electrical systems are:

- Convenience duplex circuit number 1 (pattern number DE1DR1)
- Convenience duplex circuit number 2 (pattern number DE1DR2)
- Convenience duplex circuit number 3 (pattern number DE1DR3)
- Isolated duplex circuit number 4 (pattern number DE1DR4)

Isolated duplex receptacle number 4 has an orange-colored triangle on black background to identify an isolated duplex.

An optional orange-colored isolated duplex is also available. It has the isolated identifying triangle outlined in black.

- Isolated orange-colored duplex circuit number 4 (pattern number DE1DOR4)

3+1 Electrical System Technical Specifications

The 3+1 electrical system consists of four 20A, 120 volt, 60-Hertz circuits. The plug-in, duplex receptacles are rated at 15A (5-15R). Circuits will accommodate 120 volt single phase, 120/240 volt split phase and 120/208 volt three phase power. The US National Electrical Code (NEC) limits 20A circuit total planned loads to 80% of capacity or 16 amps. As the Canadian Electrical Code (CEC) calls for the circuit's overcurrent protection rating to match the 15A receptacle rating, 15A Circuit Breakers are **required** in the panel box. 15A circuit total

planned loads should not exceed 80% of capacity or 12 amps. Typically, each circuit can power 8-10 duplex convenience outlets with normal loads. In heavier load situations, such as computer systems, each circuit will power 3-5 duplex outlets. If each workstation has two convenience duplex outlets and one protected duplex, the 8-wire (4-circuit) system can supply a cluster of 6 -10 workstations from each infeed.

SPECIFYING ELECTRICAL COMPONENTS

Panel Power Module


Specify one panel power module per panel that matches the width of the panel where duplexes or infeeds are required.

Power Connector

Specify one power connector (with or without post) to connect panel power modules in adjacent panels.

Power Jumper

Specify one power jumper that matches the width of the panel(s) being passed through to connect to panel power modules in nonadjacent panels.



2+2 Electrical System

The Dividends Horizon 2+2 electrical system is designed for areas where power usage is significant and sensitive electronic equipment requiring two isolated circuits are required.

The wiring configuration of the (2+2) electrical system is (see chart):

- Hot "A" (black)
- Hot "B" (red)
- Shared neutral "N1" (white/black) for circuits #1 and 2
- Shared ground "G1" (green, bare copper) for circuits #1 and 2
- Hot "Y" (tan)
- Hot "X" (pink)
- Isolated Shared Neutral "N2" (white/red) for circuits #4 and 5
- Isolated Shared ground "G2" (green/yellow) for circuits #4 and 5

Circuits 1 and 2 share common neutral and ground. Circuits 4 and 5 share a separate common neutral and ground.

Compatibility

All Dividends Horizon power systems use components that appear similar. However, components from the three different power systems are not functionally, fully interchangeable.

2+2 Duplex Receptacles

Duplex receptacles used in 8-wire (2+2) electrical systems are:

- Convenience duplex circuit number 1 (pattern number DE1DR1)
- Convenience duplex circuit number 2 (pattern number DE1DR2)
- Isolated duplex circuit number 4 (pattern number DE1DR4)
- Isolated duplex circuit number 5 (pattern number DE1DR5)

2+2 Electrical System Technical Specifications

The 2+2 electrical system consists of four 20A, 120 volt, 60-Hertz circuits. The plug-in, duplex receptacles are rated 15A (5-15R). Circuits will accommodate 120 volt single phase, 120/240 volt split phase and 120/208 volt three phase power. The US National Electrical Code (NEC) limits 20A circuit total planned loads to 80% of capacity or 16 amps. As the Canadian Electrical Code (CEC) calls for the circuit's overcurrent protection rating to match the 15A receptacle rating, 15A Circuit Breakers are **required** in the panel box. 15A circuit total planned loads should not exceed 80% of capacity or 12 amps.

SPECIFYING ELECTRICAL COMPONENTS

Panel Power Module

Specify one panel power module per panel that matches the width of the panel where duplexes or infeeds are required.


Power Connector

Specify one power connector (with or without post) to connect power modules in adjacent panels.

Power Jumper

Specify one power jumper that matches the width of the panel(s) being passed through to connect to panel power modules in nonadjacent panels.

Wiring Diagram (2+2)



3+3 Electrical System

The Dividends Horizon 3+3 electrical system is designed for areas where power usage is significant and sensitive electronic equipment requiring multiple isolated circuits is required.

The wiring configuration of the 3+3 electrical system is (see chart):

- Hot "A" (black)
- Hot "B" (red)
- Hot "C" (blue)
- Shared neutral "N1" (white/black) for circuits #1, 2 and 3
- Shared ground "G1" (green or bare copper) for circuits #1, 2 and 3
- Hot "Z" (orange)
- Hot "X" (pink)
- Hot "Y" (tan)
- Isolated neutral "N2" (white/red) for circuits 4, 5 and 6
- Isolated ground "G2" (green/yellow) for circuits 4, 5 and 6

For convenience power, Circuits 1, 2 and 3 share a common neutral and ground (N1 & G1). Circuits 4, 5 and 6 share a separate common neutral and ground (N2 & G2).

Compatibility

All Dividends Horizon power systems use components that appear similar. However, components from the three different power systems are not functionally, fully interchangeable. 3+3 components can be connected to 3+1 systems, however only 8-wires will function.

3+3 Duplex Receptacles

Duplex receptacles used in 3+3 electrical systems are:

- Convenience duplex circuit number 1 (pattern number DE1DR1)
- Convenience duplex circuit number 2 (pattern number DE1DR2)
- Convenience duplex circuit number 3 (pattern number DE1DR3)
- Isolated duplex circuit number 4 (pattern number DE1DR4)
- Isolated duplex circuit number 5 (pattern number DE1DR5)
- Isolated duplex circuit number 6 (pattern number DE1DR6)

Isolated duplex receptacles number 4, 5 and 6 have an orange-colored triangle on black background to signify as an isolated duplex.

Optional orange-colored isolated duplexes are also available. They have the isolated identifying triangle outlined in black.

- Isolated orange-colored duplex circuit number 4 (pattern number DE1DOR4)
- Isolated orange-colored duplex circuit number 5 (pattern number DE1DOR5)
- Isolated orange-colored duplex circuit number 6 (pattern number DE1DOR6)

3+3 Electrical System Technical Specifications

The 3+3 electrical system consists of six 20A, 120 volt, 60-Hertz circuits. The plug-in duplex receptacles are rated 15A (5-15R). Circuits will accommodate 120 volt single phase, 120/240 volt split phase and 120/208 volt three phase power. The US National Electrical Code (NEC) limits 20A circuit total planned loads to 80% of capacity or 16 amps. As the Canadian Electrical Code (CEC) calls for the circuit's overcurrent protection rating to match the 15A receptacle rating, 15A Circuit Breakers are **required** at the panel box. 15A circuit total planned loads should not exceed 80% of capacity or 12 amps. Typically, each circuit can power 8-10 duplex convenience outlets with normal loads. In heavier load situations, such as computer systems, each circuit will power 3-5 duplex outlets. If each workstation has two convenience duplex outlets and one protected duplex, the 10-wire (6 circuit) system can supply a cluster of 9-15 workstations from each infeed.

SPECIFYING ELECTRICAL COMPONENTS

Panel Power Module

Specify one panel power module per panel that matches the width of the panel where duplexes or infeeds are required.


Power Connector

Specify one power connector (with or without post) to connect panel power modules in adjacent panels.

Power Jumper

Specify one power jumper that matches the width of the panel(s) being passed through to connect to panel power modules in nonadjacent panels.

Wiring Diagram (3+3)



250V Electrical System

The Dividends Horizon 250V electrical system is designed for areas where power usable is significant and sensitive electronic equipment requiring two isolated circuits is required.

The wiring configuration of the 250V electrical system is (see chart).

- Hot 1 (black)
- Neutral 1 (white/black)
- Hot 2 (red)
- Neutral 2 (white/red)
- Shared ground “G1” (green or bare copper) for circuits #1 and 2.
- Hot 3 (blue)
- Neutral 3 (white/blue)
- Hot 4 (pink)
- Neutral 4 (white/purple)
- Shared ground “G2” (green/yellow) for circuits # 3 and 4.
- Neutral 4 (white/purple)

Each circuit possesses a dedicated neutral. Circuits 1 and 2 share a ground. Circuits 3 and 4 share an separate ground.

Compatibility

All Dividends Horizon power systems use components that appear similar. However, components from the four different power systems are not functionally, fully interchangeable.

250V Duplex Receptacles

Duplex receptacles used in the 250V electrical system are:

- Convenience duplex circuit number 1 (pattern number DE1DR12V)
- Convenience duplex circuit number 2 (pattern number DE1DR22V)
- Dedicated duplex circuit number 3 (pattern number DE1DR32V)
- Dedicated duplex circuit number 4 (pattern number DE1DR42V)

250V Electrical System Technical Specifications

The 250V electrical system consists of four 20A, 250 volt, 60-Hertz circuits. The 250V plug-in, duplex receptacles are rated 20A. Circuits will accommodate 250 volt single and three phase power. Total planned loads should not exceed 16A per circuit in accordance with US and Canadian electrical code requirements.

SPECIFYING ELECTRICAL COMPONENTS

Panel Power Module

Specify one panel power module per panel that matches the width of the panel where duplexes or infeeds are required.


Power Connector

Specify one power connector (with or without post) to connect power modules in adjacent panels.

Power Jumper

Specify one power jumper that matches the width of the panel(s) being passed through to connect to panel power modules in nonadjacent panels.

Wiring Diagram (250V)



Base Raceway Electrical

Power Modules, Power Jumpers

Specifications

Dividends Horizon

Base Raceway Electrical

Power can be distributed through the base raceway.

Four systems are available:

- 3 + 1
- 2 + 2
- 3 + 3
- 250v

Modular components are used to distribute power through the base raceway and consist of:

- Power modules
- Power connectors
- Power jumpers
- Duplex receptacles
- Power infeeds

All electrical components and data cables are field-installed.

CAUTION: DO NOT CONNECT POWER UNTIL INSTALLATION IS COMPLETE. CONNECTION TO THE BUILDING POWER SOURCE MUST BE PERFORMED BY A LICENSED ELECTRICIAN.

Power Modules

Power modules are the primary electrical components for distributing electrical within panels. They are also the only components that accept duplex receptacles and power infeeds for access.

Panels 24" and wider can accept power modules. 18" wide panels only accept power jumpers.

Power modules consist of terminal blocks at each end connected by a hard-wired metal conduit. The terminal blocks accept duplex receptacles or power infeeds. Power modules snap into integral channels in base raceways and can be accessed on one or both panel sides.

Power Jumpers

Power jumpers connect between power modules in non-adjacent panels. Power jumpers take the place of power modules in panels not requiring duplexes to provide pass-through power.

Three versions are available:


- Single panel power jumpers
- Single panel power jumpers with post
- Multiple panel power jumpers

Single panel power jumpers carry power from a panel with a power module through a single non-electrified panel to an adjacent panel with a power module when a post connector is not involved.

Single panel power jumpers with post carry power from a panel with a power module through a single non-electrified panel and post connector to an adjacent panel with a power module.

Multiple panel power jumpers carry power from a panel with a power module through multiple panels with or without a post to the next available power module.

Base Raceway Electrical



Base Raceway Electrical 3+1, 2+2 and 3+3 Systems Specifications

Dividends Horizon

Power Connectors

Power connectors carry power from power module to power module in adjacent panels.

Two versions are available:

- 12" no post
- 15" with post

12" power connectors connect adjacent power modules in straight configurations when no post connector is involved.

15" power connectors are used in applications involving adjacent power modules separated by post connectors.

Duplex Receptacles

Duplex receptacles provide access to power along the base raceway.

Two duplex receptacles can be installed per panel side in base raceways 24" and wider. 18" wide panels cannot accept duplex receptacles.

Receptacles insert into terminal blocks in outlet positions at either end of power modules and attach with a single screw.

Duplexes are available in (3+1), (2+2) and (3+3) and (250v) systems. Each system engages a different combination of circuit wiring within the power module. For detailed wiring diagrams, refer to the electrical system required:

- 3 + 1
- 2 + 2
- 3 + 3
- 250v

3+1, 2+2 and 3+3 and 250v Electrical Systems

Each electrical system is designed for different usage.

The (2+2) electrical system is for areas requiring 2 circuits for standard power usage and 2 circuits for isolated power usage.

The (3+1) electrical system is for areas requiring significant power usage and an isolated circuit.

The (3+3) electrical system is for areas with significant power usage and a need for multiple isolated circuits.


The (250v) electrical system is designed for areas where power usage is significant and sensitive electronic equipment requiring two isolated circuits is present.

Base Power Infeeds


Base power infeeds route power from the building's electrical source to the panel base raceway.

Power infeeds plug into any terminal block position on panel power modules.


Power Connector



Duplex Receptacle



Base Infeed



Legend


- Power Module
- Power Jumper
- Power Connector

Note: Power connectors or power jumpers can only plug into power modules


Power Connectors




Power Connector, no post




Power Connector, with post



Power Connector, with post (2 required)




Power Connector, with post




Power Connector, with post (3 required)

Single Panel Power Jumpers





Power Jumper




Power Jumper, with post

Multiple Panel Power Jumpers



Multiple Panel Power Jumper and Power Connector






Base Raceway Electrical

Power Modules, Connectors and Jumpers

(3+1), (2+2), (3+3) and (250v)

Dividends Horizon

description	type	pattern no.	E	8	250v T
Power Module - Double sided for raceway on both sides 	24"W Panel	DE1(E,8,T,2V) PM24	\$131.	\$145.	\$150.
	30"W Panel	DE1(E,8,T,2V) PM30	140.	154.	154.
	36"W Panel	DE1(E,8,T,2V) PM36	145.	158.	162.
	42"W Panel	DE1(E,8,T,2V) PM42	156.	170.	169.
	48"W Panel	DE1(E,8,T,2V) PM48	165.	179.	177.
	60"W Panel	DE1(E,8,T,2V) PM60	184.	203.	203.
Power Module - Single sided for raceway on one side 	24"W Panel	DE1(E,8,T,2V) PMS24	131.	145.	150.
	30"W Panel	DE1(E,8,T,2V) PMS30	140.	154.	154.
	36"W Panel	DE1(E,8,T,2V) PMS36	145.	158.	162.
	42"W Panel	DE1(E,8,T,2V) PMS42	156.	170.	169.
	48"W Panel	DE1(E,8,T,2V) PMS48	165.	179.	177.
	60"W Panel	DE1(E,8,T,2V) PMS60	184.	203.	203.
Power Connector - (power module-to-power module) 	12" no post	DE1(2V) PCNPM	86.	92.	104.
	12" no post	DE1(E,8,T) PCNP	86.	92.	104.
	15" with post	DE1(2V) PCWPM	88.	95.	112.
	15" with post	DE1(E,8,T) PCWP	88.	95.	112.
	21" Mesh with post	DE1(E,8,T,2V) PC21M	95.	101.	111.
Power Jumper 	15" Panel	DE1(E,8,T,2V) PJ15NP	98.	115.	145.
	18" Panel	DE1(E,8,T,2V) PJ18NP	98.	115.	145.
	24" Panel	DE1(E,8,T,2V) PJ24NP	114.	121.	152.
	30" Panel	DE1(E,8,T,2V) PJ30NP	117.	126.	157.
	36" Panel	DE1(E,8,T,2V) PJ36NP	121.	132.	166.
	42" Panel	DE1(E,8,T,2V) PJ42NP	126.	141.	170.
	48" Panel	DE1(E,8,T,2V) PJ48NP	136.	151.	177.
Power Jumper (with post) 	15" Panel + Post	DE1(E,8,T,2V) PJ15WP	109.	118.	150.
	18" Panel + Post	DE1(E,8,T,2V) PJ18WP	109.	118.	150.
	24" Panel + Post	DE1(E,8,T,2V) PJ24WP	115.	124.	156.
	30" Panel + Post	DE1(E,8,T,2V) PJ30WP	118.	130.	161.
	36" Panel + Post	DE1(E,8,T,2V) PJ36WP	124.	139.	169.
	42" Panel + Post	DE1(E,8,T,2V) PJ42WP	131.	145.	173.
	48" Panel + Post	DE1(E,8,T,2V) PJ48WP	140.	154.	183.

Ordering Information	Order Code	Included with:	Options
Power Jumper	Power Jumper	Power Jumper	Power Jumper
1. Pattern Number	<i>Example:</i> DE1E PJ42NP DE1E Pattern Number PJ42NP		Options (E) = 3+1 (8) = 2+2 (T) = 3+3 (2V) = 250v

Note: Double-sided power module will not fit in a panel base raceway with tile to the floor on one side.

Base Raceway Electrical

Power Modules, Connectors and Jumpers

(3+1), (2+2), (3+3) and (250v)

Dividends Horizon

description	type	pattern no.	E	8	250v T
Multiple Panel Power Jumper (with or without post) 	54" Panel Run	DE1(E,8,T,2V) PJ54WP	\$148.	\$161.	\$190.
	60" Panel Run	DE1(E,8,T,2V) PJ60WP	151.	166.	190.
	66" Panel Run	DE1(E,8,T,2V) PJ66WP	158.	173.	204.
	72" Panel Run	DE1(E,8,T,2V) PJ72WP	162.	177.	210.
	78" Panel Run	DE1(E,8,T,2V) PJ78WP	169.	186.	214.
	84" Panel Run	DE1(E,8,T,2V) PJ84WP	175.	196.	218.
	96" Panel Run	DE1(E,8,T,2V) PJ96WP	185.	206.	236.

Ordering Information	Order Code	Included with:	Options
Power Jumper	Power Jumper	Power Jumper	Power Jumper
1. Pattern Number	<i>Example:</i> DE1E PJ42NP DE1E Pattern Number PJ42NP		Options (E) = 3+1 (8) = 2+2 (T) = 3+3 (2V) = 250v Note: Double-sided power module will not fit in a panel base raceway with tile to the floor on one side.

Duplex Receptacles

Duplexes are field-installed into power modules within beltway and base raceways. Duplex receptacles insert into panel power module terminal block positions and attach with a single screw.

Identification of Duplexes

Duplexes are clearly marked to indicate which circuits they access. Convenience duplex receptacles are black or white in color with the circuit identification in white.

Isolated duplexes are black or white in color with the circuit identification in white and an orange triangle located in the lower right corner.

Orange isolated duplexes are also available for ease of identification. In orange-colored duplexes the identifying triangle is outlined in black.

Types of Duplex Receptacles

Several types of duplex outlets are available. Each is specific to the circuit it accesses and is listed by power system.

Specify the duplex receptacle related to the power system being used (example: 8-wire) and circuit accessed (example: circuit 4). Black, white or orange finish.

3+1 Duplex Receptacles

Receptacles in a 3+1 electrical system can access circuits 1, 2 and 3 (convenience power) and circuit 4 (isolated power)

2+2 Duplex Receptacles

Receptacles in a 2+2 electrical system can access circuits 1 and 2 (convenience power) and circuits 4 and 5 (isolated power)

Please note that circuit 3 is not available in a 2+2 electrical system.

3+3 Duplex Receptacles

Receptacles in a 3+3 electrical system can access circuits 1, 2 and 3 (convenience power) and circuits 4, 5 and 6 (isolated power)

250v Receptacles

Receptacles in a 250v electrical system can access circuits 1 and 2 (convenience power) and circuits 3 and 4 (isolated power)

Power Capacity

Each duplex circuit has a capacity of 20 amps. The National Electrical Code (NEC) requires that each circuit does not exceed 80% of capacity or 16 amps continuous use on each 20 amp circuit.

Duplex Receptacle Dimensions

- Overall dimensions: 4 ⁵/₈" wide, 2 ¹/₁₆" high, 1" deep
- Face dimensions: 2 ⁵/₈" wide, 1 ¹/₄" high

Access


Non-electrified panels can accept data ports in any raceway cover knockout. Panels with power modules can only accept data ports in the center knockout due to the location of the terminal block.

Typical Power Requirements of Various Equipment

Equipment	Amp (approx.)
Calculator	.25
Coffee maker*	8.5-15
Desktop copier*	10-15
Fan	1
Fax (plain paper)	5-8
Heater*	8.5-15
Laser printer	6-10
Lighting	.5-1.5
Microwave*	10-20
PC	4-8
Refrigerator*	10-15
Terminal	1-3
Typewriter	1-2
Scanner	.25-.5

*Requires separate circuit

Note: The above amperage chart is based on the estimated average amount of power required and is intended as a general guide only. For precise amperage requirements, refer to the equipment manufacturer's amperage specifications and compare to the available amperage on each circuit.



Base Raceway Covers (knockout locations)

18W	
24W	
30W	
36W	
42W	
48W	

Beltway Covers (knockout locations)

18W	
24W	
30W	
36W	
42W	
48W	

Receptacles

Knockout Replacement Covers

Dividends Horizon

description	type	pattern no.	Single pack list	Ten pack list
Receptacle, (3+1) 	Duplex circuit 1	DE1DR1 ()	\$46.	\$363.
	Duplex circuit 2	DE1DR2 ()	46.	363.
	Duplex circuit 3	DE1DR3 ()	46.	363.
	Duplex circuit 4	DE1DR4 ()	46.	363.
Receptacle, (2+2) 	Duplex circuit 1	DE1DR1 ()	46.	363.
	Duplex circuit 2	DE1DR2 ()	46.	363.
	Duplex circuit 4	DE1DR4 ()	46.	363.
	Duplex circuit 5	DE1DR5 ()	46.	363.
Receptacle, (3+3) 	Duplex circuit 1	DE1DR1 ()	46.	363.
	Duplex circuit 2	DE1DR2 ()	46.	363.
	Duplex circuit 3	DE1DR3 ()	46.	363.
	Duplex circuit 4	DE1DR4 ()	46.	363.
	Duplex circuit 5	DE1DR5 ()	46.	363.
	Duplex circuit 6	DE1DR6 ()	46.	363.
Receptacle, (Orange) 	Duplex circuit 4	DE1DOR4()	46.	363.
	Duplex circuit 5	DE1DOR5()	46.	363.
	Duplex circuit 6	DE1DOR6()	46.	363.
Receptacle, (With Controlled Symbol) 	Duplex circuit 1	DE1DR1C ()	46.	363.
	Duplex circuit 2	DE1DR2C ()	46.	363.
	Duplex circuit 3	DE1DR3C ()	46.	363.
	Duplex circuit 4	DE1DR4C ()	46.	363.
	Duplex circuit 5	DE1DR5C ()	46.	363.
	Duplex circuit 6	DE1DR6C ()	46.	363.
Receptacle, (250v) 	Duplex circuit 1	DE1DR12V ()	47.	363.
	Duplex circuit 2 (orange)	DE1DR22V ()	47.	363.
	Duplex circuit 3	DE1DR32V ()	47.	363.
	Duplex circuit 4	DE1DR42V ()	47.	363.
Base Raceway Knockout Replacement Cover (for electrical or data) 	Package of 10	DE2KC10	n/a	92.

Electrical/Data Components

Ordering Information	Order Code	Included with:	Options
Receptacle	Receptacle	Receptacle	Receptacle
1. Pattern Number	<i>Example:</i> DE1 DR4 DE1 DR4 Pattern Number		Quantity Option: (SP) = Single Pack (TP) = Ten Pack Color Option: 111 = Black 114 = Folkstone Grey 115 = Medium Grey 118 = White 117 = Soft Grey 611 = Beige Mist Metallic

Receptacles

USB

Dividends Horizon

description	type	pattern no.	Single pack list	Ten pack list
 USB Receptacle Vertical	Circuit 1	DE1USB1V()	\$128.	\$1,210.
	Circuit 2	DE1USB2V()	128.	1,210.
	Circuit 3	DE1USB3V()	128.	1,210.
	Circuit 4	DE1USB4V()	128.	1,210.
	Circuit 5	DE1USB5V()	128.	1,210.
	Circuit 6	DE1USB6V()	128.	1,210.
 USB Receptacle Horizontal	Circuit 1	DE1USB1H()	128.	1,210.
	Circuit 2	DE1USB2H()	128.	1,210.
	Circuit 3	DE1USB3H()	128.	1,210.
	Circuit 4	DE1USB4H()	128.	1,210.
	Circuit 5	DE1USB5H()	128.	1,210.
	Circuit 6	DE1USB6H()	128.	1,210.

Ordering Information	Order Code	Included with:	Options
Vertical Power Module 1. Pattern Number	Vertical Power Module <i>Example:</i> DE1 USB 1V10W DE1USB Pattern Number 1V10W	Vertical Power Module • USB Receptacle	Vertical Power Module Quantity Option: (V) = Vertical Single Pack (V10) = Vertical Ten Pack (H) = Horizontal Single Pack (H10) = Horizontal Ten Pack Color Option: 111 = Black 114 = Folkstone Grey 115 = Medium Grey 118 = White 117 = Soft Grey 611 = Beige Mist Metallic

This page intentionally left blank

Vertical Electrical

Power Module, Electrical Receptacle and Trim Plate Specifications

Dividends Horizon

Vertical Power Module

A vertical power module is an alternative to using base raceway electrical. The use of a vertical power module allows for electrical access along the vertical side of the panel. Vertical power modules can be positioned at predefined locations or field drilled to allow placement at almost any height.

A panel's left-hand or right-hand vertical rail (see below) allows for installation of a vertical power module. Vertical power modules may be installed with 1-sided or 2-sided access, allowing users of both panel faces access to an electrical receptacle.

Base Power Jumpers

Base raceway power jumpers are used to connect the adjacent panel's base power module to the vertical power module. Power can also be routed directly from a power infeed into the vertical power module.

Additional vertical power modules may be "daisy-chained" together with base power jumpers. If one vertical power module is installed, an additional vertical power module may be added within the same panel. A base power jumper connects between the two vertical power modules.

Vertical power modules can also be daisy-chained in adjacent panels. A base power jumper passes through the beltway panel frame opening to connect to the additional vertical power module.

Vertical Electrical Receptacle

Double vertical power modules use the same receptacles as the base raceway electrical while single vertical power modules use receptacles designed to work with a deeper faceplate. Receptacles and faceplates are ordered separately from the vertical power module

Double modules support 2 duplex receptacles on the front and 2 on the back for a total of 8 outlets per power module and are compatible with 3+1, 2+2, 3+3 and 250v systems. Double modules require one receptacle on each side to be flipped over so when you have two placed side by side they face in opposite directions but are aligned vertically. Single modules support 1 duplex receptacle on the front and 1 duplex receptacle on the back for a total of 4 outlets per module and are compatible with 3+1, 2+2, 3+3 and 250v systems.

Panel tiles are field cut for all vertical applications including fabric, laminate and steel. Vertical electrical is not recommended for slatwall tiles.

Vertical electrical faceplates, ordered separately, provide a finished trim around the field cut hole through the tile. Outlet fillers are available and sold in packs of 10.

Desktop Power module

Desktop power modules (DE3WSME) provide two low-profile outlets at worksurface height. The desktop power module also helps meet ADA requirements regarding power access at worksurface height. A mounting bracket and attachment screw allow the desktop power module to be installed at any point along the rear of a worksurface without tools or the removal of the worksurface. Dimensions are 3³/₄" wide and 4¹/₂" high.

Base Raceway Power Jumpers

To specify a base power jumper that connects a desk height vertical power module to an adjacent panel's base power module, specify a 48" base power jumper for panel widths of 36" or less. Use a 54" base power jumper for panel widths of 42" or 48". If a vertical power module is to be installed higher than worksurface height within a 64" high panel, a 66" base power jumper is required and an 84" base power jumper is required for 78" high panels.

To specify a base power jumper to span the width of two vertical power modules within two adjacent panels, identify the base power jumper length by combining the panel widths and height differences between the two vertical power modules.


Note: The base power jumper passes through the panel's beltway opening that is at a height of 33".

The panel's beltway opening (at 33" high) must not be obstructed as to allow for the base power jumper to pass through.


Note: 36" high panel frames do not have beltway openings and do not support horizontal power pass through at 33".

Note: Single vertical electrical modules can be used with a technology tile. Double vertical electrical modules are not compatible with a technology tiles.


Double Vertical Electrical
within Same Frame



Double Vertical Electrical
within Adjacent Frame



Double Vertical Electrical with Trim Plate



Vertical Electrical

Power Module, Electrical Receptacle and Trim Plate Specifications

Dividends Horizon

Communications and Data Distribution

Dividends Horizon panels can accommodate communications and data cables horizontally in three ways:

- Along the top cableway
- Along the beltway (with optional cable tray)
- Along the base raceway (with optional cable tray)

Vertical cable distribution is through the panel's internal panel cavity which is accessed by cable slots located in both the upper and lower horizontal panel frame. Since cables are distributed internally within Dividends Horizon panels, no external cable managers are required.

Raceway cover data knockouts have an opening of $1\frac{3}{8}$ " high x $2\frac{11}{16}$ " wide. Data port covers are no longer available from Knoll and must be supplied from a communications vendor.

Data Port Access

Non-electrified panels can accept data ports in any raceway cover knockout.

Panels with power modules can only accept data ports in the center knockout due to the location of the terminal blocks.

Single Floating Data Port

Dividends Horizon floating data ports allow data and communications to be mounted in any location on the panel surface.

Floating data ports include front and back mounting plates and attachment screws. All data port kits must be specified separately for floating data ports. Floating data ports involve field-cutting the panel insert for installation.


Includes front and back mounting plates and two mounting screws. Data ports kits or data port components must be specified separately from a communications vendor. Black finish.

Desktop Modules




The desktop data module provides up to two data/communication ports at worksurface height. The desktop power module provides two convenient electrical outlets at worksurface height. The desktop power and data module includes two data/communication ports and two electrical outlets at worksurface height. The thumbscrew on the bracket allows user adjustability if desired. Black finish.

Data modules do not include data jacks. Data jacks need to be purchased separately. This data module has two openings that can accept most standard jack sizes. The data module comes with adapter pieces that can accommodate most standard data jacks.


Topway Panel Cable Routing




Floating Data Port




Desktop Data Module



Desktop Power and Data Module



Desktop Power Module




Vertical Electrical

Power Module, Electrical Receptacle and Trim Plate

Double and Single Ports

Dividends Horizon

description	type	pattern no.	Single pack	Ten pack	3+1	2+2	250v 3+3
Technology Tile Trim Plate (field install kit)	Faceplate, backplate filler and hardware	DE6 FDP	\$60.	n/a			




Base Raceway Power Jumpers 	48" Jumper	DE1(E,8,T,2V) PJ48WP			140.	154.	183.
	54" Jumper	DE1(E,8,T,2V) PJ54WP			148.	161.	190.
	60" Jumper	DE1(E,8,T,2V) PJ60WP			151.	166.	190.
	66" Jumper	DE1(E,8,T,2V) PJ66WP			158.	173.	204.
	72" Jumper	DE1(E,8,T,2V) PJ72WP			162.	177.	210.
	78" Jumper	DE1(E,8,T,2V) PJ78WP			169.	186.	214.
	84" Jumper	DE1(E,8,T,2V) PJ84WP			175.	196.	218.

Ordering Information	Order Code	Included with:	Options
Vertical Power Module	Vertical Power Module	Vertical Power Module	Vertical Power Module
1. Pattern Number	<i>Example:</i> DE5 VPM	Base Raceway Power Jumper	Base Raceway Power Jumper
Base Raceway Power Jumper	DE5 VPM Pattern Number		Insert appropriate letter for type of wiring required within the parentheses of the pattern number.
1. Pattern Number	Base Raceway Power Jumper		(E) = 3+1
	<i>Example:</i> DE1(E) BPJ30		(8) = 2+2
	DE1(E) Pattern Number		(T) = 3+3
	BPJ30		(2V) = 250v
			Receptacle Quantity Option:
			(SP) = Single Pack
			(TP) = Ten Pack
			Note: Trim plate filler for use with technology tile trim plate only.
			Color Option:
			111 = Black
			114 = Folkstone Grey
			115 = Medium Grey
			118 = White
			117 = Soft Grey
			611 = Beige Mist Metallic


Single Vertical Electrical Power Module, Electrical Receptacle and Trim Plate Single Ports

Dividends Horizon


description	type	pattern no.	Single pack	Ten pack	3+1	2+2	250v 3+3
Single Vertical Power Module	Vertical Power Module	DE6 VPM	\$237.	n/a			




Vertical Electrical Receptacle for single unit (3+1)	Duplex circuit 1	DE6 VDR1()	46.	363.
	Duplex circuit 2	DE6 VDR2()	46.	363.
	Duplex circuit 3	DE6 VDR3()	46.	363.
	Duplex circuit 4	DE6 VDR4()	46.	363.



Vertical Electrical Receptacle for single unit (2+2)	Duplex circuit 1	DE6 VDR1()	46.	363.
	Duplex circuit 2	DE6 VDR2()	46.	363.
	Duplex circuit 4	DE6 VDR4()	46.	363.
	Duplex circuit 5	DE6 VDR5()	46.	363.



Vertical Electrical Receptacle for single unit (3+3)	Duplex circuit 1	DE6 VDR1()	46.	363.
	Duplex circuit 2	DE6 VDR2()	46.	363.
	Duplex circuit 3	DE6 VDR3()	46.	363.
	Duplex circuit 4	DE6 VDR4()	46.	363.
	Duplex circuit 5	DE6 VDR5()	46.	363.
	Duplex circuit 6	DE6 VDR6()	46.	363.




Ordering Information	Order Code	Included with:	Options
Vertical Power Module 1. Pattern Number	Vertical Power Module <i>Example:</i> DE5 VPM DE5 VPM Pattern Number	Vertical Power Module Base Raceway Power Jumper	Vertical Power Module Base Raceway Power Jumper Insert appropriate letter for type of wiring required within the parentheses of the pattern number. (E) = 3+1 (8) = 2+2 (T) = 3+3 (2V) = 250v
Base Raceway Power Jumper 1. Pattern Number	Base Raceway Power Jumper <i>Example:</i> DE1(E) BPJ30 DE1(E) Pattern Number BPJ30		Receptacle Quantity Option: (SP) = Single Pack (TP) = Ten Pack Note: Trim plate filler for use with technology tile trim plate only. Color Option: 111 = Black 114 = Folkstone Grey 115 = Medium Grey 118 = White 117 = Soft Grey 611 = Beige Mist Metallic


Single Vertical Electrical Power Module, Electrical Receptacle and Trim Plate Single Ports

Dividends Horizon


description	type	pattern no.	Single pack	Ten pack	3+1	2+2	250v 3+3
Vertical Electrical Receptacle (With Controlled Symbol) for Single Unit	Duplex circuit 1	DE6 VDR1C()	\$46.	\$363.			
	Duplex circuit 2	DE6 VDR2C()	46.	363.			
	Duplex circuit 3	DE6 VDR3C()	46.	363.			
	Duplex circuit 4	DE6 VDR4C()	46.	363.			
	Duplex circuit 5	DE6 VDR5C()	46.	363.			
	Duplex circuit 6	DE6 VDR6C()	46.	363.			



Single Trim Plate Filler	Package of 10	DE6 FDPF	n/a	48.
--------------------------	---------------	-----------------	-----	-----




Single Floating Data Port Trim Plate (field install kit)	Faceplate, backplate and hardware	DE1 FDP	55.	n/a
---	--------------------------------------	----------------	-----	-----



Ordering Information	Order Code	Included with:	Options
Vertical Power Module 1. Pattern Number	Vertical Power Module <i>Example:</i> DE5 VPM DE5 VPM Pattern Number	Vertical Power Module	Vertical Power Module
Base Raceway Power Jumper 1. Pattern Number	Base Raceway Power Jumper <i>Example:</i> DE1(E) BPJ30 DE1(E) Pattern Number BPJ30	Base Raceway Power Jumper	Base Raceway Power Jumper Insert appropriate letter for type of wiring required within the parentheses of the pattern number. (E) = 3+1 (8) = 2+2 (T) = 3+3 (2V) = 250v Receptacle Quantity Option: (SP) = Single Pack (TP) = Ten Pack Note: Trim plate filler for use with technology tile trim plate only. Color Option: 111 = Black 114 = Folkstone Grey 115 = Medium Grey 118 = White 117 = Soft Grey 611 = Beige Mist Metallic

Double Verical Electrical
Power Module and Trim Plate
Double Ports

Dividends Horizon

description	type	pattern no.	Single pack	Ten pack	3+1	2+2	250v 3+3
Double Vertical Power Module	Double Vertical Power Module	DE6 D VPM	\$232.	n/a			
							
Double Vertical Power Module Trim Plate	Trim Plate - Double	DE6 D FD P	59.	n/a			
							

Ordering Information	Order Code	Included with:	Options
Vertical Power Module 1. Pattern Number	Double Vertical Power Module <i>Example:</i> DE6 D VPM	Vertical Power Module	Vertical Power Module
Base Raceway Power Jumper 1. Pattern Number	DE6 D VPM Pattern Number	Base Raceway Power Jumper	Insert appropriate letter for type of wiring required within the parentheses of the pattern number: (E) = 3+1 (8) = 2+2 (T) = 3+3 (2V) = 250v Double Trim Plate Color Option: 111 = Black 114 = Folkstone Grey 115 = Medium Grey 118 = White 117 = Soft Grey 611 = Beige Mist Metallic

Desktop Power and Data Modules

Table Undermount Outlet

Dividends Horizon





description	type	pattern no.	list
Electrical Outlet for Table Undermount 210, 2 power + 1 dual USB + 0 data 	120" cordset	DE4TU210120(BB/WW/WS)	\$602.
	72" cordset	DE4TU21072(BB/WW/WS)	582.
	72" hardwire	DE4TU210H(BB/WW/WS)	649.
Electrical Outlet for Table Undermount 202, 2 power + 0 dual USB + 2 data 	120" cordset	DE4TU202120(BB/WW/WS)	548.
	72" cordset	DE4TU20272(BB/WW/WS)	502.
	72" hardwire	DE4TU202H(BB/WW/WS)	628.
Electrical Outlet for Table Undermount 311, 3 power + 1 dual USB + 1 data 	120" cordset	DE4TU311120(BB/WW/WS)	724.
	72" cordset	DE4TU31172(BB/WW/WS)	705.
	72" hardwire	DE4TU311H(BB/WW/WS)	797.
Electrical Outlet for Table Undermount 412, 4 power + 1 dual USB + 2 data 	120" cordset	DE4TU412120(BB/WW/WS)	804.
	72" cordset	DE4TU41272(BB/WW/WS)	785.
	72" hardwire	DE4TU412H(BB/WW/WS)	878.

Order Code	Specification Information	Application Notes
Example: DE4TU21072 (BB)	<i>To order please specify pattern number including:</i> 1. Color option, (housing / bracket): BB=Black/Black WW = White/White WS=White/Silver	Installation instruction sheet available on Knoll Exchange.
DE4 Dividends Horizon Desktop Outlet		Refer to planning guide pages for complete description.
TU Table Undermount		USB outlet is for recharging purposes only. No data transfer. All Desktop outlets are UL listed.
210 2 Power, 1 USB, 0 Data		Simplex receptacles and USB charging ports are wired together and on the same circuit.
72 72" cordset, 120=120" cord, H=72" Hardwire		
() Color Option		

Desktop Power and Data Modules

Clamp-on

Dividends Horizon

description	type	pattern no.	list
 Clamp-on Electrical Outlet 210, 2 power + 1 dual USB + 0 data	120" cordset	DE4CL210120(BB/WW/WS)	\$646.
	72" cordset	DE4CL21072(BB/WW/WS)	628.
	72" hardwire	DE4CL210H(BB/WW/WS)	694.
 Clamp-on Electrical Outlet 202, 2 power + 0 dual USB + 2 data	120" cordset	DE4CL202120(BB/WW/WS)	542.
	72" cordset	DE4CL20272(BB/WW/WS)	520.
	72" hardwire	DE4CL202H(BB/WW/WS)	614.
 Clamp-on Electrical Outlet 311, 3 power + 1 dual USB + 1 data	120" cordset	DE4CL311120(BB/WW/WS)	713.
	72" cordset	DE4CL31172(BB/WW/WS)	693.
	72" hardwire	DE4CL311H(BB/WW/WS)	786.
 Clamp-on Electrical Outlet 412, 4 power + 1 dual USB + 2 data	120" cordset	DE4CL412120(BB/WW/WS)	797.
	72" cordset	DE4CL41272(BB/WW/WS)	777.
	72" hardwire	DE4CL412H(BB/WW/WS)	870.
 Thumb Screw Kit	1 set = 2 screws	RDOTK1	14.





Electrical/Data
Components

Order Code	Specification Information	Application Notes
Example: DE4CL21072 (BB)	<i>To order please specify pattern number including:</i>	Installation instruction sheet available on Knoll Exchange.
DE4 Dividends Horizon Desktop Outlet	1. Color option, (housing / bracket): BB=Black/Black WW = White/White WS=White/Silver	Refer to planning guide pages for complete description.
CL Clamp-on		USB outlet is for recharging purposes only. No data transfer. All Desktop outlets are UL listed.
210 2 Power, 1 USB, 0 Data		Simplex receptacles and USB charging ports are wired together and on the same circuit.
72 72" cordset, 120=120" cord, H=72" Hardwire		
() Color Option		

Desktop Power and Data Modules

Offset Clamp-on

Dividends Horizon

description	type	pattern no.	list
 Offset Clamp-on Electrical Outlet 202, 2 power + 0 dual USB + 2 data	72" cordset	DE4OC20272 (BB/WW/WS)	\$520.
	120" cordset	DE4OC202120 (BB/WW/WS)	542.
	72" hardwire	DE4OC202H (BB/WW/WS)	614.
 Offset Clamp-on Electrical Outlet 210, 2 power + 1 dual USB + 0 data	72" cordset	DE4OC21072 (BB/WW/WS)	628.
	120" cordset	DE4OC210120 (BB/WW/WS)	646.
	72" hardwire	DE4OC210H (BB/WW/WS)	694.
 Offset Clamp-on Electrical Outlet 311, 3 power + 1 dual USB + 1 data	72" cordset	DE4OC31172 (BB/WW/WS)	693.
	120" cordset	DE4OC311120 (BB/WW/WS)	713.
	72" hardwire	DE4OC311H (BB/WW/WS)	786.
 Offset Clamp-on Electrical Outlet 412, 4 power + 1 dual USB + 2 data	72" cordset	DE4OC41272 (BB/WW/WS)	777.
	120" cordset	DE4OC412120 (BB/WW/WS)	797.
	72" hardwire	DE4OC412H (BB/WW/WS)	870.

Order Code	Specification Information	Application Notes
Example: DE4OC21072 (BB)	<i>To order please specify pattern number including:</i> 1. Color option, (housing / bracket): BB=Black/Black WW = White/White WS=White/Silver	Installation instruction sheet available on Knoll Exchange.
DE4 Dividends Horizon Desktop Outlet		Refer to planning guide pages for complete description.
OC Offset Clamp-on		USB outlet is for recharging purposes only. No data transfer. All Desktop outlets are UL listed.
210 2 Power, 1 USB, 0 Data		Simplex receptacles and USB charging ports are wired together and on the same circuit.
72 72" cordset, 120=120" cord, H=72" Hardwire		
() Color Option		

Desktop Power and Data Modules

Clamp mount

Dividends Horizon

description	type	w	d	h	pattern no.	list
Desktop Power Module, clamp mount	With 108" Cord	3 3/4"	4 1/2"	2 1/2"	DE4WSME108	\$169.
	With 72" Cord	3 3/4"	4 1/2"	2 1/2"	DE4WSME72	135.



Desktop Power + Data Module, clamp mount	With 108" Cord	6 1/8"	4 1/2"	2 1/2"	DE4WSMED108	362.
	With 72" Cord	6 1/8"	4 1/2"	2 1/2"	DE4WSMED72	327.



Desktop Data Module, clamp mount		3 3/4"	4 1/2"	2 1/2"	DE4WSMC	120.
-------------------------------------	--	--------	--------	--------	----------------	------



Ordering Information	Order Code	Included with	Options
Desktop Power Module	Desktop Power Module		
1. Pattern Number	<i>Example:</i> DE4 WSME108		

Beltway Electrical

Power can be distributed through the beltway

Four systems are available:

- 3+1
- 2+2
- 3+3
- 250v

Modular components are used to distribute power within beltways and consist of:

- Beltway power modules
- Beltway power connectors
- Beltway power jumpers
- Beltway vertical power jumpers
- Duplex receptacles

All electrical components and data cables are field-installed.

WARNING: DO NOT CONNECT POWER UNTIL INSTALLATION IS COMPLETE. CONNECTING TO THE BUILDING POWER SOURCE MUST BE PERFORMED BY A LICENSED ELECTRICIAN.

Beltway modules accept duplex receptacles and vertical power jumpers for bringing the power to the beltway from the base raceway. Another alternative for desk height electrical is a vertical power module.

Depending on the number of desk height receptacles required in each panel, consider the list price of both beltway electrical and vertical power module in each application.

Beltway Power Modules

Power modules are the primary electrical components for distributing power within beltways. Beltway power modules are also components that accept duplex receptacles and vertical power jumpers for bringing the power to the beltway from the base raceway.

Beltway raceways 30" and wider can accept beltway power modules while 18" and 24" wide panels can accept power jumpers for pass-through power only.

Beltway power modules screw into the vertical channels of panel frames and include a steel horizontal mounting support.

Specify one beltway power module per panel that matches the width of the panel where duplexes are required. Available one- or two-sided.

Just like base raceway power modules, beltway power modules consist of a terminal block at each end connected by a hard-wired metal conduit.

Beltway power modules are one- or two-sided. This allows planning options such as beltway one side and monolithic or tiled inserts on the other, or beltway one side and no inserts on the other for against-the-wall applications. The terminal blocks accept either duplex receptacles or vertical power jumpers.

Beltway Power Connectors

Beltway power connectors carry power from power module to power module in adjacent panels.

Two versions are available:


- no post
- with post.

Beltway power connectors, no post, connect adjacent power modules in straight configurations when a post connector is not involved.

Beltway power connectors, with post, are used in applications involving adjacent power modules separated by post connectors in straight through post configurations only.

Specify one beltway power connector (with or without post) to connect beltway power module or beltway power jumper in adjacent panels. In straight line configurations only.

Beltway Electrical



Beltway Profiles

Beltway Power Jumpers

Beltway power jumpers connect between power modules in nonadjacent panels.

Beltway power jumpers take the place of power modules in panels not requiring duplexes to provide pass-through power.

Three versions are available:

- Single panel jumpers
- Single panel jumpers with post
- Multiple panel jumpers

Single panel beltway jumpers carry power from a panel with a beltway power module through a single non-electrified panel to an adjacent panel with a beltway power module when a post is not involved in straight line configurations only.

Single beltway panel jumpers with post carry power from a panel with a power module through a single non-electrified panel and post connector to an adjacent panel with a beltway power module in straight through post configurations only.

Multiple beltway panel jumpers carry power from a panel with a power module through multiple panels with or without a post to the next available beltway power module in straight line configurations only.

Specify one beltway power jumper per panel that matches the width of the panel for pass-through electrical where duplexes are not required for straight line configurations only.

90° Beltway Power Jumper

A 90° beltway power jumper connects adjacent beltway power modules at a 90° “L” panel connection.

The following illustrations outline the various components required for beltway applications with a post.

Note: A 90° beltway power jumper can only be used with adjacent panels in a “X”, “T” or “L” conditions. The 90° jumper cannot be used to span multiple panels.

To specify correct jumper length, determine the largest panel width between the two adjacent corner panels in which jumper is to be installed.

Vertical Power Jumpers

To carry power from the base raceway to the beltway located in the same panel requires a vertical power jumper. Vertical power jumpers function as an extension of the base raceway power system.

Attachment is from any unused outlet position in the base raceway to the end terminal block connection in the beltway power module. The vertical power jumper cable is concealed in the cavity of the panel frame.

Power can also be carried to a beltway run from the base raceway of an adjacent panel with a power module. This is accomplished by using a panel power jumper.

Specify one vertical power jumper per beltway electrical run not to exceed the electrical systems capacity. See the technical specifications for the electrical system being utilized.

Note: Length of power jumper allows for connections with or without post conditions.

Power Infeeds

A ceiling infeed may also be used to bring power directly to the beltway power module without having to go directly to a base raceway power module.


Duplex Receptacles

Duplex receptacles provide access to power along the beltway. Duplexes used in the beltway are the same as the duplexes used in the base raceway.


Two duplex receptacles can be installed per panel side in beltway raceways 30" and wider. 24"W panels will accept beltway power jumpers for pass-through power only.

Receptacles insert into terminal blocks in outlet positions at either end of power modules and attach with a single screw.


Beltway Power Jumper Configurations



Beltway Post Connections



Beltway Electrical Components






Legend

- Power Module
- Power Jumper
- Power Jumper, with post

Beltway Electrical

Power Modules, Power Connectors and Power Jumpers

Dividends Horizon

description	type	length	pattern no.	list	3+1	2+2	250v 3+3
		30"	DE1() BPM301	\$183.	\$202.	\$202.	
		36"	DE1() BPM361	192.	210.	206.	
		42"	DE1() BPM421	202.	216.	214.	
		48"	DE1() BPM481	210.	234.	223.	
		60"	DE1() BPM601	237.	243.	243.	
		30"	DE1() BPM302	183.	202.	202.	
		36"	DE1() BPM362	192.	210.	206.	
		42"	DE1() BPM422	202.	216.	214.	
		48"	DE1() BPM482	210.	234.	223.	
		60"	DE1() BPM602	237.	243.	243.	
	17" No Post		DE2() BPCNP	90.	97.	113.	
	20" With Post		DE2() BPCWP	92.	107.	116.	
	21" Mesh with post		DE1(E,8,T,2V) PC21M	95.	101.	111.	
Intermediate Connector	Independent Neutral (2+2, 3+1, 3+3)		DE1IPA	27.			
	Shared Neutral (4-4-2)		DE1SPA	27.			
		18"	DE2() BPJ18NP	113.	120.	150.	
		24"	DE2() BPJ24NP	116.	125.	155.	
		30"	DE2() BPJ30NP	120.	131.	165.	
		36"	DE2() BPJ36NP	125.	139.	169.	
		42"	DE2() BPJ42NP	134.	149.	176.	
		48"	DE2() BPJ48NP	138.	152.	182.	
		18"	DE2() BPJ18WP	114.	123.	154.	
		24"	DE2() BPJ24WP	117.	129.	159.	
		30"	DE2() BPJ30WP	123.	137.	168.	
		36"	DE2() BPJ36WP	130.	145.	171.	
		42"	DE2() BPJ42WP	138.	152.	182.	
		48"	DE2() BPJ48WP	149.	155.	184.	
		54" Panel Run	DE2() BPJ54WP	149.	165.	188.	
		60" Panel Run	DE2() BPJ60WP	156.	171.	202.	
		66" Panel Run	DE2() BPJ66WP	161.	175.	208.	
		72" Panel Run	DE2() BPJ72WP	168.	184.	212.	
		78" Panel Run	DE2() BPJ78WP	174.	192.	216.	
		84" Panel Run	DE2() BPJ84WP	184.	206.	234.	
		96" Panel Run	DE2() BPJ96WP	198.	213.	242.	

Ordering Information	Order Code	Included with:	Options
Beltway Power Jumper 1. Pattern Number Note: Insert appropriate letter for type of wiring required within the parentheses of the pattern number.	Beltway Power Jumper <i>Example:</i> DE1(E) BPJ30 DE1(E) Pattern Number BPJ30	Beltway Power Jumper	Beltway Power Jumper Insert appropriate letter for type of wiring required within the parentheses of the pattern number. • E= 3+1 • 8= 2+2 • T= 3+3 • 2V= 250v

Beltway Electrical

Power Modules, Power Connectors and Power Jumpers

Dividends Horizon

description	type	length	pattern no.	list	3+1	2+2	250v 3+3
90° Beltway Power Jumper 		30" Beltway Panel	DE1() PJ120WP		\$239.	\$262.	\$300.
		36" Beltway Panel	DE1() PJ126WP		246.	272.	313.
		42" Beltway Panel	DE1() PJ138WP		258.	285.	322.
		48" Beltway Panel	DE1() PJ144WP		266.	295.	335.
Vertical Power Jumper (Within Same Panel) 			DE1() VPJ		206.	223.	212.
Vertical Power Jumper (From Adjacent Panel) 		30" Beltway Panel	DE1(E,8,T,2V) PJ48WP		140.	154.	183.
		36" Beltway Panel	DE1(E,8,T,2V) PJ54WP		148.	161.	190.
		42" Beltway Panel	DE1(E,8,T,2V) PJ54WP		148.	161.	190.
		48" Beltway Panel	DE1(E,8,T,2V) PJ60WP		151.	166.	190.

Ordering Information	Order Code	Included with:	Options
Beltway Power Jumper 1. Pattern Number Note: Insert appropriate letter for type of wiring required within the parentheses of the pattern number.	Beltway Power Jumper <i>Example:</i> DE1(E) BPJ30 DE1(E) Pattern Number BPJ30	Beltway Power Jumper	Beltway Power Jumper Insert appropriate letter for type of wiring required within the parentheses of the pattern number. • E= 3+1 • 8= 2+2 • T= 3+3 • 2V= 250v

Power Infeeds

Power infeeds carry power from the building's electrical source to the panel system's base raceway. Two styles are available:

- Base power infeeds
- Ceiling infeeds

Base Power Infeed

Dividends Horizon base power infeeds route power from floor monuments or electrical boxes to any terminal block duplex position on base raceway power modules. Two screws secure the base power infeed to the power module.

Note: When connected, a base power infeed takes the place of one duplex outlet.

Base power infeeds have a 56" long liquid tight conduit and pigtail for connection to the building's power supply.

Infeeds are specified either right- or left-handed. This allows the conduit to enter the outlet position from either the left or right side.

In addition to right- or left handed base power infeeds is a reversible base power infeed with a 56" long liquid tight conduit. The reversible infeed rotates to provide either a right- or left-hand power entry.

Specify the base infeed that matches the power system accessed and left or right cable entry (example: (3+1), left-hand entry).

Ceiling Infeeds

Raceway-to-ceiling infeeds route power from a ceiling-located power source to the panel system's base raceway. Unlike base infeeds which plug into any terminal block outlet position, ceiling infeeds must plug into the end of a base raceway power module. Ceiling infeeds have a 19 1/2' long metal conduit and pigtail. Two components are required for installation:

- Raceway to ceiling infeed
- Power pole

Ceiling infeed may be installed directly into a beltway power module for beltway electrical only.

Specify the ceiling infeed that matches the power system accessed.

Power Poles

Power poles can accommodate one raceway-to-ceiling infeed along with data cables. The power pole can also be used to route data cables only, if required. Cable capacity for power poles with the electrical conduit installed is 30, category 5 cables and without an electrical conduit is 40, category 5 cables.


Power poles integrate within the panel system footprint by mounting atop existing post connectors in "L", "T" or "X" configurations.

Power poles are available in three lengths in order to accommodate all three heights of post connectors. All power poles measure 126" or 144" when added to the height of the post connector. For ceilings less than 126" or 144" high, field-cut the power pole to the required height. Power poles include ceiling trim plate, connecting hardware and post/power pole trim covers.

Dividends Horizon DP8 Power Pole Construction

Power pole is extruded aluminum, with removable cover, powder coated in any Knoll Core or Dividends Horizon Legacy finish. One side of the power pole is open, allowing cables to be inserted or removed when the cover is removed.

CAUTION: DO NOT CONNECT POWER UNTIL INSTALLATION IS COMPLETE. CONNECTION TO BUILDING POWER SOURCE MUST BE PERFORMED BY A LICENSED ELECTRICIAN.



Electrical Infeeds and Power Poles

Base Power and Raceway-to-Ceiling Infeeds

Dividends Horizon

description	type	length	pattern no.	list
Base Power Infeed (specify left or right) (right shown) 	250v	56"	DE12V BI56(L/R)	\$179.
	3+1	56"	DE1E BI56(L/R)	236.
	2+2	56"	DE18 BI56(L/R)	259.
	3+3	56"	DE1T BI56(L/R)	303.
	2+2	144"	DE18 BI144(L/R)	376.
	3+1	144"	DE1E BI144(L/R)	376.
	3+3	144"	DE1T BI144(L/R)	409.
	2+2	156"	DE18 BI156(L/R)	179.
	3+1	156"	DE1E BI156(L/R)	239.
	3+3	156"	DE1T BI156(L/R)	259.
	250v	156"	DE12V BI156(L/R)	303.
	2+2	216"	DE18 BI216(L/R)	512.
	3+0	216"	DE1E BI216(L/R)	512.
	3+3	216"	DE1T BI216(L/R)	553.
	2+2	288"	DE18 BI288(L/R)	720.
	3+1	288"	DE1E BI288(L/R)	720.
	3+3	288"	DE1T BI288(L/R)	783.
Base Power Infeed (reversible) 	250v	56"	DE12V RBI56	187.
	3+1	56"	DE1E RBI56	286.
	2+2	56"	DE18 RBI56	313.
	3+3	56"	DE1T RBI56	374.
	2+2	144"	DE18 RBI144	459.
	3+1	144"	DE1E RBI144	459.
	3+3	144"	DE1T RBI144	494.
	2+2	156"	DE18 RBI156	187.
	3+1	156"	DE1E RBI156	286.
	3+3	156"	DE1T RBI156	313.
	250v	156"	DE12V RBI156	374.
	2+2	216"	DE18 RBI216	613.
	3+1	216"	DE1E RBI216	613.
	3+3	216"	DE1T RBI216	660.
	2+2	288"	DE18 RBI288	768.
	3+1	288"	DE1E RBI288	768.
	3+3	288"	DE1T RBI288	838.
Raceway-to-Ceiling Infeed 	250v	144"	DE2V CI144	194.
	3+1	144"	DE1E CI144	344.
	2+2	144"	DE18 CI144	378.
	3+3	144"	DE1T CI144	437.

Ordering Information	Order Code	Included with:	Options
Base Power Infeed (L/R)	Base Power Infeed (L/R)	Base Power Infeed (L/R)	Base Power Infeed (L/R)
1. Pattern Number	<i>Example:</i> DE18 BI56(L)	Power Pole	To specify direction of entry, add either an "L" or "R" suffix to the pattern number.
Power Pole	DE18 Pattern Number (left entry)	- Power pole - Ceiling trim plate - Connecting hardware - Post/power pole trim cover	Insert appropriate number for post cover option within the parentheses of the pattern number
1. Pattern Number	Power Pole	Note: Power pole does not include raceway-to-ceiling infeed which must be ordered separately.	Dividends Horizon Power Pole
2. Trim Finish	<i>Example:</i> DE(1) PP64S, 117		Post cover
Note: Power poles mount atop existing post connectors in "L", "T" and "X" configurations	DE(1) Pattern Number		
	PP64S		
	117 Soft Grey trim finish		

Electrical Infeeds and Power Poles

DP7 and DP8 Power Poles

Dividends Horizon

description	type	length	pattern no.	P1	P2	P3
Dividends Horizon Power Pole for use with DP7 & DP8 Series Posts only (does not include Raceway-to-Ceiling Infeed) For 126" ceiling height	For 36"H DP7 Post	90"	DP7PP36S	\$487.	\$511.	\$536.
	For 42"H DP7 Post	84"	DP7PP42S	448.	469.	494.
	For 50"H DP7 Post	76"	DP7PP50S	413.	432.	452.
	For 57"H DP7 Post	69"	DP7PP57S	364.	381.	402.
	For 64"H DP7 Post	62"	DP7PP64S	359.	374.	395.
	For 78"H DP7 Post	48"	DP7PP78S	359.	374.	395.
Dividends Horizon Power Pole for use with DP7 & DP8 Series Posts only (does not include Raceway-to-Ceiling Infeed) For 144" ceiling height	For 36"H DP7 Post	108"	DP7PP36T	497.	522.	545.
	For 42"H DP7 Post	102"	DP7PP42T	454.	479.	502.
	For 50"H DP7 Post	94"	DP7PP50T	413.	432.	452.
	For 57"H DP7 Post	86"	DP7PP57T	364.	381.	402.
	For 64"H DP7 Post	80"	DP7PP64T	359.	374.	395.
	For 78"H DP7 Post	66"	DP7PP78T	359.	374.	395.

Ordering Information

Power Pole

1. Pattern Number
2. Trim Finish

Order Code

Power Pole

Example: **DE(2) PP64S, 117**

DE(2) Pattern Number

PP64S

117 Soft Grey trim finish

Included With

Power Pole

- Power pole
- Ceiling trim plate
- Connecting hardware
- Post/power pole trim cover



Note: Power pole does not include raceway-to-ceiling infeed which must be ordered separately.

Note: Power poles mount atop existing post connectors in "L", "T" and "X" configurations.

Electrical Infeeds

Raceway-to-Ceiling and End-of-Run Infeeds

Dividends Horizon

description	type	length	pattern no.	list
 Raceway-to-Ceiling Infeed	2+2	288"	DE18 CI288	\$642.
	3+1	288"	DE1E CI288	642.
	3+3	288"	DE1T CI288	697.
 End-of-Run Infeed	10-wire (2+2)	56"	DE1X ERE56	564.
	2+2	56"	DE18 ERE56	528.
	250v	56"	DE12V ERE56	572.
	3+1	56"	DE1E ERE56	531.
	3+3	56"	DE1T ERE56	569.

Ordering Information	Order Code	Included with:	Options
Base Power Infeed (L/R) 1. Pattern Number Power Pole 1. Pattern Number 2. Trim Finish Note: Power poles mount atop existing post connectors in "L", "T" and "X" configurations	Base Power Infeed (L/R) <i>Example:</i> DE18 BI56(L) DE18 Pattern Number (left entry) BI56(L) Power Pole <i>Example:</i> DE(1) PP64S, 117 DE(1) Pattern Number PP64S 117 Soft Grey trim finish	Base Power Infeed (L/R) Power Pole - Power pole - Ceiling trim plate - Connecting hardware - Post/power pole trim cover Note: Power pole does not include raceway-to-ceiling infeed which must be ordered separately.	Base Power Infeed (L/R) - To specify direction of entry, add either an "L" or "R" suffix to the pattern number. Insert appropriate number for post cover option within the parentheses of the pattern number Dividends Horizon Power Pole - Post cover

New York City Hardwire Infeeds

The New York City hardwire infeed is comprised of a junction box and a power connector exiting from one side.

New York City infeeds are available in one size which mount within any base raceway 24" or wider.

The New York City infeed takes the place of a power module and prevents the installation of duplex receptacles in the panel housing the infeed. The hardwire infeed's power connector plugs into a power module which must be located in the adjacent panel.

The New York City infeed can be rotated to either the right or left side of the base raceway to provide power to either the adjacent left or right panel.

If power is required in both directions, specify a separate power jumper the length of the panel containing the infeed. The power jumper connects panel power modules located at either side of the panel containing the NYC hardwire infeed and is routed within the same raceway as the NYC hardwire infeed.

The power jumper is then routed in the opposite direction and connects to a power module located in the adjacent panel on the panel's other side (refer to the diagram below).

The panel containing the NYC hardwire infeed must be specified without base raceway cover knockouts.

A template for drilling the base raceway cover to accept the NYC hardwire infeed conduit is included.

Chicago Hardwire

Pre-wired modular electrical systems are not permitted in the City of Chicago. All electrical must be hard-wired by a qualified electrician.

In order to conform to City of Chicago electrical codes, a hardwire receptacle raceway kit(s) must be installed in all panel base raceways that require duplex receptacles. In order to conform to the City of Chicago electrical code for base power infeed, the hardwire infeed raceway kit must be installed within the panel base raceway. Hardwire receptacle raceway kit(s) and hardwire infeed raceway kit(s) mount in the base raceway between the panel feet and are available in 24" to 48" widths.

Hardwire receptacle raceway kits are secured by four screws. In addition, the base raceway covers on both sides of a panel with hardwire receptacle raceway kits must be secured with two screws each. A template for drilling attachment holes in base raceway covers is included with the hardwire receptacle raceway kit.


Optional Chicago base raceway covers can be ordered separately to replace existing covers if pre-drilled covers are desired.

When passing (jumping) hardwired power through panels, panels must be specified without knockouts in the base raceway to conform to the City of Chicago electrical code. All panels containing hardwire receptacle raceway kits must be specified with base raceway knockouts.

Note: Dividends Horizon beltway electrical is not available with Chicago hardware.

New York Electrical Configurations


NYC Infeeds are reversible and one direction




NYC Infeeds (positioned at left side of raceway)



NYC Infeeds (positioned at right side of raceway)




New York Electrical



New York City Infeed



Chicago Electrical



Hardwire Infeed Raceway Kit (Chicago)

New York City, San Francisco and Chicago Electrical Infeeds and Retrofit Kit




Dividends Horizon

description	type	l	pattern no.	list
 Hardwire Infeed (NYC) - 1 Direction	2+2		DE18 B1NY1	\$714.
	3+1		DE1E B1NY1	619.
	3+3		DE1T B1NY1	799.
 Base Power Infeed (San Francisco)	2+2	56"	DE18 BI56()SF	245.
	3+1	56"	DE1E BI56()SF	220.
	3+3	56"	DE1T BI56()SF	289.
 Reversible Base Power Infeed (San Francisco)	2+2	56"	DE18 RBI56SF	298.
	3+1	56"	DE1E RBI56SF	270.
	3+3	56"	DE1T RBI56SF	357.
Electrical Retrofit Kit (Chicago) (for electrical on new panel base raceway)			DP7CERK	79.

Ordering Information	Order Code	Included with:	Options
Hardwire Infeed (NYC) 1. Pattern Number	Hardwire Infeed (NYC) Example: DE1E B1NY1 DE1E Pattern Number B1NY1	Hardwire Infeed (NYC) • Junction box with power connector and infeed • Ceiling trim plate • Attachment screws	Hardwire Infeed (NYC) Power System • 3+1 • 2+2 • 3+3 San Francisco Infeed direction option (L) = Left (R) = Right Note: The electrical retrofit kit provides brackets that connect Chicago Electrical components that were manufactured prior to June 2008 to DP8 panel base raceways.

New York City, San Francisco and Chicago Electrical Infeeds, Receptacle Kits and Replacement Kits

Dividends Horizon

description	type	l	pattern no.	list
 Hardwire Infeed Raceway Kit (Chicago)	Double Sided	24"	DP7HIRKD24	\$439.
	Double Sided	30"	DP7HIRKD30	743.
	Double Sided	36"	DP7HIRKD36	749.
	Double Sided	42"	DP7HIRKD42	755.
	Double Sided	48"	DP7HIRKD48	760.
	Double Sided	60"	DP7HIRKD60	771.
	Single Sided	24"	DP7HIRKS24	616.
	Single Sided	30"	DP7HIRKS30	876.
	Single Sided	36"	DP7HIRKS36	881.
	Single Sided	42"	DP7HIRKS42	884.
	Single Sided	48"	DP7HIRKS48	890.
	Single Sided	60"	DP7HIRKS60	906.
 Hardwire Receptacle Raceway Kit (Chicago)	Double Sided	24"	DP7HRRKD24	337.
	Double Sided	30"	DP7HRRKD30	564.
	Double Sided	36"	DP7HRRKD36	572.
	Double Sided	42"	DP7HRRKD42	575.
	Double Sided	48"	DP7HRRKD48	581.
	Double Sided	60"	DP7HRRKD60	595.
	Single Sided	24"	DP7HRRKS24	391.
	Single Sided	30"	DP7HRRKS30	550.
	Single Sided	36"	DP7HRRKS36	556.
	Single Sided	42"	DP7HRRKS42	556.
	Single Sided	48"	DP7HRRKS48	561.
	Single Sided	60"	DP7HRRKS60	574.
 Pre-Drilled Replacement Covers, Pair (Chicago)	24" Wide Panel	24"	DP7RCCH24	48.
	30" Wide Panel	30"	DP7RCCH30	52.
	36" Wide Panel	36"	DP7RCCH36	55.
	42" Wide Panel	42"	DP7RCCH42	63.
	48" Wide Panel	48"	DP7RCCH48	67.
	60" Wide Panel	60"	DP7RCCH60	79.

Ordering Information	Order Code	Included with:	Options
Hardwire Infeed (NYC) 1. Pattern Number	Hardwire Infeed (NYC) Example: DE1E B1NY1 DE1E Pattern Number B1NY1	Hardwire Infeed (NYC) • Junction box with power connector and infeed • Ceiling trim plate • Attachment screws	Hardwire Infeed (NYC) Power System • 3+1 • 2+2 • 3+3 San Francisco Infeed direction option (L) = Left (R) = Right Note: The electrical retrofit kit provides brackets that connect Chicago Electrical components that were manufactured prior to June 2008 to DP8 panel base raceways.

This page intentionally left blank

Base Raceway Cable Tray

Optional steel cable trays are available for installations requiring the use of data and communications cables within the base raceway. The cable tray mounts between the panel feet.

Cable trays are field-installed and accessible from either side of the base raceway. A single sided base raceway cable tray should be specified when attaching to a tile-to-floor panel base.

Note: Cables should not be installed in base raceways without cable trays.

Beltway Cable Tray

An optional cable tray is available for data and communications cables within the beltway. Beltway cable trays should be used when wires are being routed horizontally from panel-to-panel at the beltway. The cable tray mounts into slots located on the vertical panel frame.

Cable trays are 1 $\frac{1}{4}$ " high, 1 $\frac{5}{16}$ " deep and are field-installed. Construction is 20-gauge steel with black finish.

Note: Beltway cable trays can be installed in monolithic panels to provide additional mid span insert support when required.

Worksurface Cable Management Basket

Constructed of black finished steel wire, the worksurface cable management basket mounts to the underside of worksurfaces to provide management of excess cords and cables. Once installed, the cable management basket slides forward to a position abutting the panel face to allow the passage of cords and cables.

Specify by width available between worksurface supports. Black finish.

Worksurface cable management baskets are 1 $\frac{1}{2}$ " high, 3 $\frac{1}{2}$ " deep and 19 $\frac{1}{2}$ " to 41 $\frac{1}{2}$ " wide.

Vertical Wire Pathway Grommet

An optional plastic grommet that snaps into the vertical wire pathway on the horizontal panel frame to separate cables from the panel frame. Located in center of topway and base raceway.

Topway Cable Grommet

The primary location for cable management for Dividends Horizon is in the topway. In order to utilize the topway channel effectively, the outside knockouts must be removed by using pliers. When the knockouts are removed the cables can be easily managed in the channel.


If required, a topway knockout grommet may be installed inside of the topway channel. Four grommets would be required per panel topway.

Worksurface Cable Management Clip


An optional cable management clip. $\frac{3}{4}$ " x $\frac{1}{2}$ " (internal dimension) plastic clip manages cables on the underside of worksurfaces.

Data Shield


If separation of cabling and electrical wires is required within the base raceway, a data shield can be attached below a base raceway power module at either end. Data shields are field-installed. The data shield should be used with base raceway panels or tile to floor panels only.



Base Raceway Cable Tray





Beltway Cable Tray





Worksurface Cable Management Basket

Vertical Wire Pathway





Topway Cable Grommet

Worksurface Cable Management Clip






Data Shield

description	type	pattern no.	list
	19 1/2" wide	D1WB20	\$51.
	25 1/2" wide	D1WB26	53.
	31 1/2" wide	D1WB32	67.
	35" wide	D1WB36	74.
	41" wide	D1WB42	79.
Vertical Wire Pathway Grommet (optional)	Package of 10	DP1 VWG	216.
			
Topway Cable Grommet	Package of 40	DP1 TKC	75.
			
Worksurface Cable Management Clip	Package of 10	D1WC	49.
			
Data Shield	1 Pair for use with base raceway	DE1DATSHD	50.
	1 Pair for use with tile to floor	DE1DATSHDF	67.
			

Ordering Information	Order Code	Included with:	Options
Base Raceway Cable Tray	Base Raceway Cable Tray	Base Raceway Cable Tray	Base Raceway Cable Tray
1. Pattern Number	<i>Example:</i> DP1 RCT24 DP1 Pattern Number RCT24		Note: Cable trays are for use with all DP7 and DP8 series panels and all panels produced prior to November 2007. Note: Data Shield is not compatible with open base panels.

Base Raceway and Beltway Cable Trays

description	type	pattern no.	list
Base Raceway Cable Tray - double sided for use with raceway on both sides (optional) 	18" Panel Width	DP72RCT18	\$32.
	24" Panel Width	DP72RCT24	34.
	30" Panel Width	DP72RCT30	39.
	36" Panel Width	DP72RCT36	42.
	42" Panel Width	DP72RCT42	44.
	48" Panel Width	DP72RCT48	49.
	60" Panel Width	DP72RCT60	52.
Base Raceway Cable Tray - single sided for use with raceway on one side (optional) 	18" Panel Width	DP71RCT18	32.
	24" Panel Width	DP71RCT24	34.
	30" Panel Width	DP71RCT30	39.
	36" Panel Width	DP71RCT36	42.
	42" Panel Width	DP71RCT42	44.
	48" Panel Width	DP71RCT48	49.
	60" Panel Width	DP71RCT60	52.
Beltway Cable Tray (optional) 	18" Panel Width	DP1BCT18	34.
	24" Panel Width	DP1BCT24	35.
	30" Panel Width	DP1BCT30	41.
	36" Panel Width	DP1BCT36	43.
	42" Panel Width	DP1BCT42	46.
	48" Panel Width	DP1BCT48	50.
	60" Panel Width	DP1BCT60	73.

Ordering Information**Base Raceway Cable Tray**

1. Pattern Number

Order Code**Base Raceway Cable Tray***Example:* **DP1 RCT24****DP1** Pattern Number
RCT24**Included with:****Base Raceway Cable Tray****Options****Base Raceway Cable Tray****Note:** Cable trays are for use with all DP7 and DP8 series panels and all panels produced prior to November 2007.

This page intentionally left blank

Flip-Up Door Overheads

Panel- and Wall-Mounted

Dividends, Series 2 and Series 3 Overheads - Specifications

Dividends Horizon

Flip-Up Door Overheads

Flip-up overheads mount to the integral vertical channels on Dividends Horizon panels or wall mount tracks to provide overhead storage within workstations or private offices.

Flip-up overhead cabinets consist of a top, shelf, end panels, overhead door with or without lock and required assembly screws. 30" to 48" wide cabinets have single doors while cabinets 54", 60", 66" and 72" wide have double doors. 54" wide overhead cabinets will ship with one 24" and one 30" door. 66" wide overhead cabinets will ship with one 30" and one 36" door. 54" and 66" overhead doors may be removed and reversed.

Overheads must match the width of single or multiple panels and cannot be mounted off-module. All cabinets are shipped knocked-down.

Series 2 Flip-up Door Overhead

Series 2 overhead cabinets offer an alternative aesthetic to the original Dividends Horizon Series 1 overhead. Unlike the radiused door profile of the Series 1 overhead door, the Series 2 door profile is rectilinear with soft radiused corners (see door profile drawing below). The Series 2 overhead offers a painted steel or veneer overhead door front.

Series 3 Flip-up Door Overhead

Series 3 cabinets offer a third aesthetic choice for flip-up overhead cabinets. The series 3 door profile is similar to the rectilinear door of the Series 2 cabinet, but the corners have a sharper radius to complement Dividends Horizon flat profile trim. Series 3 cabinets are offered with steel, laminate or veneer doors.

Note: Horizon Series 3 overheads are designed to complement and work next to other Series 3 overheads only.

Available Sizes

- Height: 15"
- Depth: 14¹/₈"
- Widths: 24", 30", 36", 42", 48", 54", 60", 66" and 72"

Construction:

- **Horizontal top and shelf:** 18-gauge painted roll-formed steel
- **Overhead door:**
 - Steel: 20-gauge painted steel
 - Laminate: 3/4" particle board with laminate on the outside and a paper backer on the inside. 1mm edgeband.
 - Veneer: 3/4" thick particle board with 0.6mm thick veneer on the top and edge.
- **Overhead door end trim:** Color injected, molded plastic (on Series 1 only)
- **End panels:** 16-gauge painted steel with integral mounting hooks
- **Overhead door suspension:** Steel ball bearing

Interior Dimensions

The interior dimensions of overhead cabinets and shelves are:

- Depth: 12"
- Usable interior height: 12⁵/₈"
- Width: 1/8" shorter than the exterior width

Cabinet Door Clearance

Cabinet doors open over the tops of cabinets. Required clearance is 16¹/₄" total height (height of cabinet plus top clearance required).

Touchdown Overhead Cabinets

Touchdown overhead cabinets are equipped with hydraulic assist cylinders that allow the overhead cabinet front to gently fall to a closed position.

Retrofit mechanisms may be field added to any flip-up overhead cabinet with a steel door.

Note: Touchdown mechanisms are not available with laminate or veneer doors.

Task Lights

All Dividends cabinets and shelves will accept task lights. Task lights must be specified separately.


Locks

Locks are standard on overhead cabinets and keyed randomly unless otherwise specified. Other keying options include keyed alike or keyed with lock cores K001-K250. All locks are factory-installed and are black finish. Cabinets can also be specified without locks if required. When locks are not specified on Series 1 and Series 2 overheads, a plug is located in the lock position. Lock retrofit kits are available for field installation at a later date for Series 1 and Series 2 overheads only.


Note: Horizon Series 3 flip-up overheads are only available in Knoll Core finishes.

Flip-up Door Overhead Configurations


24-48 Wide Overhead Cabinet (Single Door)




54 or 66" Wide Overhead Cabinet (Double Door)




72 Wide Overhead Cabinet (Offset Double Door)



Interior Dimensions




Front View, Interior Height





Top View, Interior Depth

Cabinet Door Clearance



Side View

Flip-up Door Overhead Profiles






Flip-Up Door Overheads

Panel- and Wall-Mounted

Series 2 and Horizon Series 3

Dividends Horizon

description	w*	w	d	h	pattern no.	P1	P2	P3	V1-P1	V1-P2	V1-P3
Series 2 Flip-Up Overhead w/ Steel or Veneer Door 	24"	23 7/8"	14 1/8"	15"	DS2PM24L	\$655.	\$757.	\$791.	\$1,028.	\$1,131.	\$1,159.
	30"	29 7/8"	14 1/8"	15"	DS2PM30L	655.	757.	791.	1,028.	1,131.	1,159.
	36"	35 7/8"	14 1/8"	15"	DS2PM36L	714.	822.	857.	1,040.	1,145.	1,182.
	42"	41 7/8"	14 1/8"	15"	DS2PM42L	781.	894.	931.	1,064.	1,185.	1,224.
	48"	47 7/8"	14 1/8"	15"	DS2PM48L	857.	983.	1,028.	1,143.	1,271.	1,316.
	54"	53 7/8"	14 1/8"	15"	DS2PM54L	1,016.	1,171.	1,224.	1,630.	1,780.	1,832.
	60"	59 7/8"	14 1/8"	15"	DS2PM60L	1,016.	1,171.	1,224.	1,630.	1,780.	1,832.
	66"	65 7/8"	14 1/8"	15"	DS2PM66L	1,134.	1,303.	1,361.	1,704.	1,875.	1,932.
	72"	71 7/8"	14 1/8"	15"	DS2PM72L	1,134.	1,303.	1,361.	1,704.	1,875.	1,932.
Dividends "touchdown" retro-fit (two kits required for 54"w - 72"w)					DS1EAKIT	341.					
Series 3 Flip-Up Overhead w/ Steel Door 	30"	29 7/8"	14 1/2"	15"	DS3PMS30L	635.	700.	732.			
	36"	35 7/8"	14 1/2"	15"	DS3PMS36L	654.	720.	752.			
	42"	41 7/8"	14 1/2"	15"	DS3PMS42L	673.	743.	777.			
	48"	47 7/8"	14 1/2"	15"	DS3PMS48L	697.	767.	799.			
	60"	59 7/8"	14 1/2"	15"	DS3PMS60L	877.	966.	1,013.			
	66"	65 7/8"	14 1/2"	15"	DS3PMS66L	955.	1,053.	1,100.			
	72"	71 7/8"	14 1/2"	15"	DS3PMS72L	955.	1,053.	1,100.			
Series 3 Flip-Up Overhead w/ Laminate Door 	30"	29 7/8"	14 1/2"	15"	DS3PML30L	959.	1,070.	1,117.			
	36"	35 7/8"	14 1/2"	15"	DS3PML36L	1,004.	1,097.	1,146.			
	42"	41 7/8"	14 1/2"	15"	DS3PML42L	1,032.	1,131.	1,181.			
	48"	47 7/8"	14 1/2"	15"	DS3PML48L	1,093.	1,201.	1,253.			
	60"	59 7/8"	14 1/2"	15"	DS3PML60L	1,638.	1,796.	1,874.			
	66"	65 7/8"	14 1/2"	15"	DS3PML66L	1,662.	1,824.	1,919.			
	72"	71 7/8"	14 1/2"	15"	DS3PML72L	1,710.	1,880.	1,964.			

w* = nominal width

Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Dividends Series 1 Flip-Up Door Overhead 1. Pattern Number 2. Paint Finish 3. Door End Cap Finish Series 2 Flip-Up Door Overhead 1. Pattern Number 2. Paint Finish 3. Door Finish (veneer door only) Series 3 Flip-Up Door Overhead 1. Pattern Number 2. Paint Finish case 3. Door Finish (laminated and veneer door only) 4. Door Edge Finish (laminated door only)	Dividends Series 1 Flip-Up Door Overhead <i>Example:</i> DS1O 30L, 113, 113 DS1O 30L Pattern Number 113 Dark grey paint finish 113 Dark grey End cap finish Series 2 Flip-Up Overhead w/ Steel Door <i>Example:</i> DS2PM 30L, 115 DS2PM Pattern Number 30L 115 Medium grey paint finish	Dividends Series 1 Flip-Up Door Overhead Series 2 Flip-Up Overhead Series 3 Flip-Up Overhead Note: Touchdown mechanism not available on veneer or laminate front Flip-Up overheads. Note: Series 3 Horizon overheads are only available in Knoll core finishes. Wallmount bracket specified separately.	Flip-Up Door Door Overhead To specify overhead cabinet without locks replace the "L" suffix from the pattern number with "N" Deduct \$20. For 54", 60", 66" and 72" overhead cabinets Deduct \$40 To specify Touchdown overhead cabinet, add "E" as the 2nd to last digit of the pattern number <i>Example:</i> DS3PML48EL (Add \$163 for cabinet widths of 48" or less. Add \$327 for cabinet widths of 54" or greater). Series 2 and Series 3 Flip-Up Door Overhead Finish Option: Add a "Y" to the end of the pattern number to specify a different finish for the door versus the case. Use P3 pricing for this dual finish option.


Flip-Up Door Overheads

Panel- and Wall-Mounted

Series 2 and Horizon Series 3

Dividends Horizon

description	w*	w	d	h	pattern no.	P1	P2	P3	V1-P1	V1-P2	V1-P3
Series 3 Flip-Up Overhead w/ Veneer Door	30"	29 ⁷ / ₈ "	14 ¹ / ₂ "	15"	DS3PMV30L	\$1,326.	\$1,451.	\$1,517.			
	36"	35 ⁷ / ₈ "	14 ¹ / ₂ "	15"	DS3PMV36L	1,356.	1,487.	1,556.			
	42"	41 ⁷ / ₈ "	14 ¹ / ₂ "	15"	DS3PMV42L	1,386.	1,523.	1,592.			
	48"	47 ⁷ / ₈ "	14 ¹ / ₂ "	15"	DS3PMV48L	1,448.	1,574.	1,646.			
	60"	59 ⁷ / ₈ "	14 ¹ / ₂ "	15"	DS3PMV60L	2,335.	2,564.	2,678.			
	66"	65 ⁷ / ₈ "	14 ¹ / ₂ "	15"	DS3PMV66L	2,397.	2,637.	2,768.			
	72"	71 ⁷ / ₈ "	14 ¹ / ₂ "	15"	DS3PMV72L	2,417.	2,652.	2,775.			



w* = nominal width

Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Dividends Series 1 Flip-Up Door Overhead 1. Pattern Number 2. Paint Finish 3. Door End Cap Finish	Dividends Series 1 Flip-Up Door Overhead <i>Example:</i> DS10 30L, 113, 113 DS10 30L Pattern Number 113 Dark grey paint finish 113 Dark grey End cap finish	Dividends Series 1 Flip-Up Door Overhead Series 2 Flip-Up Overhead Series 3 Flip-Up Overhead Note: Touchdown mechanism not available on veneer or laminate front Flip-Up overheads. Note: Series 3 Horizon overheads are only available in Knoll core finishes. Wallmount bracket specified separately.	Flip-Up Door Door Overhead To specify overhead cabinet without locks replace the "L" suffix from the pattern number with "N" Deduct \$20. For 54", 60", 66" and 72" overhead cabinets Deduct \$40 To specify Touchdown overhead cabinet, add "E" as the 2nd to last digit of the pattern number <i>Example:</i> DS3PML48EL (Add \$163 for cabinet widths of 48" or less. Add \$327 for cabinet widths of 54" or greater).
Series 2 Flip-Up Door Overhead 1. Pattern Number 2. Paint Finish 3. Door Finish (veneer door only)	Series 2 Flip-Up Overhead w/ Steel Door <i>Example:</i> DS2PM 30L, 115 DS2PM Pattern Number 30L 115 Medium grey paint finish		Series 2 and Series 3 Flip-Up Door Overhead Finish Option: Add a "Y" to the end of the pattern number to specify a different finish for the door versus the case. Use P3 pricing for this dual finish option.
Series 3 Flip-Up Door Overhead 1. Pattern Number 2. Paint Finish case 3. Door Finish (laminate and veneer door only) 4. Door Edge Finish (laminate door only)			

This page intentionally left blank

Sliding Door Overheads

Panel-, Center- and Wall-Mounted Specifications

Dividends Horizon

Sliding Door Overheads

Sliding door overheads complement the aesthetic of the Dividends Horizon system. The rectilinear door profile was designed to match Dividends Horizon flat profile trim details.

Dividends Horizon sliding door overhead cabinets mount to integral vertical channels on Dividends Horizon panels or wall mount tracks to provide overhead storage within workstations or private offices.

Sliding door overhead cabinets consist of a top, shelf, mid cabinet septum, end panels and a door with handle. Units are available with or without locks.

Overheads must match the width of single or multiple panels and cannot be mounted off-module. All cabinets are shipped knocked-down.

Note: Series 3 overheads are designed to complement and work next to other Series 3 overheads only.

Available Sizes

- Height: 14" and 21"
- Depth: 13 $\frac{1}{2}$ "
- Widths: 30", 36", 42", 48", 54" 60", 66" and 72"

Construction:

- **Horizontal top and shelf:** 18-gauge painted roll-formed steel
- **Sliding door:**
 - Steel: 20-gauge painted steel
 - Laminate: 3/4" particle board with laminate on the outside and a paper backer on the inside. 1mm edgeband.
 - Veneer: 3/4" thick particle board with 0.6mm thick veneer on the top and edge.
- **Fixed shelf:** 16-gauge painted steel
- **End panels:** 16-gauge painted steel with integral mounting hooks
- **Sliding door mechanism:** Integral track in top and bottom shelves with full length abs plastic extrusion. Door brackets are injection molded nylon.
- **Door handle:** painted aluminum (same color as case)

Interior Dimensions

The interior dimensions of overhead cabinets and shelves are:

- Depth: 12 $\frac{1}{4}$ "
- Usable interior height: 12 $\frac{5}{8}$ "
- Width: $\frac{1}{8}$ " shorter than the exterior width

Task Lights


All Dividends Horizon cabinets and shelves will accept task lights. Task lights must be ordered separately. Please see individual price list pages to determine which task lights are compatible.

Locks

Locks are standard on overhead cabinets and keyed randomly unless otherwise specified. All locks are factory-installed and are black finish. Cabinets can also be specified without locks if required.

Note: Horizon sliding door overheads are only available in Knoll Core finishes.

Sliding Door Overhead Configurations




Interior Dimensions for 14"H Overhead

Front View, Interior Height




Top View, Interior Height




Interior Dimensions for 21"H Overhead

Front View, Interior Height



Top View, Interior Height




Sliding Door Overheads

14" High Panel-Mounted


Dividends Horizon and Template Doors

Dividends Horizon


description	w *	w	d	h	pattern no.	P1	P2	P3
Dividends Horizon Panel-Mounted Overhead without Door	29 7/8"	30"	12 1/2"	14"	DS3PMNS3014	\$374.	\$410.	\$430.
	35 7/8"	36"	12 1/2"	14"	DS3PMNS3614	390.	428.	450.
	41 7/8"	42"	12 1/2"	14"	DS3PMNS4214	400.	442.	460.
	47 7/8"	48"	12 1/2"	14"	DS3PMNS4814	415.	456.	476.
	59 7/8"	60"	12 1/2"	14"	DS3PMNS6014	474.	520.	546.
	65 7/8"	66"	12 1/2"	14"	DS3PMNS6614	489.	538.	560.
	71 7/8"	72"	12 1/2"	14"	DS3PMNS7214	500.	552.	578.




Template Panel-Mounted Sliding Door Overhead with Steel Doors	35 7/8"	36"	15"	14"	DS3PMT(S/G)3614L	813.	894.	933.
	41 7/8"	42"	15"	14"	DS3PMT(S/G)4214L	842.	927.	967.
	47 7/8"	48"	15"	14"	DS3PMT(S/G)4814L	868.	953.	999.
	59 7/8"	60"	15"	14"	DS3PMT(S/G)6014L	1,238.	1,363.	1,424.
	71 7/8"	72"	15"	14"	DS3PMT(S/G)7214L	1,309.	1,440.	1,508.



Dividends Horizon Panel-Mounted Sliding Door Overhead w/Steel Door	29 7/8"	30"	13 1/2"	14"	DS3PMSS3014L	618.	682.	712.
	35 7/8"	36"	13 1/2"	14"	DS3PMSS3614L	635.	699.	734.
	41 7/8"	42"	13 1/2"	14"	DS3PMSS4214L	657.	723.	754.
	47 7/8"	48"	13 1/2"	14"	DS3PMSS4814L	667.	735.	770.
	59 7/8"	60"	13 1/2"	14"	DS3PMSS6014L	754.	831.	868.
	65 7/8"	66"	13 1/2"	14"	DS3PMSS6614L	775.	853.	891.
	71 7/8"	72"	13 1/2"	14"	DS3PMSS7214L	787.	866.	904.



Dividends Horizon Panel-Mounted Sliding Door Overhead w/ Laminate Door	29 7/8"	30"	13 1/2"	14"	DS3PMSL3014L	1,068.	1,174.	1,227.
	35 7/8"	36"	13 1/2"	14"	DS3PMSL3614L	1,099.	1,204.	1,257.
	41 7/8"	42"	13 1/2"	14"	DS3PMSL4214L	1,129.	1,238.	1,295.
	47 7/8"	48"	13 1/2"	14"	DS3PMSL4814L	1,159.	1,270.	1,327.
	59 7/8"	60"	13 1/2"	14"	DS3PMSL6014L	1,189.	1,305.	1,361.
	65 7/8"	66"	13 1/2"	14"	DS3PMSL6614L	1,219.	1,338.	1,396.
	71 7/8"	72"	13 1/2"	14"	DS3PMSL7214L	1,248.	1,368.	1,430.



w* = nominal width
Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information	Order Code	Included With	Options
Sliding Door Overheads:	Sliding Door Overhead w/ Steel Door	Sliding Door Overhead	Sliding Door Overhead
1. Pattern number	<i>Example:</i> DS3PMSS3014L /117/117	Note: Sliding door overheads are only available in Knoll core finishes.	Lock/No lock For non-locking units substitute the "L" suffix with a "N" and deduct \$20.00 from the list price.
2. Paint finish case			
3. Door finish (laminate and veneer door only)	DS3PMSS Pattern Number	Specify one of the following for Template Glass door option: (Temp) = Clear (GL13) = Powder (GL25) = Bronze (GL35) = Grey	Paint Configuration Option: Add "Y" at the end of the pattern number to specify a different paint finish on the case and sliding door. P3 pricing applies to all products with dual paint finishes.
4. Door edge finish (laminate door only)	3014L		
	117 Dark grey paint finish case		
			Overheads with Template style doors only accept LED task light. T5 task light mounting brackets are not compatible.


Sliding Door Overheads

14" High Panel-Mounted

Dividends Horizon and Template Doors

Dividends Horizon

description	w *	w	d	h	pattern no.	P1	P2	P3
Dividends Horizon Panel-Mounted	29 ⁷ / ₈ "	30"	13 ¹ / ₂ "	14"	DS3PMSV3014L	\$1,181.	\$1,295.	\$1,354.
Sliding Door Overhead w/ Veneer Door	35 ⁷ / ₈ "	36"	13 ¹ / ₂ "	14"	DS3PMSV3614L	1,219.	1,337.	1,396.
	41 ⁷ / ₈ "	42"	13 ¹ / ₂ "	14"	DS3PMSV4214L	1,254.	1,378.	1,437.
	47 ⁷ / ₈ "	48"	13 ¹ / ₂ "	14"	DS3PMSV4814L	1,294.	1,421.	1,483.
	59 ⁷ / ₈ "	60"	13 ¹ / ₂ "	14"	DS3PMSV6014L	1,331.	1,462.	1,526.
	65 ⁷ / ₈ "	66"	13 ¹ / ₂ "	14"	DS3PMSV6614L	1,368.	1,502.	1,569.
	71 ⁷ / ₈ "	72"	13 ¹ / ₂ "	14"	DS3PMSV7214L	1,408.	1,545.	1,615.



w* = nominal width

Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information	Order Code	Included With	Options
Sliding Door Overheads:	Sliding Door Overhead w/ Steel Door	Sliding Door Overhead	Sliding Door Overhead
1. Pattern number		Note: Sliding door overheads are only available in Knoll core finishes.	Lock/No lock
2. Paint finish case			For non-locking units substitute the "L" suffix with a "N" and deduct \$20.00 from the list price.
3. Door finish (laminare and veneer door only)	<i>Example:</i> DS3PMSS3014L /117/117		
4. Door edge finish (laminare door only)	DS3PMSS Pattern Number	Specify one of the following for Template Glass door option:	Paint Configuration Option:
	3014L	(Temp) = Clear	Add "Y" at the end of the pattern number to specify a different paint finish on the case and sliding door. P3 pricing applies to all products with dual paint finishes.
	117 Dark grey paint finish case	(GL13) = Powder	
		(GL25) = Bronze	
		(GL35) = Grey	
			Overheads with Template style doors only accept LED task light. T5 task light mounting brackets are not compatible.


Sliding Door Overheads

21" High Panel-Mounted


Dividends Horizon Full Height Door

Dividends Horizon


description	w *	w	d	h	pattern no.	P1	P2	P3
Dividends Horizon Panel-Mounted Overhead without Door	29 ⁷ / ₈ "	30"	12 ¹ / ₂ "	21"	DS3PMNS3021	\$516.	\$569.	\$594.
	35 ⁷ / ₈ "	36"	12 ¹ / ₂ "	21"	DS3PMNS3621	540.	591.	618.
	41 ⁷ / ₈ "	42"	12 ¹ / ₂ "	21"	DS3PMNS4221	556.	611.	638.
	47 ⁷ / ₈ "	48"	12 ¹ / ₂ "	21"	DS3PMNS4821	578.	633.	661.
	59 ⁷ / ₈ "	60"	12 ¹ / ₂ "	21"	DS3PMNS6021	657.	723.	754.
	65 ⁷ / ₈ "	66"	12 ¹ / ₂ "	21"	DS3PMNS6621	538.	590.	616.
	71 ⁷ / ₈ "	72"	12 ¹ / ₂ "	21"	DS3PMNS7221	695.	767.	799.




Dividends Horizon Panel-Mounted Sliding Door Overhead w/ Steel Door	29 ⁷ / ₈ "	30"	13 ¹ / ₂ "	21"	DS3PMSS3021FL	805.	885.	926.
	35 ⁷ / ₈ "	36"	13 ¹ / ₂ "	21"	DS3PMSS3621FL	831.	914.	954.
	41 ⁷ / ₈ "	42"	13 ¹ / ₂ "	21"	DS3PMSS4221FL	860.	942.	986.
	47 ⁷ / ₈ "	48"	13 ¹ / ₂ "	21"	DS3PMSS4821FL	881.	967.	1,013.
	59 ⁷ / ₈ "	60"	13 ¹ / ₂ "	21"	DS3PMSS6021FL	1,010.	1,110.	1,162.
	65 ⁷ / ₈ "	66"	13 ¹ / ₂ "	21"	DS3PMSS6621FL	1,037.	1,139.	1,193.
	71 ⁷ / ₈ "	72"	13 ¹ / ₂ "	21"	DS3PMSS7221FL	1,059.	1,163.	1,216.



Dividends Horizon Panel-Mounted Sliding Door Overhead w/ Laminate Door	29 ⁷ / ₈ "	30"	13 ¹ / ₂ "	21"	DS3PMSL3021FL	1,331.	1,462.	1,524.
	35 ⁷ / ₈ "	36"	13 ¹ / ₂ "	21"	DS3PMSL3621FL	1,370.	1,503.	1,572.
	41 ⁷ / ₈ "	42"	13 ¹ / ₂ "	21"	DS3PMSL4221FL	1,412.	1,547.	1,619.
	47 ⁷ / ₈ "	48"	13 ¹ / ₂ "	21"	DS3PMSL4821FL	1,455.	1,593.	1,662.
	59 ⁷ / ₈ "	60"	13 ¹ / ₂ "	21"	DS3PMSL6021FL	1,490.	1,639.	1,707.
	65 ⁷ / ₈ "	66"	13 ¹ / ₂ "	21"	DS3PMSL6621FL	1,528.	1,681.	1,754.
	71 ⁷ / ₈ "	72"	13 ¹ / ₂ "	21"	DS3PMSL7221FL	1,569.	1,723.	1,798.



Dividends Horizon Panel-Mounted Sliding Door Overhead w/ Veneer Door	29 ⁷ / ₈ "	30"	13 ¹ / ₂ "	21"	DS3PMSV3021FL	1,450.	1,591.	1,661.
	35 ⁷ / ₈ "	36"	13 ¹ / ₂ "	21"	DS3PMSV3621FL	1,501.	1,650.	1,722.
	41 ⁷ / ₈ "	42"	13 ¹ / ₂ "	21"	DS3PMSV4221FL	1,558.	1,707.	1,785.
	47 ⁷ / ₈ "	48"	13 ¹ / ₂ "	21"	DS3PMSV4821FL	1,612.	1,770.	1,849.
	59 ⁷ / ₈ "	60"	13 ¹ / ₂ "	21"	DS3PMSV6021FL	1,664.	1,830.	1,911.
	65 ⁷ / ₈ "	66"	13 ¹ / ₂ "	21"	DS3PMSV6621FL	1,720.	1,890.	1,973.
	71 ⁷ / ₈ "	72"	13 ¹ / ₂ "	21"	DS3PMSV7221FL	1,777.	1,950.	2,037.



w* = nominal width

Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information	Order Code	Included With	Options
Sliding Door Overheads:	Sliding Door Overhead w/ Steel Door	Sliding Door Overhead	Sliding Door Overhead
1. Pattern number	<i>Example:</i> DS3PMSS3021FL	Note: Sliding door overheads are only available in Knoll core finishes.	Lock/No lock
2. Paint finish case	/117/117		For non-locking units substitute the "L" suffix with a "N" and deduct \$20.00 from the list price.
3. Door finish (laminate and veneer door only)	DS3PMSS Pattern Number		Paint Configuration Option:
4. Door edge finish (laminate door only)	3021FL		Add "Y" at the end of the pattern number to specify a different paint finish on the case and sliding door. P3 pricing applies to all products with dual paint finishes.
	117 Dark grey paint finish case		


Sliding Door Overheads

21" High Panel-Mounted


Dividends Horizon Partial Height Door

Dividends Horizon


description	w *	w	d	h	pattern number	P1	P2	P3
Dividends Horizon Panel-Mounted Sliding Door Overhead w/ Steel Door	29 ⁷ / ₈ "	30"	13 ¹ / ₂ "	21"	DS3PMSS3021PL	\$799.	\$881.	\$919.
	35 ⁷ / ₈ "	36"	13 ¹ / ₂ "	21"	DS3PMSS3621PL	827.	906.	950.
	41 ⁷ / ₈ "	42"	13 ¹ / ₂ "	21"	DS3PMSS4221PL	852.	934.	976.
	47 ⁷ / ₈ "	48"	13 ¹ / ₂ "	21"	DS3PMSS4821PL	873.	960.	1,006.
	59 ⁷ / ₈ "	60"	13 ¹ / ₂ "	21"	DS3PMSS6021PL	966.	1,063.	1,112.
	65 ⁷ / ₈ "	66"	13 ¹ / ₂ "	21"	DS3PMSS6621PL	999.	1,094.	1,143.
	71 ⁷ / ₈ "	72"	13 ¹ / ₂ "	21"	DS3PMSS7221PL	1,015.	1,114.	1,165.



Dividends Horizon Panel-Mounted Sliding Door Overhead w/ Laminate Door	29 ⁷ / ₈ "	30"	13 ¹ / ₂ "	21"	DS3PMSL3021PL	1,321.	1,450.	1,513.
	35 ⁷ / ₈ "	36"	13 ¹ / ₂ "	21"	DS3PMSL3621PL	1,359.	1,492.	1,558.
	41 ⁷ / ₈ "	42"	13 ¹ / ₂ "	21"	DS3PMSL4221PL	1,398.	1,533.	1,603.
	47 ⁷ / ₈ "	48"	13 ¹ / ₂ "	21"	DS3PMSL4821PL	1,436.	1,577.	1,649.
	59 ⁷ / ₈ "	60"	13 ¹ / ₂ "	21"	DS3PMSL6021PL	1,477.	1,622.	1,693.
	65 ⁷ / ₈ "	66"	13 ¹ / ₂ "	21"	DS3PMSL6621PL	1,515.	1,663.	1,740.
	71 ⁷ / ₈ "	72"	13 ¹ / ₂ "	21"	DS3PMSL7221PL	1,553.	1,705.	1,784.



Dividends Horizon Panel-Mounted Sliding Door Overhead w/ Veneer Door	29 ⁷ / ₈ "	30"	13 ¹ / ₂ "	21"	DS3PMSV3021PL	1,450.	1,591.	1,659.
	35 ⁷ / ₈ "	36"	13 ¹ / ₂ "	21"	DS3PMSV3621PL	1,492.	1,640.	1,709.
	41 ⁷ / ₈ "	42"	13 ¹ / ₂ "	21"	DS3PMSV4221PL	1,536.	1,688.	1,760.
	47 ⁷ / ₈ "	48"	13 ¹ / ₂ "	21"	DS3PMSV4821PL	1,584.	1,735.	1,813.
	59 ⁷ / ₈ "	60"	13 ¹ / ₂ "	21"	DS3PMSV6021PL	1,625.	1,784.	1,863.
	65 ⁷ / ₈ "	66"	13 ¹ / ₂ "	21"	DS3PMSV6621PL	1,665.	1,832.	1,914.
	71 ⁷ / ₈ "	72"	13 ¹ / ₂ "	21"	DS3PMSV7221PL	1,710.	1,883.	1,964.



w* = nominal width

Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information	Order Code	Included With	Options
Sliding Door Overheads:	Sliding Door Overhead w/ Steel Door	Sliding Door Overhead	Sliding Door Overhead
1. Pattern number	<i>Example:</i> DS3PMSS3021PL	Note: Sliding door overheads are only available in Knoll core finishes.	Lock/No lock For non-locking units substitute the "L" suffix with a "N" and deduct \$20.00 from the list price.
2. Paint finish case	/117/117		
3. Door finish (laminate and veneer door only)	DS3PMSS Pattern Number		
4. Door edge finish (laminate door only)	3021PL		
	117 Dark grey paint finish case		
			Paint Configuration Option:
			Add "Y" at the end of the pattern number to specify a different paint finish on the case and sliding door. P3 pricing applies to all products with dual paint finishes.


Sliding Door Overheads

14" High Wall-Mounted


Dividends Horizon and Template Doors

Dividends Horizon


description	w *	w	d	h	pattern no.	P1	P2	P3
Dividends Horizon Wall-Mounted Sliding Door Overhead without Door	35 ⁷ / ₈ "	36"	14"	14"	DS3WMN3614	\$903.	\$996.	\$1,038.
	42 ⁷ / ₈ "	42"	14"	14"	DS3WMN4214	954.	1,055.	1,099.
	47 ⁷ / ₈ "	48"	14"	14"	DS3WMN4814	1,005.	1,102.	1,151.
	59 ⁷ / ₈ "	60"	14"	14"	DS3WMN6014	1,370.	1,508.	1,576.
	71 ⁷ / ₈ "	72"	14"	14"	DS3WMN7214	1,485.	1,638.	1,707.




Dividends Horizon Wall-Mounted Sliding Door Overhead w/ Steel Door	35 ⁷ / ₈ "	36"	15"	14"	DS3WMSS3614L	1,135.	1,248.	1,305.
	42 ⁷ / ₈ "	42"	15"	14"	DS3WMSS4214L	1,192.	1,314.	1,371.
	47 ⁷ / ₈ "	48"	15"	14"	DS3WMSS4814L	1,241.	1,365.	1,426.
	59 ⁷ / ₈ "	60"	15"	14"	DS3WMSS6014L	1,619.	1,781.	1,863.
	71 ⁷ / ₈ "	72"	15"	14"	DS3WMSS7214L	1,742.	1,915.	2,003.



Dividends Horizon Wall-Mounted Sliding Door Overhead w/ Laminate Door	35 ⁷ / ₈ "	36"	15"	14"	DS3WMSL3614L	n/a	n/a	1,515.
	42 ⁷ / ₈ "	42"	15"	14"	DS3WMSL4214L	n/a	n/a	1,572.
	47 ⁷ / ₈ "	48"	15"	14"	DS3WMSL4814L	n/a	n/a	1,625.
	59 ⁷ / ₈ "	60"	15"	14"	DS3WMSL6014L	n/a	n/a	2,018.
	71 ⁷ / ₈ "	72"	15"	14"	DS3WMSL7214L	n/a	n/a	2,150.



Dividends Horizon Wall-Mounted Sliding Door Overhead w/ Veneer Door	35 ⁷ / ₈ "	36"	15"	14"	DS3WMSV3614L	n/a	n/a	1,757.
	41 ⁷ / ₈ "	42"	15"	14"	DS3WMSV4214L	n/a	n/a	1,822.
	47 ⁷ / ₈ "	48"	15"	14"	DS3WMSV4814L	n/a	n/a	1,898.
	59 ⁷ / ₈ "	60"	15"	14"	DS3WMSV6014L	n/a	n/a	2,297.
	71 ⁷ / ₈ "	72"	15"	14"	DS3WMSV7214L	n/a	n/a	2,452.



Ordering Information	Order Code	Included With	Options
Sliding Door Overheads:	Sliding Door Overhead	Sliding Door Overhead	Sliding Door Overhead
1. Pattern number	<i>Example:</i> DS3WMSS4214N	Wall mount cleat	Lock Option:
2. Paint finish case	/118/118	Hardware	For non-locking units substitute the "L" suffix with a "N" and deduct \$20.00 from the list price.
3. Door finish (laminare and veneer door only)	DS3WM Pattern Number	Specify one of the following for Template Glass door option:	Paint Configuration Option:
4. Door edge finish (laminare door only)	SS Steel Door	(Temp) = Clear	Add "Y" at the end of the pattern number to specify a different paint finish on the case and sliding door. P3 pricing applies to all products with dual paint finishes.
	42 Width	(GL13) = Powder	
	14 Height	(GL25) = Bronze	
	N No lock	(GL35) = Grey	
	118 Bright White Paint Finish		
	118 Bright White Paint Finish		

Note: Sliding door overheads are only available in Knoll core finishes.

Overheads on this page accept LED task lights only. T5 task light brackets are not compatible.


Sliding Door Overheads

14" High Wall-Mounted

Dividends Horizon and Template Doors

Dividends Horizon

description	w *	w	d	h	pattern no.	P1	P2	P3
Template Wall-Mounted	35 ⁷ / ₈ "	36"	15"	14"	DS3WMT(S/G)3614L	\$1,114.	\$1,228.	\$1,285.
Sliding Door Overhead w/Steel or Glass Doors	42 ⁷ / ₈ "	42"	15"	14"	DS3WMT(S/G)4214L	1,177.	1,295.	1,354.
	47 ⁷ / ₈ "	48"	15"	14"	DS3WMT(S/G)4814L	1,228.	1,348.	1,412.
	59 ⁷ / ₈ "	60"	15"	14"	DS3WMT(S/G)6014L	1,615.	1,777.	1,857.
	71 ⁷ / ₈ "	72"	15"	14"	DS3WMT(S/G)7214L	1,746.	1,922.	2,009.



Ordering Information	Order Code	Included With	Options
Sliding Door Overheads:	Sliding Door Overhead	Sliding Door Overhead	Sliding Door Overhead
1. Pattern number	<i>Example:</i> DS3WMSS4214N	Wall mount cleat	Lock Option:
2. Paint finish case	/118/118	Hardware	For non-locking units substitute the "L" suffix with a "N" and deduct \$20.00 from the list price.
3. Door finish (laminated and veneer door only)	DS3WM Pattern Number	Specify one of the following for Template Glass door option:	Paint Configuration Option:
4. Door edge finish (laminated door only)	SS Steel Door	(Temp) = Clear	Add "Y" at the end of the pattern number to specify a different paint finish on the case and sliding door.
	42 Width	(GL13) = Powder	P3 pricing applies to all products with dual paint finishes.
	14 Height	(GL25) = Bronze	
	N No lock	(GL35) = Grey	
	118 Bright White Paint Finish		
	118 Bright White Paint Finish		

Note: Sliding door overheads are only available in Knoll core finishes.

Overheads on this page accept LED task lights only. T5 task light brackets are not compatible.


Sliding Door Overheads

14" High Shared Center-Mounted


Dividends Horizon and Template Doors

Dividends Horizon


description	w *	w	d	h	pattern no.	P1	P2	P3
Dividends Horizon Shared Top-Mounted Sliding Door Overhead without Door	35 7/8"	36"	14"	14"	DS3SMN3614	\$1,211.	\$1,333.	\$1,395.
	42 7/8"	42"	14"	14"	DS3SMN4214	1,263.	1,391.	1,456.
	47 7/8"	48"	14"	14"	DS3SMN4814	1,302.	1,431.	1,496.
	59 7/8"	60"	14"	14"	DS3SMN6014	1,541.	1,695.	1,774.
	71 7/8"	72"	14"	14"	DS3SMN7214	1,610.	1,770.	1,850.




Template Shared Top-Mounted Sliding Door Overhead with Steel Doors	35 7/8"	36"	15"	14"	DS3SMT(S/G)3614L	1,432.	1,577.	1,649.
	42 7/8"	42"	15"	14"	DS3SMT(S/G)4214L	1,492.	1,642.	1,715.
	47 7/8"	47"	15"	14"	DS3SMT(S/G)4814L	1,526.	1,681.	1,754.
	59 7/8"	60"	15"	14"	DS3SMT(S/G)6014L	1,781.	1,960.	2,048.
	71 7/8"	72"	15"	14"	DS3SMT(S/G)7214L	1,884.	2,074.	2,166.



Dividends Horizon Shared Top-Mounted Sliding Door Overhead with Steel Door	35 7/8"	36"	15"	14"	DS3SMSS3614L	1,513.	1,663.	1,741.
	42 7/8"	42"	15"	14"	DS3SMSS4214L	1,573.	1,730.	1,805.
	47 7/8"	48"	15"	14"	DS3SMSS4814L	1,610.	1,770.	1,850.
	59 7/8"	60"	15"	14"	DS3SMSS6014L	1,858.	2,045.	2,139.
	71 7/8"	72"	15"	14"	DS3SMSS7214L	1,960.	2,154.	2,254.



Dividends Horizon Shared Top-Mounted Sliding Door Overhead with Laminate Door	35 7/8"	36"	15"	14"	DS3SMSL3614L	n/a	n/a	2,323.
	42 7/8"	42"	15"	14"	DS3SMSL4214L	n/a	n/a	2,377.
	47 7/8"	48"	15"	14"	DS3SMSL4814L	n/a	n/a	2,421.
	59 7/8"	60"	15"	14"	DS3SMSL6014L	n/a	n/a	2,678.
	71 7/8"	72"	15"	14"	DS3SMSL7214L	n/a	n/a	2,794.



Ordering Information	Order Code	Included With	Options
Sliding Door Overheads:	Sliding Door Overhead	Sliding Door Overhead	Sliding Door Overhead
1. Pattern number	<i>Example:</i> DS3SMSS4214N	Hardware	Lock Option:
2. Case paint finish	/118/118	Specify one of the following for Template Glass door option:	For non-locking units substitute the "L" suffix with a "N" and deduct \$20.00 from the list price. Deduct \$40.00 for shared overheads.
3. Door finish (laminate and veneer door only)	DS3SM Pattern Number		Paint Configuration Option:
4. Door edge finish (laminate door only)	SS Steel Door		Add "Y" at the end of the pattern number to specify a different paint finish on the case and sliding door. P3 pricing applies to all products with dual paint finishes.
	42 Width		
	14 Height		
	N No lock		
	118 Bright White Paint Finish		
	118 Bright White Paint Finish		

Note: Sliding door overheads are only available in Knoll core finishes.

Note: Center-mounted sliding door overheads mount on full view panels only and must mount on module with panel widths.

Overheads on this page accept LED task lights only. T5 task light brackets are not compatible.

Storage Components


Sliding Door Overheads

14" High Shared Center-Mounted

Dividends Horizon and Template Doors

Dividends Horizon

description	w *	w	d	h	pattern no.	P1	P2	P3
Dividends Horizon Shared Top-Mounted	35 ⁷ / ₈ "	36"	15"	14"	DS3SMSV3614L	n/a	n/a	\$2,809.
Sliding Door Overhead with Veneer Door	42 ⁷ / ₈ "	42"	15"	14"	DS3SMSV4214L	n/a	n/a	2,880.
	47 ⁷ / ₈ "	48"	15"	14"	DS3SMSV4814L	n/a	n/a	2,961.
	59 ⁷ / ₈ "	60"	15"	14"	DS3SMSV6014L	n/a	n/a	3,235.
	71 ⁷ / ₈ "	72"	15"	14"	DS3SMSV7214L	n/a	n/a	3,398.



Ordering Information	Order Code	Included With	Options
Sliding Door Overheads:	Sliding Door Overhead	Sliding Door Overhead	Sliding Door Overhead
1. Pattern number	<i>Example:</i> DS3SMSS4214N	Hardware	Lock Option:
2. Case paint finish	/118/118	Specify one of the following for	For non-locking units substitute the
3. Door finish	DS3SM Pattern Number	Template Glass door option:	"L" suffix with a "N" and deduct
(laminated and veneer door only)	SS Steel Door	(Temp) = Clear	\$20.00 from the list price. Deduct
4. Door edge finish	42 Width	(GL13) = Powder	\$40.00 for shared overheads.
(laminated door only)	14 Height	(GL25) = Bronze	
	N No lock	(GL35) = Grey	
	118 Bright White Paint Finish		Paint Configuration Option:
	118 Bright White Paint Finish		Add "Y" at the end of the pattern
			number to specify a different paint
			finish on the case and sliding door.
			P3 pricing applies to all products
			with dual paint finishes.
			Note: Sliding door overheads are
			only available in Knoll core
			finishes.
			Note: Center-mounted sliding door
			overheads mount on full view panels
			only and must mount on module
			with panel widths.
			Overheads on this page accept LED
			task lights only. T5 task light
			brackets are not compatible.


Sliding Door Overheads

14" High Individual Center-Mounted


Dividends Horizon Doors / Template Doors

Dividends Horizon


description	w *	w	d	h	pattern no.	P1	P2	P3	LAM	V1
Dividends Horizon Individual Center-Mounted Overhead without Door	35 7/8"	36"	14"	14"	DS3CMN3614	\$970.	\$1,067.	\$1,114.		
	41 7/8"	42"	14"	14"	DS3CMN4214	1,012.	1,113.	1,164.		
	47 7/8"	48"	14"	14"	DS3CMN4814	1,037.	1,139.	1,193.		
	59 7/8"	60"	14"	14"	DS3CMN6014	1,447.	1,590.	1,661.		
	71 7/8"	72"	14"	14"	DS3CMN7214	1,521.	1,677.	1,748.		



Template Individual Center-Mounted Sliding Door Overhead with Steel Doors	35 7/8"	36"	15"	14"	DS3CMT(S/G)3614L	1,161.	1,278.	1,334.		
	42 7/8"	42"	15"	14"	DS3CMT(S/G)4214L	1,210.	1,331.	1,394.		
	47 7/8"	48"	15"	14"	DS3CMT(S/G)4814L	1,241.	1,365.	1,426.		
	59 7/8"	60"	15"	14"	DS3CMT(S/G)6014L	1,688.	1,857.	1,940.		
	71 7/8"	72"	15"	14"	DS3CMT(S/G)7214L	1,783.	1,961.	2,050.		



Dividends Horizon Individual Center-Mounted Sliding Door Overhead with Steel Doors	35 7/8"	36"	15"	14"	DS3CMSS3614L	1,281.	1,410.	1,473.	0.	0.
	41 7/8"	42"	15"	14"	DS3CMSS4214L	1,329.	1,463.	1,529.		
	47 7/8"	48"	15"	14"	DS3CMSS4814L	1,365.	1,501.	1,572.		
	59 7/8"	60"	15"	14"	DS3CMSS6014L	1,638.	1,797.	1,882.		
	71 7/8"	72"	15"	14"	DS3CMSS7214L	1,729.	1,902.	1,988.		



Ordering Information	Order Code	Included With	Options
Sliding Door Overheads:	Sliding Door Overhead	Sliding Door Overhead	Sliding Door Overhead
1. Pattern number	<i>Example:</i> DS3CMTS4214N	Hardware	Lock Option:
2. Case paint finish	/118/118	Specify one of the following for Template Glass door option:	For non-locking units substitute the "L" suffix with a "N" and deduct \$20.00 from the list price.
3. Door finish	DS3CM Pattern Number	(Temp) = Clear	Paint Configuration Option:
4. Door edge finish (laminate door only)	T Template Style Door	(GL13) = Powder	Add "Y" at the end of the pattern number to specify a different paint finish on the case and sliding door. P3 pricing applies to all products with dual paint finishes.
	S Steel Door	(GL25) = Bronze	Note: Sliding door overheads are only available in Knoll core finishes.
	42 Width	(GL35) = Grey	Note: Center-mounted sliding door overheads mount on full view panels only and must mount on module with panel widths.
	14 Height		
	N No lock		
	118 Bright White Paint Finish		
	118 Bright White Paint Finish		

Storage Components


Sliding Door Overheads

14" High Individual Center-Mounted


Dividends Horizon Doors / Template Doors

Dividends Horizon

description	w *	w	d	h	pattern no.	P1	P2	P3	LAM	V1
Dividends Horizon Individual Center-Mounted Sliding Door Overhead with Laminate Doors	35 7/8"	36"	15"	14"	DS3CMSL3614L	n/a	n/a	n/a	\$1,665.	n/a
	41 7/8"	42"	15"	14"	DS3CMSL4214L	n/a	n/a	n/a	1,716.	n/a
	47 7/8"	48"	15"	14"	DS3CMSL4814L	n/a	n/a	n/a	1,754.	n/a
	59 7/8"	60"	15"	14"	DS3CMSL6014L	n/a	n/a	n/a	2,039.	n/a
	71 7/8"	72"	15"	14"	DS3CMSL7214L	n/a	n/a	n/a	2,139.	n/a



Dividends Horizon Individual Center-Mounted Sliding Door Overhead with Veneer Doors	35 7/8"	36"	15"	14"	DS3CMSV3614L	n/a	n/a	n/a	n/a	1,908.
	41 7/8"	42"	15"	14"	DS3CMSV4214L	n/a	n/a	n/a	n/a	1,965.
	47 7/8"	48"	15"	14"	DS3CMSV4814L	n/a	n/a	n/a	n/a	2,028.
	59 7/8"	60"	15"	14"	DS3CMSV6014L	n/a	n/a	n/a	n/a	2,312.
	71 7/8"	72"	15"	14"	DS3CMSV7214L	n/a	n/a	n/a	n/a	2,439.



Ordering Information	Order Code	Included With	Options
Sliding Door Overheads:	Sliding Door Overhead	Sliding Door Overhead	Sliding Door Overhead
1. Pattern number	<i>Example:</i> DS3CMTS4214N	Hardware	Lock Option:
2. Case paint finish	/118/118	Specify one of the following for Template Glass door option:	For non-locking units substitute the "L" suffix with a "N" and deduct \$20.00 from the list price.
3. Door finish	DS3CM Pattern Number	(Temp) = Clear	Paint Configuration Option:
4. Door edge finish (laminate door only)	T Template Style Door	(GL13) = Powder	Add "Y" at the end of the pattern number to specify a different paint finish on the case and sliding door. P3 pricing applies to all products with dual paint finishes.
	S Steel Door	(GL25) = Bronze	Note: Sliding door overheads are only available in Knoll core finishes.
	42 Width	(GL35) = Grey	Note: Center-mounted sliding door overheads mount on full view panels only and must mount on module with panel widths.
	14 Height		
	N No lock		
	118 Bright White Paint Finish		
	118 Bright White Paint Finish		

Overheads on this page accept LED task lights only. T5 task light brackets are not compatible.

This page intentionally left blank

Panel Up Mounted Overhead Cabinets

Up mounted cabinets mount to 50" or 57" high panels only to provide overhead storage within workstations and are an alternative to overheads panel-mounted on 64" high panels. Up mounted cabinets have full finished backs and require up mount brackets for mounting.

When installed on 50" high panels, up mounted cabinets match up to the overall 64" height of panel-mounted overhead cabinets and freestanding overdesks to provide a consistent height within the facility.

Overhead cabinets consist of a top, shelf, end panels, enclosed back, overhead door with or without lock and required assembly screws. 30" to 48" wide cabinets have single doors while cabinets 54", 60", 66" and 72" wide have double doors. 54" wide overhead cabinets will ship with one 24" and one 30" door. 66" wide overhead cabinets will ship with one 30" and one 36" door. 54" and 66" overhead doors may be removed and reversed.

Up mounted cabinets are shipped knocked-down.

Up mounted overheads must match the width of single or multiple panels and cannot be mounted off module.

Series 1 Flip-up Overhead Cabinets

Series 1 flip-up overhead cabinets match the aesthetics of the original Dividends Horizon system. The radiused fronts and molded plastic end trim match the radiused profile trim used on panel topcaps and end trim. Series 1 cabinets are offered with steel doors.

Series 2 Flip-up Overhead Cabinets

Series 2 overhead cabinets offer an alternative aesthetic to the Dividends Horizon Series 1 overhead. Unlike the radiused door profile of the Series 1 overhead door, the Series 2 door profile is rectilinear with soft radiused corners (see door profile drawing below). The Series 2 overhead offers a painted steel or veneer overhead door front.

Available Sizes

- Height: 15"
- Depth: 13 $\frac{1}{2}$ "
- Widths: 30", 36", 42", 48", 54", 60", 66" and 72"

Construction:

- Horizontal top and shelf: 18-gauge (30" to 48" wide), 16-gauge (60" to 72" wide) painted roll-formed steel
- Overhead door: 20-gauge painted
- Overhead door suspension: Steel ball-bearing
- Overhead door end trim: Color injected, molded plastic (Series 1 only)
- End panels: 16-gauge painted steel with integral mounting hooks
- Up mount brackets: 14-gauge steel

Interior Dimensions

Up mounted cabinet interiors measure:

- Depth 12"
- Usable interior height: 12 $\frac{5}{8}$ "
- Width: $\frac{1}{8}$ " shorter than the exterior width.

Cabinet Door Clearance

Cabinet doors open over the tops of cabinets. Required clearance is: 16 $\frac{1}{4}$ " total height (height of cabinet plus top clearance required).

Panel Up Mounted Overhead for Stack Frames

Dividends Horizon non-load bearing stacking frames do not allow for panel-mount hanging components. To provide overhead storage, a panel up mounted overhead cabinet with enclosed back can be utilized.

Up mount brackets

Cabinet up mount brackets are required for up mounted applications.

Up mount brackets are ordered separately in pairs. Up mount brackets can be used on both Dividends Horizon Series 1 and Series 2 up mounted cabinets.

Touchdown Overhead Cabinets

Touchdown overhead cabinets are equipped with hydraulic assist cylinders that allows the overhead cabinet front to gently fall to a closed position.

Retrofit mechanisms may be field added to any flip-up overhead cabinet with a steel door.

Note: Touchdown mechanisms are not available with laminate or veneer doors.

Locks

Locks are standard on overhead cabinets and keyed randomly unless otherwise specified. Other keying options include keyed alike or keyed with lock cores K001-K250. All locks are factory-installed and are black finish. Cabinets can also be specified without locks if required.


When locks are not specified a plug is located in the lock position.

Optional lock retrofit kits are available for field-installation at a later date if required.


Task Lights

All Dividends up mounted cabinets will accept task lights. Task lights must be ordered separately.


Panel Up Mounted Cabinet




Up Mount Brackets



Interior Dimensions




Front View, Interior Height



Top View, Interior Depth

Cabinet Door Clearance



Up Mounted Overheads

Dividends and Series 2

Dividends Horizon

description	w *	w	d	h	pattern no.	P1	P2	P3	V1-P1	V1-P2	V1-P3
Series 2 Overhead Cabinet With Enclosed Back and Lock 	30"	29 ⁷ / ₈ "	14 ¹ / ₈ "	15"	DS2UM30L	\$840.	\$968.	\$1,007.	\$1,135.	\$1,261.	\$1,306.
	36"	35 ⁷ / ₈ "	14 ¹ / ₈ "	15"	DS2UM36L	866.	998.	1,041.	1,169.	1,304.	1,347.
	42"	41 ⁷ / ₈ "	14 ¹ / ₈ "	15"	DS2UM42L	896.	1,028.	1,074.	1,214.	1,351.	1,393.
	48"	47 ⁷ / ₈ "	14 ¹ / ₈ "	15"	DS2UM48L	912.	1,048.	1,093.	1,280.	1,418.	1,462.
	54"	53 ⁷ / ₈ "	14 ¹ / ₈ "	15"	DS2UM54L	1,225.	1,410.	1,469.	1,791.	1,977.	2,032.
	60"	59 ⁷ / ₈ "	14 ¹ / ₈ "	15"	DS2UM60L	1,225.	1,410.	1,469.	1,791.	1,977.	2,032.
	66"	65 ⁷ / ₈ "	14 ¹ / ₈ "	15"	DS2UM66L	1,280.	1,473.	1,538.	1,872.	2,066.	2,125.
	72"	71 ⁷ / ₈ "	14 ¹ / ₈ "	15"	DS2UM72L	1,280.	1,473.	1,538.	1,872.	2,066.	2,125.
Overhead Upmount Brackets (Pair)		⁷ / ₈ "	12 ³ / ₁₆ "	11 ³ / ₄ "	DB1U18	90.	97.	102.	n/a	n/a	n/a



w* = nominal width

Dimensions listed under w h d are actual to the nearest ¹/₁₆"

Ordering Information	Order Code	Included with:	Options
Upmount Overhead Cabinet 1. Pattern Number 2. Paint Finish 3. Door End Cap Finish	Upmount Overhead Cabinet <i>Example:</i> DS1E 30L, 113, 113 DS1E 30L Pattern Number 113 Dark grey paint finish 113 Dark grey end cap finish Series 2 Overhead Cabinet <i>Example:</i> DS2UM 30L, 115 DS2UM Pattern Number 30L 115 Medium grey paint finish	Upmount Overhead Cabinet Series 2 Overhead Cabinet Up Mount overheads include an enclosed back. Up Mount brackets are required and must be ordered separately.	Upmount Overhead Cabinet To specify overhead cabinet without locks, replace the "L" suffix from the pattern number with "N" Deduct \$20 For 54", 60", 66" and 72" overhead cabinets Deduct \$40 To specify Touchdown overhead cabinet, add "E" as the 2nd to last digit of the pattern number <i>Example:</i> DS3PML48EL (Add \$163 for cabinet widths of 48" or less. Add \$327 for cabinet widths of 54" or greater). Series 2 Up Mount Overhead Finish Option: Add a "Y" to the end of the pattern number to specify a front color that is different than the case color. Use P3 pricing for this dual finish option.

Overhead Book Shelves

Dividends Horizon bookshelves mount to the integral vertical channels on Dividends Horizon panels or to wall mount tracks to provide overhead storage within workstations or private offices.

Bookshelves include a shelf, end panels, open back and required assembly screws.

Shelves must match the width of single or multiple panels and cannot be mounted off-module.

All book shelves are shipped knocked-down.


Available Sizes

- Height: shelf 8"
- Depth: 14 1/8"
- Widths: 24", 30", 36", 42", 48", 54" 60", 66" and 72"

Construction:

- Horizontal shelf: 18-gauge (24" to 48" wide), 16-gauge (60" to 72" wide) painted roll-formed steel
- End panels: 16-gauge painted steel with integral mounting hooks


Bookshelf



Overhead Bookshelf

7 1/4" High

Dividends Horizon

description	w *	w	d	h	pattern no.	P1	P2	P3
 Overhead Bookshelf	24"	23 7/8"	14 1/8"	7 1/4"	DS1S 24	\$197.	\$220.	\$231.
	30"	29 7/8"	14 1/8"	7 1/4"	DS1S 30	197.	220.	231.
	36"	35 7/8"	14 1/8"	7 1/4"	DS1S 36	209.	220.	232.
	42"	41 7/8"	14 1/8"	7 1/4"	DS1S 42	219.	232.	240.
	48"	47 7/8"	14 1/8"	7 1/4"	DS1S 48	230.	238.	249.
	54"	53 7/8"	14 1/8"	7 1/4"	DS1S 54	244.	259.	271.
	60"	59 7/8"	14 1/8"	7 1/4"	DS1S 60	244.	259.	271.
	66"	65 7/8"	14 1/8"	7 1/4"	DS1S 66	265.	282.	295.
	72"	71 7/8"	14 1/8"	7 1/4"	DS1S 72	265.	282.	295.

w* = nominal width

Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information

Overhead Bookshelf

1. Pattern Number
2. Paint Finish

Order Code

Overhead Bookshelf

Example: **DS1S 60, 113**

DS1S 60 Pattern Number

113 Dark Grey Finish

Included with:

Note: An upcharge applies when specifying a Legacy laminate. See Legacy finish page for more information.

Mounting Brackets and Accessories

Backstop, Wall-Mount and Panel Mount Specifications

Dividends Horizon

Optional Overhead Back Stop

Panel-mounted overhead cabinet and bookshelf backs are open and use the panel face as the back. When required, an optional field-installed back stop is available. Attachment can be made to an assembled unit. Construction is dark grey extruded plastic.

Specify the overhead back stop width to match the width of the shelf or overhead cabinet.

Overhead Cabinet Wall-Mount Brackets

Wall-mount brackets allow Dividends Horizon panel-mounted overheads to be wall-mounted to dry-wall construction. Wall-mounting brackets are available in sizes 30", 36", 42" and 48".

Specify the width of wall-mount bracket to match the width of the panel-mounted overhead cabinet.

If a 60" cabinet is desired, two (2) 30" wide wall-mount brackets may be installed side-by-side to support the overhead cabinet. When a 72" cabinet is used, two (2) 36" wall-mount brackets may be used.

Shelf Wall-Mount Brackets

Wall-mount brackets allow Dividends Horizon panel-mounted shelves to be wall-mounted to dry-wall construction. Wallmounting brackets are painted black, and are available in sizes 30", 42" and 48".

Specify the width of wall-mount bracket to match the width of the panel-mounted overhead shelf. Specify paint finish to match the shelf paint finish.

A metal shelf back will ship with the wall-mount bracket, which is painted to match the shelf color. Overhead shelves larger than 48" wide cannot be wall mounted using the Dividends Horizon wall-mount bracket.

NOTE: WALL-MOUNT BRACKETS MUST ONLY BE USED WITH STRUCTURAL WALLS. TO ENSURE PROPER INSTALLATION, PLEASE FOLLOW THE INSTALLATION INSTRUCTIONS ENCLOSED WITH THE BRACKETS.

Up mount brackets

Cabinet up mount brackets are required for up mounted applications.

Up mount brackets are ordered separately in pairs. Up mount brackets can be used on both Dividends Horizon Series 1 and Series 2 up mounted cabinets.

Currents Downmount Bracket

This downmount bracket allows for Dividends Horizon or Series 2 panel mounted overhead cabinets to be mounted into Currents spine wall. This downmount bracket can only be used with Currents 64"H spine wall only.

Specify to match the overhead cabinet width. Specify paint finish to match the overhead cabinet finish.


Vertical Dividers

Optional vertical dividers attach to the shelves within overhead cabinets and bookshelves to provide inner cabinet organization. Construction is 18-gauge steel with dark grey finish.


Overhead Cabinet Lock Retrofit Kit

The overhead cabinet lock retrofit kit allows non-locking Series 1 and Series 2 flip-up overhead cabinets to be converted to locking overhead cabinets.


Optional Overhead Backstop




Overhead Wall-Mount Bracket




Shelf Wall-Mount Bracket



Upmount Brackets





Vertical Divider



Mounting Brackets and Accessories

Overhead Backstop, Wall-mount Brackets and Currents Downmount Brackets

Dividends Horizon

description	w *	w	d	h	pattern no.	black	P1	P2	P3
 Overhead Back Stop (Dark Grey Only)	24"	23 11/16"	5/8"	1 7/16"	DS1BS 24		\$4.	n/a	n/a
	30"	29 11/16"	5/8"	1 7/16"	DS1BS 30		4.	n/a	n/a
	36"	35 11/16"	5/8"	1 7/16"	DS1BS 36		4.	n/a	n/a
	42"	41 11/16"	5/8"	1 7/16"	DS1BS 42		7.	n/a	n/a
	48"	47 11/16"	5/8"	1 7/16"	DS1BS 48		7.	n/a	n/a
	54"	53 11/16"	5/8"	1 7/16"	DS1BS 54		10.	n/a	n/a
	60"	59 11/16"	5/8"	1 7/16"	DS1BS 60		10.	n/a	n/a
	66"	65 11/16"	5/8"	1 7/16"	DS1BS 66		10.	n/a	n/a
 14" H Overhead Wall-Mount Bracket	24"	24"	1/2"	1 4 1/4"	DS1WM 24	93.	97.	101.	104.
	30"	30"	1/2"	1 4 1/4"	DS1WM 30	93.	97.	101.	104.
	36"	36"	1/2"	1 4 1/4"	DS1WM 36	98.	102.	105.	114.
	42"	42"	1/2"	1 4 1/4"	DS1WM 42	107.	115.	123.	127.
	48"	48"	1/2"	1 4 1/4"	DS1WM 48	118.	126.	130.	134.
 Overhead Shelf-Mount Bracket	30"	30"	1/2"	7"	DS1SWM 30		164.	176.	190.
	36"	36"	1/2"	7"	DS1SWM 36		171.	193.	204.
	42"	42"	1/2"	7"	DS1SWM 42		190.	213.	219.
	48"	48"	1/2"	7"	DS1SWM 48		208.	225.	232.
 Dividends Series 2 Downmount Brackets (For Currents spine use)	24"				DSCSWDB24		301.	n/a	n/a
	30"				DSCSWDB30		311.	n/a	n/a
	36"				DSCSWDB36		318.	n/a	n/a
	42"				DSCSWDB42		328.	n/a	n/a
	48"				DSCSWDB48		336.	n/a	n/a

w* = nominal width

Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Overhead Wall-Mount Bracket	Overhead Wall-Mount Bracket	Overhead Wall-Mount Bracket	Overhead Wall-Mount Bracket
1. Pattern Number	<i>Example:</i> DS1WM 30	Overhead Back Stop	Overhead Back Stop
Overhead Back Stop	DS1WM Pattern Number		
1. Pattern Number	30		
	Overhead Back Stop		
	<i>Example:</i> DB1BS 30		
	DB1BS 30 Pattern Number		

Mounting Brackets and Accessories

Upmount Brackets, Vertical Dividers and Lock Retrofit Kit

Dividends Horizon

description	pattern no.	black	P1	P2	P3
Vertical Dividers (for flip-up overheads and open shelves) Package of 4 	DS1 VD	\$130.	\$134.	\$140.	\$146.
Overhead Cabinet Lock Retrofit Kit 	DS1 OHL	74.	n/a	n/a	n/a
Overhead Upmount Brackets (Pair) 	DB1U18	n/a	90.	97.	102.

Ordering Information	Order Code	Included with:	Options
Vertical Dividers 1. Pattern Number	Vertical Dividers <i>Example:</i> DS1 VD	Vertical Dividers (4) Vertical dividers	Vertical Dividers

This page intentionally left blank

Task Lights

Dividends Horizon offers T5 and LED task lights. T5 task lights are available in standard and advanced models. Task lights must be ordered separately from shelves, overhead cabinets, and overdesk units.

Task lights are TCLP compliant and meet requirements of California Title 20 and Title 24. T5 advanced task lights are fitted with ballasts and lamps compliant with LEED requirements. All task lights are approved for New York City installations.

T5 Task Lights

T5 task lights include T5 cool white (4100K) fluorescent lamp, electronic ballast, 9 foot grounded cordset, prismatic lens, rocker switch, one cord exit management clip and mounting hardware. T5 task light housings are painted black.

The T5 task light cordset is a center exit. On smaller units the cord exit is off-center, but still not handed, allowing the cordset to be positioned either to the right or left of the task light for easy access to the closest available duplex.

All T5 task lights include mounting hardware for attachment to overhead cabinets, shelves, up mounted cabinets and freestanding overdesks. Specify task lights one size or less than the overall cabinet or overdesk width. T5 task lights have adjustable mounting brackets that lock into integral channels in the underside of the cabinet's lower shelf. The spring steel adjustable mounting brackets flex to install without requiring tools and allow the light to be positioned at any position side-to-side and front-to-back.

City of Chicago T5 task lights have a 9 foot power cord with a resettable circuit breaker built into the plug.

LED Task Lights

LED task lights include LED's, a power supply with 9'-12' cord and mounting hardware. Housings are clear anodized aluminum with white color end-caps. Cord management clips must be ordered separately. The power supply cord attaches to either end of the fixture, allowing for easier access to the closest available duplex.

LED task lights mount into the recess in the underside of overhead cabinets and shelves at least 5" wider than the task light width..


Cord Management Clips

Cord management clips attach to the integral slotted channels on panel frames to manage task light cordsets. Clips are 3/8" high black molded plastic construction.


Task Light Specifications

Model Number	Fixture Length	Lamp Length	Lamp Part Number	Lamp Watts	Input Watts
T5 Standard Task Lights					
DL3T5E19S	19"	12"	FULHAM F8T5/CW	8	8
DL3T5E25S	25"	21.6"	FULHAM F14T5/41K	14	15
DL3T5E37S	37"	33.4"	FULHAM F21T5/41K	21	24
DL3T5E49S	49"	45.2"	FULHAM F28T5/41K	28	31
T5 Advanced Task Lights					
DL3T5E25A	25"	22.2"	PHILIPS F14T5/841/ALTO	14	18
DL3T5E37A	37"	33.98"	PHILIPS F21T5/841/ALTO	21	24
DL3T5E49A	49"	45.8"	PHILIPS F28T5/841/ALTO	28	31
LED Task Lights					
DL4L17	17"	16.4"	N/A	6.6	7.8
DL4L31	31"	30.1"	N/A	14.8	17.6
DL4L44	44"	43.7"	N/A	21.8	25.9
DL4L58	58"	57.4"	N/A	28.2	33.6


T5 Task Light




LED Task Light



Cord Management Clip Attachment



Task Lights
Cord Management Clip

description	type	w	d	h	pattern no.	list
 LED Task Light	Use with 44" and wider overhead (72 LED's)	44"	2"	1/2"	DL4L44	\$1,273.
	Use with 66" and wider overhead (96 LED's)	58"	2"	1/2"	DL4L58	1,596.
	Use with 24" and wider overhead (24 LED's)	17"	2"	1/2"	DL4L17	584.
	Use with 36" and wider overhead (48 LED's)	31"	2"	1/2"	DL4L31	976.
 Cord management clip	(package of 50)				DL3TC	56.

Ordering Information

Task Lights

1. Pattern Number

Cord Management Clip

1. Pattern Number

Order Code

LED Task Light

Example: DL4L17	
DL4	Task Light
L	LED
17	Width

Included with:

LED Task Lights:

Includes LED's, power supply with 9-12' cord and mounting hardware. Housings are clear anodized aluminum with white color end-caps.

Cord Management Clips:

Additional clips must be ordered separately.

Options

LED Task Lights:

Power cord is able to attach to either end of fixture.

Notes:

All task lights mount into the recess in the underside of overhead cabinets and shelves at least 6" wider than task light width.

All task lights are TCLP compliant and meet requirements of California Title 20 and Title 24.

Series 2 Floorstanding, Doublewide and Mobile Specifications

Series 2 Floorstanding Pedestals

Series 2 floorstanding pedestals are used to support worksurfaces in both panel wrapped and freestanding applications. No cantilevers or other supports are required at the end of the worksurface supported by a pedestal.

Two drawer configurations are available: box/box/file and file/ file. Mobile pedestals are not available without locks.

The Series 2 24" deep pedestal design offers case without a back. In panel applications or in freestanding desking applications where the desk is against the wall, a back is not necessary.

In desking applications where the back of the case is exposed, an optional back is used to conceal the pedestals contents.

The 18" and 30" deep Series 2 pedestals include a back with each case.

Mobile Pedestals

Series 2 mobile pedestals provide moveable storage within a workstation and tuck beneath worksurfaces when not in use. Available drawer configurations are box/file, box/box/file and file/file.

Mobile pedestals roll on four corner-mounted swivel casters and one bottom drawer-mounted caster for stability when the lower drawer is in the open position. The front corner casters are locking.

Mobile pedestals may be specified with an optional handle allowing easy mobility.

All mobile pedestals include 13-gauge finished tops. A back is included with all Series 2 mobile pedestals.

Pedestals may be specified without the top for attachment of a pedestal cushion. Pedestal cushion may be ordered through the Knoll Currents product line.

Available Sizes

Depths: 18", 24" and 30" (Floorstanding pedestal only)

Width: 15"

Height: 26 $\frac{7}{8}$ "

Series 2 Doublewide Pedestals

The doublewide pedestal incorporates two 12" high drawers in a 30" or 36" width (18 $\frac{3}{4}$ " depth) and is intended for below worksurface applications only. The doublewide's design allows for side-to-side letter or legal filing and front-to-back letter filing.

Doublewide pedestals can be used below 19", 24", 30" or 36" deep worksurfaces, not 18" deep worksurfaces.

Available Sizes

Depth: 18 $\frac{3}{4}$ " (floorstanding pedestal only)

Width: 30" and 36"

Height: 26 $\frac{7}{8}$ "

Construction:

- Outer wrapper: 20-gauge steel
- Drawer front: 20-gauge steel (double wide front: 18-gauge)
- Pedestal back: 20-gauge
- $\frac{3}{4}$ " extension ball bearing slides on 6" box drawers

- Full extension ball bearing slides on 12" file drawers
- Leveling glides: $\frac{3}{8}$ " diameter steel stem with 1 $\frac{1}{2}$ " of height adjustment (double wide ped: $\frac{5}{16}$ " diameter steel stem with a 1 $\frac{9}{16}$ " of height adjustment

Internal Drawer Dimensions (DS2, 24"d)

Box drawer

- Internal height: 4 $\frac{5}{16}$ "
- Internal width: 12 $\frac{1}{16}$ "
- Internal depths: 18 $\frac{3}{8}$ "

File drawer

- Internal height: 9 $\frac{1}{4}$ "
- Internal width: 12 $\frac{1}{8}$ "
- Internal depths: 18 $\frac{3}{8}$ "

File drawer (doublewide pedestal)

- Internal height: 9 $\frac{3}{4}$ "
- Internal width: 26 $\frac{3}{4}$ " and 32 $\frac{3}{4}$ "
- Internal depth: 15 $\frac{3}{4}$ "

Locks


Series 2 mobile pedestals are available not available without locks. Series 2 doublewide pedestals can be ordered with or without locks.

Locks are randomly keyed unless otherwise specified. Other keying options include keyed alike or keyed with lock cores K001-K250. All locks are factory-installed and have a black finish.

Pedestal Accessories

All Series 2 freestanding pedestal accessories including the hanging file bar must be specified separately. Series 2 double wide pedestals are shipped with hanging file bars.

Interior drawer dimensions for DS2 are 18" deep and 30" deep. Pedestals are the same as DS1 dimensions listed on page 228.




Mobile Pedestal


Series 2 Floorstanding, Doublewide and Mobile
18", 24" and 30" Depths

description	type	d*	d	w	h	pattern no.	P1	P2	P3
Series 2 Floorstanding Pedestals with Locks 	6/6/12 w/back	18"	17 1/2"	14 7/8"	26 7/8"	DS2PF L18A	\$752.	\$865.	\$902.
	12/12 w/back	18"	17 1/2"	14 7/8"	26 7/8"	DS2PF L18B	722.	833.	867.
	6/6/12 no back	24"	23 1/2"	14 7/8"	26 7/8"	DS2PF L24A	645.	744.	773.
	12/12 no back	24"	23 1/2"	14 7/8"	26 7/8"	DS2PF L24B	611.	703.	732.
	6/6/12 w/back	30"	24 1/2"	14 7/8"	26 7/8"	DS2PF L30A	867.	998.	1,045.
	12/12 w/back	30"	29 1/2"	14 7/8"	26 7/8"	DS2PF L30B	829.	952.	994.

Series 2 Floorstanding Case Back (For 24" deep units only)



				14 7/8"	26 7/8"	DS2XPB	115.	131.	134.
--	--	--	--	---------	---------	---------------	------	------	------

	Series 2 Mobile Pedestals with Locks	6/6/12	18"	16 3/4"	14 7/8"	26 3/8"	DS2PM L18A	1,103.	1,265.	1,320.
		12/12	18"	16 3/4"	14 7/8"	26 3/8"	DS2PM L18B	1,067.	1,229.	1,282.
		6/12	18"	16 3/4"	14 7/8"	20 5/8"	DS2PM L18F	979.	1,129.	1,176.
		6/6/12	24"	22 3/4"	14 7/8"	26 3/8"	DS2PM L24A	906.	1,047.	1,092.
		12/12	24"	22 3/4"	14 7/8"	26 3/8"	DS2PM L24B	906.	1,074.	1,092.
		6/12	24"	22 3/4"	14 7/8"	20 5/8"	DS2PM L24F	814.	935.	973.

d* = nominal depth

Dimensions listed under d w h are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Pedestals	Floorstanding Pedestals	Floorstanding Pedestals	Floorstanding Pedestals
1. Pattern Number	<i>Example:</i> DS2PF L24A, 117	• Hanging file bar not included	• To specify pedestals without locks, replace the "L" suffix with an "N". Deduct \$15
2. Paint Finish	DS2PF Pattern Number	Note: 24" deep floorstanding pedestals do not include a back panel. Back panels must be ordered separately. 18" and 30" deep floorstanding pedestals have backs.	Doublewide Pedestals
	117 Soft Grey paint finish		• To specify pedestals without locks, replace the "L" suffix with an "N". Deduct \$20
	Doublewide Pedestals	Mobile Pedestals	Mobile Pedestals
	<i>Example:</i> DS2DW 30L, 113	• Hanging file bar not included	• To specify a Series 2 mobile pedestal without a steel top, replace "M" character with "O" in the pattern number ie. DS2P(O)L24A Deduct \$35
	DS2DW Pattern Number		• Add \$55 list for mobile handle. Add a "P" between the "L" lock code and the case size to designate the handle option, example (DS2PMLP24A)
	30L	Doublewide Pedestals	Finish Option:
	113 Dark grey paint finish	• Hanging File Bar (front-to-back) • Hanging file rail (side-to-side)	Add a "Y" to the end of the pattern number to specify a different finish for the door versus the case. Use P3 pricing for this dual finish option.
		Doublewide pedestals are not intended for freestanding use and must be secured beneath a panel supported worksurface.	Full Extension Drawer Slide Option
			To specify full extension drawer slides for box drawers, add "F" at the end of the pattern number and add \$25 to the list price.

*Series 2 Floorstanding, Doublewide and Mobile
18", 24" and 30" Depths*

description	type	d*	d	w	h	pattern no.	P1	P2	P3
Series 2 Doublewide Pedestals with Locks	12/12	19"	18 ³ / ₄ "	30"	26 ⁷ / ₈ "	DS2DW 30L	\$1,140.	\$1,312.	\$1,368.
	12/12	19"	18 ³ / ₄ "	36"	26 ⁷ / ₈ "	DS2DW 36L	1,204.	1,386.	1,446.



d* = nominal depth

Dimensions listed under d w h are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Pedestals	Floorstanding Pedestals	Floorstanding Pedestals	Floorstanding Pedestals
1. Pattern Number	<i>Example:</i> DS2PF L24A, 117	Hanging file bar not included	To specify pedestals without locks, replace the "L" suffix with an "N". Deduct \$15
2. Paint Finish	DS2PF Pattern Number	Note: 24" deep floorstanding pedestals do not include a back panel. Back panels must be ordered separately. 18" and 30" deep floorstanding pedestals have backs.	
	L24A		Doublewide Pedestals
	117 Soft Grey paint finish		To specify pedestals without locks, replace the "L" suffix with an "N". Deduct \$20
	Doublewide Pedestals	Mobile Pedestals	Mobile Pedestals
	<i>Example:</i> DS2DW 30L, 113	Hanging file bar not included	To specify a Series 2 mobile pedestal without a steel top, replace "M" character with "O" in the pattern number ie. DS2P(O)L24A Deduct \$35
	DS2DW Pattern Number		Add \$55 list for mobile handle. Add a "P" between the "L" lock code and the case size to designate the handle option, example (DS2PMLP24A)
	30L	Doublewide Pedestals	Finish Option:
	113 Dark grey paint finish	- Hanging File Bar (front-to-back) - Hanging file rail (side-to-side) Doublewide pedestals are not intended for freestanding use and must be secured beneath a panel supported worksurface.	Add a "Y" to the end of the pattern number to specify a different finish for the door versus the case. Use P3 pricing for this dual finish option.
			Full Extension Drawer Slide Option
			To specify full extension drawer slides for box drawers, add "F" at the end of the pattern number and add \$25 to the list price.

This page intentionally left blank


Pencil Tray

Five section tray rides on drawer sides of box drawers. Plastic injection molded construction. 13¹/₄" wide, 5⁷/₁₆" deep and 7/8" high. Black or clear finish available.


Hanging File Bar

Allows for side-to-side hanging folders. 20-gauge steel construction. Set of two. Black finish.


A hanging file bar is included with each file drawer when ordering Series 1 desks or pedestals. Hanging file bars are not included with Series 2 pedestals or desks - order separately.




Pencil Tray



Hanging File Bar



Drawer Divider, Box



Drawer Divider, File Drawer

Drawer Dividers

Two styles available: box drawer and file drawer sizes. 18-gauge steel construction. Black finish.


Stationery Inserts

Set of four trays for use in box drawers. 18-gauge steel construction. Can accommodate letter-and legal-sized stationery. Black finish.


Pencil Drawer

For use with freestanding desks or panel-mounted worksurfaces with depths of 24" or more. 24" wide, 17 5/8" deep and 2" high. Black finish.

Attachment: Mounts on underside of worksurface with included mounting hardware



Stationery Inserts




Pencil Drawer

Pedestal Lock Retrofit Kit

Allows existing nonlocking pedestals to be field-retrofitted with locks. Includes lock housing, lock core and lock rod assembly (must be specified box/box/file or file/file).

Worksurface Edge Grommet

Available factory-installed when ordering worksurfaces or as a kit for field installation. Can be installed in any location along the rear edge of worksurfaces. Includes a cutting template, grommet and cover. Dark grey finish.



Worksurface
Edge Grommet

description	type	w	d	h	pattern no.	list
 Pencil Tray	Black finish	13 1/4"	5 7/8"	7/8"	DS2PPTN	\$48.
	Clear finish	13 1/4"	5 7/8"	7/8"	DS2PPTC	55.
 Hanging File Bar		12 3/16"	2 15/16"	1/2"	DS1PFS	42.
 Drawer Divider, Box		12 3/8"	3"	3 1/8"	DS1PBD	42.
 Drawer Divider, File		10	3 5/8"	6 3/8"	DS1PFD	42.
 Stationary Inserts, box (4 trays)		13	15 1/16"	8 7/8"	DS1PST	220.
 Pencil Drawer		24"	17 5/8"	2"	DS1PCD	293.
 Worksurface Grommet Kit (Dark Grey)		2 3/16"	2 5/16"	1 3/8"	D1WSG	30.
Dividends Floorstanding Pedestal Lock Retrofit Kit					DS1LKKT	90.
Series 2 Floorstanding Pedestal Lock Retrofit Kit	24" ped only				DS2LKKT	76.
Dividends Doublewide Pedestal Lock Retrofit Kit					DS1DWDPL	82.
Series 2 Doublewide Pedestal Lock Retrofit Kit		30"			DS2DWDPL30	79.
		36"			DS2DWDPL36	82.

Ordering Information

Pencil Tray

1. Pattern Number

Order Code

Pencil Tray

Example: **DS2PPT****DS2PPT** Pattern Number

Included with:

Pencil Tray

Options

Single Depth Credenzas

Dividends Horizon single depth credenzas increase planning and design options by blending residential furniture attributes within systems furniture applications. Credenzas offer a practical solution for functional under worksurface storage, while increasing the overall aesthetics of an office.

Credenzas consist of a metal, laminate, or veneer top option with a shelf and binder storage area. Single depth credenzas have four configuration options: sliding door only, drawer only, sliding door and drawer combination, and open shelves without a sliding door or a drawer.

The sliding door is a single steel, laminate, or veneer door with a handle that conceals half the width of the binder storage area. A single drawer may be specified for the location above the shelf. The drawer may be installed in either the right or left location, the drawer location does not need to be specified when ordered. When a drawer is specified along with a sliding door, the drawer front and sliding door finishes are the same. Units that include a drawer have a full back and those without a drawer have a partial back that encloses the binder storage area below the shelf.

Shorter width credenzas, 24, 30, and 36 inches wide, are available with a laminate or veneer top only. 24 inch wide credenzas do not include a center vertical septum and are only available as open shelf units, without a sliding door or drawer. Units are shipped knocked down and may be specified with or without locks. Dividends Horizon credenzas are available in all Knoll Core finishes. Legacy finishes are not available.

Available Sizes

Heights: 24 inches

Depth: 13-5/16 inches

Widths: 24 – 72 inches

Construction

• Top:

- Steel: 16-gauge painted steel
- Laminate: 1-1/4 inch thick particle board with laminate on top and a paper backer on the underside with 2mm edgeband
- Veneer: 1-1/4 inch thick particle board with 0.6mm veneer on top and edge.

• End Panels: 16-gauge painted steel

• Back Panel: 20-gauge painted steel

• Door:

- Steel: 20-gauge panted steel
- Laminate: 3/4 inch thick particle board with laminate on the outside and a paper backer on the inside with 1mm edgeband
- Veneer 3/4 inch thick particle board with 0.6mm thick veneer on top and edge

• Fixed Shelf: 16-gauge painted steel

• Door Handle: painted aluminum (same color as case)

Interior Dimensions

Heights: 12-1/2 inches for the lower section,


5-7/8 inches for the upper section

Depth: 12-1/16 inches


Locks

Locks are standard on credenzas with doors and/or drawers and are keyed randomly unless otherwise specified. All locks are factory installed and have a black finish. Credenzas can also be specified without locks if required.


**Single Depth Credenza
with Open Shelves**




**Single Depth Credenza
with a Drawer**



**Single Depth Credenza
with a Sliding Door**



**Single Depth Credenza
with a Drawer and a
Sliding Door**







Credenzas

Single Depth with Steel Top

With or Without a Sliding Door




Dividends Horizon

description	w	h	d	pattern no.	P1	P2	P3
 Credenza without Door	42"	24"	13 ⁵ / ₁₆ "	DS4LC1ANS42N	\$810.	\$889.	\$930.
	48"	24"	13 ⁵ / ₁₆ "	DS4LC1ANS48N	831.	913.	956.
	54"	24"	13 ⁵ / ₁₆ "	DS4LC1ANS54N	925.	1,019.	1,067.
	60"	24"	13 ⁵ / ₁₆ "	DS4LC1ANS60N	935.	1,030.	1,077.
	66"	24"	13 ⁵ / ₁₆ "	DS4LC1ANS66N	963.	1,059.	1,107.
	72"	24"	13 ⁵ / ₁₆ "	DS4LC1ANS72N	1,004.	1,103.	1,149.
 Credenza with Steel Sliding Door	42"	24"	13 ⁵ / ₁₆ "	DS4LC1BSS42L	1,003.	1,100.	1,146.
	48"	24"	13 ⁵ / ₁₆ "	DS4LC1BSS48L	1,020.	1,124.	1,174.
	54"	24"	13 ⁵ / ₁₆ "	DS4LC1BSS54L	1,136.	1,250.	1,305.
	60"	24"	13 ⁵ / ₁₆ "	DS4LC1BSS60L	1,141.	1,259.	1,314.
	66"	24"	13 ⁵ / ₁₆ "	DS4LC1BSS66L	1,177.	1,295.	1,355.
	72"	24"	13 ⁵ / ₁₆ "	DS4LC1BSS72L	1,219.	1,335.	1,397.
 Credenza with Laminate Sliding Door	42"	24"	13 ⁵ / ₁₆ "	DS4LC1BLS42L	1,624.	1,786.	1,864.
	48"	24"	13 ⁵ / ₁₆ "	DS4LC1BLS48L	1,665.	1,827.	1,909.
	54"	24"	13 ⁵ / ₁₆ "	DS4LC1BLS54L	1,702.	1,871.	1,953.
	60"	24"	13 ⁵ / ₁₆ "	DS4LC1BLS60L	1,741.	1,913.	1,996.
	66"	24"	13 ⁵ / ₁₆ "	DS4LC1BLS66L	1,782.	1,955.	2,042.
	72"	24"	13 ⁵ / ₁₆ "	DS4LC1BLS72L	1,821.	1,996.	2,088.
 Credenza with Veneer Sliding Door	42"	24"	13 ⁵ / ₁₆ "	DS4LC1BVS42L	1,732.	1,903.	1,989.
	48"	24"	13 ⁵ / ₁₆ "	DS4LC1BVS48L	1,782.	1,955.	2,041.
	54"	24"	13 ⁵ / ₁₆ "	DS4LC1BVS54L	1,829.	2,009.	2,098.
	60"	24"	13 ⁵ / ₁₆ "	DS4LC1BVS60L	1,878.	2,062.	2,154.
	66"	24"	13 ⁵ / ₁₆ "	DS4LC1BVS66L	1,926.	2,115.	2,208.
	72"	24"	13 ⁵ / ₁₆ "	DS4LC1BVS72L	1,973.	2,165.	2,264.

Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Credenza with Sliding Door: 1. Pattern number 2. Paint finish 3. Door finish (laminate and veneer only) 4. Door edge finish (laminate only)	Credenza with Sliding Door: Example: DS4LC1BSS42L/117 DS4LC1B Pattern Number SS42L 117 Dark grey paint Credenza without a Sliding Door: Example: DS4LC1ANS42N/117 DS4LC1A Pattern Number NS42N 117 Dark grey paint	Credenza with or without Sliding Door: Note: Credenzas are only available in Knoll core finishes.	Credenza with or without Sliding Door: Lock/No lock option For non-locking credenzas with a sliding door or a drawer, substitute the "L" suffix with an "N" and deduct \$20 from the list price. Note: Credenzas with a drawer have a full back. Credenzas without a drawer have a partial back that encloses the binder storage area below the shelf. Paint Configuration Option: Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

*Single Depth with Steel Top**Without a Sliding Door and with a Drawer*

description	w	h	d	pattern no.	P1	P2	P3
 Credenza with Steel Drawer	42"	24"	13 ⁵ / ₁₆ "	DS4LC1CSS42L	\$1,217.	\$1,293.	\$1,335.
	48"	24"	13 ⁵ / ₁₆ "	DS4LC1CSS48L	1,234.	1,316.	1,357.
	54"	24"	13 ⁵ / ₁₆ "	DS4LC1CSS54L	1,331.	1,423.	1,468.
	60"	24"	13 ⁵ / ₁₆ "	DS4LC1CSS60L	1,341.	1,433.	1,481.
	66"	24"	13 ⁵ / ₁₆ "	DS4LC1CSS66L	1,365.	1,463.	1,512.
	72"	24"	13 ⁵ / ₁₆ "	DS4LC1CSS72L	1,405.	1,508.	1,558.
 Credenza with Laminate Drawer	42"	24"	13 ⁵ / ₁₆ "	DS4LC1CLS42L	1,439.	1,518.	1,562.
	48"	24"	13 ⁵ / ₁₆ "	DS4LC1CLS48L	1,460.	1,541.	1,581.
	54"	24"	13 ⁵ / ₁₆ "	DS4LC1CLS54L	1,558.	1,649.	1,695.
	60"	24"	13 ⁵ / ₁₆ "	DS4LC1CLS60L	1,566.	1,660.	1,704.
	66"	24"	13 ⁵ / ₁₆ "	DS4LC1CLS66L	1,594.	1,689.	1,735.
	72"	24"	13 ⁵ / ₁₆ "	DS4LC1CLS72L	1,629.	1,731.	1,782.
 Credenza with Veneer Drawer	42"	24"	13 ⁵ / ₁₆ "	DS4LC1CVS42L	1,487.	1,568.	1,609.
	48"	24"	13 ⁵ / ₁₆ "	DS4LC1CVS48L	1,510.	1,592.	1,633.
	54"	24"	13 ⁵ / ₁₆ "	DS4LC1CVS54L	1,603.	1,697.	1,742.
	60"	24"	13 ⁵ / ₁₆ "	DS4LC1CVS60L	1,614.	1,707.	1,754.
	66"	24"	13 ⁵ / ₁₆ "	DS4LC1CVS66L	1,642.	1,735.	1,785.
	72"	24"	13 ⁵ / ₁₆ "	DS4LC1CVS72L	1,679.	1,781.	1,829.

Dimensions listed under w h d are actual to the nearest ¹/₁₆"


Ordering Information	Order Code	Included with:	Options
Credenza with a Drawer: 1. Pattern number 2. Paint finish 3. Drawer front finish (laminate and veneer only) 4. Drawer front edge finish (laminate only)	Credenza with a Drawer: <i>Example:</i> DS4LC1CLS42L /117/118/118 DS4LC1C Pattern Number LS42L 117 Dark grey paint 118 Bright white drawer front 118 Bright white drawer front edge	Credenza with a Drawer: Note: Credenzas are only available in Knoll core finishes.	Credenza with a Drawer: Lock/No lock option For non-locking credenzas with a sliding door or a drawer, substitute the "L" suffix with an "N" and deduct \$20 from the list price. Note: Credenzas with a drawer have a full back. Credenzas without a drawer have a partial back that encloses the binder storage area below the shelf.

Paint Configuration Option:


Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

*Single Depth with Steel Top**With a Sliding Door and with a Drawer*


description	w	h	d	pattern no.	P1	P2	P3
Credenza with Steel Sliding Door and Drawer	42"	24"	13 ⁵ / ₁₆ "	DS4LC1DSS42L	\$1,404.	\$1,507.	\$1,556.
	48"	24"	13 ⁵ / ₁₆ "	DS4LC1DSS48L	1,425.	1,527.	1,576.
	54"	24"	13 ⁵ / ₁₆ "	DS4LC1DSS54L	1,538.	1,652.	1,707.
	60"	24"	13 ⁵ / ₁₆ "	DS4LC1DSS60L	1,548.	1,662.	1,718.
	66"	24"	13 ⁵ / ₁₆ "	DS4LC1DSS66L	1,579.	1,698.	1,757.
	72"	24"	13 ⁵ / ₁₆ "	DS4LC1DSS72L	1,620.	1,736.	1,802.



Credenza with Laminate Sliding Door and Drawer	42"	24"	13 ⁵ / ₁₆ "	DS4LC1DLS42L	2,030.	2,189.	2,266.
	48"	24"	13 ⁵ / ₁₆ "	DS4LC1DLS48L	2,070.	2,232.	2,312.
	54"	24"	13 ⁵ / ₁₆ "	DS4LC1DLS54L	2,105.	2,272.	2,358.
	60"	24"	13 ⁵ / ₁₆ "	DS4LC1DLS60L	2,145.	2,315.	2,402.
	66"	24"	13 ⁵ / ₁₆ "	DS4LC1DLS66L	2,183.	2,360.	2,448.
	72"	24"	13 ⁵ / ₁₆ "	DS4LC1DLS72L	2,224.	2,402.	2,491.



Credenza with Veneer Sliding Door and Drawer	42"	24"	13 ⁵ / ₁₆ "	DS4LC1DVS42L	2,136.	2,307.	2,394.
	48"	24"	13 ⁵ / ₁₆ "	DS4LC1DVS48L	2,183.	2,360.	2,446.
	54"	24"	13 ⁵ / ₁₆ "	DS4LC1DVS54L	2,233.	2,412.	2,502.
	60"	24"	13 ⁵ / ₁₆ "	DS4LC1DVS60L	2,279.	2,463.	2,557.
	66"	24"	13 ⁵ / ₁₆ "	DS4LC1DVS66L	2,326.	2,518.	2,611.
	72"	24"	13 ⁵ / ₁₆ "	DS4LC1DVS72L	2,376.	2,571.	2,667.



Dimensions listed under w h d are actual to the nearest ¹/₁₆"




Ordering Information	Order Code	Included with:	Options
Credenza with a Sliding Door and a Drawer: 1. Pattern number 2. Paint finish 3. Drawer/Door finish (laminite and veneer only) 4. Drawer/Door edge finish (laminite only)	Credenza with a Sliding Door and a Drawer: <i>Example:</i> DS4LC1DSS42L/117 DS4LC1D Pattern Number SS42L 117 Dark grey paint	Credenza with a Sliding Door and a Drawer: Note: Credenzas are only available in Knoll core finishes.	Credenza with a Sliding Door and a Drawer: Lock/No lock option For non-locking credenzas with a sliding door or a drawer, substitute the "L" suffix with an "N" and deduct \$40 from the list price. Note: Credenzas with a drawer have a full back. Credenzas without a drawer have a partial back that encloses the binder storage area below the shelf. Paint Configuration Option: Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Credenzas

Single Depth with Laminate Top

With or without a Sliding Door

Dividends Horizon

description	w	h	d	pattern no.	P1	P2	P3
 Credenza without Door	24"	24"	13 ⁵ / ₁₆ "	DS4LC1ANL24N	\$1,089.	\$1,194.	\$1,253.
	30"	24"	13 ⁵ / ₁₆ "	DS4LC1ANL30N	1,089.	1,194.	1,253.
	36"	24"	13 ⁵ / ₁₆ "	DS4LC1ANL36N	1,089.	1,194.	1,253.
	42"	24"	13 ⁵ / ₁₆ "	DS4LC1ANL42N	1,089.	1,194.	1,253.
	48"	24"	13 ⁵ / ₁₆ "	DS4LC1ANL48N	1,120.	1,231.	1,289.
	54"	24"	13 ⁵ / ₁₆ "	DS4LC1ANL54N	1,206.	1,329.	1,388.
	60"	24"	13 ⁵ / ₁₆ "	DS4LC1ANL60N	1,208.	1,331.	1,390.
	66"	24"	13 ⁵ / ₁₆ "	DS4LC1ANL66N	1,250.	1,376.	1,437.
	72"	24"	13 ⁵ / ₁₆ "	DS4LC1ANL72N	1,292.	1,422.	1,484.
 Credenza with Steel Sliding Door	30"	24"	13 ⁵ / ₁₆ "	DS4LC1BSL30L	1,268.	1,393.	1,456.
	36"	24"	13 ⁵ / ₁₆ "	DS4LC1BSL36L	1,268.	1,393.	1,456.
	42"	24"	13 ⁵ / ₁₆ "	DS4LC1BSL42L	1,268.	1,393.	1,456.
	48"	24"	13 ⁵ / ₁₆ "	DS4LC1BSL48L	1,297.	1,428.	1,494.
	54"	24"	13 ⁵ / ₁₆ "	DS4LC1BSL54L	1,410.	1,553.	1,620.
	60"	24"	13 ⁵ / ₁₆ "	DS4LC1BSL60L	1,411.	1,556.	1,623.
	66"	24"	13 ⁵ / ₁₆ "	DS4LC1BSL66L	1,456.	1,601.	1,673.
	72"	24"	13 ⁵ / ₁₆ "	DS4LC1BSL72L	1,497.	1,648.	1,722.
 Credenza with Laminate Sliding Door	30"	24"	13 ⁵ / ₁₆ "	DS4LC1BLL30L	1,766.	1,939.	2,027.
	36"	24"	13 ⁵ / ₁₆ "	DS4LC1BLL36L	1,766.	1,939.	2,027.
	42"	24"	13 ⁵ / ₁₆ "	DS4LC1BLL42L	1,766.	1,939.	2,027.
	48"	24"	13 ⁵ / ₁₆ "	DS4LC1BLL48L	1,821.	1,996.	2,090.
	54"	24"	13 ⁵ / ₁₆ "	DS4LC1BLL54L	1,877.	2,061.	2,151.
	60"	24"	13 ⁵ / ₁₆ "	DS4LC1BLL60L	1,932.	2,122.	2,215.
	66"	24"	13 ⁵ / ₁₆ "	DS4LC1BLL66L	1,987.	2,181.	2,278.
	72"	24"	13 ⁵ / ₁₆ "	DS4LC1BLL72L	2,040.	2,244.	2,345.

Dimensions listed under w h d are actual to the nearest 1/16"


Ordering Information	Order Code	Included with:	Options
Credenza with Sliding Door: 1. Pattern number 2. Paint finish 3. Top finish 4. Top edge finish 5. Door finish (laminate and veneer only) 6. Door edge finish (laminate only)	Credenza with Sliding Door: <i>Example:</i> DS4LC1BLL42L /117/118/117/118/118 DS4LC1B Pattern Number LL42L 117 Dark grey paint 118 Bright white top 117 Dark grey top edge 118 Bright white door 118 Bright white door edge	Credenza with or without Sliding Door: Note: Credenzas are only available in Knoll core finishes.	Credenza with or without Sliding Door: Lock/No lock option For non-locking credenzas with sliding door or a drawer, substitute the "L" suffix with a "N" and deduct \$20. from the list price. Note: Credenzas with a drawer have a full back. Credenzas without a drawer have a partial back that encloses the binder storage area below the shelf.
Credenza without Sliding Door: 1. Pattern number 2. Paint finish 3. Top finish 4. Top edge finish	Credenza without a Sliding Door: <i>Example:</i> DS4LC1ANL42N/117 DS4LC1A Pattern Number NL42N 117 Dark grey paint 118 Bright white top 117 Dark grey top edge		Paint Configuration Option: Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Credenzas

Single Depth with Laminate Top

With or without a Sliding Door




Dividends Horizon

description	w	h	d	pattern no.	P1	P2	P3
 Credenza with Veneer Sliding Door	30"	24"	13 ⁵ / ₁₆ "	DS4LC1BVL30L	\$1,877.	\$2,061.	\$2,154.
	36"	24"	13 ⁵ / ₁₆ "	DS4LC1BVL36L	1,877.	2,061.	2,154.
	42"	24"	13 ⁵ / ₁₆ "	DS4LC1BVL42L	1,877.	2,061.	2,154.
	48"	24"	13 ⁵ / ₁₆ "	DS4LC1BVL48L	1,940.	2,131.	2,226.
	54"	24"	13 ⁵ / ₁₆ "	DS4LC1BVL54L	2,001.	2,202.	2,301.
	60"	24"	13 ⁵ / ₁₆ "	DS4LC1BVL60L	2,069.	2,271.	2,373.
	66"	24"	13 ⁵ / ₁₆ "	DS4LC1BVL66L	2,131.	2,341.	2,448.
	72"	24"	13 ⁵ / ₁₆ "	DS4LC1BVL72L	2,195.	2,412.	2,520.

Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Credenza with Sliding Door: 1. Pattern number 2. Paint finish 3. Top finish 4. Top edge finish 5. Door finish (laminate and veneer only) 6. Door edge finish (laminate only)	Credenza with Sliding Door: <i>Example:</i> DS4LC1BLL42L /117/118/117/118/118 DS4LC1B Pattern Number LL42L 117 Dark grey paint 118 Bright white top 117 Dark grey top edge 118 Bright white door 118 Bright white door edge	Credenza with or without Sliding Door: Note: Credenzas are only available in Knoll core finishes.	Credenza with or without Sliding Door: Lock/No lock option For non-locking credenzas with sliding door or a drawer, substitute the "L" suffix with a "N" and deduct \$20. from the list price. Note: Credenzas with a drawer have a full back. Credenzas without a drawer have a partial back that encloses the binder storage area below the shelf.
Credenza without Sliding Door: 1. Pattern number 2. Paint finish 3. Top finish 4. Top edge finish	Credenza without a Sliding Door: <i>Example:</i> DS4LC1ANL42N/117 DS4LC1A Pattern Number NL42N 117 Dark grey paint 118 Bright white top 117 Dark grey top edge		Paint Configuration Option: Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.




*Single Depth with Laminate Top
Without a Sliding Door and with a Drawer*

description	w	h	d	pattern no.	P1	P2	P3
	30"	24"	13 5/16"	DS4LC1CSL30L	\$1,494.	\$1,599.	\$1,655.
	36"	24"	13 5/16"	DS4LC1CSL36L	1,494.	1,599.	1,655.
	42"	24"	13 5/16"	DS4LC1CSL42L	1,494.	1,599.	1,655.
	48"	24"	13 5/16"	DS4LC1CSL48L	1,523.	1,635.	1,691.
	54"	24"	13 5/16"	DS4LC1CSL54L	1,610.	1,731.	1,793.
	60"	24"	13 5/16"	DS4LC1CSL60L	1,612.	1,732.	1,794.
	66"	24"	13 5/16"	DS4LC1CSL66L	1,652.	1,780.	1,841.
	72"	24"	13 5/16"	DS4LC1CSL72L	1,695.	1,825.	1,887.
	30"	24"	13 5/16"	DS4LC1CLL30L	1,720.	1,825.	1,882.
	36"	24"	13 5/16"	DS4LC1CLL36L	1,720.	1,825.	1,882.
	42"	24"	13 5/16"	DS4LC1CLL42L	1,720.	1,825.	1,882.
	48"	24"	13 5/16"	DS4LC1CLL48L	1,749.	1,860.	1,917.
	54"	24"	13 5/16"	DS4LC1CLL54L	1,837.	1,955.	2,021.
	60"	24"	13 5/16"	DS4LC1CLL60L	1,839.	1,956.	2,022.
	66"	24"	13 5/16"	DS4LC1CLL66L	1,879.	2,001.	2,067.
	72"	24"	13 5/16"	DS4LC1CLL72L	1,921.	2,050.	2,114.
	30"	24"	13 5/16"	DS4LC1CVL30L	1,769.	1,874.	1,931.
	36"	24"	13 5/16"	DS4LC1CVL36L	1,769.	1,874.	1,931.
	42"	24"	13 5/16"	DS4LC1CVL42L	1,769.	1,874.	1,931.
	48"	24"	13 5/16"	DS4LC1CVL48L	1,797.	1,908.	1,967.
	54"	24"	13 5/16"	DS4LC1CVL54L	1,884.	2,003.	2,069.
	60"	24"	13 5/16"	DS4LC1CVL60L	1,886.	2,004.	2,070.
	66"	24"	13 5/16"	DS4LC1CVL66L	1,929.	2,051.	2,115.
	72"	24"	13 5/16"	DS4LC1CVL72L	1,970.	2,098.	2,160.

Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Credenza with a Drawer: 1. Pattern number 2. Paint finish 3. Top finish 4. Top edge finish 5. Drawer finish (laminate and veneer only) 6. Drawer edge finish (laminate only)	Credenza with a Drawer: <i>Example:</i> DS4LC1CSL42L /117/118/117 DS4LC1C Pattern Number SL42L 117 Dark grey paint 118 Bright white top 117 Dark grey top edge 	Credenza with a Drawer: Note: Credenzas are only available in Knoll core finishes.	Credenza with a Drawer: Lock/No lock option For non-locking credenzas with a sliding door or a drawer, substitute the "L" suffix with an "N" and deduct \$20 from the list price. Note: Credenzas with a drawer have a full back. Credenzas without a drawer have a partial back that encloses the binder storage area below the shelf. Paint Configuration Option: Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

*Single Depth with Laminate Top
With a Sliding Door and with a Drawer*

description	w	d	h	pattern no.	P1	P2	P3
Credenza with Steel Sliding Door and Drawer 	30"	13 ⁵ / ₁₆ "	24"	DS4LC1DSL30L	\$1,669.	\$1,797.	\$1,860.
	36"	13 ⁵ / ₁₆ "	24"	DS4LC1DSL36L	1,669.	1,797.	1,860.
	42"	13 ⁵ / ₁₆ "	24"	DS4LC1DSL42L	1,669.	1,797.	1,860.
	48"	13 ⁵ / ₁₆ "	24"	DS4LC1DSL48L	1,701.	1,834.	1,897.
	54"	13 ⁵ / ₁₆ "	24"	DS4LC1DSL54L	1,813.	1,953.	2,025.
	60"	13 ⁵ / ₁₆ "	24"	DS4LC1DSL60L	1,814.	1,954.	2,028.
	66"	13 ⁵ / ₁₆ "	24"	DS4LC1DSL66L	1,860.	2,003.	2,079.
	72"	13 ⁵ / ₁₆ "	24"	DS4LC1DSL72L	1,900.	2,050.	2,126.
Credenza with Laminate Sliding Door and Drawer 	30"	13 ⁵ / ₁₆ "	24"	DS4LC1DLL30L	2,168.	2,345.	2,430.
	36"	13 ⁵ / ₁₆ "	24"	DS4LC1DLL36L	2,168.	2,345.	2,430.
	42"	13 ⁵ / ₁₆ "	24"	DS4LC1DLL42L	2,168.	2,345.	2,430.
	48"	13 ⁵ / ₁₆ "	24"	DS4LC1DLL48L	2,224.	2,402.	2,492.
	54"	13 ⁵ / ₁₆ "	24"	DS4LC1DLL54L	2,278.	2,462.	2,556.
	60"	13 ⁵ / ₁₆ "	24"	DS4LC1DLL60L	2,335.	2,523.	2,619.
	66"	13 ⁵ / ₁₆ "	24"	DS4LC1DLL66L	2,390.	2,585.	2,684.
	72"	13 ⁵ / ₁₆ "	24"	DS4LC1DLL72L	2,443.	2,647.	2,744.
Credenza with Veneer Sliding Door and Drawer 	30"	13 ⁵ / ₁₆ "	24"	DS4LC1DVL30L	2,278.	2,462.	2,557.
	36"	13 ⁵ / ₁₆ "	24"	DS4LC1DVL36L	2,278.	2,462.	2,557.
	42"	13 ⁵ / ₁₆ "	24"	DS4LC1DVL42L	2,278.	2,462.	2,557.
	48"	13 ⁵ / ₁₆ "	24"	DS4LC1DVL48L	2,346.	2,534.	2,632.
	54"	13 ⁵ / ₁₆ "	24"	DS4LC1DVL54L	2,408.	2,603.	2,703.
	60"	13 ⁵ / ₁₆ "	24"	DS4LC1DVL60L	2,470.	2,676.	2,777.
	66"	13 ⁵ / ₁₆ "	24"	DS4LC1DVL66L	2,534.	2,742.	2,854.
	72"	13 ⁵ / ₁₆ "	24"	DS4LC1DVL72L	2,599.	2,816.	2,922.

Dimensions listed under w h d are actual to the nearest 1/16"




Ordering Information	Order Code	Included with:	Options
Credenza with a Sliding Door and a Drawer: 1. Pattern number 2. Paint finish 3. Top finish 4. Top edge finish 5. Drawer/Door finish (laminate and veneer only) 6. Drawer/Door edge finish (laminate only)	Credenza with a Sliding Door and a Drawer: <i>Example:</i> DS4LC1DSL42L /117/118/117 DS4LC1D Pattern Number SL42L 117 Dark grey paint 118 Bright white top 117 Dark grey top edge	Credenza with a Sliding Door and a Drawer: Note: Credenzas are only available in Knoll core finishes.	Credenza with a Sliding Door and a Drawer: Lock/No lock option For non-locking credenzas with a sliding door or a drawer substitute the "L" suffix with an "N" and deduct \$40 from the list price. Note: Credenzas with a drawer have a full back. Credenzas without a drawer have a partial back that encloses the binder storage area below the shelf. Paint Configuration Option: Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Credenzas

Single Depth with Veneer Top

With or without a Sliding Door

Dividends Horizon

description	w	h	d	pattern no.	P1	P2	P3
 Credenza without Door	24"	24"	13 ³ / ₁₆ "	DS4LC1ANV24N	\$1,667.	\$1,836.	\$1,918.
	30"	24"	13 ³ / ₁₆ "	DS4LC1ANV30N	1,667.	1,836.	1,918.
	36"	24"	13 ³ / ₁₆ "	DS4LC1ANV36N	1,667.	1,836.	1,918.
	42"	24"	13 ³ / ₁₆ "	DS4LC1ANV42N	1,667.	1,836.	1,918.
	48"	24"	13 ³ / ₁₆ "	DS4LC1ANV48N	1,705.	1,879.	1,966.
	54"	24"	13 ³ / ₁₆ "	DS4LC1ANV54N	1,748.	1,925.	2,010.
	60"	24"	13 ³ / ₁₆ "	DS4LC1ANV60N	1,789.	1,968.	2,057.
	66"	24"	13 ³ / ₁₆ "	DS4LC1ANV66N	1,827.	2,010.	2,102.
	72"	24"	13 ³ / ₁₆ "	DS4LC1ANV72N	1,869.	2,056.	2,148.
 Credenza with Steel Sliding Door	30"	24"	13 ³ / ₁₆ "	DS4LC1BSV30L	1,760.	1,933.	2,021.
	36"	24"	13 ³ / ₁₆ "	DS4LC1BSV36L	1,760.	1,933.	2,021.
	42"	24"	13 ³ / ₁₆ "	DS4LC1BSV42L	1,760.	1,933.	2,021.
	48"	24"	13 ³ / ₁₆ "	DS4LC1BSV48L	1,803.	1,981.	2,069.
	54"	24"	13 ³ / ₁₆ "	DS4LC1BSV54L	1,846.	2,027.	2,119.
	60"	24"	13 ³ / ₁₆ "	DS4LC1BSV60L	1,887.	2,075.	2,165.
	66"	24"	13 ³ / ₁₆ "	DS4LC1BSV66L	1,931.	2,121.	2,213.
	72"	24"	13 ³ / ₁₆ "	DS4LC1BSV72L	1,973.	2,165.	2,264.
 Credenza with Laminate Sliding Door	30"	24"	13 ³ / ₁₆ "	DS4LC1BLV30L	2,138.	2,350.	2,454.
	36"	24"	13 ³ / ₁₆ "	DS4LC1BLV36L	2,138.	2,350.	2,454.
	42"	24"	13 ³ / ₁₆ "	DS4LC1BLV42L	2,138.	2,350.	2,454.
	48"	24"	13 ³ / ₁₆ "	DS4LC1BLV48L	2,180.	2,396.	2,502.
	54"	24"	13 ³ / ₁₆ "	DS4LC1BLV54L	2,224.	2,442.	2,551.
	60"	24"	13 ³ / ₁₆ "	DS4LC1BLV60L	2,266.	2,490.	2,603.
	66"	24"	13 ³ / ₁₆ "	DS4LC1BLV66L	2,309.	2,539.	2,652.
	72"	24"	13 ³ / ₁₆ "	DS4LC1BLV72L	2,355.	2,587.	2,703.

Dimensions listed under w h d are actual to the nearest 1/16"


Ordering Information	Order Code	Included with:	Options
Credenza with Sliding Door: 1. Pattern number 2. Paint finish 3. Top finish 4. Door finish (laminate and veneer) 5. Door edge finish (laminate only)	Credenza with Sliding Door: <i>Example:</i> DS4LC1BSV42L /117/Y319 DS4LC1B Pattern Number SV42L 117 Dark grey paint Y319 Cherry Techwood top	Credenza with or without Sliding Door: Note: Credenzas are only available in Knoll core finishes.	Credenza with or without a Sliding Door: Lock/No lock option For non-locking credenzas with a sliding door or a drawer, substitute the "L" suffix with an "N" and deduct \$20 from the list price. Note: Credenzas with a drawer have a full back. Credenzas without a drawer have a partial back that encloses the binder storage area below the shelf. Paint Configuration Option: Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.
Credenza without a Sliding Door: 1. Pattern number 2. Paint finish 3. Top finish	Credenza without a Sliding Door: <i>Example:</i> DS4LC1ANV42N /117/Y319 DS4LC1A Pattern Number NV42N 117 Dark grey paint Y319 Cherry Techwood top		

Credenzas

Single Depth with Veneer Top

With or without a Sliding Door




Dividends Horizon

description	w	h	d	pattern no.	P1	P2	P3
 Credenza with Veneer Sliding Door	30"	24"	13 ⁵ / ₁₆ "	DS4LC1BVV30L	\$2,249.	\$2,467.	\$2,583.
	36"	24"	13 ⁵ / ₁₆ "	DS4LC1BVV36L	2,249.	2,467.	2,583.
	42"	24"	13 ⁵ / ₁₆ "	DS4LC1BVV42L	2,249.	2,467.	2,583.
	48"	24"	13 ⁵ / ₁₆ "	DS4LC1BVV48L	2,301.	2,527.	2,643.
	54"	24"	13 ⁵ / ₁₆ "	DS4LC1BVV54L	2,354.	2,585.	2,702.
	60"	24"	13 ⁵ / ₁₆ "	DS4LC1BVV60L	2,404.	2,643.	2,759.
	66"	24"	13 ⁵ / ₁₆ "	DS4LC1BVV66L	2,456.	2,699.	2,820.
	72"	24"	13 ⁵ / ₁₆ "	DS4LC1BVV72L	2,510.	2,754.	2,879.

Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Credenza with Sliding Door: 1. Pattern number 2. Paint finish 3. Top finish 4. Door finish (laminate and veneer) 5. Door edge finish (laminate only)	Credenza with Sliding Door: <i>Example:</i> DS4LC1BSV42L / 117/Y319 DS4LC1B Pattern Number SV42L 117 Dark grey paint Y319 Cherry Techwood top	Credenza with or without Sliding Door: Note: Credenzas are only available in Knoll core finishes.	Credenza with or without a Sliding Door: Lock/No lock option For non-locking credenzas with a sliding door or a drawer, substitute the "L" suffix with an "N" and deduct \$20 from the list price. Note: Credenzas with a drawer have a full back. Credenzas without a drawer have a partial back that encloses the binder storage area below the shelf. Paint Configuration Option: Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.
Credenza without a Sliding Door: 1. Pattern number 2. Paint finish 3. Top finish	Credenza without a Sliding Door: <i>Example:</i> DS4LC1ANV42N / 117/Y319 DS4LC1A Pattern Number NV42N 117 Dark grey paint Y319 Cherry Techwood top		


*Single Depth with Veneer Top
Without a Sliding Door and with a Drawer*


description	w	h	d	pattern no.	P1	P2	P3
	30"	24"	13 5/16"	DS4LC1CSV30L	\$2,073.	\$2,237.	\$2,319.
	36"	24"	13 5/16"	DS4LC1CSV36L	2,073.	2,237.	2,319.
	42"	24"	13 5/16"	DS4LC1CSV42L	2,073.	2,237.	2,319.
	48"	24"	13 5/16"	DS4LC1CSV48L	2,112.	2,281.	2,366.
	54"	24"	13 5/16"	DS4LC1CSV54L	2,150.	2,325.	2,415.
	60"	24"	13 5/16"	DS4LC1CSV60L	2,192.	2,368.	2,459.
	66"	24"	13 5/16"	DS4LC1CSV66L	2,232.	2,415.	2,508.
	72"	24"	13 5/16"	DS4LC1CSV72L	2,271.	2,457.	2,550.
	30"	24"	13 5/16"	DS4LC1CLV30L	2,299.	2,463.	2,546.
	36"	24"	13 5/16"	DS4LC1CLV36L	2,299.	2,463.	2,546.
	42"	24"	13 5/16"	DS4LC1CLV42L	2,299.	2,463.	2,546.
	48"	24"	13 5/16"	DS4LC1CLV48L	2,337.	2,509.	2,593.
	54"	24"	13 5/16"	DS4LC1CLV54L	2,376.	2,550.	2,642.
	60"	24"	13 5/16"	DS4LC1CLV60L	2,418.	2,595.	2,685.
	66"	24"	13 5/16"	DS4LC1CLV66L	2,457.	2,642.	2,734.
	72"	24"	13 5/16"	DS4LC1CLV72L	2,496.	2,684.	2,777.
	30"	24"	13 5/16"	DS4LC1CVV30L	2,348.	2,512.	2,595.
	36"	24"	13 5/16"	DS4LC1CVV36L	2,348.	2,512.	2,595.
	42"	24"	13 5/16"	DS4LC1CVV42L	2,348.	2,512.	2,595.
	48"	24"	13 5/16"	DS4LC1CVV48L	2,384.	2,557.	2,643.
	54"	24"	13 5/16"	DS4LC1CVV54L	2,425.	2,600.	2,688.
	60"	24"	13 5/16"	DS4LC1CVV60L	2,465.	2,645.	2,734.
	66"	24"	13 5/16"	DS4LC1CVV66L	2,505.	2,688.	2,781.
	72"	24"	13 5/16"	DS4LC1CVV72L	2,545.	2,733.	2,826.


Dimensions listed under w h d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Credenza with a Drawer: 1. Pattern number 2. Paint finish 3. Top finish 4. Door finish (laminate and veneer only) 5. Door edge finish (laminate only)	Credenza with a Drawer: <i>Example:</i> DS4LC1CSV42L /117/ Y319 DS4LC1C Pattern Number SV42L 117 Dark grey paint Y319 Cherry Techwood top	Credenza with a Drawer: Note: Credenzas are only available in Knoll core finishes.	Credenza with a Drawer: Lock/No lock option For non-locking credenzas with a sliding door or a drawer, substitute the "L" suffix with an "N" and deduct \$20 from the list price. Note: Credenzas with a drawer have a full back. Credenzas without a drawer have a partial back that encloses the binder storage area below the shelf. Paint Configuration Option: Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

*Single Depth with Veneer Top
With a Sliding Door and with a Drawer*

description	w	h	d	pattern no.	P1	P2	P3
Credenza with Steel Sliding Door and Drawer 	30"	24"	13 ⁵ / ₁₆ "	DS4LC1DSV30L	\$2,162.	\$2,337.	\$2,421.
	36"	24"	13 ⁵ / ₁₆ "	DS4LC1DSV36L	2,162.	2,337.	2,421.
	42"	24"	13 ⁵ / ₁₆ "	DS4LC1DSV42L	2,162.	2,337.	2,421.
	48"	24"	13 ⁵ / ₁₆ "	DS4LC1DSV48L	2,206.	2,382.	2,470.
	54"	24"	13 ⁵ / ₁₆ "	DS4LC1DSV54L	2,249.	2,430.	2,520.
	60"	24"	13 ⁵ / ₁₆ "	DS4LC1DSV60L	2,292.	2,478.	2,571.
	66"	24"	13 ⁵ / ₁₆ "	DS4LC1DSV66L	2,334.	2,522.	2,618.
	72"	24"	13 ⁵ / ₁₆ "	DS4LC1DSV72L	2,376.	2,571.	2,667.

Credenza with Laminate Sliding Door and Drawer 	30"	24"	13 ⁵ / ₁₆ "	DS4LC1DLV30L	2,540.	2,750.	2,858.
	36"	24"	13 ⁵ / ₁₆ "	DS4LC1DLV36L	2,540.	2,750.	2,858.
	42"	24"	13 ⁵ / ₁₆ "	DS4LC1DLV42L	2,540.	2,750.	2,858.
	48"	24"	13 ⁵ / ₁₆ "	DS4LC1DLV48L	2,584.	2,797.	2,908.
	54"	24"	13 ⁵ / ₁₆ "	DS4LC1DLV54L	2,629.	2,848.	2,955.
	60"	24"	13 ⁵ / ₁₆ "	DS4LC1DLV60L	2,669.	2,895.	3,006.
	66"	24"	13 ⁵ / ₁₆ "	DS4LC1DLV66L	2,710.	2,944.	3,055.
	72"	24"	13 ⁵ / ₁₆ "	DS4LC1DLV72L	2,755.	2,991.	3,106.

Credenza with Veneer Sliding Door and Drawer 	30"	24"	13 ⁵ / ₁₆ "	DS4LC1DVV30L	2,651.	2,871.	2,988.
	36"	24"	13 ⁵ / ₁₆ "	DS4LC1DVV36L	2,651.	2,871.	2,988.
	42"	24"	13 ⁵ / ₁₆ "	DS4LC1DVV42L	2,651.	2,871.	2,988.
	48"	24"	13 ⁵ / ₁₆ "	DS4LC1DVV48L	2,703.	2,931.	3,044.
	54"	24"	13 ⁵ / ₁₆ "	DS4LC1DVV54L	2,754.	2,990.	3,105.
	60"	24"	13 ⁵ / ₁₆ "	DS4LC1DVV60L	2,807.	3,044.	3,165.
	66"	24"	13 ⁵ / ₁₆ "	DS4LC1DVV66L	2,860.	3,102.	3,224.
	72"	24"	13 ⁵ / ₁₆ "	DS4LC1DVV72L	2,914.	3,160.	3,281.

Dimensions listed under w h d are actual to the nearest ¹/₁₆"

Ordering Information	Order Code	Included with:	Options
Credenza with a Sliding Door and a Drawer: 1. Pattern number 2. Paint finish 3. Top finish 4. Drawer/Door finish (laminated and veneer only) 5. Drawer/Door edge finish (laminated only)	Credenza with a Sliding Door and a Drawer: <i>Example:</i> DS4LC1SV42L /117/Y319 DS4LC1 Pattern Number SV42L 117 Dark grey paint Y319 Cherry Techwood top	Credenza with a Sliding Door and a Drawer: Note: Credenzas are only available in Knoll core finishes.	Credenza with a Sliding Door and a Drawer: Lock/No lock option For non-locking credenzas with a sliding door or a drawer, substitute the "L" suffix with an "N" and deduct \$40 from the list price. Note: Credenzas with a drawer have a full back. Credenzas without a drawer have a partial back that encloses the binder storage area below the shelf. Paint Configuration Option: Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Flip-up Door Overdesk Units

Series 1 and Series 2 freestanding flip-up door overdesk units mount atop freestanding desks to provide overhead storage.

Pass-through communications or visual privacy can be obtained with a removeable privacy screen. When installed on freestanding desks, overdesks match up to 64" high panels to provide a consistent height within the facility.

Flip-up door overdesk units consist of an overhead cabinet with or without lock and enclosed back along with desk-mount stanchions. Tackable privacy screens are optional and mount between the stanchions. Overdesks 30" to 48" wide have single overhead doors while units 60" and 72" wide have double doors.

Available Sizes

- Height: 37 $\frac{1}{2}$ "
- Depth: 13 $\frac{1}{2}$ "
- Widths: 36", 42", 48", 54", 60", 66" and 72"

Flip-up Door Overdesk Attachment

Flip-up door overdesks can be mounted to both single and double pedestal desks. The stanchion design provides attachment directly through the top of the worksurface. In addition, overdesks can be attached virtually anywhere along the worksurface provided that proper floorstanding worksurface support is used.

NOTE: ATTACHMENT REQUIRES DRILLING TOP OF WORKSURFACES.

Construction

- Outer cabinet: 20-gauge steel
- Cabinet top and lower shelf: 18-gauge for 36", 42" and 48" widths and 16-gauge for 60" and 72" widths
- Overhead doors: 20-gauge painted steel
- Door end trim: Color injected, molded plastic
- Overhead door suspension: Steel ball-bearing
- Outer stanchions: 14-gauge steel
- Inner stanchions: 20-gauge steel

Wire Management

Vertical wire management channels for task light wires are located inside stanchions and are concealed by the inner stanchion.

Locks

Locks are standard on overdesks and keyed randomly unless otherwise specified. Other keying options include keyed alike or keyed with lock cores (K001-K250). All locks are factory-installed and are black finish. Overdesks can also be specified without locks if required.

Optional lock retrofit kits are available for field installation in flip-up door overdesks without locks at a later date if required.

Tackable Privacy Screen

Flip-up door overdesk privacy screen provides visual privacy and a tackable surface. Privacy screens mount between flip-up door overdesk stanchions and are available in all overdesk widths.

Privacy screen construction is similar to the fabric insert used on Dividends panel frames. Two fabric wrapped inserts sandwich a honeycomb core providing both tackable and acoustic features.

Note: Tackable privacy screens are for use with Series 1 and Series 2 flip-up door overdesks only. They are not compatible with sliding door overdesks.

"Touchdown" Overhead Cabinets


Touchdown overhead cabinets are equipped with hydraulic assist cylinders that allows the overhead cabinet front to gently fall to a closed position.

Retrofit mechanisms may be field added to any flip-up door overdesk.

Task Lights


Series 1 and 2 flip-up door overdesks will accept task lights. Task lights must be ordered separately.

Flip-Up Door Overdesk Applications




Overdesk units can span a single worksurface or two worksurfaces in "L" configuration.

Flip-Up Door Overdesk Unit Components



Flip-Up Door Overdesk Size Configurations




Flip-up Door Overdesk and Tackboards


Dividends and Series 2

Dividends Horizon

description	w	d	h	pattern no.	black	P1	P2	P3	V1-P1	V1-P2	V1-P3
Flip-Up Door Overdesk with Enclosed Back and Lock (includes Stanchions)	36"	13 1/2"	15"	DD2OD 36L	n/a	\$1,057.	\$1,166.	\$1,221.	n/a	n/a	n/a
	42"	13 1/2"	15"	DD2OD 42L	n/a	1,112.	1,225.	1,286.	n/a	n/a	n/a
	48"	13 1/2"	15"	DD2OD 48L	n/a	1,146.	1,262.	1,324.	n/a	n/a	n/a
	54"	13 1/2"	15"	DD2OD 54L	n/a	1,295.	1,535.	1,616.	n/a	n/a	n/a
	60"	13 1/2"	15"	DD2OD 60L	n/a	1,397.	1,535.	1,616.	n/a	n/a	n/a
	66"	13 1/2"	15"	DD2OD 66L	n/a	1,433.	1,579.	1,661.	n/a	n/a	n/a
	72"	13 1/2"	15"	DD2OD 72L	n/a	1,433.	1,579.	1,661.	n/a	n/a	n/a



Series 2 Flip-Up Door Overdesk with Enclosed Back and Lock (includes Stanchions)	36"	13 1/2"	15"	DS2OD 36L	n/a	1,470.	1,692.	1,765.	1,794.	2,019.	2,091.
	42"	13 1/2"	15"	DS2OD 42L	n/a	1,501.	1,726.	1,798.	1,844.	2,065.	2,143.
	48"	13 1/2"	15"	DS2OD 48L	n/a	1,520.	1,746.	1,821.	1,911.	2,141.	2,210.
	54"	13 1/2"	15"	DS2OD 54L	n/a	1,849.	2,127.	2,224.	2,454.	2,734.	2,822.
	60"	13 1/2"	15"	DS2OD 60L	n/a	1,849.	2,127.	2,224.	2,454.	2,734.	2,822.
	66"	13 1/2"	15"	DS2OD 66L	n/a	1,911.	2,199.	2,293.	2,539.	2,824.	2,921.
	72"	13 1/2"	15"	DS2OD 72L	n/a	1,911.	2,199.	2,293.	2,539.	2,824.	2,921.



Vertical Dividers (for flip-up overheads and open shelves)	DS1 VD	130.	134.	140.	146.
Package of 4					



Ordering Information	Order Code	Included with:	Options
Pedestals 1. Pattern Number 2. Paint Finish 3. Door End Cap Finish	Overdesk Cabinet <i>Example:</i> DD2OD 48L, 613, 113 DD2OD Pattern Number 48L 613 Silver paint finish 113 Dark grey door end cap finish	Overdesk Cabinet Stanchion mount overdesk cabinets included an enclosed back.	Overdesk Cabinet To specify overhead cabinet without locks, replace the "L": suffix from the pattern number with "N". For 30" to 48" wide overdesk units, Deduct \$20 . For 54", 60" 66" and 72" wide overdesk units, Deduct \$40 . To specify Touchdown overhead cabinet, add "E" as the 2nd to last digit of the pattern number. Example: DS3PML48EL (Add \$163 for cabinet widths of 48" or less. Add \$327 for cabinet widths for 54" or greater). Add "Y" to the end of the pattern number to specify a different finish for the door versus the case. Use P3 pricing for this dual finish option.

Dividends Horizon

292

This page intentionally left blank

Sliding Door Overdesks

The rectilinear door profile of the sliding door overdesk was designed to complement the flat profile trim details of the Dividends Horizon system. Sliding door overdesks can be used in paneled workstation configurations or freestanding office applications.

Sliding door overdesks mount atop worksurfaces to provide overhead storage. When installed on a worksurface, sliding door overdesks match up to 57" and 64" high panels to provide a consistent height within the facility. 14" or 21" high sliding door overdesks consist of a top, shelf, mid cabinet septum, end panels/stanchions, and a door with a handle.

14" high cabinets and 21" high cabinets with full doors are standard with fully enclosed backs behind the storage area. No door units and 21" high cabinets with partial doors have a partial or full back option available. Partial backs cover the upper storage section of the cabinet. Full backs enclose both the upper and lower storage section of the cabinet.

21" high cabinets are able to be specified with a full or partial door. A partial door covers the upper section of the cabinet. A full door covers both the upper and lower section of the cabinet.

Available Sizes

- Height: 14" and 21"
- Depth: 13-1/2"
- Widths: 30", 36", 42", 48", 60", 66", and 72"

Construction

- **Horizontal top and shelf:** 18-gauge (30" to 48" wide), 16-gauge (60" to 72" wide) painted steel
- **Sliding door:**
 - Steel: 20-gauge painted steel
 - Laminate: 3/4" particle board with laminate on the outside and a paper backer on the inside. 1mm edgeband.
 - Veneer: 3/4" thick particle board with 0.6mm thick veneer on top and edge.
- **End panels/stanchions:** 16-gauge painted steel
- **Sliding door mechanism:** integral track in top and bottom shelves with full length abs plastic extrusion. Door brackets are injection molded nylon.
- **Fixed Shelf:** 16-gauge painted steel
- **Door handle:** painted aluminum (same color as case)
- **Back panel:** 20-gauge painted steel

Interior Dimensions

The interior dimensions of sliding door overdesks are:

- Depth: 12 1/4"
- Usable interior height: 12-1/2" high for 14"H cabinets and upper portion of 21"H cabinets; 6-1/8"H for lower portion of 21"H cabinets.
- Width: 1" shorter than exterior width

Overdesk Attachment

Overdesks can be mounted to both single and double pedestal desks as well as panel hung worksurfaces. The stanchion design provides attachment directly through the top of the worksurface. In addition, overdesks can be attached virtually anywhere along the worksurface provided that proper worksurface support is used.

Dividends Horizon Series 3 Overdesk units are sized to the nominal dimension, and are designed for use on the width dimension of Dividends Horizon rectangular worksurfaces.

Series 3 overheads are not compatible with use on extended corner worksurfaces, or a combination of other worksurfaces that are less than the nominal dimension.

NOTE: ATTACHMENT REQUIRES DRILLING TOP OF WORKSURFACES.

Task Lights

Sliding door overdesks will accept task lights. Task lights must be ordered separately.


Locks

Locks are standard on overhead cabinets and keyed randomly unless otherwise specified. All locks are factory-installed and are a black finish. Overdesks can also be specified without locks if required.


Note: Sliding door overdesks are only available in Knoll Core finishes.

Interior Dimensions for 14"H Overhead

Front View, Interior Height




Top View, Interior Height



Interior Dimensions for 21"H Overhead


Front View, Interior Height



Top View, Interior Height




Sliding Door Overdesks




57" High Cabinet with 14" High Storage, 14" High Door


description	width	pattern no.	P1	P2	P3
57"h Overdesk without Door with 14" Tall Cabinet	30"	DS3ODNS1573014	\$1,257.	\$1,383.	\$1,440.
	36"	DS3ODNS1573614	1,282.	1,410.	1,473.
	42"	DS3ODNS1574214	1,305.	1,433.	1,499.
	48"	DS3ODNS1574814	1,354.	1,484.	1,552.
	60"	DS3ODNS1576014	1,467.	1,614.	1,684.
	66"	DS3ODNS1576614	1,499.	1,652.	1,728.
	72"	DS3ODNS1577214	1,525.	1,677.	1,751.




57"h Overdesk with Steel Sliding Door and 14" Tall Cabinet	30"	DS3ODSS1573014L	1,358.	1,491.	1,556.
	36"	DS3ODSS1573614L	1,388.	1,525.	1,591.
	42"	DS3ODSS1574214L	1,420.	1,557.	1,626.
	48"	DS3ODSS1574814L	1,466.	1,607.	1,679.
	60"	DS3ODSS1576014L	1,600.	1,763.	1,838.
	66"	DS3ODSS1576614L	1,640.	1,803.	1,883.
	72"	DS3ODSS1577214L	1,666.	1,827.	1,907.



57"h Overdesk with Laminate Sliding Door and 14" Tall Cabinet	30"	DS3ODSL1573014L	1,791.	1,970.	2,057.
	36"	DS3ODSL1573614L	1,839.	2,023.	2,110.
	42"	DS3ODSL1574214L	1,885.	2,073.	2,165.
	48"	DS3ODSL1574814L	1,937.	2,126.	2,221.
	60"	DS3ODSL1576014L	1,984.	2,179.	2,275.
	66"	DS3ODSL1576614L	2,030.	2,232.	2,332.
	72"	DS3ODSL1577214L	2,076.	2,283.	2,385.




57"h Overdesk with Veneer Sliding Door and 14" Tall Cabinet	30"	DS3ODSV1573014L	1,888.	2,075.	2,170.
	36"	DS3ODSV1573614L	1,946.	2,136.	2,234.
	42"	DS3ODSV1574214L	2,001.	2,196.	2,297.
	48"	DS3ODSV1574814L	2,055.	2,257.	2,360.
	60"	DS3ODSV1576014L	2,110.	2,319.	2,423.
	66"	DS3ODSV1576614L	2,170.	2,382.	2,488.
	72"	DS3ODSV1577214L	2,223.	2,441.	2,552.




Ordering Information	Order Code	Included with:	Options
Sliding Door Overdesk	Sliding Door Overdesk	Sliding Door Overdesk	No lock - substitute "N" for "L" at the end of pattern number, subtract \$20.
1. Pattern Number	<i>Example:</i> DS3ODSS	Note: Overheads are only available in Knoll core finishes.	Paint Configuration Option:
2. Case Finish	1573014FL,613		Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.
3. Door Finish	DS3ODSS Pattern number		
4. Edge Finish (laminate door only)	1573014FL		
	613 Silver Paint Finish		

57" High Cabinet with 21" High Storage, (Full Height Door)


description	width	pattern no.	P1	P2	P3
57"h without Sliding Door Overdesk with 21" Tall Cabinet	30"	DS3ODNS()573021	\$1,355.	\$1,490.	\$1,556.
	36"	DS3ODNS()573621	1,385.	1,525.	1,593.
	42"	DS3ODNS()574221	1,419.	1,558.	1,627.
	48"	DS3ODNS()574821	1,473.	1,621.	1,694.
	60"	DS3ODNS()576021	1,611.	1,774.	1,854.
	66"	DS3ODNS()576621	1,653.	1,821.	1,901.
	72"	DS3ODNS()577221	1,681.	1,845.	1,936.




57"h Steel Sliding Door Overdesk with 21" Tall Cabinet	30"	DS3ODSS2573021FL	1,545.	1,697.	1,774.
	36"	DS3ODSS2573621FL	1,574.	1,731.	1,805.
	42"	DS3ODSS2574221FL	1,621.	1,778.	1,858.
	48"	DS3ODSS2574821FL	1,712.	1,876.	1,962.
	60"	DS3ODSS2576021FL	1,877.	2,062.	2,153.
	66"	DS3ODSS2576621FL	1,939.	2,128.	2,228.
	72"	DS3ODSS2577221FL	1,979.	2,174.	2,271.



57"h Laminate Sliding Door Overdesk with 21" Tall Cabinet	30"	DS3ODSL2573021FL	2,027.	2,228.	2,326.
	36"	DS3ODSL2573621FL	2,095.	2,301.	2,406.
	42"	DS3ODSL2574221FL	2,162.	2,379.	2,484.
	48"	DS3ODSL2574821FL	2,234.	2,451.	2,559.
	60"	DS3ODSL2576021FL	2,300.	2,530.	2,644.
	66"	DS3ODSL2576621FL	2,369.	2,606.	2,718.
	72"	DS3ODSL2577221FL	2,437.	2,679.	2,800.



57"h Veneer Sliding Door Overdesk with 21" Tall Cabinet	30"	DS3ODSV2573021FL	2,130.	2,339.	2,444.
	36"	DS3ODSV2573621FL	2,210.	2,433.	2,543.
	42"	DS3ODSV2574221FL	2,298.	2,526.	2,639.
	48"	DS3ODSV2574821FL	2,381.	2,614.	2,733.
	60"	DS3ODSV2576021FL	2,465.	2,707.	2,831.
	66"	DS3ODSV2576621FL	2,547.	2,800.	2,924.
	72"	DS3ODSV2577221FL	2,631.	2,892.	3,022.



Ordering Information

Sliding Door Overdesk

1. Pattern Number
2. Case Finish
3. Door Finish
4. Edge Finish (laminate door only)

Order Code

Sliding Door Overdesk

Example: **DS3ODSS
2573021FL,613**

DS3ODSS Pattern number
2573021FL

613 Silver Paint Finish

Included with:

Sliding Door Overdesk

Note: Overheads are only available in Knoll core finishes.

Options

No lock - substitute "N" for "L" at the end of pattern number, subtract \$20.


Back option for No Door units
(1)= Back covering overhead only
(2)= Back covering overhead and shelf section.

Paint Configuration Option:


Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

57" High Cabinet with 21" High Storage, (Partial Height Door)


description	width	pattern no.	P1	P2	P3
57"h Steel Sliding Door Overdesk with 21" Tall Cabinet	30"	DS3ODSS()573021PL	\$1,545.	\$1,697.	\$1,774.
	36"	DS3ODSS()573621PL	1,574.	1,731.	1,805.
	42"	DS3ODSS()574221PL	1,621.	1,778.	1,858.
	48"	DS3ODSS()574821PL	1,712.	1,876.	1,962.
	60"	DS3ODSS()576021PL	1,877.	2,062.	2,153.
	66"	DS3ODSS()576621PL	1,939.	2,128.	2,228.
	72"	DS3ODSS()577221PL	1,979.	2,174.	2,271.



57"h Laminate Sliding Door Overdesk with 21" Tall Cabinet	30"	DS3ODSL()573021PL	2,015.	2,210.	2,310.
	36"	DS3ODSL()573621PL	2,083.	2,289.	2,388.
	42"	DS3ODSL()574221PL	2,150.	2,362.	2,467.
	48"	DS3ODSL()574821PL	2,216.	2,436.	2,546.
	60"	DS3ODSL()576021PL	2,288.	2,508.	2,623.
	66"	DS3ODSL()576621PL	2,355.	2,589.	2,704.
	72"	DS3ODSL()577221PL	2,421.	2,660.	2,782.



57"h Veneer Sliding Door Overdesk with 21" Tall Cabinet	30"	DS3ODSV()573021PL	2,111.	2,322.	2,425.
	36"	DS3ODSV()573621PL	2,190.	2,406.	2,509.
	42"	DS3ODSV()574221PL	2,263.	2,490.	2,603.
	48"	DS3ODSV()574821PL	2,342.	2,573.	2,690.
	60"	DS3ODSV()576021PL	2,418.	2,656.	2,778.
	66"	DS3ODSV()576621PL	2,497.	2,742.	2,864.
	72"	DS3ODSV()577221PL	2,570.	2,828.	2,954.



Ordering Information

Sliding Door Overdesk

1. Pattern Number
2. Case Finish
3. Door Finish
4. Edge Finish
(laminated door only)

Order Code

Sliding Door Overdesk

Example: **DS3ODSS**
2573021FL,613

DS3ODSS Pattern number
2573021FL

613 Silver Paint Finish

Included with:

Sliding Door Overdesk

Note: Overheads are only available
in Knoll core finishes.

Options

No lock - substitute "N" for "L" at
the end of pattern number, subtract
\$20.

Back option for No Door units
(1)= Back covering overhead only
(2)= Back covering overhead and
shelf section.


Paint Configuration Option:

Add "Y" at the end of the pattern
number to specify a different paint
finish on the case and fronts. P3
pricing applies on all product with
dual paint finishes.


Sliding Door Overdesks 64" High Cabinet with 14" High Storage

Dividends Horizon


description	width	pattern no.	P1	P2	P3
64"h without Sliding Door Overdesk with 14" Tall Cabinet	30"	DS3ODNS1643014	\$1,301.	\$1,429.	\$1,492.
	36"	DS3ODNS1643614	1,312.	1,438.	1,505.
	42"	DS3ODNS1644214	1,355.	1,484.	1,548.
	48"	DS3ODNS1644814	1,472.	1,615.	1,684.
	60"	DS3ODNS1646014	1,517.	1,665.	1,735.
	66"	DS3ODNS1646614	1,548.	1,702.	1,777.
	72"	DS3ODNS1647214	1,570.	1,725.	1,798.



64"h Steel Sliding Door Overdesk with 14" Tall Cabinet	30"	DS3ODSS1643014L	1,370.	1,503.	1,570.
	36"	DS3ODSS1643614L	1,401.	1,537.	1,602.
	42"	DS3ODSS1644214L	1,431.	1,570.	1,638.
	48"	DS3ODSS1644814L	1,478.	1,622.	1,694.
	60"	DS3ODSS1646014L	1,616.	1,775.	1,854.
	66"	DS3ODSS1646614L	1,661.	1,821.	1,901.
	72"	DS3ODSS1647214L	1,677.	1,839.	1,922.



64"h Laminate Sliding Door Overdesk with 14" Tall Cabinet	30"	DS3ODSL1643014L	1,805.	1,985.	2,073.
	36"	DS3ODSL1643614L	1,855.	2,038.	2,128.
	42"	DS3ODSL1644214L	1,904.	2,091.	2,185.
	48"	DS3ODSL1644814L	1,951.	2,145.	2,241.
	60"	DS3ODSL1646014L	2,001.	2,196.	2,297.
	66"	DS3ODSL1646614L	2,048.	2,249.	2,352.
	72"	DS3ODSL1647214L	2,096.	2,302.	2,407.




Ordering Information	Order Code	Included with:	Options
Sliding Door Overdesk	Sliding Door Overdesk	Sliding Door Overdesk	No lock - substitute "N" for "L" at the end of pattern number, subtract \$20.
1. Pattern Number	<i>Example:</i> DS3ODSS	Note: Overheads are only available in Knoll core finishes.	Paint Configuration Option:
2. Case Finish	2643014FL,613		Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.
3. Door Finish	DS3ODSS Pattern number		
4. Edge Finish (laminate door only)	2643014FL		
	613 Silver Paint Finish		

Sliding Door Overdesks

64" High Cabinet with 14" High Storage

Dividends Horizon

description	width	pattern no.	P1	P2	P3
64"h Veneer Sliding Door Overdesk with 14" Tall Cabinet	30"	DS3ODSV1643014L	\$1,904.	\$2,092.	\$2,187.
	36"	DS3ODSV1643614L	1,962.	2,153.	2,249.
	42"	DS3ODSV1644214L	2,019.	2,216.	2,314.
	48"	DS3ODSV1644814L	2,075.	2,278.	2,382.
	60"	DS3ODSV1646014L	2,134.	2,340.	2,447.
	66"	DS3ODSV1646614L	2,190.	2,405.	2,509.
	72"	DS3ODSV1647214L	2,246.	2,465.	2,580.




Ordering Information	Order Code	Included with:	Options
Sliding Door Overdesk	Sliding Door Overdesk	Sliding Door Overdesk	No lock - substitute "N" for "L" at the end of pattern number, subtract \$20.
1. Pattern Number	<i>Example:</i> DS3ODSS	Note: Overheads are only available in Knoll core finishes.	Paint Configuration Option:
2. Case Finish	2643014FL,613		Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.
3. Door Finish	DS3ODSS Pattern number		
4. Edge Finish (laminate door only)	2643014FL		
	613 Silver Paint Finish		

Sliding Door Overdesks


Dividends Horizon

64" High Cabinet with 21" High Storage (Full Height Door)


description	width	pattern no.	P1	P2	P3
64"h without Sliding Door Overdesk with 21" Tall Cabinet	30"	DS3ODNS()643021	\$1,383.	\$1,523.	\$1,588.
	36"	DS3ODNS()643621	1,406.	1,545.	1,616.
	42"	DS3ODNS()644221	1,438.	1,586.	1,663.
	48"	DS3ODNS()644821	1,533.	1,684.	1,764.
	60"	DS3ODNS()646021	1,682.	1,850.	1,937.
	66"	DS3ODNS()646621	1,735.	1,909.	1,998.
	72"	DS3ODNS()647221	1,776.	1,953.	2,042.



64"h Steel Sliding Door Overdesk with 21" Tall Cabinet	30"	DS3ODSS2643021FL	1,556.	1,710.	1,783.
	36"	DS3ODSS2643621FL	1,586.	1,740.	1,821.
	42"	DS3ODSS2644221FL	1,628.	1,788.	1,870.
	48"	DS3ODSS2644821FL	1,720.	1,885.	1,974.
	60"	DS3ODSS2646021FL	1,885.	2,073.	2,165.
	66"	DS3ODSS2646621FL	1,948.	2,141.	2,237.
	72"	DS3ODSS2647221FL	1,990.	2,185.	2,283.



64"h Laminate Sliding Door Overdesk with 21" Tall Cabinet	30"	DS3ODSL2643021FL	2,045.	2,247.	2,349.
	36"	DS3ODSL2643621FL	2,111.	2,322.	2,425.
	42"	DS3ODSL2644221FL	2,183.	2,397.	2,504.
	48"	DS3ODSL2644821FL	2,249.	2,474.	2,584.
	60"	DS3ODSL2646021FL	2,318.	2,548.	2,665.
	66"	DS3ODSL2646621FL	2,387.	2,623.	2,742.
	72"	DS3ODSL2647221FL	2,457.	2,701.	2,823.




Ordering Information	Order Code	Included with:	Options
Sliding Door Overdesk	Sliding Door Overdesk	Sliding Door Overdesk	No lock - substitute "N" for "L" at the end of pattern number, subtract \$20.
1. Pattern Number	<i>Example:</i> DS3ODSS	Note: Overheads are only available in Knoll core finishes.	Back option for No Door units
2. Case Finish	2643021FL,613		(1)= Back covering overhead only
3. Door Finish	DS3ODSS Pattern number		(2)= Back covering overhead and shelf section.
4. Edge Finish (laminate door only)	2643021FL		
	613 Silver Paint Finish		

Paint Configuration Option:
Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

64" High Cabinet with 21" High Storage (Full Height Door)

description	width	pattern no.	P1	P2	P3
64"h Veneer Sliding Door Overdesk with 21" Tall Cabinet	30"	DS3ODSV2643021FL	\$2,149.	\$2,360.	\$2,466.
	36"	DS3ODSV2643621FL	2,234.	2,451.	2,559.
	42"	DS3ODSV2644221FL	2,314.	2,545.	2,657.
	48"	DS3ODSV2644821FL	2,398.	2,639.	2,751.
	60"	DS3ODSV2646021FL	2,484.	2,727.	2,852.
	66"	DS3ODSV2646621FL	2,565.	2,820.	2,947.
	72"	DS3ODSV2647221FL	2,651.	2,912.	3,041.

**Ordering Information****Sliding Door Overdesk**

1. Pattern Number
2. Case Finish
3. Door Finish
4. Edge Finish
(laminate door only)

Order Code**Sliding Door Overdesk**

Example: **DS3ODSS**
2643021FL,613

DS3ODSS Pattern number
2643021FL

613 Silver Paint Finish

Included with:**Sliding Door Overdesk**

Note: Overheads are only available
in Knoll core finishes.

Options

No lock - substitute "N" for "L" at
the end of pattern number, subtract
\$20.

Back option for No Door units
(1)= Back covering overhead only
(2)= Back covering overhead and
shelf section.


Paint Configuration Option:
Add "Y" at the end of the pattern
number to specify a different paint
finish on the case and fronts. P3
pricing applies on all product with
dual paint finishes.

Sliding Door Overdesks


Dividends Horizon

64" High Cabinet with 21" High Storage, (Partial Height Door)


description	width	pattern no.	P1	P2	P3
64"h Steel Sliding Door Overdesk with 21" Tall Cabinet	30"	DS3ODSS()643021PL	\$1,556.	\$1,710.	\$1,783.
	36"	DS3ODSS()643621PL	1,586.	1,740.	1,821.
	42"	DS3ODSS()644221PL	1,628.	1,788.	1,870.
	48"	DS3ODSS()644821PL	1,720.	1,885.	1,974.
	60"	DS3ODSS()646021PL	1,885.	2,073.	2,165.
	66"	DS3ODSS()646621PL	1,948.	2,141.	2,237.
	72"	DS3ODSS()647221PL	1,990.	2,185.	2,283.



64"h Laminate Sliding Door Overdesk with 21" Tall Cabinet	30"	DS3ODSL()643021PL	2,033.	2,235.	2,335.
	36"	DS3ODSL()643621PL	2,099.	2,308.	2,410.
	42"	DS3ODSL()644221PL	2,171.	2,384.	2,490.
	48"	DS3ODSL()644821PL	2,237.	2,457.	2,566.
	60"	DS3ODSL()646021PL	2,303.	2,534.	2,648.
	66"	DS3ODSL()646621PL	2,372.	2,608.	2,721.
	72"	DS3ODSL()647221PL	2,439.	2,682.	2,803.



64"h Veneer Sliding Door Overdesk with 21" Tall Cabinet	30"	DS3ODSV()643021PL	2,134.	2,342.	2,447.
	36"	DS3ODSV()643621PL	2,206.	2,429.	2,536.
	42"	DS3ODSV()644221PL	2,286.	2,507.	2,621.
	48"	DS3ODSV()644821PL	2,362.	2,596.	2,709.
	60"	DS3ODSV()646021PL	2,437.	2,679.	2,797.
	66"	DS3ODSV()646621PL	2,511.	2,760.	2,887.
	72"	DS3ODSV()647221PL	2,591.	2,847.	2,975.




Ordering Information	Order Code	Included with:	Options
Sliding Door Overdesk	Sliding Door Overdesk	Sliding Door Overdesk	No lock - substitute "N" for "L" at the end of pattern number, subtract \$20.
1. Pattern Number	<i>Example:</i> DS3ODSS	Note: Overheads are only available in Knoll core finishes.	Back option for No Door units
2. Case Finish	2643021FL,613		(1) = Back covering overhead only
3. Door Finish	DS3ODSS Pattern number		(2) = Back covering overhead and shelf section.
4. Edge Finish (laminated door only)	2643021FL		
	613 Silver Paint Finish		Paint Configuration Option:
			Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Sliding Door Overdesks with Tackboard


57" High Cabinet with 14" High Storage, 14" High Door

Dividends Horizon


description	width	pattern no.	P1	P2	P3
57"h Overdesk without Door with 14" Tall Cabinet with tackboard	30"	DS3ODNS1573014T	\$1,659.	\$1,784.	\$1,842.
	36"	DS3ODNS1573614T	1,691.	1,821.	1,881.
	42"	DS3ODNS1574214T	1,738.	1,869.	1,936.
	48"	DS3ODNS1574814T	1,799.	1,931.	1,999.
	60"	DS3ODNS1576014T	1,946.	2,092.	2,163.
	66"	DS3ODNS1576614T	1,979.	2,134.	2,206.



57"h Overdesk with Steel Sliding Door and 14" Tall Cabinet with tackboard	30"	DS3ODSS1573014LT	1,760.	1,891.	1,954.
	36"	DS3ODSS1573614LT	1,799.	1,936.	2,001.
	42"	DS3ODSS1574214LT	1,855.	1,991.	2,059.
	48"	DS3ODSS1574814LT	1,914.	2,053.	2,128.
	60"	DS3ODSS1576014LT	2,081.	2,241.	2,317.
	66"	DS3ODSS1576614LT	2,125.	2,284.	2,364.
	72"	DS3ODSS1577214LT	2,183.	2,344.	2,424.



57"h Overdesk with Laminate Sliding Door and 14" Tall Cabinet with tackboard	30"	DS3ODSL1573014LT	2,194.	2,370.	2,459.
	36"	DS3ODSL1573614LT	2,249.	2,433.	2,522.
	42"	DS3ODSL1574214LT	2,319.	2,507.	2,602.
	48"	DS3ODSL1574814LT	2,384.	2,570.	2,666.
	60"	DS3ODSL1576014LT	2,462.	2,657.	2,752.
	66"	DS3ODSL1576614LT	2,507.	2,709.	2,811.
	72"	DS3ODSL1577214LT	2,595.	2,800.	2,904.




Ordering Information	Order Code	Included with:	Options
Sliding Door Overdesk	Sliding Door Overdesk	Sliding Door Overdesk	No lock - substitute "N" for "L" at the end of pattern number, subtract \$20.
1. Pattern Number	<i>Example:</i> DS3ODSS	Note: Overheads are only available in Knoll core finishes.	Paint Configuration Option:
2. Case Finish	1573014FL,613	Note: Fabric tackboard covers from top of worksurface to bottom of lower shelf.	Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.
3. Door Finish	DS3ODSS Pattern number		
4. Edge Finish (laminate door only)	1573014FL		
5. Tackboard fabric	613 Silver Paint Finish		

Sliding Door Overdesks with Tackboard

57" High Cabinet with 14" High Storage, 14" High Door

Dividends Horizon

description	width	pattern no.	P1	P2	P3
57"h Overdesk with Veneer Sliding Door and 14" Tall Cabinet with tackboard	30"	DS3ODSV1573014LT	\$2,288.	\$2,476.	\$2,567.
	36"	DS3ODSV1573614LT	2,357.	2,546.	2,645.
	42"	DS3ODSV1574214LT	2,437.	2,631.	2,733.
	48"	DS3ODSV1574814LT	2,504.	2,706.	2,807.
	60"	DS3ODSV1576014LT	2,594.	2,802.	2,904.
	66"	DS3ODSV1576614LT	2,648.	2,859.	2,967.
	72"	DS3ODSV1577214LT	2,739.	2,958.	3,068.





Ordering Information	Order Code	Included with:	Options
Sliding Door Overdesk	Sliding Door Overdesk	Sliding Door Overdesk	No lock - substitute "N" for "L" at the end of pattern number, subtract \$20.
1. Pattern Number	<i>Example:</i> DS3ODSS	Note: Overheads are only available in Knoll core finishes.	Paint Configuration Option:
2. Case Finish	1573014FL,613		Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.
3. Door Finish	DS3ODSS Pattern number	Note: Fabric tackboard covers from top of worksurface to bottom of lower shelf.	
4. Edge Finish (laminated door only)	1573014FL		
5. Tackboard fabric	613 Silver Paint Finish		


Sliding Door Overdesks with Tackboard

57" High Cabinet with 21" High Storage, (Full Height Door)

Dividends Horizon

description	width	pattern no.	P1	P2	P3
 57" h without Sliding Door Overdesk with 21" Tall Cabinet with tackboard	30"	DS3ODNS()573021T	\$1,632.	\$1,769.	\$1,835.
	36"	DS3ODNS()573621T	1,675.	1,814.	1,880.
	42"	DS3ODNS()574221T	1,732.	1,870.	1,940.
	48"	DS3ODNS()574821T	1,798.	1,946.	2,023.
	60"	DS3ODNS()576021T	1,970.	2,133.	2,210.
	66"	DS3ODNS()576621T	2,012.	2,179.	2,258.
	72"	DS3ODNS()577221T	2,076.	2,243.	2,332.

 57" h Steel Sliding Door Overdesk with 21" Tall Cabinet with tackboard	30"	DS3ODSS2573021FLT	1,825.	1,978.	2,051.
	36"	DS3ODSS2573621FLT	1,866.	2,022.	2,096.
	42"	DS3ODSS2574221FLT	1,934.	2,092.	2,174.
	48"	DS3ODSS2574821FLT	2,036.	2,201.	2,286.
	60"	DS3ODSS2576021FLT	2,236.	2,420.	2,511.
	66"	DS3ODSS2576621FLT	2,297.	2,485.	2,584.
	72"	DS3ODSS2577221FLT	2,377.	2,566.	2,665.

 57" h Laminate Sliding Door Overdesk with 21" Tall Cabinet with tackboard	30"	DS3ODSL2573021FLT	2,303.	2,505.	2,606.
	36"	DS3ODSL2573621FLT	2,384.	2,594.	2,694.
	42"	DS3ODSL2574221FLT	2,476.	2,691.	2,797.
	48"	DS3ODSL2574821FLT	2,557.	2,778.	2,887.
	60"	DS3ODSL2576021FLT	2,658.	2,887.	2,999.
	66"	DS3ODSL2576621FLT	2,727.	2,963.	3,077.
	72"	DS3ODSL2577221FLT	2,833.	3,075.	3,195.


Ordering Information	Order Code	Included with:	Options
Sliding Door Overdesk 1. Pattern Number 2. Case Finish 3. Door Finish 4. Edge Finish (laminated door only) 5. Tackboard fabric	Sliding Door Overdesk <i>Example:</i> DS3ODSS 2573021FL,613 DS3ODSS Pattern number 2573021FL 613 Silver Paint Finish	Sliding Door Overdesk Note: Overheads are only available in Knoll core finishes. Note: Fabric tackboard covers from top of worksurface to bottom of lower shelf.	No lock - substitute "N" for "L" at the end of pattern number, subtract \$20. Back option for No Door units (1) = Back covering overhead only (2) = Back covering overhead and shelf section. Paint Configuration Option: Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Sliding Door Overdesks with Tackboard

57" High Cabinet with 21" High Storage, (Full Height Door)

Dividends Horizon

description	width	pattern no.	P1	P2	P3
57"h Veneer Sliding Door Overdesk with 21" Tall Cabinet with tackboard	30"	DS3ODSV2573021FLT	\$2,409.	\$2,617.	\$2,721.
	36"	DS3ODSV2573621FLT	2,502.	2,719.	2,832.
	42"	DS3ODSV2574221FLT	2,611.	2,841.	2,951.
	48"	DS3ODSV2574821FLT	2,706.	2,940.	3,059.
	60"	DS3ODSV2576021FLT	2,823.	3,064.	3,188.
	66"	DS3ODSV2576621FLT	2,906.	3,157.	3,283.
	72"	DS3ODSV2577221FLT	3,027.	3,288.	3,415.




Ordering Information	Order Code	Included with:	Options
Sliding Door Overdesk	Sliding Door Overdesk	Sliding Door Overdesk	No lock - substitute "N" for "L" at the end of pattern number, subtract \$20.
1. Pattern Number	<i>Example:</i> DS3ODSS	Note: Overheads are only available in Knoll core finishes.	
2. Case Finish	2573021FL,613		
3. Door Finish	DS3ODSS Pattern number	Note: Fabric tackboard covers from top of worksurface to bottom of lower shelf.	Back option for No Door units
4. Edge Finish (laminate door only)	2573021FL		(1) = Back covering overhead only
5. Tackboard fabric	613 Silver Paint Finish		(2) = Back covering overhead and shelf section.
			Paint Configuration Option: Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Sliding Door Overdesks with Tackboard


57" High Cabinet with 21" High Storage, (Partial Height Door)

Dividends Horizon


description	width	pattern no.	P1	P2	P3
57"h Steel Sliding Door Overdesk with 21" Tall Cabinet with tackboard	36"	DS3ODSS()573021PLT	\$1,825.	\$1,978.	\$2,051.
	36"	DS3ODSS()573621PLT	1,866.	2,022.	2,096.
	42"	DS3ODSS()574221PLT	1,934.	2,092.	2,174.
	48"	DS3ODSS()574821PLT	2,036.	2,201.	2,286.
	60"	DS3ODSS()576021PLT	2,236.	2,420.	2,511.
	66"	DS3ODSS()576621PLT	2,297.	2,485.	2,584.
	72"	DS3ODSS()577221PLT	2,377.	2,566.	2,665.



57"h Laminate Sliding Door Overdesk with 21" Tall Cabinet with tackboard	30"	DS3ODSL()573021PLT	2,295.	2,491.	2,593.
	36"	DS3ODSL()573621PLT	2,372.	2,581.	2,679.
	42"	DS3ODSL()574221PLT	2,463.	2,675.	2,782.
	48"	DS3ODSL()574821PLT	2,543.	2,759.	2,871.
	60"	DS3ODSL()576021PLT	2,648.	2,868.	2,981.
	66"	DS3ODSL()576621PLT	2,712.	2,944.	3,061.
	72"	DS3ODSL()577221PLT	2,816.	3,058.	3,176.



57"h Veneer Sliding Door Overdesk with 21" Tall Cabinet with tackboard	30"	DS3ODSV()573021PLT	2,395.	2,603.	2,706.
	36"	DS3ODSV()573621PLT	2,479.	2,694.	2,802.
	42"	DS3ODSV()574221PLT	2,580.	2,804.	2,915.
	48"	DS3ODSV()574821PLT	2,667.	2,900.	3,015.
	60"	DS3ODSV()576021PLT	2,777.	3,015.	3,135.
	66"	DS3ODSV()576621PLT	2,854.	3,098.	3,222.
	72"	DS3ODSV()577221PLT	2,966.	3,222.	3,351.



Ordering Information	Order Code	Included with:	Options
Sliding Door Overdesk	Sliding Door Overdesk	Sliding Door Overdesk	No lock - substitute "N" for "L" at the end of pattern number, subtract \$20.
1. Pattern Number	<i>Example:</i> DS3ODSS	Note: Overheads are only available in Knoll core finishes.	
2. Case Finish	2573021FL,613		
3. Door Finish	DS3ODSS Pattern number	Note: Fabric tackboard covers from top of worksurface to bottom of lower shelf.	Back option for No Door units
4. Edge Finish (laminated door only)	2573021FL		(1)= Back covering overhead only
5. Tackboard fabric	613 Silver Paint Finish		(2)= Back covering overhead and shelf section.


Paint Configuration Option:
Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Sliding Door Overdesks with Tackboard


64" High Cabinet with 14" High Storage

Dividends Horizon


description	width	pattern no.	P1	P2	P3
64"h without Sliding Door Overdesk with 14" Tall Cabinet with tackboard	30"	DS3ODNS1643014T	\$1,741.	\$1,870.	\$1,934.
	36"	DS3ODNS1643614T	1,764.	1,891.	1,954.
	42"	DS3ODNS1644214T	1,830.	1,964.	2,029.
	48"	DS3ODNS1644814T	1,965.	2,104.	2,178.
	60"	DS3ODNS1646014T	2,042.	2,191.	2,262.
	66"	DS3ODNS1646614T	2,076.	2,231.	2,302.
	72"	DS3ODNS1647214T	2,139.	2,293.	2,367.



64"h Steel Sliding Door Overdesk with 14" Tall Cabinet with tackboard	30"	DS3ODSS1643014LT	1,814.	1,944.	2,012.
	36"	DS3ODSS1643614LT	1,853.	1,990.	2,054.
	42"	DS3ODSS1644214LT	1,911.	2,047.	2,118.
	48"	DS3ODSS1644814LT	1,970.	2,111.	2,188.
	60"	DS3ODSS1646014LT	2,141.	2,300.	2,382.
	66"	DS3ODSS1646614LT	2,187.	2,347.	2,431.
	72"	DS3ODSS1647214LT	2,245.	2,409.	2,488.



64"h Laminate Sliding Door Overdesk with 14" Tall Cabinet with tackboard	30"	DS3ODSL1643014LT	2,247.	2,425.	2,513.
	36"	DS3ODSL1643614LT	2,306.	2,488.	2,580.
	42"	DS3ODSL1644214LT	2,383.	2,567.	2,663.
	48"	DS3ODSL1644814LT	2,444.	2,639.	2,734.
	60"	DS3ODSL1646014LT	2,530.	2,721.	2,824.
	66"	DS3ODSL1646614LT	2,577.	2,778.	2,880.
	72"	DS3ODSL1647214LT	2,665.	2,873.	2,975.




Ordering Information	Order Code	Included with:	Options
Sliding Door Overdesk	Sliding Door Overdesk	Sliding Door Overdesk	No lock - substitute "N" for "L" at the end of pattern number, subtract \$20.
1. Pattern Number	<i>Example:</i> DS3ODSS	Note: Overheads are only available in Knoll core finishes.	Paint Configuration Option:
2. Case Finish	2643014FLT,613		Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.
3. Door Finish	DS3ODSS Pattern number	Note: Fabric tackboard covers from top of worksurface to bottom of lower shelf.	
4. Edge Finish (laminated door only)	2643014FLT		
5. Tackboard fabric	613 Silver Paint Finish		
	W1360 Annex Tackboard fabric		

Sliding Door Overdesks with Tackboard

64" High Cabinet with 14" High Storage

Dividends Horizon

description	width	pattern no.	P1	P2	P3
64"h Veneer Sliding Door Overdesk with 14" Tall Cabinet with tackboard	30"	DS3ODSV1643014LT	\$2,345.	\$2,534.	\$2,628.
	36"	DS3ODSV1643614LT	2,411.	2,607.	2,704.
	42"	DS3ODSV1644214LT	2,498.	2,694.	2,796.
	48"	DS3ODSV1644814LT	2,566.	2,769.	2,873.
	60"	DS3ODSV1646014LT	2,658.	2,868.	2,974.
	66"	DS3ODSV1646614LT	2,716.	2,930.	3,040.
	72"	DS3ODSV1647214LT	2,815.	3,035.	3,149.




Ordering Information	Order Code	Included with:	Options
Sliding Door Overdesk	Sliding Door Overdesk	Sliding Door Overdesk	No lock - substitute "N" for "L" at the end of pattern number, subtract \$20.
1. Pattern Number	<i>Example:</i> DS3ODSS	Note: Overheads are only available in Knoll core finishes.	Paint Configuration Option: Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.
2. Case Finish	2643014FLT,613		
3. Door Finish	DS3ODSS Pattern number	Note: Fabric tackboard covers from top of worksurface to bottom of lower shelf.	
4. Edge Finish (lamine door only)	2643014FLT		
5. Tackboard fabric	613 Silver Paint Finish		
	W1360 Annex Tackboard fabric		

Sliding Door Overdesks with Tackboard


64" High Cabinet with 21" High Storage (Full Height Door)

Dividends Horizon


description	width	pattern no.	P1	P2	P3
64"h without Sliding Door Overdesk with 21" Tall Cabinet with tackboard	30"	DS3ODNS()643021T	\$1,784.	\$1,924.	\$1,990.
	36"	DS3ODNS()643621T	1,817.	1,954.	2,027.
	42"	DS3ODNS()644221T	1,875.	2,023.	2,096.
	48"	DS3ODNS()644821T	1,981.	2,134.	2,209.
	60"	DS3ODNS()646021T	2,161.	2,331.	2,414.
	66"	DS3ODNS()646621T	2,216.	2,387.	2,478.
	72"	DS3ODNS()647221T	2,293.	2,472.	2,558.



64"h Steel Sliding Door Overdesk with 21" Tall Cabinet with tackboard	30"	DS3ODSS2643021FLT	1,954.	2,108.	2,184.
	36"	DS3ODSS2643621FLT	1,998.	2,151.	2,233.
	42"	DS3ODSS2644221FLT	2,064.	2,225.	2,303.
	48"	DS3ODSS2644821FLT	2,165.	2,335.	2,420.
	60"	DS3ODSS2646021FLT	2,366.	2,553.	2,647.
	66"	DS3ODSS2646621FLT	2,431.	2,620.	2,716.
	72"	DS3ODSS2647221FLT	2,506.	2,704.	2,800.



64"h Laminate Sliding Door Overdesk with 21" Tall Cabinet with tackboard	30"	DS3ODSL2643021FLT	2,447.	2,651.	2,750.
	36"	DS3ODSL2643621FLT	2,525.	2,734.	2,839.
	42"	DS3ODSL2644221FLT	2,616.	2,832.	2,939.
	48"	DS3ODSL2644821FLT	2,698.	2,920.	3,031.
	60"	DS3ODSL2646021FLT	2,800.	3,028.	3,145.
	66"	DS3ODSL2646621FLT	2,868.	3,103.	3,220.
	72"	DS3ODSL2647221FLT	2,974.	3,217.	3,341.




Ordering Information	Order Code	Included with:	Options
Sliding Door Overdesk 1. Pattern Number 2. Case Finish 3. Door Finish 4. Edge Finish (laminated door only) 5. Tackboard fabric	Sliding Door Overdesk <i>Example:</i> DS3ODSS 2643021FL,613 DS3ODSS Pattern number 2643021FL 613 Silver Paint Finish W1360 Annex Tackboard Finish	Sliding Door Overdesk Note: Overheads are only available in Knoll core finishes. Note: Fabric tackboard covers from top of work surface to bottom of lower shelf.	No lock - substitute "N" for "L" at the end of pattern number, subtract \$20. Back option for No Door units (1) = Back covering overhead only (2) = Back covering overhead and shelf section. Paint Configuration Option: Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Sliding Door Overdesks with Tackboard

64" High Cabinet with 21" High Storage (Full Height Door)

Dividends Horizon

description	width	pattern no.	P1	P2	P3
64"h Veneer Sliding Door Overdesk with 21" Tall Cabinet with tackboard	30"	DS3ODSV2643021FLT	\$2,549.	\$2,759.	\$2,868.
	36"	DS3ODSV2643621FLT	2,645.	2,863.	2,973.
	42"	DS3ODSV2644221FLT	2,751.	2,979.	3,093.
	48"	DS3ODSV2644821FLT	2,846.	3,086.	3,199.
	60"	DS3ODSV2646021FLT	2,963.	3,205.	3,330.
	66"	DS3ODSV2646621FLT	3,046.	3,301.	3,426.
	72"	DS3ODSV2647221FLT	3,166.	3,429.	3,557.



Ordering Information

Sliding Door Overdesk

1. Pattern Number
2. Case Finish
3. Door Finish
4. Edge Finish
(laminated door only)
5. Tackboard fabric

Order Code

Sliding Door Overdesk

Example: **DS3ODSS**
2643021FL,613

DS3ODSS Pattern number
2643021FL

613 Silver Paint Finish

W1360 Annex Tackboard Finish

Included with:

Sliding Door Overdesk

Note: Overheads are only available in Knoll core finishes.

Note: Fabric tackboard covers from top of work surface to bottom of lower shelf.

Options

No lock - substitute "N" for "L" at the end of pattern number, subtract \$20.

Back option for No Door units
(1)= Back covering overhead only
(2)= Back covering overhead and shelf section.


Paint Configuration Option:
Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

Sliding Door Overdesks with Tackboard


64" High Cabinet with 21" High Storage, (Partial Height Door)

Dividends Horizon


description	width	pattern no.	P1	P2	P3
64"h Steel Sliding Door Overdesk with 21" Tall Cabinet with tackboard	30"	DS3ODSS()643021PLT	\$1,954.	\$2,108.	\$2,184.
	36"	DS3ODSS()643621PLT	1,998.	2,151.	2,233.
	42"	DS3ODSS()644221PLT	2,064.	2,225.	2,303.
	48"	DS3ODSS()644821PLT	2,165.	2,335.	2,420.
	60"	DS3ODSS()646021PLT	2,366.	2,553.	2,647.
	66"	DS3ODSS()646621PLT	2,431.	2,620.	2,716.
	72"	DS3ODSS()647221PLT	2,506.	2,704.	2,800.



64"h Laminate Sliding Door Overdesk with 21" Tall Cabinet with tackboard	30"	DS3ODSL()643021PLT	2,434.	2,637.	2,735.
	36"	DS3ODSL()643621PLT	2,509.	2,718.	2,820.
	42"	DS3ODSL()644221PLT	2,604.	2,817.	2,924.
	48"	DS3ODSL()644821PLT	2,684.	2,905.	3,015.
	60"	DS3ODSL()646021PLT	2,785.	3,014.	3,125.
	66"	DS3ODSL()646621PLT	2,852.	3,088.	3,203.
	72"	DS3ODSL()647221PLT	2,957.	3,199.	3,319.



64"h Veneer Sliding Door Overdesk with 21" Tall Cabinet with tackboard	30"	DS3ODSV()643021PLT	2,534.	2,744.	2,850.
	36"	DS3ODSV()643621PLT	2,616.	2,840.	2,947.
	42"	DS3ODSV()644221PLT	2,719.	2,942.	3,059.
	48"	DS3ODSV()644821PLT	2,809.	3,043.	3,157.
	60"	DS3ODSV()646021PLT	2,917.	3,159.	3,276.
	66"	DS3ODSV()646621PLT	2,991.	3,245.	3,365.
	72"	DS3ODSV()647221PLT	3,109.	3,362.	3,494.



Ordering Information	Order Code	Included with:	Options
Sliding Door Overdesk	Sliding Door Overdesk	Sliding Door Overdesk	No lock - substitute "N" for "L" at the end of pattern number, subtract \$20.
1. Pattern Number	<i>Example:</i> DS3ODSS	Note: Overheads are only available in Knoll core finishes.	
2. Case Finish	2643021FL,613		
3. Door Finish	DS3ODSS Pattern number	Note: Fabric tackboard covers from top of worksurface to bottom of lower shelf.	Back option for No Door units
4. Edge Finish (laminite door only)	2643021FL		(1)= Back covering overhead only
5. Tackboard fabric	613 Silver Paint Finish		(2)= Back covering overhead and shelf section.
	W1360 Annex Tackboard Finish		Paint Configuration Option:
			Add "Y" at the end of the pattern number to specify a different paint finish on the case and fronts. P3 pricing applies on all product with dual paint finishes.

This page intentionally left blank

Available Worksurface Styles

- Rectangular
- Rectilinear corner
- Split top corner
- Curvilinear corner
- Trapezoid
- Smooth wave
- Curvilinear wave end
- Half-round
- Quarter-round
- Blended "D" shape
- "D" shape peninsula
- "P" and "9" shape peninsula
- Counter Worksurfaces
- Transition

Universal Applications

The undersides of worksurfaces are pre-drilled to accept various panel-hung and freestanding supports. Cascade edge worksurfaces do not have pre-drilled holes.

All supports must be ordered separately.

In panel-hung applications, worksurfaces are supported by:

- Cantilevers
- Pedestals
- Panel-to-worksurface brackets
- Flat brackets
- Panel-mounted C-leg support
- Open support legs

In peninsula applications, worksurfaces are supported by panels on one end and the other end is supported by:

- Support column
- A leg
- T support base

For freestanding applications, worksurface support is provided by:

- Pedestals
- End units
- Flat brackets

Construction

Laminate

- Surface material: .028 laminate on top surface with a paper backer on under side
- Edge material: 2mm ABS on straight and curved surfaces
- Core material: 45 lb. density particle board
- Thickness: 1 1/4"

Techwood

- Surface material: 0.6mm veneer
- Edge material: 2mm veneer on straight and curved surfaces
- Core material: 45 lb. density particle board
- Thickness: 1 1/4"

For available sizes, refer to the individual worksurface categories within this section.

Optional Edge Grommets

Edge grommets are optional and can be specified factory-installed centered along the rear edge of rectangular, rectilinear corner,

curvilinear wave end, and curvilinear corner worksurfaces. Grommets can also be retrofitted to worksurfaces by ordering an edge grommet kit (pattern number D1WSG). The edge grommet kit allows grommets to be field-installed in any location along the rear edge of worksurfaces.

Note: Edge grommets on 'D', '9', and 'P' peninsula worksurfaces are located on the panel hung side.

Cable Management


A 1/2" reveal is provided between the worksurface and panel for cable management. When edge grommets are specified, the grommet works in conjunction with the 1/2" reveal to allow plugs to be inserted through the grommet and cables to be positioned anywhere along the rear edge of the worksurface.

Loading Capacities


Maximum weight allowed for worksurfaces:

- 24"-42" wide: 200 lbs.
- 48" wide: 216 lbs.
- 54" wide: 243 lbs.
- 60" wide: 270 lbs.
- 66" wide: 297 lbs.
- 72" wide: 324 lbs.
- 78" wide: 351 lbs.
- 84" wide: 378 lbs.
- 90" wide: 405 lbs.
- 96" wide: 432 lbs.


Note: Installations which violate these requirements will not be covered by the Knoll, Inc. warranty.






Worksurfaces and Supports,
Panel Application



Worksurfaces and Supports,
Freestanding Application



2mm ABS Edge Detail




Worksurface Cable Management

Laminate Worksurface Grain Direction

The standard grain direction for wood grain or brushed laminates for each worksurface shape is shown below.

When wood grain or brushed laminates are specified on Dividends Horizon corner worksurfaces, a left, right or diagonal grain direction option must be specified as shown below. Insert the desired grain direction option (L, R or D) after the laminate finish code. The diagonal option is an upcharge. This option applies only to corner worksurfaces with the same dimension on each rear side.

Laminate Worksurface Grain Direction




Techwood Worksurface Grain Direction

The standard grain direction for Techwood worksurfaces for each worksurface shape is shown below.

Techwood corner worksurfaces with the same dimension on each rear side have a diagonal grain direction.

Techwood Worksurface Grain Direction



Panel-Hung Worksurface Support

All worksurfaces require support every 48" in width. In panel-hung applications, mid-span support must be provided by cantilevers, panel-mounted C-legs or open support legs.

When worksurfaces are mounted perpendicular to panels, the worksurface depth must equal the width of the panel when using panel-to-worksurface brackets.

Cantilevers are available in three depths to match worksurface depths.

- 18" deep worksurfaces are supported by 18" deep cantilevers.
- 24" deep worksurfaces are supported by 24" deep cantilevers.
- 30" deep worksurfaces are not recommended to be supported by cantilevers. 30" deep cantilevers are used for mid-span support.
- 36" deep worksurfaces cannot be supported by cantilevers.

Panel-mounted C-leg supports are available to support 24" and 30" worksurface depths in heavier worksurface load applications.


Open support legs are available to support 18", 24" and 30" worksurfaces depths.

Freestanding Worksurface Support


For freestanding desk applications, specify freestanding pedestals, end units and/or intermediate support every 48" in width.

- 18" deep worksurfaces can be supported by 18" deep pedestals and end units only
- 24" deep worksurfaces can be supported by either 18" or 24" deep pedestals or end units
- 30" deep worksurfaces can be supported by either 24" or 30" deep pedestals or end units
- 36" deep worksurfaces can only be supported by 30" deep pedestals or end units and provide a 6" front overhang for desk applications.

Maximum Width Between Panel-Hung Worksurface Supports



Maximum Width Between Freestanding Worksurface Supports




Worksurface Reinforcement

Worksurface reinforcements are required for worksurface spans greater than 48 inches. This includes freestanding desk worksurfaces over 48 inches using desk end units. Worksurface reinforcements have a black paint finish.



Notes:

- Whenever using pedestals they should be connected to panels with panel-to-worksurface brackets
- Panel runs must be floor-supported every 8 feet (i.e., pedestal with panel-to-worksurface brackets or panel-mounted C-leg)
- When a panel mounted C-leg is used, unsupported worksurface span is not to exceed 48".



Legend



Worksurface Reinforcement Panel Hung Application



Worksurface Reinforcement Freestanding Desk Application



Rectangular Worksurfaces

18" and 24" Deep Specifications

Dividends Horizon

Rectangular Worksurfaces

Dividends Horizon rectangular worksurfaces are universal and may be used in:

- Panel-hung applications
- Freestanding applications

Available Sizes

- Depths: 18" and 24"
- Widths: 24" to 96"


Panel-Hung Applications

When a worksurface spans multiple panels a cantilever or freestanding support is required every 48" of width.


Freestanding Applications

Rectangular worksurfaces in "build-to-spec" applications use pedestals and end units as the primary support for freestanding desks. Back panels are optional and can be specified as required.

The most common freestanding applications involve desks, returns and bridge units in "L" and "U" configurations.




24"D Rectangular Worksurface





18"D Rectangular Worksurface

18"D	24"D
24"	24"
30"	30"
36"	36"
42"	42"
48"	48"
54"	54"
60"	60"
66"	66"
72"	72"
78"	78"
84"	84"
90"	90"
96"	96"

Rectangular Sizes Available



Worksurfaces over 48" W require mid-span support



Freestanding Desk Applications

Rectangular Worksurfaces

18" Deep

Dividends Horizon

description	w *	w	d	t	pattern no.	laminate w/ ABS edge	laminate w/ woodgrain edge	laminate w/ metal edge	techwood w/ techwood edge
18" Deep Rectangular No Grommets 	18"	17 ¹³ / ₁₆ "	17 1/2"	1 1/4"	D1R 1818N	\$190.	\$208.	\$226.	\$467.
	21"	20 ¹³ / ₁₆ "	17 1/2"	1 1/4"	D1R 2118N	194.	214.	235.	500.
	24"	23 ¹³ / ₁₆ "	17 1/2"	1 1/4"	D1R 2418N	200.	218.	237.	488.
	27"	26 ¹³ / ₁₆ "	17 1/2"	1 1/4"	D1R 2718N	204.	224.	245.	502.
	30"	29 ¹³ / ₁₆ "	17 1/2"	1 1/4"	D1R 3018N	210.	231.	250.	513.
	33"	32 ¹³ / ₁₆ "	17 1/2"	1 1/4"	D1R 3318N	219.	246.	267.	521.
	36"	35 ¹³ / ₁₆ "	17 1/2"	1 1/4"	D1R 3618N	234.	259.	283.	537.
	39"	38 ¹³ / ₁₆ "	17 1/2"	1 1/4"	D1R 3918N	246.	277.	306.	551.
	42"	41 ¹³ / ₁₆ "	17 1/2"	1 1/4"	D1R 4218N	271.	297.	323.	563.
	45"	44 ¹³ / ₁₆ "	17 1/2"	1 1/4"	D1R 4518N	287.	315.	346.	574.
	48"	47 ¹³ / ₁₆ "	17 1/2"	1 1/4"	D1R 4818N	301.	333.	363.	587.
	51"	50 ¹³ / ₁₆ "	17 1/2"	1 1/4"	D1R 5118N	312.	342.	370.	600.
	54"	53 ¹³ / ₁₆ "	17 1/2"	1 1/4"	D1R 5418N	320.	352.	386.	607.
	57"	56 ¹³ / ₁₆ "	17 1/2"	1 1/4"	D1R 5718N	335.	367.	397.	616.
	60"	59 ¹³ / ₁₆ "	17 1/2"	1 1/4"	D1R 6018N	349.	383.	418.	631.
	63"	62 ¹³ / ₁₆ "	17 1/2"	1 1/4"	D1R 6318N	358.	400.	441.	646.
	66"	65 ¹³ / ₁₆ "	17 1/2"	1 1/4"	D1R 6618N	376.	414.	451.	656.
	69"	68 ¹³ / ₁₆ "	17 1/2"	1 1/4"	D1R 6918N	379.	418.	460.	668.
	72"	71 ¹³ / ₁₆ "	17 1/2"	1 1/4"	D1R 7218N	396.	435.	475.	678.
	75"	74 ¹³ / ₁₆ "	17 1/2"	1 1/4"	D1R 7518N	406.	450.	492.	695.
	78"	77 ¹³ / ₁₆ "	17 1/2"	1 1/4"	D1R 7818N	426.	468.	511.	707.
	81"	80 ¹³ / ₁₆ "	17 1/2"	1 1/4"	D1R 8118N	438.	480.	528.	722.
	84"	83 ¹³ / ₁₆ "	17 1/2"	1 1/4"	D1R 8418N	448.	493.	536.	734.
	87"	86 ¹³ / ₁₆ "	17 1/2"	1 1/4"	D1R 8718N	470.	513.	559.	749.
	90"	89 ¹³ / ₁₆ "	17 1/2"	1 1/4"	D1R 9018N	500.	551.	596.	763.
	93"	92 ¹³ / ₁₆ "	17 1/2"	1 1/4"	D1R 9318N	525.	574.	623.	778.
	96"	95 ¹³ / ₁₆ "	17 1/2"	1 1/4"	D1R 9618N	554.	605.	661.	791.
	99"	98 ¹³ / ₁₆ "	17 1/2"	1 1/4"	D1R 9918N	576.	627.	681.	819.

w* = nominal width

Dimensions listed under w d t are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Worksurfaces	Worksurfaces	Worksurfaces	Worksurfaces
1. Pattern Number	<i>Example:</i> D1R 4818N, 114, 114	Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.	- Center-Located Edge Grommet - Woodgrain ABS edge - Metal edge - Techwood edge
2. Top Finish Type	D1R Pattern Number		
3. Edge Finish	4818N		
	114 Folkstone Grey Laminate		To specify edge grommet, replace the "N" suffix from the pattern number with "G".
	114 Folkstone Grey Edge Band		Add \$19.

Rectangular Worksurfaces

24" Deep

Dividends Horizon

description	w	w	d	t	pattern no.	laminate w/ ABS edge	laminate w/ woodgrain edge	laminate w/ metal edge	techwood w/ techwood edge
24" Deep Rectangular No Grommets 	18"	17 ¹³ / ₁₆ "	23 ¹ / ₂ "	1 ¹ / ₄ "	D1R 1824N	\$200.	\$218.	\$237.	\$488.
	21"	20 ¹³ / ₁₆ "	23 ¹ / ₂ "	1 ¹ / ₄ "	D1R 2124N	204.	224.	246.	493.
	24"	23 ¹³ / ₁₆ "	23 ¹ / ₂ "	1 ¹ / ₄ "	D1R 2424N	211.	233.	256.	503.
	27"	26 ¹³ / ₁₆ "	23 ¹ / ₂ "	1 ¹ / ₄ "	D1R 2724N	225.	251.	271.	518.
	30"	29 ¹³ / ₁₆ "	23 ¹ / ₂ "	1 ¹ / ₄ "	D1R 3024N	243.	266.	289.	531.
	33"	32 ¹³ / ₁₆ "	23 ¹ / ₂ "	1 ¹ / ₄ "	D1R 3324N	253.	278.	309.	546.
	36"	35 ¹³ / ₁₆ "	23 ¹ / ₂ "	1 ¹ / ₄ "	D1R 3624N	269.	294.	320.	560.
	39"	38 ¹³ / ₁₆ "	23 ¹ / ₂ "	1 ¹ / ₄ "	D1R 3924N	287.	311.	346.	575.
	42"	41 ¹³ / ₁₆ "	23 ¹ / ₂ "	1 ¹ / ₄ "	D1R 4224N	308.	338.	372.	589.
	45"	44 ¹³ / ₁₆ "	23 ¹ / ₂ "	1 ¹ / ₄ "	D1R 4524N	324.	358.	388.	603.
	48"	47 ¹³ / ₁₆ "	23 ¹ / ₂ "	1 ¹ / ₄ "	D1R 4824N	343.	379.	415.	618.
	51"	50 ¹³ / ₁₆ "	23 ¹ / ₂ "	1 ¹ / ₄ "	D1R 5124N	358.	398.	429.	634.
	54"	53 ¹³ / ₁₆ "	23 ¹ / ₂ "	1 ¹ / ₄ "	D1R 5424N	373.	410.	447.	652.
	57"	56 ¹³ / ₁₆ "	23 ¹ / ₂ "	1 ¹ / ₄ "	D1R 5724N	389.	425.	467.	668.
	60"	59 ¹³ / ₁₆ "	23 ¹ / ₂ "	1 ¹ / ₄ "	D1R 6024N	405.	443.	481.	683.
	63"	62 ¹³ / ₁₆ "	23 ¹ / ₂ "	1 ¹ / ₄ "	D1R 6324N	421.	458.	502.	700.
	66"	65 ¹³ / ₁₆ "	23 ¹ / ₂ "	1 ¹ / ₄ "	D1R 6624N	434.	477.	521.	712.
	69"	68 ¹³ / ₁₆ "	23 ¹ / ₂ "	1 ¹ / ₄ "	D1R 6924N	441.	491.	533.	725.
	72"	71 ¹³ / ₁₆ "	23 ¹ / ₂ "	1 ¹ / ₄ "	D1R 7224N	453.	501.	547.	744.
	75"	74 ¹³ / ₁₆ "	23 ¹ / ₂ "	1 ¹ / ₄ "	D1R 7524N	478.	518.	562.	763.
	78"	77 ¹³ / ₁₆ "	23 ¹ / ₂ "	1 ¹ / ₄ "	D1R 7824N	488.	534.	582.	779.
	81"	80 ¹³ / ₁₆ "	23 ¹ / ₂ "	1 ¹ / ₄ "	D1R 8124N	500.	550.	602.	793.
	84"	83 ¹³ / ₁₆ "	23 ¹ / ₂ "	1 ¹ / ₄ "	D1R 8424N	515.	569.	619.	812.
	87"	86 ¹³ / ₁₆ "	23 ¹ / ₂ "	1 ¹ / ₄ "	D1R 8724N	551.	613.	658.	838.
	90"	89 ¹³ / ₁₆ "	23 ¹ / ₂ "	1 ¹ / ₄ "	D1R 9024N	581.	636.	698.	847.
	93"	92 ¹³ / ₁₆ "	23 ¹ / ₂ "	1 ¹ / ₄ "	D1R 9324N	611.	679.	735.	862.
	96"	95 ¹³ / ₁₆ "	23 ¹ / ₂ "	1 ¹ / ₄ "	D1R 9624N	632.	699.	764.	879.
	99"	98 ¹³ / ₁₆ "	23 ¹ / ₂ "	1 ¹ / ₄ "	D1R 9924N	644.	733.	791.	911.
	102"	101 ¹³ / ₁₆ "	23 ¹ / ₂ "	1 ¹ / ₄ "	D1R 10224N	663.	724.	801.	928.
	108"	107 ¹³ / ₁₆ "	23 ¹ / ₂ "	1 ¹ / ₄ "	D1R 10824N	745.	796.	877.	1,008.
	120"	119 ¹³ / ₁₆ "	23 ¹ / ₂ "	1 ¹ / ₄ "	D1R 12024N	802.	827.	911.	1,120.

w* = nominal width

Dimensions listed under w d t are actual to the nearest ¹/₁₆"

Ordering Information	Order Code	Included with:	Options
Worksurfaces 1. Pattern Number 2. Top Finish Type 3. Edge Finish	Worksurfaces <i>Example:</i> D1R 4818N, 114, 114 D1R Pattern Number 4818N 114 Folkstone Grey Laminate 114 Folkstone Grey Edge Band	Worksurfaces Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.	Worksurfaces - Center-Located Edge Grommet - Woodgrain ABS edge - Metal edge - Techwood edge To specify edge grommet, replace the "N" suffix from the pattern number with "G". Add \$19.

This page intentionally left blank

Rectangular Worksurfaces

19" Deep Specifications

Dividends Horizon

Rectangular Worksurfaces

The 19" deep rectangular worksurface aligns with the depth of a doublewide pedestal.

Dividends Horizon worksurfaces provide a 1/2" reveal between the worksurface and panel for cable management.

Dividends Horizon 19" deep rectangular worksurfaces are universal and may be used in:

- Panel-hung applications
- Freestanding applications

Available Sizes

- Depths: 19"
- Widths: 24" to 96"


Panel-Hung Applications

When a worksurface spans multiple panels, a cantilever or freestanding support is required every 48" of width.


Freestanding Applications

Rectangular worksurfaces in "build-to-spec" applications use pedestals and end units as the primary support for freestanding desks. Back panels are optional and can be specified as required.


The most common freestanding applications involve desks, returns and bridge units in "L" and "U" configurations.




19"D Rectangular Worksurface



Rectangular Sizes Available



Worksurfaces over 48" W require mid-span support



19" Deep Worksurface Application

Doublewide Pedestal

Rectangular Worksurfaces

19" Deep

Dividends Horizon

description	w *	w	d	t	pattern no.	laminate w/ ABS edge	laminate w/ woodgrain edge	laminate w/ metal edge	techwood w/ techwood edge
19" Deep Rectangular - No Grommets (for use with doublewide pedestals)	24"	23 ¹³ / ₁₆ "	18 ³ / ₄ "	1 ¹ / ₄ "	D1R2419N	\$202.	\$220.	\$241.	\$490.
	30"	29 ¹³ / ₁₆ "	18 ³ / ₄ "	1 ¹ / ₄ "	D1R3019N	216.	236.	258.	515.
	36"	35 ¹³ / ₁₆ "	18 ³ / ₄ "	1 ¹ / ₄ "	D1R3619N	241.	265.	288.	543.
	42"	41 ¹³ / ₁₆ "	18 ³ / ₄ "	1 ¹ / ₄ "	D1R4219N	276.	304.	333.	567.
	48"	47 ¹³ / ₁₆ "	18 ³ / ₄ "	1 ¹ / ₄ "	D1R4819N	308.	339.	371.	593.
	54"	53 ¹³ / ₁₆ "	18 ³ / ₄ "	1 ¹ / ₄ "	D1R5419N	329.	363.	396.	617.
	60"	59 ¹³ / ₁₆ "	18 ³ / ₄ "	1 ¹ / ₄ "	D1R6019N	359.	393.	430.	641.
	66"	65 ¹³ / ₁₆ "	18 ³ / ₄ "	1 ¹ / ₄ "	D1R6619N	384.	425.	463.	663.
	72"	71 ¹³ / ₁₆ "	18 ³ / ₄ "	1 ¹ / ₄ "	D1R7219N	408.	447.	489.	691.
	78"	77 ¹³ / ₁₆ "	18 ³ / ₄ "	1 ¹ / ₄ "	D1R7819N	434.	477.	522.	719.
	84"	83 ¹³ / ₁₆ "	18 ³ / ₄ "	1 ¹ / ₄ "	D1R8419N	460.	506.	554.	746.
	90"	89 ¹³ / ₁₆ "	18 ³ / ₄ "	1 ¹ / ₄ "	D1R9019N	513.	563.	616.	776.
	96"	95 ¹³ / ₁₆ "	18 ³ / ₄ "	1 ¹ / ₄ "	D1R9619N	565.	621.	679.	804.

w* = nominal width

Dimensions listed under w d t are actual to the nearest ¹/₁₆"

Ordering Information

Worksurfaces

1. Pattern Number
2. Top Finish Type
3. Edge Finish

Order Code

Worksurfaces

Example: **D1R 4819N, 114, 114**

D1R Pattern Number
4819N

114 Folkstone Grey
Laminate

114 Folkstone Grey Edge
Band

Included with:

Worksurfaces

Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.

Options

Worksurfaces

- Center-Located Edge Grommet
- Woodgrain ABS edge
- Metal edge
- Techwood edge

To specify edge grommet, replace the "N" suffix from the pattern number with "G".
Add \$19.

Rectangular Worksurfaces

30" and 36" Deep Specifications

Dividends Horizon

Rectangular Worksurfaces

Dividends Horizon rectangular worksurfaces are universal and can be used in:

- Panel-hung applications
- Freestanding applications

See page 166 for the following:

- Worksurface construction
- Optional edge grommets
- Loading capacities

Available Sizes

- Depths: 30" and 36"
- Widths: 24" to 96" (30"D), 60" to 72" (36"D)

Panel-Hung Applications

When a worksurface spans multiple panels a cantilever or freestanding floor support is required every 48". 36" deep worksurfaces cannot be supported by cantilevers. Worksurfaces over 48" W require mid-span support


Freestanding Applications

Refer to the freestanding desk section for "preconfigured" applications. Rectangular worksurfaces in "build-to-spec" applications use pedestals and end units as the primary support for freestanding desks. Back panels are optional and can be specified as required.


The most common freestanding applications involve desks, returns and bridge units in "L" and "U" configurations.

Overhang Desks


Overhang desks can be ordered by component by specifying desk supports and worksurfaces separately. To specify, select either a 30" or 36" deep worksurface in 60", 66" or 72" widths. Back panels should be specified to match the worksurface width while supports (pedestals or end units) should be one size smaller than the worksurface depth to provide a 6" front overhang. Example: 36" deep worksurface with 30" deep pedestals or end units.





30"D Rectangular Worksurface



36"D Rectangular Worksurface



Worksurfaces over 48"W
require mid-span support




Freestanding Desk Applications

Rectangular Worksurfaces

30" and 36" Deep

Dividends Horizon

description	w	w	d	t	pattern no.	laminates w/ ABS edge	laminates w/ woodgrain edge	laminates w/ metal edge	techwood w/ techwood edge
30" Deep Rectangular No Grommets 	24"	23 13/16"	29 1/2"	1 1/4"	D1R 2430N	\$270.	\$295.	\$321.	\$521.
	27"	26 13/16"	29 1/2"	1 1/4"	D1R 2730N	286.	309.	338.	536.
	30"	29 13/16"	29 1/2"	1 1/4"	D1R 3030N	301.	333.	363.	562.
	33"	32 13/16"	29 1/2"	1 1/4"	D1R 3330N	317.	347.	384.	577.
	36"	35 13/16"	29 1/2"	1 1/4"	D1R 3630N	335.	368.	404.	601.
	39"	38 13/16"	29 1/2"	1 1/4"	D1R 3930N	349.	380.	413.	620.
	42"	41 13/16"	29 1/2"	1 1/4"	D1R 4230N	363.	398.	432.	641.
	45"	44 13/16"	29 1/2"	1 1/4"	D1R 4530N	386.	423.	465.	658.
	48"	47 13/16"	29 1/2"	1 1/4"	D1R 4830N	405.	443.	481.	680.
	51"	50 13/16"	29 1/2"	1 1/4"	D1R 5130N	434.	463.	510.	695.
	54"	53 13/16"	29 1/2"	1 1/4"	D1R 5430N	457.	502.	549.	710.
	57"	56 13/16"	29 1/2"	1 1/4"	D1R 5730N	470.	531.	577.	722.
	60"	59 13/16"	29 1/2"	1 1/4"	D1R 6030N	503.	555.	602.	741.
	63"	62 13/16"	29 1/2"	1 1/4"	D1R 6330N	532.	592.	643.	754.
	66"	65 13/16"	29 1/2"	1 1/4"	D1R 6630N	559.	616.	672.	769.
	69"	68 13/16"	29 1/2"	1 1/4"	D1R 6930N	571.	626.	684.	786.
	72"	71 13/16"	29 1/2"	1 1/4"	D1R 7230N	581.	636.	698.	797.
	75"	74 13/16"	29 1/2"	1 1/4"	D1R 7530N	594.	657.	722.	814.
	78"	77 13/16"	29 1/2"	1 1/4"	D1R 7830N	620.	687.	746.	836.
	81"	80 13/16"	29 1/2"	1 1/4"	D1R 8130N	634.	712.	766.	852.
	84"	83 13/16"	29 1/2"	1 1/4"	D1R 8430N	659.	724.	793.	870.
	102"	101 13/16"	29 1/2"	1 1/4"	D1R 10230N	663.	763.	815.	958.
	87"	86 13/16"	29 1/2"	1 1/4"	D1R 8730N	679.	748.	820.	889.
	108"	107 13/16"	29 1/2"	1 1/4"	D1R 10830N	699.	794.	853.	987.
	90"	89 13/16"	29 1/2"	1 1/4"	D1R 9030N	709.	779.	850.	908.
	114"	113 13/16"	29 1/2"	1 1/4"	D1R 11430N	724.	822.	889.	1,021.
	93"	92 13/16"	29 1/2"	1 1/4"	D1R 9330N	725.	816.	885.	926.
	96"	95 13/16"	29 1/2"	1 1/4"	D1R 9630N	761.	837.	912.	944.
	99"	98 13/16"	29 1/2"	1 1/4"	D1R 9930N	775.	862.	940.	964.
	120"	119 13/16"	29 1/2"	1 1/4"	D1R 12030N	788.	873.	952.	1,108.

w* = nominal width

Dimensions listed under w h t are actual to the nearest 1/16"

Ordering Information

Worksurfaces

1. Pattern Number
2. Top Finish Type
3. Edge Finish

Order Code

Worksurfaces

Example: **D1R 6030N, 114, 114**

D1R Pattern Number
6030N

114 Folkstone Grey
Laminate

114 Folkstone Grey Edge
Band

Included with:

Worksurfaces

Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.

Options

Worksurfaces


- Center-Located Edge Grommet
- Woodgrain ABS edge
- Metal edge
- Techwood edge

To specify edge grommet, replace the "N" suffix from the pattern number with "G".
Add \$19.

Rectangular Worksurfaces

30" and 36" Deep

Dividends Horizon

description	w	w	d	t	pattern no.	laminate w/ ABS edge	laminate w/ woodgrain edge	laminate w/ metal edge	techwood w/ techwood edge
36" Deep Rectangular No Grommets 	96"	95 ^{13/16"}	35 ^{1/2"}	1 ^{1/4"}	D1R 9636N	\$1,019.	\$1,051.	\$1,078.	\$1,108.
	60"	59 ^{13/16"}	35 ^{1/2"}	1 ^{1/4"}	D1R 6036N	644.	708.	771.	878.
	66"	65 ^{13/16"}	35 ^{1/2"}	1 ^{1/4"}	D1R 6636N	711.	785.	852.	909.
	72"	71 ^{13/16"}	35 ^{1/2"}	1 ^{1/4"}	D1R 7236N	785.	865.	940.	942.
	78"	77 ^{13/16"}	35 ^{1/2"}	1 ^{1/4"}	D1R 7836N	836.	887.	950.	953.
	84"	83 ^{13/16"}	35 ^{1/2"}	1 ^{1/4"}	D1R 8436N	884.	911.	956.	962.
	90"	89 ^{13/16"}	35 ^{1/2"}	1 ^{1/4"}	D1R 9036N	953.	980.	1,018.	1,034.

w* = nominal width

Dimensions listed under w h t are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Worksurfaces 1. Pattern Number 2. Top Finish Type 3. Edge Finish	Worksurfaces <i>Example:</i> D1R 6030N, 114, 114 D1R Pattern Number 6030N 114 Folkstone Grey Laminate 114 Folkstone Grey Edge Band 	Worksurfaces Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.	Worksurfaces - Center-Located Edge Grommet - Woodgrain ABS edge - Metal edge - Techwood edge To specify edge grommet, replace the "N" suffix from the pattern number with "G". Add \$19.

This page intentionally left blank

Curvilinear Wave End Worksurfaces

Dividends Horizon curvilinear wave end worksurfaces are primarily used in panel-hung applications.

Available Sizes

Curvilinear wave end worksurfaces are handed with one side deeper than the other.

- Depths: 24"/30", 18"/30", 24"/36"
- Widths: 36" to 72"

Curvilinear Wave End Applications

36" to 48" wide wave ends are generally used as worksurface returns attached to curvilinear corners.

72" wide wave ends are used as primary worksurfaces with returns attached at the deep end.

Note: Only 18" and 24" deep returns can be attached to 72" wide wave end worksurfaces.

Curvilinear Wave End Support

In applications where worksurface ends are mounted perpendicular to panels, panel-to-worksurface brackets or a cantilever and a panel-to-worksurface bracket can be used as shown below.

72" wide curvilinear wave ends always require mid-span cantilever support including applications involving pedestal support at one end.

Pedestal Support Applications

Pedestals can be used as supports in the following locations:

- The deep end of all curvilinear wave ends
- The shallow end of all 48" and 72" wide curvilinear wave end worksurfaces

Recommended Pedestal Depths


- 18" deep wave ends require 18" deep pedestals
- 24" deep wave ends can use either a 18" or 24" deep pedestal
- 30" deep wave ends can use either a 24" or 30" deep pedestal
- 36" deep wave ends require a 30" deep pedestal

Note: When the pedestal depth is less than the worksurface depth, a panel-to-worksurface bracket must be used in the rear corner of the worksurface to the panel.

Freestanding Applications

Curvilinear wave end worksurfaces can be used to create unique freestanding workstations supported by pedestals and end units. The most common application is a 72" wide wave end worksurface with a single pedestal and end unit attached to a freestanding return.






Curvilinear Wave End Worksurface



Curvilinear Wave End Worksurface Sizes



	30"/18"D	18"/30"D
72"W		
	30"/24"D	24"/30"D
72"W		
	36"/24"D	24"/36"D
72"W		

Curvilinear Wave End Applications



** Requires a return panel, panel-mounted C-leg support, open support leg, or a pedestal with a panel-to-worksurface bracket for support.

Pedestal Support Applications





Pedestal on shallow end of curvilinear wave ends

Curvilinear Wave End Worksurfaces

Mixed Depths

Dividends Horizon


description	w *	1	2	3	A	B	t	pattern no.	laminate w/ ABS edge	laminate w/ woodgrain edge	laminate w/ metal edge	techwood w/ techwood edge
Curvilinear Wave End Left No Grommets 	36"	35 13/16"	23 1/2"	29 1/2"	14 15/16"	2 15/16"	1 1/4"	D1W 363024N	\$567.	\$621.	\$683.	\$1,087.
	42"	41 13/16"	23 1/2"	29 1/2"	14 15/16"	8 15/16"	1 1/4"	D1W 423024N	594.	657.	712.	1,120.
	48"	47 13/16"	23 1/2"	29 1/2"	14 15/16"	14 15/16"	1 1/4"	D1W 483024N	633.	700.	765.	1,150.
	72"	71 13/16"	17 1/2"	29 1/2"	23 7/16"	14 15/16"	1 1/4"	D1W 723018N	788.	866.	944.	1,182.
	72"	71 13/16"	23 1/2"	29 1/2"	23 7/16"	30 7/16"	1 1/4"	D1W 723024N	810.	889.	975.	1,217.
	72"	71 13/16"	23 1/2"	35 1/2"	23 7/16"	14 15/16"	1 1/4"	D1W 723624N	838.	918.	1,005.	1,246.
Curvilinear Wave End Right No Grommets 	36"	35 13/16"	29 1/2"	23 1/2"	2 15/16"	14 15/16"	1 1/4"	D1W 362430N	567.	621.	683.	1,087.
	42"	41 13/16"	29 1/2"	23 1/2"	8 15/16"	14 15/16"	1 1/4"	D1W 422430N	594.	657.	712.	1,120.
	48"	47 13/16"	29 1/2"	23 1/2"	14 15/16"	14 15/16"	1 1/4"	D1W 482430N	633.	700.	765.	1,150.
	72"	71 13/16"	29 1/2"	17 1/2"	14 15/16"	23 7/16"	1 1/4"	D1W 721830N	788.	866.	944.	1,182.
	72"	71 13/16"	29 1/2"	23 1/2"	30 7/16"	23 7/16"	1 1/4"	D1W 722430N	810.	889.	975.	1,217.
	72"	71 13/16"	35 1/2"	23 1/2"	14 15/16"	23 7/16"	1 1/4"	D1W 722436N	838.	918.	1,005.	1,246.

w* = nominal width

A and B = straight edge length

Dimensions listed under 1, 2 and 3 are actual to nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Worksurfaces	Worksurfaces	Worksurfaces	Worksurfaces
1. Pattern Number	<i>Example:</i> D1R 6030N, 114, 114	Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.	- Center-Located Edge Grommet - Woodgrain ABS edge - Metal edge - Techwood edge
2. Top Finish Type	D1R Pattern Number		
3. Edge Finish	6030N		
	114 Folkstone Grey Laminate		To specify edge grommet, replace the "N" suffix from the pattern number with "G". Add \$19.
	114 Folkstone Grey Edge Band		

description	w*	w	depth left	depth right	t	pattern no.	laminate w/ ABS edge	laminate w/ woodgrain edge	laminate w/ metal edge	techwood w/ techwood edge
Smooth Wave 	48"	47 13/16"	17 1/2"	23 1/2"	1 1/4"	D1W S481824N	\$633.	\$700.	\$765.	\$1,107.
	48"	47 13/16"	17 1/2"	29 1/2"	1 1/4"	D1W S481830N	633.	700.	765.	1,110.
	48"	47 13/16"	23 1/2"	17 1/2"	1 1/4"	D1W S482418N	633.	700.	765.	1,118.
	48"	47 13/16"	23 1/2"	29 1/2"	1 1/4"	D1W S482430N	633.	700.	765.	1,121.
	48"	47 13/16"	29 1/2"	17 1/2"	1 1/4"	D1W S483018N	633.	700.	765.	1,126.
	48"	47 13/16"	29 1/2"	23 1/2"	1 1/4"	D1W S483024N	633.	700.	765.	1,130.
	60"	59 13/16"	17 1/2"	23 1/2"	1 1/4"	D1W S601824N	737.	810.	882.	1,135.
	60"	59 13/16"	17 1/2"	29 1/2"	1 1/4"	D1W S601830N	737.	810.	882.	1,139.
	60"	59 13/16"	23 1/2"	17 1/2"	1 1/4"	D1W S602418N	737.	810.	882.	1,144.
	60"	59 13/16"	23 1/2"	29 1/2"	1 1/4"	D1W S602430N	737.	810.	882.	1,150.
	60"	59 13/16"	29 1/2"	17 1/2"	1 1/4"	D1W S603018N	737.	810.	882.	1,157.
	60"	59 13/16"	29 1/2"	23 1/2"	1 1/4"	D1W S603024N	737.	810.	882.	1,161.
	66"	65 13/16"	17 1/2"	23 1/2"	1 1/4"	D1W S661824N	788.	867.	947.	1,165.
	66"	65 13/16"	17 1/2"	29 1/2"	1 1/4"	D1W S661830N	788.	867.	947.	1,168.
	66"	65 13/16"	23 1/2"	17 1/2"	1 1/4"	D1W S662418N	788.	867.	947.	1,174.
	66"	65 13/16"	23 1/2"	29 1/2"	1 1/4"	D1W S662430N	788.	867.	947.	1,179.
	66"	65 13/16"	29 1/2"	17 1/2"	1 1/4"	D1W S663018N	788.	867.	947.	1,185.
	66"	65 13/16"	29 1/2"	23 1/2"	1 1/4"	D1W S663024N	788.	867.	947.	1,188.
	72"	71 13/16"	17 1/2"	23 1/2"	1 1/4"	D1W S721824N	838.	918.	1,005.	1,193.
	72"	71 13/16"	17 1/2"	29 1/2"	1 1/4"	D1W S721830N	838.	918.	1,005.	1,197.
	72"	71 13/16"	23 1/2"	17 1/2"	1 1/4"	D1W S722418N	838.	918.	1,005.	1,204.
	72"	71 13/16"	23 1/2"	29 1/2"	1 1/4"	D1W S722430N	838.	918.	1,005.	1,213.
	72"	71 13/16"	29 1/2"	17 1/2"	1 1/4"	D1W S723018N	838.	918.	1,005.	1,218.
	72"	71 13/16"	29 1/2"	23 1/2"	1 1/4"	D1W S723024N	838.	918.	1,005.	1,221.
	78"	77 13/16"	17 1/2"	23 1/2"	1 1/4"	D1W S781824N	884.	976.	1,063.	1,226.
	78"	77 13/16"	17 1/2"	29 1/2"	1 1/4"	D1W S781830N	884.	976.	1,063.	1,228.
	78"	77 13/16"	23 1/2"	17 1/2"	1 1/4"	D1W S782418N	884.	976.	1,063.	1,229.
	78"	77 13/16"	23 1/2"	29 1/2"	1 1/4"	D1W S782430N	884.	976.	1,063.	1,235.
	78"	77 13/16"	29 1/2"	17 1/2"	1 1/4"	D1W S783018N	884.	976.	1,063.	1,240.
	78"	77 13/16"	29 1/2"	23 1/2"	1 1/4"	D1W S783024N	884.	976.	1,063.	1,245.
	84"	83 13/16"	17 1/2"	23 1/2"	1 1/4"	D1W S841824N	938.	1,029.	1,124.	1,248.
	84"	83 13/16"	17 1/2"	29 1/2"	1 1/4"	D1W S841830N	938.	1,029.	1,124.	1,254.
	84"	83 13/16"	23 1/2"	17 1/2"	1 1/4"	D1W S842418N	938.	1,029.	1,124.	1,261.
	84"	83 13/16"	23 1/2"	29 1/2"	1 1/4"	D1W S842430N	938.	1,029.	1,124.	1,265.
	84"	83 13/16"	29 1/2"	17 1/2"	1 1/4"	D1W S843018N	938.	1,029.	1,124.	1,269.
	84"	83 13/16"	29 1/2"	23 1/2"	1 1/4"	D1W S843024N	938.	1,029.	1,124.	1,275.

Ordering Information

Worksurfaces

1. Pattern Number
2. Top Finish Type
3. Edge Finish

Order Code

Worksurfaces

Example: **D1R 6030N, 114, 114**

D1W	Dividends Worksurface
S	Smooth Wave Shape
72	Overall width in inches
30	Nominal depth at user's left side
24	Nominal depth at user's right side
N	No grommet
114	Folkstone Grey Laminate
114	Folkstone Grey Edge Band

Included with:

Worksurfaces

Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.

Options

Worksurfaces

- 1 Center-Located Edge Grommets
- Woodgrain ABS edge
- Metal edge
- Techwood edge

To specify edge grommets, replace the "N" suffix from the pattern number with a "G".

Add \$29

This page intentionally left blank

Faceted Worksurfaces

20, 24 and 30 Deep Specifications

Dividends Horizon

Faceted Worksurfaces

Dividends Horizon Faceted Worksurfaces make the most of compact workspaces with their Outward Facing Design and layered approach that defines active, secondary and collaborative work zones.

Planning with Faceted Worksurfaces

Dividends Horizon Faceted Worksurfaces require three unique components to complete the installation:

1. Layered Cantilever Assembly: DBVDC(L) (R) supports both Primary Faceted and the Secondary Faceted Worksurface.

Note: the Faceted Worksurfaces and the Layered Cantilever Assemblies are handed. Specify the same hand Layered Cantilever Assembly as the Primary Faceted Worksurface.

2. 2.5" Column Support: DBSCR, supports both the Primary Faceted and Bench Faceted Worksurfaces at their widest end. The 2.5" Column Support adjusts from the top, beneath the worksurface, creating a more refined aesthetic.

3. Satellite Support Assembly: DSSA(C) (R), is available in two shapes, Circular or Soft Rectangle and clamps to the edge of either the Primary or Bench Faceted Worksurface at their widest end.

The Satellite Support Assembly comes in two parts: the Satellite Mechanism and the Satellite Top. The Satellite Mechanism is available in all core paint finishes. The Satellite Top is powder coated MDF and available in three colors: Brilliant Blue (135), Honey Yellow (136) and Ruby Red (137).


The Satellite Mechanism is approximately 2.5" wide and raises the Satellite Top 3" above the worksurface. The Circular Satellite Top is approximately 16" in diameter and the Soft Rectangle Satellite Top is approximately 16" x 18".

Available Sizes


- Faceted Primary
Depths: 24"/18" and 30"/19"
Widths: 60" to 96"
- Faceted Secondary
Depths 20"/12"
Widths 60" to 96"
- Faceted Bench
Depths 24"/18" and 30"/19"
Widths: 60" to 96"

Panel-Hung Applications


When a worksurface spans multiple panels a cantilever or freestanding support is required every 48" of width.



Faceted Primary Worksurface



Faceted Secondary Worksurface



Faceted Bench Worksurface

Faceted Sizes Available

Faceted Primary


24"D	30"D
60"	60"
66"	66"
72"	72"
84"	84"
90"	90"
96"	96"

Faceted Secondary


20"D
60"
66"
72"
84"
90"
96"

Faceted Bench

24"D	30"D
60"	60"
66"	66"
72"	72"
84"	84"
90"	90"
96"	96"



Primary Faceted Worksurface with Secondary Faceted Worksurface, Satellite Assembly and 2.5" Column Support



Faceted Bench Worksurface with Satellite Assembly, 2.5" Column Support and Anchor Credenza

*Faceted Primary and Secondary Worksurfaces***Faceted Primary and Secondary Worksurfaces**

Dividends Horizon Faceted Primary and Secondary worksurfaces are layered perpendicularly and used in panel hung applications

Available Sizes (Primary)

Faceted Primary worksurfaces have an Outward Facing Design and are handed with one side deeper than the other.

- Depths: 24"/18" and 30"/19"
- Widths: 60" to 96"

Available Sizes (Secondary)

Faceted Secondary worksurfaces are handed with one end deeper than another.

- Depths: 20"/12"
- Widths: 60" to 96"

Note: end with the greatest depth determines handedness

Faceted Worksurface Applications

Primary Faceted worksurfaces are designed to be used with the Secondary Faceted worksurfaces as a return. The Secondary surface mounts beneath with Primary surface using the Layered Cantilever Assembly DBVDC(L) left DBVDC(R) right.

Faceted Bench Worksurface Applications

Faceted Bench worksurfaces are designed to be used with a credenza as a return. The shallow end of the Faceted Bench Worksurface is supported by a Crendeza Spacer, BW1CSB.

Primary Faceted Worksurface Support

Primary Faceted worksurfaces are supported by a panel-to-worksurface bracket at the deepest end and the Layered Cantilever Assembly at the shallow end. The Column Support (DBSCR) is also used to support the worksurface.

72" wide worksurfaces always require either a mid-span cantilever support or worksurface reinforcement strap (DB1WR72).

Storage Support Applications

Faceted Primary and Secondary Worksurfaces can be supported (on the shallow end) by Anchor Storage Lockers using L-bracket WLLB.

Recommended Pedestal Depths





Dividends Horizon Faceted Worksurfaces are primarily used with mobile pedestals which can double as guest seating.

Faceted Secondary surfaces are designed for use with 18" deep mobile pedestals.

Faceted Worksurfaces

Faceted Primary Worksurfaces

Dividends Horizon



description	w*	w	depth left	depth right	t	pattern no.	Laminate ABS edge band
24" Deep Primary Desk, Left Hand 	60"	59 ¹⁵ / ₁₆ "	23 ¹ / ₂ "	17 ¹ / ₂ "	1 ¹ / ₄ "	DVDP6024LN	\$734.
	66"	65 ¹⁵ / ₁₆ "	23 ¹ / ₂ "	17 ¹ / ₂ "	1 ¹ / ₄ "	DVDP6624LN	781.
	72"	71 ¹⁵ / ₁₆ "	23 ¹ / ₂ "	17 ¹ / ₂ "	1 ¹ / ₄ "	DVDP7224LN	829.
	78"	77 ¹⁵ / ₁₆ "	23 ¹ / ₂ "	17 ¹ / ₂ "	1 ¹ / ₄ "	DVDP7824LN	876.
	84"	83 ¹⁵ / ₁₆ "	23 ¹ / ₂ "	17 ¹ / ₂ "	1 ¹ / ₄ "	DVDP8424LN	923.
	90"	89 ¹⁵ / ₁₆ "	23 ¹ / ₂ "	17 ¹ / ₂ "	1 ¹ / ₄ "	DVDP9024LN	971.
	96"	95 ¹⁵ / ₁₆ "	23 ¹ / ₂ "	17 ¹ / ₂ "	1 ¹ / ₄ "	DVDP9624LN	1,017.
24" Deep Primary Desk, Right Hand 	60"	59 ¹⁵ / ₁₆ "	17 ¹ / ₂ "	23 ¹ / ₂ "	1 ¹ / ₄ "	DVDP6024RN	734.
	66"	65 ¹⁵ / ₁₆ "	17 ¹ / ₂ "	23 ¹ / ₂ "	1 ¹ / ₄ "	DVDP6624RN	781.
	72"	71 ¹⁵ / ₁₆ "	17 ¹ / ₂ "	23 ¹ / ₂ "	1 ¹ / ₄ "	DVDP7224RN	829.
	78"	77 ¹⁵ / ₁₆ "	17 ¹ / ₂ "	23 ¹ / ₂ "	1 ¹ / ₄ "	DVDP7824RN	876.
	84"	83 ¹⁵ / ₁₆ "	17 ¹ / ₂ "	23 ¹ / ₂ "	1 ¹ / ₄ "	DVDP8424RN	923.
	90"	89 ¹⁵ / ₁₆ "	17 ¹ / ₂ "	23 ¹ / ₂ "	1 ¹ / ₄ "	DVDP9024RN	971.
	96"	95 ¹⁵ / ₁₆ "	17 ¹ / ₂ "	23 ¹ / ₂ "	1 ¹ / ₄ "	DVDP9624RN	1,017.
30" Deep Primary Desk, Left Hand 	60"	59 ¹⁵ / ₁₆ "	29 ¹ / ₂ "	19 ¹ / ₁₆ "	1 ¹ / ₄ "	DVDP6030LN	745.
	66"	65 ¹⁵ / ₁₆ "	29 ¹ / ₂ "	19 ¹ / ₁₆ "	1 ¹ / ₄ "	DVDP6630LN	793.
	72"	71 ¹⁵ / ₁₆ "	29 ¹ / ₂ "	19 ¹ / ₁₆ "	1 ¹ / ₄ "	DVDP7230LN	840.
	78"	77 ¹⁵ / ₁₆ "	29 ¹ / ₂ "	19 ¹ / ₁₆ "	1 ¹ / ₄ "	DVDP7830LN	886.
	84"	83 ¹⁵ / ₁₆ "	29 ¹ / ₂ "	19 ¹ / ₁₆ "	1 ¹ / ₄ "	DVDP8430LN	934.
	90"	89 ¹⁵ / ₁₆ "	29 ¹ / ₂ "	19 ¹ / ₁₆ "	1 ¹ / ₄ "	DVDP9030LN	981.
	96"	95 ¹⁵ / ₁₆ "	29 ¹ / ₂ "	19 ¹ / ₁₆ "	1 ¹ / ₄ "	DVDP9630LN	1,028.
30" Deep Primary Desk, Right Hand 	60"	59 ¹⁵ / ₁₆ "	19 ¹ / ₁₆ "	29 ¹ / ₂ "	1 ¹ / ₄ "	DVDP6030RN	745.
	66"	65 ¹⁵ / ₁₆ "	19 ¹ / ₁₆ "	29 ¹ / ₂ "	1 ¹ / ₄ "	DVDP6630RN	793.
	72"	71 ¹⁵ / ₁₆ "	19 ¹ / ₁₆ "	29 ¹ / ₂ "	1 ¹ / ₄ "	DVDP7230RN	840.
	78"	77 ¹⁵ / ₁₆ "	19 ¹ / ₁₆ "	29 ¹ / ₂ "	1 ¹ / ₄ "	DVDP7830RN	886.
	84"	83 ¹⁵ / ₁₆ "	19 ¹ / ₁₆ "	29 ¹ / ₂ "	1 ¹ / ₄ "	DVDP8430RN	934.
	90"	89 ¹⁵ / ₁₆ "	19 ¹ / ₁₆ "	29 ¹ / ₂ "	1 ¹ / ₄ "	DVDP9030RN	981.
	96"	95 ¹⁵ / ₁₆ "	19 ¹ / ₁₆ "	29 ¹ / ₂ "	1 ¹ / ₄ "	DVDP9630RN	1,028.

Ordering Information	Order Code	Included With	Options
Worksurfaces 1. Pattern Number 2. Top Finish Type 3. Edge Finish	Worksurfaces <i>Example:</i> DVDP7230LN114114 DVD Dividends Worksurface P Primary, Faceted 72 Overall width in inches 30 Overall Depth in inches L Left or Right handed N No grommet 114 Folkstone Grey Laminate 114 Folkstone Grey Edge Band	Worksurfaces Note: Faceted worksurfaces available in standard laminates only.	

Faceted Worksurfaces

Faceted Secondary Worksurfaces

Dividends Horizon

description	w*	w	depth left	depth right	t	pattern no.	Laminate ABS edge band
20" Deep Secondary Desk, Left Hand 	60"	59 ^{15/16"}	19 ^{1/16"}	11 ^{1/2"}	1 ^{1/4"}	DVDS6020LN	\$592.
	66"	65 ^{15/16"}	19 ^{1/16"}	11 ^{1/2"}	1 ^{1/4"}	DVDS6620LN	639.
	72"	71 ^{15/16"}	19 ^{1/16"}	11 ^{1/2"}	1 ^{1/4"}	DVDS7220LN	687.
	78"	77 ^{15/16"}	19 ^{1/16"}	11 ^{1/2"}	1 ^{1/4"}	DVDS7820LN	734.
	84"	83 ^{15/16"}	19 ^{1/16"}	11 ^{1/2"}	1 ^{1/4"}	DVDS8420LN	781.
	90"	89 ^{15/16"}	19 ^{1/16"}	11 ^{1/2"}	1 ^{1/4"}	DVDS9020LN	829.
	96"	95 ^{15/16"}	19 ^{1/16"}	11 ^{1/2"}	1 ^{1/4"}	DVDS9620LN	876.
20" Deep Secondary Desk, Right Hand 	60"	59 ^{15/16"}	11 ^{1/2"}	19 ^{1/16"}	1 ^{1/4"}	DVDS6020RN	592.
	66"	65 ^{15/16"}	11 ^{1/2"}	19 ^{1/16"}	1 ^{1/4"}	DVDS6620RN	639.
	72"	71 ^{15/16"}	11 ^{1/2"}	19 ^{1/16"}	1 ^{1/4"}	DVDS7220RN	687.
	78"	77 ^{15/16"}	11 ^{1/2"}	19 ^{1/16"}	1 ^{1/4"}	DVDS7820RN	734.
	84"	83 ^{15/16"}	11 ^{1/2"}	19 ^{1/16"}	1 ^{1/4"}	DVDS8420RN	781.
	90"	89 ^{15/16"}	11 ^{1/2"}	19 ^{1/16"}	1 ^{1/4"}	DVDS9020RN	829.
	96"	95 ^{15/16"}	11 ^{1/2"}	19 ^{1/16"}	1 ^{1/4"}	DVDS9620RN	876.

Ordering Information

Worksurfaces

1. Pattern Number
2. Top Finish Type
3. Edge Finish

Order Code

Worksurfaces

<i>Example:</i>	DVDS6020LN, 114, 114
DVD	Dividends Worksurface
S	Secondary, Faceted
60	Overall width in inches
20	Overall depth in inches
L	Left or Right handed
N	No grommet
114	Folkstone Grey Laminate
114	Folkstone Grey Edge Band

Included With

Worksurfaces

Note: Faceted worksurfaces available in standard laminates only.

Options

Faceted Bench Worksurfaces

Dividends Horizon Faceted Bench worksurfaces are used primarily as a primary worksurface in Bench applications or as a primary worksurface in panel hung applications with a return.

Available Sizes

Faceted Bench worksurfaces have an Outward Facing Design and are handed with one side deeper than the other.

- Depths: 24"/18" and 30"/19"
- Widths: 60" to 96"

Note: end with the greatest depth determines handedness

Faceted Bench Worksurface Applications

Faceted Bench worksurfaces are designed to be used with either a storage element as a return or a rectilinear surface mounted beneath with Primary surface using the Layered Cantilever Assembly DBVDC(L or R)

Faceted Bench Worksurface Support

Primary Faceted worksurfaces are supported by a panel-to-worksurface bracket at the deepest end and either an 18" Cantilever or the Layered Cantilever Assembly at the shallow end. The Column Support (DBSCR) is also used to support the worksurface. See image below.

72" wide worksurfaces always require either a mid-span cantilever support or a worksurface reinforcement strap (DB1WR72).

Storage Support Applications

Faceted Bench Worksurfaces can be supported on the shallow end with a Credenza Spacer (BW1CSB) and Crendeza or by Anchor Storage Lockers using L-bracket WLLB.





Recommended Pedestal Depths

Dividends Horizon Faceted Bench Worksurfaces are primarily used with mobile pedestals which can double as guest seating.

Faceted Worksurfaces

Faceted Bench Worksurfaces

Dividends Horizon

description	w*	w	depth left	depth right	t	pattern no.	Laminate ABS edge band
24" Deep Faceted Bench, Left Hand 	60"	59 ¹⁵ / ₁₆ "	23 1/2"	17 1/2"	1 1/4"	DVDB6024LN	\$734.
	66"	65 ¹⁵ / ₁₆ "	23 1/2"	17 1/2"	1 1/4"	DVDB6624LN	781.
	72"	71 ¹⁵ / ₁₆ "	23 1/2"	17 1/2"	1 1/4"	DVDB7224LN	829.
	78"	77 ¹⁵ / ₁₆ "	23 1/2"	17 1/2"	1 1/4"	DVDB7824LN	876.
	84"	83 ¹⁵ / ₁₆ "	23 1/2"	17 1/2"	1 1/4"	DVDB8424LN	923.
	90"	89 ¹⁵ / ₁₆ "	23 1/2"	17 1/2"	1 1/4"	DVDB9024LN	971.
	96"	95 ¹⁵ / ₁₆ "	23 1/2"	17 1/2"	1 1/4"	DVDB9624LN	1,017.
24" Deep Faceted Bench, Right Hand 	60"	59 ¹⁵ / ₁₆ "	17 1/2"	23 1/2"	1 1/4"	DVDB6024RN	734.
	66"	65 ¹⁵ / ₁₆ "	17 1/2"	23 1/2"	1 1/4"	DVDB6624RN	781.
	72"	71 ¹⁵ / ₁₆ "	17 1/2"	23 1/2"	1 1/4"	DVDB7224RN	829.
	78"	77 ¹⁵ / ₁₆ "	17 1/2"	23 1/2"	1 1/4"	DVDB7824RN	876.
	84"	83 ¹⁵ / ₁₆ "	17 1/2"	23 1/2"	1 1/4"	DVDB8424RN	923.
	90"	89 ¹⁵ / ₁₆ "	17 1/2"	23 1/2"	1 1/4"	DVDB9024RN	971.
	96"	95 ¹⁵ / ₁₆ "	17 1/2"	23 1/2"	1 1/4"	DVDB9624RN	1,017.
30" Deep Faceted Bench, Left Hand 	60"	59 ¹⁵ / ₁₆ "	29 1/2"	19 1/16"	1 1/4"	DVDB6030LN	745.
	66"	65 ¹⁵ / ₁₆ "	29 1/2"	19 1/16"	1 1/4"	DVDB6630LN	793.
	72"	71 ¹⁵ / ₁₆ "	29 1/2"	19 1/16"	1 1/4"	DVDB7230LN	840.
	78"	77 ¹⁵ / ₁₆ "	29 1/2"	19 1/16"	1 1/4"	DVDB7830LN	886.
	84"	83 ¹⁵ / ₁₆ "	29 1/2"	19 1/16"	1 1/4"	DVDB8430LN	934.
	90"	89 ¹⁵ / ₁₆ "	29 1/2"	19 1/16"	1 1/4"	DVDB9030LN	981.
	96"	95 ¹⁵ / ₁₆ "	29 1/2"	19 1/16"	1 1/4"	DVDB9630LN	1,028.
30" Deep Faceted Bench, Right Hand 	60"	59 ¹⁵ / ₁₆ "	19 1/16"	29 1/2"	1 1/4"	DVDB6030RN	745.
	66"	65 ¹⁵ / ₁₆ "	19 1/16"	29 1/2"	1 1/4"	DVDB6630RN	793.
	72"	71 ¹⁵ / ₁₆ "	19 1/16"	29 1/2"	1 1/4"	DVDB7230RN	840.
	78"	77 ¹⁵ / ₁₆ "	19 1/16"	29 1/2"	1 1/4"	DVDB7830RN	886.
	84"	83 ¹⁵ / ₁₆ "	19 1/16"	29 1/2"	1 1/4"	DVDB8430RN	934.
	90"	89 ¹⁵ / ₁₆ "	19 1/16"	29 1/2"	1 1/4"	DVDB9030RN	981.
	96"	95 ¹⁵ / ₁₆ "	19 1/16"	29 1/2"	1 1/4"	DVDB9630RN	1,028.

Ordering Information

Worksurfaces

1. Pattern Number
2. Top Finish Type
3. Edge Finish

Order Code

Worksurfaces


<i>Example:</i>	DVDB6024LN,114,114
DVD	Dividends Worksurface
B	Faceted, Bench
60	Overall width in inches
24	Overall depth in inches
L	Left or right handed
N	No grommet
114	Folkstone Grey Laminate
114	Folkstone Grey Edge Band

Included With

Worksurfaces

Note: Faceted worksurfaces available in standard laminates only.

Options

description	w*	w	depth left	depth right	t	pattern no.	laminate w/ ABS edge	laminate w/ woodgrain edge	laminate w/ metal edge	techwood w/ techwood edge
Trapezoidal 	48"	47 ¹³ / ₁₆ "	23 ¹ / ₂ "	29 ¹ / ₂ "	1 ¹ / ₄ "	D1W T482430N	\$633.	\$700.	\$765.	\$793.
	48"	47 ¹³ / ₁₆ "	29 ¹ / ₂ "	23 ¹ / ₂ "	1 ¹ / ₄ "	D1W T483024N	633.	700.	765.	793.
	60"	59 ¹³ / ₁₆ "	23 ¹ / ₂ "	29 ¹ / ₂ "	1 ¹ / ₄ "	D1W T602430N	737.	810.	882.	838.
	60"	59 ¹³ / ₁₆ "	29 ¹ / ₂ "	23 ¹ / ₂ "	1 ¹ / ₄ "	D1W T603024N	737.	810.	882.	838.
	66"	65 ¹³ / ₁₆ "	23 ¹ / ₂ "	29 ¹ / ₂ "	1 ¹ / ₄ "	D1W T662430N	788.	867.	947.	880.
	66"	65 ¹³ / ₁₆ "	29 ¹ / ₂ "	23 ¹ / ₂ "	1 ¹ / ₄ "	D1W T663024N	788.	867.	947.	880.
	72"	71 ¹³ / ₁₆ "	23 ¹ / ₂ "	29 ¹ / ₂ "	1 ¹ / ₄ "	D1W T722430N	838.	918.	1,005.	925.
	72"	71 ¹³ / ₁₆ "	29 ¹ / ₂ "	23 ¹ / ₂ "	1 ¹ / ₄ "	D1W T723024N	838.	918.	1,005.	925.

Ordering Information

Worksurfaces

1. Pattern Number
2. Top Finish Type
3. Edge Finish

Order Code

Worksurfaces

<i>Example:</i> D1W T482430N	
D1W	Dividends Worksurface
T	Trapezoidal Shape
48	Overall Width, inches
24	Nominal depth at user's left side
30	Nominal depth at user's right side
N	No grommet
114	Folkstone Grey Laminate
114	Folkstone Grey Edge Band

Included with:

Worksurface

Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.

Options

Worksurfaces

- 1 Center-Located Edge Grommets
- Woodgrain ABS edge
- Metal edge
- Techwood edge

To specify edge grommets replace the "N" suffix from the pattern number with a "G".
Add \$29.

This page intentionally left blank

Corner Worksurfaces

Rectilinear and Split Top Corner Specifications

Dividends Horizon

Rectilinear Corner Worksurfaces

Dividends Horizon rectilinear corner worksurfaces are used in panel-hung and freestanding applications.

Split Top Corner Worksurfaces

Split top corner worksurfaces allow for height and angle adjustment on the front work surface.

The depth of the front keyboard work surface is 10 ⁵/₈". The front surface adjusts from a - 5 ³/₄" below the work surface to a + 7" above. The mechanism has a tilt feature of ±10 degrees.

Included with the split top work surface is the back corner work surface, the front corner work surface, the split top mechanism, one rear corner panel-to-work surface bracket and two flat brackets for attachment to return work surfaces. Cantilevers must be ordered separately and are specified to the size return

work surface depth (i.e 24" cantilevers for 24" deep return work surfaces). Panel-mounted C-leg or Open Leg work surface supports may be used in place of cantilevers.

Available Sizes

- Widths: 36", 42" and 48"
- Returns: 18", 24" and 30"
- Thickness: 1 ¹/₄"

Corner Worksurface Support

Corner worksurfaces must be supported by cantilevers at each end and a panel-to-work surface bracket at the rear corner. Panel-mounted C-leg or Open Leg work surface supports may be used instead of cantilevers for corner work surface support. Cantilevers and panel-mounted C-leg or Open Leg supports are ordered separately. Panel-to-work surface bracket is included.


Corner Worksurface Applications

Corner worksurfaces attach to adjacent work surfaces with cantilevers and flat brackets. Suggested applications are illustrated below.


Note: All dimensions are nominal except for front edge dimension.

Note: Series 3 overdesk units are not compatible with corner work surfaces.


Rectilinear Corner Worksurface




Rectilinear Split-Top Corner Worksurface




Rectilinear and Split Top Corner Worksurface Sizes Available



Corner Worksurface Support



Corner Worksurface Applications



** Requires a return panel, panel-mounted C-leg or Open Leg support or a pedestal with a panel-to-work surface bracket for support.

Corner Worksurfaces

Rectilinear and Split Top Corner

Mixed Depths

Dividends Horizon

description	1	2	3	4	t	pattern no.	laminate w/ ABS edge	laminate w/ woodgrain edge	laminate w/ metal edge	techwood w/ techwood edge
Rectilinear Corner Worksurface No Grommets	36"	36"	18"	18"	1 1/4"	D1C 3618N	\$486.	\$532.	\$581.	\$983.
	36"	36"	24"	24"	1 1/4"	D1C 3624N	494.	547.	593.	1,077.
	42"	42"	24"	24"	1 1/4"	D1C 4224N	557.	613.	665.	1,167.
	48"	48"	24"	24"	1 1/4"	D1C 4824N	634.	701.	766.	1,262.
	48"	48"	30"	30"	1 1/4"	D1C 4830N	657.	721.	788.	1,354.
Rectilinear Corner Worksurface. 24" Deep	42"	42"	24"	30"	1 1/4"	D1C 422430N	582.	641.	700.	1,269.
Return Left 30" Deep Return Right No Grommets	48"	48"	24"	30"	1 1/4"	D1C 482430N	661.	728.	796.	1,354.
										
Rectilinear Corner Worksurface. 30" Deep	42"	42"	30"	24"	1 1/4"	D1C 423024N	582.	641.	700.	1,269.
Return Left 24" Deep Return Right No Grommets	48"	48"	30"	24"	1 1/4"	D1C 483024N	661.	728.	796.	1,354.
										
Split Top Corner Worksurface No Grommets	42"	42"	24"	24"	1 1/4"	D1CS 4224N	1,979.	2,174.	2,373.	3,362.
	48"	48"	24"	24"	1 1/4"	D1CS 4824N	2,036.	2,237.	2,442.	3,473.
	48"	48"	30"	30"	1 1/4"	D1CS 4830N	2,049.	2,254.	2,462.	3,586.

Note: Above 1, 2, 3, and 4 dimensions are all nominal
Actual dimensions are 1/2" less than shown above.

Ordering Information	Order Code	Included with:	Options
Worksurfaces	Worksurfaces	Worksurfaces	Worksurfaces
1. Pattern Number	<i>Example:</i> D1C 423024N, 117, 115	• Worksurface	• 2 Center-Located Edge Grommets
2. Top Finish Type	D1C Pattern Number	• Panel-to-Worksurface Bracket	• Woodgrain PVC edge
3. Edge Finish	423024N	Split Top Corner Worksurfaces	• Metal edge
Split Top Corner Worksurfaces	117 Soft Grey Laminate	• Front Worksurface	• Techwood edge
1. Pattern Number	115 Medium Grey Edge Band	• Back Worksurface	To specify edge grommets, replace the "N" suffix from the pattern number with a "G".
2. Top Finish Type	Split Top Corner Worksurfaces	• Split Top Mechanism	Add \$29
3. Edge Finish	<i>Example:</i> D1CS 4224N, 117, 117	• Flat Brackets	Split Top Corner Worksurfaces
	D1CS Pattern Number	• Panel-to-Worksurface Bracket	• 2 Center-Located Edge Grommets
	4224N	Note: When wood grain or brushed laminates are specified on corner worksurfaces where side 1 and 2 are of equal length, one of three grain direction options must be specified. Insert the desired grain direction option (L,R or D) after the laminate code. Please add \$26 to the list price for diagonal grain (D) selection.	• Woodgrain PVC edge
	117 Soft Grey Laminate	Note: Techwood corner worksurfaces with the same dimension on side 1 and side 2 have a diagonal grain direction. See grain direction page for more information.	• Metal edge
	117 Soft Grey Edge Band	Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.	• Techwood edge

Corner Worksurfaces

Curvilinear Corner "L" Shape - 24" Depths Specifications

Dividends Horizon

Curvilinear Corner L Shape Worksurfaces

Dividends Horizon curvilinear corner "L" shape worksurfaces are specified for panel-hung applications only and provide a continuous flow when used in conjunction with other curvilinear worksurfaces.

Curvilinear Corner Worksurface Support

Curvilinear corner "L" shape worksurfaces must be supported by cantilevers at each end and a panel-to-worksurface bracket at the rear corner. Panel-mounted C-leg or open leg worksurface supports may be used instead of cantilevers for corner worksurface support.

Cantilevers, panel-mounted c-leg and open support legs are ordered separately. A panel-to-worksurface bracket is included.


Note: Worksurfaces greater than 48" wide require an additional mid-span cantilever support along the 60" or 72" side.

Note: A pedestal, panel-mounted C-leg or Open Leg Support can be substituted for a cantilever in the following locations:


- The long end of 60" and 72" wide curvilinear "L" shape corner worksurfaces

Note: Series 3 overdesk units are not compatible with corner worksurfaces.




Curvilinear Corner Worksurface





Curvilinear Corner "L" Shape Worksurface



Curvilinear Corner Worksurface Support Options



Curvilinear Corner Worksurface Applications





** Requires a return panel or pedestal/panel-mounted C-leg or Open Support Leg with panel-to-worksurface bracket for support

Corner Worksurfaces

Curvilinear Corner “L” Shape - 24” Depths

24” Depths

Dividends Horizon

description	1	2	3	4	t	pattern no.	laminates w/ ABS edge	laminates w/ woodgrain edge	laminates w/ metal edge	techwood w/ techwood edge
Curvilinear Corner “L” Shape Worksurface 24” Deep Returns Left and Right	36”	36”	24”	24”	1 1/4”	D1L 3636SSN	\$526.	\$578.	\$630.	\$1,215.
	36”	48”	24”	24”	1 1/4”	D1L 3648SSN	546.	607.	655.	1,327.
	36”	54”	24”	24”	1 1/4”	D1L 3654SSN	643.	709.	774.	1,369.
	36”	60”	24”	24”	1 1/4”	D1L 3660SSN	863.	961.	1,031.	1,352.
	36”	72”	24”	24”	1 1/4”	D1L 3672SSN	918.	1,013.	1,112.	1,579.
	36”	78”	24”	24”	1 1/4”	D1L 3678SSN	928.	1,032.	1,121.	1,674.
	42”	42”	24”	24”	1 1/4”	D1L 4242SSN	632.	699.	764.	1,288.
	42”	48”	24”	24”	1 1/4”	D1L 4248SSN	702.	778.	844.	1,388.
	42”	54”	24”	24”	1 1/4”	D1L 4254SSN	712.	794.	856.	1,408.
	42”	60”	24”	24”	1 1/4”	D1L 4260SSN	873.	960.	1,049.	1,437.
	42”	66”	24”	24”	1 1/4”	D1L 4266SSN	896.	993.	1,078.	1,475.
	42”	72”	24”	24”	1 1/4”	D1L 4272SSN	930.	1,023.	1,119.	1,549.
	42”	78”	24”	24”	1 1/4”	D1L 4278SSN	940.	1,034.	1,129.	1,621.
	42”	84”	24”	24”	1 1/4”	D1L 4284SSN	1,005.	1,054.	1,121.	1,621.
	48”	36”	24”	24”	1 1/4”	D1L 4836SSN	546.	607.	656.	1,328.
	48”	42”	24”	24”	1 1/4”	D1L 4842SSN	702.	778.	835.	1,390.
	48”	48”	24”	24”	1 1/4”	D1L 4848SSN	712.	788.	854.	1,360.
	48”	54”	24”	24”	1 1/4”	D1L 4854SSN	781.	863.	1,019.	1,481.
	48”	60”	24”	24”	1 1/4”	D1L 4860SSN	882.	972.	1,058.	1,512.
	48”	66”	24”	24”	1 1/4”	D1L 4866SSN	914.	1,007.	1,095.	1,586.
	48”	72”	24”	24”	1 1/4”	D1L 4872SSN	951.	1,043.	1,134.	1,656.
	48”	78”	24”	24”	1 1/4”	D1L 4878SSN	1,049.	1,150.	1,254.	1,694.
	48”	84”	24”	24”	1 1/4”	D1L 4884SSN	1,174.	1,292.	1,411.	1,729.
	48”	96”	24”	24”	1 1/4”	D1L 4896SSN	1,056.	1,098.	1,134.	1,694.
	54”	36”	24”	24”	1 1/4”	D1L 5436SSN	643.	709.	784.	1,337.
	54”	42”	24”	24”	1 1/4”	D1L 5442SSN	712.	794.	856.	1,408.
	54”	48”	24”	24”	1 1/4”	D1L 5448SSN	781.	863.	1,019.	1,481.

Note: Above 1, 2, 3, and 4 dimensions are all nominal
Actual dimensions are 1/2” less than shown above.



Ordering Information	Order Code	Included with:	Options
1. Worksurfaces	Worksurfaces	Worksurfaces	Worksurfaces
2. Pattern Number	<i>Example:</i> D1L 4860SSN, 117, 117	• Worksurface	• 2 center-located edge grommets
3. Top Finish Type	D1L Pattern Number	• Panel-to-Worksurface Bracket	• Woodgrain ABS edge
4. Edge Finish	4860SSN	Note: When wood grain or brushed laminates are specified on corner worksurfaces where side 1 and 2 are of equal length, one of three grain direction options must be specified. Insert the desired grain direction option (L,R or D) after the laminate code. Please add \$26 to the list price for diagonal grain (D) selection.	• Metal edge
	117 Soft Grey laminate		• Techwood
	117 Soft Grey Edge Band	Note: Techwood corner worksurfaces with the same dimension on side 1 and side 2 have a diagonal grain direction. See grain direction page for more information.	To specify edge grommets, replace the “N” suffix from the pattern number with “G” Add \$29
		Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.	Note: Overdesk units are not compatible with corner worksurfaces.

Corner Worksurfaces

Curvilinear Corner “L” Shape - 24” Depths

24” Depths

Dividends Horizon

description	1	2	3	4	t	pattern no.	laminate w/ ABS edge	laminate w/ woodgrain edge	laminate w/ metal edge	techwood w/ techwood edge
Curvilinear Corner “L” Shape Worksurface 24”	60”	36”	24”	24”	1 1/4”	D1L 6036SSN	\$863.	\$962.	\$1,031.	\$1,461.
Deep Returns Left and Right	60”	42”	24”	24”	1 1/4”	D1L 6042SSN	873.	960.	1,049.	1,437.
	60”	48”	24”	24”	1 1/4”	D1L 6048SSN	882.	972.	1,058.	1,512.
	66”	42”	24”	24”	1 1/4”	D1L 6642SSN	896.	993.	1,078.	1,475.
	66”	48”	24”	24”	1 1/4”	D1L 6648SSN	914.	1,007.	1,095.	1,586.
	72”	36”	24”	24”	1 1/4”	D1L 7236SSN	908.	1,013.	1,112.	1,580.
	72”	42”	24”	24”	1 1/4”	D1L 7242SSN	930.	1,023.	1,119.	1,549.
	72”	48”	24”	24”	1 1/4”	D1L 7248SSN	951.	1,043.	1,134.	1,656.
	78”	36”	24”	24”	1 1/4”	D1L 7836SSN	928.	1,032.	1,121.	1,642.
	78”	42”	24”	24”	1 1/4”	D1L 7842SSN	940.	1,034.	1,129.	1,621.
	78”	48”	24”	24”	1 1/4”	D1L 7848SSN	1,049.	1,150.	1,254.	1,694.
	84”	42”	24”	24”	1 1/4”	D1L 8442SSN	1,005.	1,054.	1,127.	1,621.
	84”	48”	24”	24”	1 1/4”	D1L 8448SSN	1,174.	1,292.	1,411.	1,729.
	96”	48”	24”	24”	1 1/4”	D1L 9648SSN	1,056.	1,098.	1,032.	1,695.

Note: Above 1, 2, 3, and 4 dimensions are all nominal
Actual dimensions are 1/2” less than shown above.

Ordering Information	Order Code	Included with:	Options
1. Worksurfaces	Worksurfaces	Worksurfaces	Worksurfaces
2. Pattern Number	<i>Example:</i> D1L 4860SSN, 117, 117	• Worksurface	• 2 center-located edge grommets
3. Top Finish Type	D1L Pattern Number	• Panel-to-Worksurface Bracket	• Woodgrain ABS edge
4. Edge Finish	4860SSN	Note: When wood grain or brushed laminates are specified on corner worksurfaces where side 1 and 2 are of equal length, one of three grain direction options must be specified. Insert the desired grain direction option (L,R or D) after the laminate code. Please add \$26 to the list price for diagonal grain (D) selection.	• Metal edge
	117 Soft Grey laminate	Note: Techwood corner worksurfaces with the same dimension on side 1 and side 2 have a diagonal grain direction. See grain direction page for more information.	• Techwood
	117 Soft Grey Edge Band	Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.	To specify edge grommets, replace the “N” suffix from the pattern number with “G” Add \$29 Note: Overdesk units are not compatible with corner worksurfaces.

This page intentionally left blank

Corner Worksurfaces

Curvilinear Corner "L" shape-Mixed Depths Specifications

Dividends Horizon

Curvilinear Corner "L" Shape Worksurfaces

Dividends Horizon curvilinear corner, "L" shape worksurfaces are specified for panel-hung applications only and provide a continuous flow when used in conjunction with other curvilinear worksurfaces.

Curvilinear Corner Worksurface Support

Curvilinear corner "L" shape worksurfaces must be supported by cantilevers at each end and a panel-to-worksurface bracket at the rear corner. Panel-mounted C-leg or open leg worksurface supports may be used instead of cantilevers for corner worksurface support.

Cantilevers and panel-mounted C-leg or open leg supports are ordered separately. A panel-to-worksurface bracket is included.

Note: 60" and 72" wide curvilinear corners require an additional mid-span cantilever support along the 60" or 72" side.


Note: A pedestal or panel-mounted C-leg can be substituted for a cantilever in the following locations:

- The long end of 60" and 72" wide curvilinear "L" shape corner worksurfaces


Curvilinear Corner Worksurface Applications

Curvilinear "L" shape corner worksurfaces are primarily used with wave end and rectangular worksurface returns.




Curvilinear Corner Worksurface





Curvilinear Corner "L" Shape Worksurface



Curvilinear Corner Worksurface Support Options



Curvilinear Corner Worksurface Applications





** Requires a return panel or pedestal/panel-mounted C-leg or Open Leg Support with panel-to-worksurface bracket for support

Corner Worksurfaces

Curvilinear Corner “L” shape-Mixed Depths

Mixed Depths

Dividends Horizon

description	1	2	3	4	t	pattern no.	laminate w/ ABS edge	laminate w/ woodgrain edge	laminate w/ metal edge	techwood w/ techwood edge
Curvilinear Corner “L” Shape Worksurface. 30” Deep Returns Left and Right	48”	48”	30”	30”	1 1/4”	D1L 4848DDN	\$769.	\$847.	\$920.	\$1,376.
Curvilinear Corner “L” Shape Worksurface 24” Deep Return Left 30” Deep Return Right 	48”	48”	24”	30”	1 1/4”	D1L 4848SDN	761.	837.	912.	1,376.
	48”	60”	24”	30”	1 1/4”	D1L 4860SDN	868.	956.	1,038.	1,413.
	48”	66”	24”	30”	1 1/4”	D1L 4866SDN	911.	1,003.	1,091.	1,447.
	48”	72”	24”	30”	1 1/4”	D1L 4872SDN	956.	1,051.	1,142.	1,484.
	60”	48”	24”	30”	1 1/4”	D1L 6048SDN	850.	934.	1,020.	1,523.
	66”	48”	24”	30”	1 1/4”	D1L 6648SDN	893.	981.	1,076.	1,561.
	72”	48”	24”	30”	1 1/4”	D1L 7248SDN	938.	1,032.	1,126.	1,596.
Curvilinear Corner “L” Shape Worksurface 30” Deep Return Left 24” Deep Return Right 	48”	48”	30”	24”	1 1/4”	D1L 4848DSN	761.	837.	912.	1,376.
	48”	60”	30”	24”	1 1/4”	D1L 4860DSN	850.	934.	1,020.	1,413.
	48”	66”	30”	24”	1 1/4”	D1L 4866DSN	893.	981.	1,076.	1,447.
	48”	72”	30”	24”	1 1/4”	D1L 4872DSN	938.	1,032.	1,126.	1,484.
	60”	48”	30”	24”	1 1/4”	D1L 6048DSN	868.	956.	1,038.	1,523.
	66”	48”	30”	24”	1 1/4”	D1L 6648DSN	911.	1,003.	1,091.	1,561.
	72”	48”	30”	24”	1 1/4”	D1L 7248DSN	956.	1,051.	1,142.	1,596.

Note: Above 1, 2, 3, and 4 dimensions are all nominal
Actual dimensions are 1/2” less than shown above.

Ordering Information	Order Code	Included with:	Options
Worksurfaces	Worksurfaces	Worksurfaces	Worksurfaces
1. Pattern Number	<i>Example:</i> D1L 4860SDN, 117, 117	• Worksurface	• 2 center-located edge grommets
2. Top Finish Type	D1L Pattern Number	• Panel-to-worksurface bracket	• Woodgrain ABS edge
3. Edge Band Finish	4860SDN	Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.	• Metal edge
	117 Soft Grey Laminate		• Techwood
	117 Soft Grey edge band		To specify edge grommets, replace the “N” suffix from the pattern number with “G” Add \$29

Note: An overdesk unit will not align with the width of a corner worksurface due to the 1/2” wire drop gap. The overdesk will be 1/2” too wide.

Peninsula Worksurfaces

"D", "P", "9" and Blended "D"

Specifications

Dividends Horizon

"D", Blended "D", Conferencing, "P" and "9" Shape Peninsula Worksurfaces

Dividends Horizon peninsula worksurfaces mount perpendicular to panels of the same width to provide conferencing area within a workstation.

"D", "P" and "9" tops are supported by panel-to-worksurface brackets on the flat end and a support column, T leg or A leg support at the free end. Adjacent worksurfaces can attach to peninsula tops with flat brackets.

All brackets and supports are ordered separately. "D", "P" and "9" shape peninsula worksurfaces may be used in freestanding applications.

"D" Shaped Peninsula

Available Sizes

- Depths: 24", 30" and 36"
- Widths: 48", 60", 66" and 72"
- Thickness: 1 1/4"

"P" and "9" Shaped Peninsula

Available Sizes

- Depth: 30" panel depth
- Widths: 66", 72" and 78"
- Conferencing diameter: 36" and 42"
- Thickness: 1 1/4"

Blended "D" Peninsula


Available Sizes

- Depths: 48"
- Widths: 72" and 66"
- Thickness: 1 1/4"


Conferencing Worksurfaces

- Depth: 48"
- Width: 60"
- Thickness: 1 1/4"


"D" and "P" Shape Peninsula Worksurfaces



Blended "D" Shape Peninsula Worksurface



Conferencing Worksurface Dimensions




Peninsula Worsurfaces

“D”, “P”, “9” and Blended “D”

Mixed Depths

Dividends Horizon

description	type	w *	w	d	dia.	t	pattern no.	laminate w/ ABS edge	laminate w/ woodgrain edge	laminate w/ metal edge	techwood w/ techwood edge
“D” Peninsula Worksurface Laminate No Grommets 		30"	29 ^{13/16"}	23 ^{13/16"}	1 ^{1/4"}		D1D 3024N	\$428.	\$485.	\$536.	\$1,212.
		30"	29 ^{13/16"}	29 ^{13/16"}	1 ^{1/4"}		D1D 3030N	449.	505.	557.	1,222.
		36"	35 ^{13/16"}	23 ^{13/16"}	1 ^{1/4"}		D1D 3624N	449.	505.	557.	1,222.
		36"	35 ^{13/16"}	29 ^{13/16"}	1 ^{1/4"}		D1D 3630N	469.	513.	577.	1,240.
		48"	47 ^{13/16"}	23 ^{13/16"}	1 ^{1/4"}		D1D 4824N	521.	574.	626.	1,293.
		54"	53 ^{13/16"}	23 ^{13/16"}	1 ^{1/4"}		D1D 5424N	571.	696.	870.	1,348.
		48"	47 ^{13/16"}	29 ^{13/16"}	1 ^{1/4"}		D1D 4830N	574.	630.	692.	1,336.
		54"	53 ^{13/16"}	29 ^{13/16"}	1 ^{1/4"}		D1D 5430N	622.	736.	817.	1,367.
		54"	53 ^{13/16"}	35 ^{13/16"}	1 ^{1/4"}		D1D 5436N	673.	788.	868.	1,379.
		60"	59 ^{13/16"}	23 ^{13/16"}	1 ^{1/4"}		D1D 6024N	675.	791.	873.	1,383.
		60"	59 ^{13/16"}	35 ^{13/16"}	1 ^{1/4"}		D1D 6036N	696.	811.	894.	1,417.
		66"	65 ^{13/16"}	23 ^{13/16"}	1 ^{1/4"}		D1D 6624N	696.	811.	894.	1,417.
		66"	65 ^{13/16"}	35 ^{13/16"}	1 ^{1/4"}		D1D 6636N	716.	832.	914.	1,430.
		60"	59 ^{13/16"}	29 ^{13/16"}	1 ^{1/4"}		D1D 6030N	734.	807.	880.	1,379.
		66"	65 ^{13/16"}	29 ^{13/16"}	1 ^{1/4"}		D1D 6630N	801.	879.	960.	1,423.
		72"	71 ^{13/16"}	23 ^{13/16"}	1 ^{1/4"}		D1D 7224N	806.	908.	990.	1,443.
		78"	77 ^{13/16"}	23 ^{13/16"}	1 ^{1/4"}		D1D 7824N	826.	938.	960.	1,516.
		72"	71 ^{13/16"}	29 ^{13/16"}	1 ^{1/4"}		D1D 7230N	843.	925.	1,011.	1,464.
		78"	77 ^{13/16"}	29 ^{13/16"}	1 ^{1/4"}		D1D 7830N	847.	959.	980.	1,529.
		78"	77 ^{13/16"}	35 ^{13/16"}	1 ^{1/4"}		D1D 7836N	867.	979.	1,001.	1,567.
		84"	83 ^{13/16"}	23 ^{13/16"}	1 ^{1/4"}		D1D 8424N	872.	984.	1,007.	1,618.
		84"	83 ^{13/16"}	29 ^{13/16"}	1 ^{1/4"}		D1D 8430N	893.	1,005.	1,028.	1,663.
		84"	83 ^{13/16"}	35 ^{13/16"}	1 ^{1/4"}		D1D 8436N	914.	1,025.	1,049.	1,688.
		96"	95 ^{13/16"}	23 ^{13/16"}	1 ^{1/4"}		D1D 9624N	915.	1,029.	1,054.	1,694.
		72"	71 ^{13/16"}	35 ^{13/16"}	1 ^{1/4"}		D1D 7236N	920.	1,013.	1,107.	1,509.
		96"	95 ^{13/16"}	29 ^{13/16"}	1 ^{1/4"}		D1D 9630N	936.	1,049.	1,074.	1,722.
		96"	95 ^{13/16"}	35 ^{13/16"}	1 ^{1/4"}		D1D 9636N	957.	1,076.	1,101.	1,768.
Blended “D” Peninsula Worksurface (Left hand shown) 	LH w/ 24" return depth	60"	59 ^{13/16"}	47 ^{13/16"}	1 ^{1/4"}		D1BD6048SL	830.	918.	1,002.	2,998.
		66"	65 ^{13/16"}	47 ^{13/16"}	1 ^{1/4"}		D1BD6648SL	851.	938.	1,022.	3,018.
		72"	71 ^{13/16"}	41 ^{13/16"}	1 ^{1/4"}		D1BD7242SL	851.	938.	1,022.	3,039.
		72"	71 ^{13/16"}	47 ^{13/16"}	1 ^{1/4"}		D1BD7248SL	870.	959.	1,046.	3,045.
		78"	77 ^{13/16"}	47 ^{13/16"}	1 ^{1/4"}		D1BD7848SL	950.	1,053.	1,149.	3,055.
		84"	83 ^{13/16"}	47 ^{13/16"}	1 ^{1/4"}		D1BD8448SL	990.	1,093.	1,189.	3,096.
	LH w/ 30" return depth	66"	65 ^{13/16"}	47 ^{13/16"}	1 ^{1/4"}		D1BD6648DL	896.	993.	1,078.	3,018.

w* = nominal width
 Dimensions listed under w d t are actual to the nearest 1/16"



Ordering Information	Order Code	Included with:	Options
“D” Worksurface 1. Pattern Number 2. Top Finish Type 3. Edge Finish	“D” Worksurface <i>Example:</i> D1H 6030, 114, 114 D1H 6030 Pattern Number 114 Folkstone Grey Laminate 114 Folkstone Grey Edge Band	Worksurface Note: Support column and panel-to-worksurface brackets must be ordered separately. Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.	Worksurfaces • Woodgrain ABS edge • Metal edge • Techwood edge To specify an edge grommet, replace “N” suffix from pattern number with “G”. Add \$19.

Peninsula Worksurfaces

“D”, “P”, “9” and Blended “D”

Mixed Depths

Dividends Horizon

description	type	w *	w	d	dia.	t	pattern no.	laminate w/ ABS edge	laminate w/ woodgrain edge	laminate w/ metal edge	techwood w/ techwood edge
Blended “D” Peninsula Worksurface (Left hand shown) 	LH w/ 30” return depth	72”	71 ¹³ / ₁₆ ”	41 ¹³ / ₁₆ ”	1 ¹ / ₄ ”		D1BD7242DL	\$861.	\$949.	\$1,032.	\$3,049.
		72”	71 ¹³ / ₁₆ ”	47 ¹³ / ₁₆ ”	1 ¹ / ₄ ”		D1BD7248DL	929.	1,022.	1,118.	3,045.
		78”	77 ¹³ / ₁₆ ”	47 ¹³ / ₁₆ ”	1 ¹ / ₄ ”		D1BD7848DL	960.	1,063.	1,159.	3,065.
		84”	83 ¹³ / ₁₆ ”	47 ¹³ / ₁₆ ”	1 ¹ / ₄ ”		D1BD8448DL	1,001.	1,104.	1,200.	3,106.
	RH w/ 24” return depth	60”	59 ¹³ / ₁₆ ”	47 ¹³ / ₁₆ ”	1 ¹ / ₄ ”		D1BD6048SR	830.	918.	1,002.	2,998.
		66”	65 ¹³ / ₁₆ ”	47 ¹³ / ₁₆ ”	1 ¹ / ₄ ”		D1BD6648SR	851.	938.	1,022.	3,018.
		72”	71 ¹³ / ₁₆ ”	41 ¹³ / ₁₆ ”	1 ¹ / ₄ ”		D1BD7242SR	851.	938.	1,022.	3,039.
		72”	71 ¹³ / ₁₆ ”	47 ¹³ / ₁₆ ”	1 ¹ / ₄ ”		D1BD7248SR	870.	959.	1,046.	3,045.
		78”	77 ¹³ / ₁₆ ”	47 ¹³ / ₁₆ ”	1 ¹ / ₄ ”		D1BD7848SR	950.	1,053.	1,149.	3,055.
		84”	83 ¹³ / ₁₆ ”	47 ¹³ / ₁₆ ”	1 ¹ / ₄ ”		D1BD8448SR	990.	1,093.	1,189.	3,096.
	RH w/ 30” return depth	66”	65 ¹³ / ₁₆ ”	47 ¹³ / ₁₆ ”	1 ¹ / ₄ ”		D1BD6648DR	896.	993.	1,078.	3,018.
		72”	71 ¹³ / ₁₆ ”	41 ¹³ / ₁₆ ”	1 ¹ / ₄ ”		D1BD7242DR	861.	949.	1,032.	3,049.
		72”	71 ¹³ / ₁₆ ”	47 ¹³ / ₁₆ ”	1 ¹ / ₄ ”		D1BD7248DR	929.	1,022.	1,118.	3,045.
		78”	77 ¹³ / ₁₆ ”	47 ¹³ / ₁₆ ”	1 ¹ / ₄ ”		D1BD7848DR	960.	1,063.	1,159.	3,065.
		84”	83 ¹³ / ₁₆ ”	47 ¹³ / ₁₆ ”	1 ¹ / ₄ ”		D1BD8448DR	1,001.	1,104.	1,200.	3,106.
Conferencing worksurface (left hand shown) 		60”	59 ¹³ / ₁₆ ”	48”	24”	1 ¹ / ₄ ”	DB1BD48SL	1,173.	1,291.	1,410.	2,989.
		60”	59 ¹³ / ₁₆ ”	48”	24”	1 ¹ / ₄ ”	DB1BD48SR	1,173.	1,291.	1,410.	2,989.
Peninsula Worksurface-Laminate No Grommets (9-shaped shown) 	P-shaped	54”	53 ¹³ / ₁₆ ”	29 ¹³ / ₁₆ ”	36	1 ¹ / ₄ ”	D1P 5430N	818.	898.	984.	1,841.
		60”	59 ¹³ / ₁₆ ”	29 ¹³ / ₁₆ ”	36	1 ¹ / ₄ ”	D1P 6030N	828.	908.	995.	1,892.
		66”	65 ¹³ / ₁₆ ”	29 ¹³ / ₁₆ ”	36	1 ¹ / ₄ ”	D1P 6630N	838.	918.	1,005.	1,933.
		72”	71 ¹³ / ₁₆ ”	29 ¹³ / ₁₆ ”	42	1 ¹ / ₄ ”	D1P 7230N	852.	939.	1,023.	1,987.
		78”	77 ¹³ / ₁₆ ”	29 ¹³ / ₁₆ ”	42	1 ¹ / ₄ ”	D1P 7830N	958.	1,053.	1,144.	2,042.
		78”	77 ¹³ / ₁₆ ”	35 ¹³ / ₁₆ ”	48	1 ¹ / ₄ ”	D1P 7836N	968.	1,064.	1,155.	2,083.
		84”	83 ¹³ / ₁₆ ”	29 ¹³ / ₁₆ ”	42	1 ¹ / ₄ ”	D1P 8430N	978.	1,074.	1,165.	2,105.
		90”	89 ¹³ / ₁₆ ”	29 ¹³ / ₁₆ ”	42	1 ¹ / ₄ ”	D1P 9030N	999.	1,094.	1,185.	2,140.
	9-shaped	54”	53 ¹³ / ₁₆ ”	29 ¹³ / ₁₆ ”		1 ¹ / ₄ ”	D19 5430N	818.	898.	984.	1,841.

w* = nominal width
 Dimensions listed under w d t are actual to the nearest 1/16”

Ordering Information	Order Code	Included with:	Options
“D” Worksurface 1. Pattern Number 2. Top Finish Type 3. Edge Finish	“D” Worksurface <i>Example:</i> D1H 6030, 114, 114 D1H 6030 Pattern Number 114 Folkstone Grey Laminate 114 Folkstone Grey Edge Band	Worksurface Note: Support column and panel-to-worksurface brackets must be ordered separately. Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.	Worksurfaces • Woodgrain ABS edge • Metal edge • Techwood edge To specify an edge grommet, replace “N” suffix from pattern number with “G”. Add \$19.

Peninsula Worsurfaces

“D”, “P”, “9” and Blended “D”

Mixed Depths

Dividends Horizon

description	type	w *	w	d	dia.	t	pattern no.	laminate w/ ABS edge	laminate w/ woodgrain edge	laminate w/ metal edge	techwood w/ techwood edge
Peninsula Worksurface-Laminate No Grommets (9-shaped shown) 	9-shaped	60"	59 ^{13/16"}	29 ^{13/16"}		1 1/4"	D19 6030N	\$828.	\$908.	\$995.	\$1,892.
		66"	65 ^{13/16"}	29 ^{13/16"}		1 1/4"	D19 6630N	838.	918.	1,005.	1,933.
		72"	71 ^{13/16"}	29 ^{13/16"}		1 1/4"	D19 7230N	852.	939.	1,023.	1,987.
		78"	77 ^{13/16"}	29 ^{13/16"}		1 1/4"	D19 7830N	958.	1,053.	1,144.	2,042.
		78"	77 ^{13/16"}	35 ^{13/16"}		1 1/4"	D19 7836N	968.	1,064.	1,155.	2,083.
		84"	83 ^{13/16"}	29 ^{13/16"}		1 1/4"	D19 8430N	978.	1,074.	1,165.	2,105.
		90"	89 ^{13/16"}	29 ^{13/16"}		1 1/4"	D19 9030N	999.	1,094.	1,185.	2,140.

w* = nominal width
 Dimensions listed under w d t are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
“D” Worksurface 1. Pattern Number 2. Top Finish Type 3. Edge Finish	“D” Worksurface <i>Example:</i> D1H 6030, 114, 114 D1H 6030 Pattern Number 114 Folkstone Grey Laminate 114 Folkstone Grey Edge Band	Worksurface Note: Support column and panel-to-worksurface brackets must be ordered separately. Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.	Worksurfaces • Woodgrain ABS edge • Metal edge • Techwood edge To specify an edge grommet, replace “N” suffix from pattern number with “G”. Add \$19.

Curvilinear Half-Round Worksurfaces

Curvilinear half-round worksurfaces are sized to match up to the width of two back-to-back 24" deep or two back-to-back 30" deep freestanding desks.

Panel-supported half-round worksurfaces are notched along the flat end to accommodate the panel end trim.

Attachment is with a column support, T leg or A leg (must be ordered separately) at the free end of the worksurface and with flat brackets on the flat end of the half-round worksurface. The flat brackets attach to the adjacent freestanding desks. Flat brackets are black.

Available Sizes

- Depths: 18" and 24"
- Widths: 48" and 63"
- Thickness: 1 1/4"

Note: All Dividends Horizon worksurfaces include a 1/2" wire drop at the rear edge. When used back to back with Half-Round worksurface, these two 1/2" wire drops will meet to form a 1" space between worksurfaces.

Transition Worksurfaces

Attachment is with a column support, T leg or A leg (must be ordered separately) at the free end of the worksurface and with flat brackets on the flat end of the transition worksurface. The flat brackets attach to the adjacent freestanding desks. Flat brackets are black.

Available Sizes

- Depths: 24", 36", 48"
- Widths: 48"
- Thickness: 1 1/4"

Corner Round Worksurfaces

Corner-round worksurfaces are designed to "finish" a run of panel-mounted worksurfaces. Corner-round may be specified in two ways.

In a 90° "L" configuration, a notched corner-round worksurface is used to wrap around the panels. Two cantilevers and flat brackets (must be ordered separately) support the corner-round worksurface.

In an end run configuration, the corner-round worksurface is handed and must be specified as a left-hand or a right-hand top. One cantilever with a flat bracket and one panel-to-worksurface bracket (must be ordered separately) support the corner-round top.


Available Sizes

- Depth: 24"
- Width: 24"
- Thickness: 1 1/4"


Optional Edge Grommets

Grommets are not available for worksurfaces on this page.


Curvilinear Half-Round Worksurfaces (without panels)



Curvilinear Half-Round Worksurfaces (with panels)




Corner-Round Worksurface




Notched Corner Worksurfae



Corner-Round Applications



Corner-Round - Notched "L" Configuration



Corner-Round - End Run Configuration (right-hand shown)
Quarter-round Surface

Curvilinear Half- and Corner-Round Worksurfaces

Mixed Depths

Dividends Horizon

description	type	w	return depth	t	pattern no.	laminate w/ ABS edge	laminate w/ woodgrain edge	laminate w/ metal edge	techwood w/ techwood edge
	Curvilinear Half-Round Worksurface	w/o panels	48"	18"	1 1/4"	D1H4818	\$453.	\$501.	\$547.
		w/o panels	60"	24"	1 1/4"	D1H6024	625.	690.	749.
		w/panels	51"	18"	1 1/4"	D1H5118P	461.	510.	555.
		w/panels	63"	24"	1 1/4"	D1H6324P	631.	698.	763.
	Transition Worksurface	w panels	51"	24"	1 1/4"	D2H5124P	557.	613.	665.
		w panels	51"	36"	1 1/4"	D2H5136P	567.	621.	683.
		w panels	51"	48"	1 1/4"	D2H5148P	578.	633.	696.
		w/o panels	48"	24"	1 1/4"	D2H4824	551.	602.	658.
		w/o panels	48"	36"	1 1/4"	D2H4836	558.	614.	671.
		w/o panels	48"	48"	1 1/4"	D2H4848	571.	626.	687.
	Corner Round Worksurface	left	23 13/16"	23 1/2"	1 1/4"	D1CRL24	356.	389.	423.
		notched	23 1/2"	23 1/2"	1 1/4"	D1CRN24	356.	389.	423.
		right	23 13/16"	23 1/2"	1 1/4"	D1CRR24	356.	389.	423.
		right	29 13/16"	23 13/16"	1 1/4"	D1CRR30	376.	409.	444.

Ordering Information	Order Code	Included with:	Options
Half-Round Worksurface 1. Pattern Number 2. Top Finish Type 3. Edge Finish	Half-Round Worksurface <i>Example:</i> D1H 5118P, 118, 118 D1H Pattern Number 5118P 118 Bright White Laminate 118 Bright White Edge Band Transition Worksurface <i>Example:</i> D2H 5136P, 117, 117 D2H Pattern Number 5136P 117 Soft Grey Laminate 117 Soft Grey Edge Band	Half-Round Worksurface • Worksurface • 2 flat brackets Note: Support column must be ordered separately. Transition Worksurface • Worksurface • 2 flat brackets Note: Support column must be ordered separately. Corner Round Worksurface • Worksurface Note: 2 cantilevers must be ordered separately. Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.	Half-Round Worksurface • Woodgrain ABS edge • Metal edge • Techwood edge Transition Worksurface • Woodgrain ABS edge • Metal edge • Techwood edge Corner-Round Worksurface • Woodgrain ABS edge • Metal edge • Techwood edge Curvilinear Half-Round and Transition Worksurface Option Add an 'F' suffix to the pattern number when using with flat profile panel trim.

Transaction Counter Worksurfaces

15" Deep Specifications

Dividends Horizon

15"D Counter Worksurfaces

Dividends Horizon 15"D counter worksurfaces attach to the tops of 42" high panels to provide a transaction area within workstations. Three types are available:

- Straight
- Square corner
- Quarter-round corner

Available Sizes

- Depth: 15"
- Widths: 24" to 96"
- Thickness: 1 1/4"

Straight Counter Worksurface Support

Straight counter worksurfaces can span single or multiple panels. Counter worksurfaces are supported by four counter worksurface brackets which are included with the straight counter worksurfaces. Counter worksurface brackets are required at panel or post junctions for proper support.

Note: High-low panel end trim must be field cut when using countertops in a high-low straight panel run application.

Note: Counter worksurfaces may NOT be used with on any screens or 36H panels.

Square and Quarter-Round Corner Counter Worksurfaces

Square corners allow rectilinear "L", "T" and "X" configurations while quarter-round corners allow radiused "L" configurations. When using corner counter worksurfaces, all adjoining straight counter worksurfaces must be 6" less than panel(s) width dimension. Square and quarter-round counter worksurfaces are supported by flat brackets which are included with corner worksurfaces. Additional support is provided by counter worksurface brackets from the adjoining straight counter worksurfaces.

Square-corner counter worksurfaces include three flat brackets while quarter-round counters include two flat brackets. Flat brackets are dark grey finish.

Counter Worksurface Corner Applications


Suggested applications and configurations are illustrated below.

Note: When connecting a 15" deep counter worksurface with either corner counter worksurface, specify 6" shorter than the required width to accommodate the width of the corner counter worksurface.

Counter Worksurface Supports

Straight counter worksurfaces 24" to 48" wide include four counter worksurface brackets while straight counters 54" to 96" wide include six counter worksurface brackets.

15"D Counter Worksurface



15"D Square-Shape Counter Worksurface








15"D Quarter Round Counter Worksurface



15"D Counter Worksurface Sizes Available

15D	
24	
30	
36	
42	
48	
54	
60	
66	
72	
78	
84	
90	
96	
15	
15	

15"D Counter Worksurface Applications



Transaction Counter Worksurfaces

Rectangular, Square Corner and Quarter-round Corner

15" Deep

Dividends Horizon

description	w *	w	d	t	pattern no.	laminate w/ ABS edge	laminate w/ woodgrain edge	laminate w/ metal edge	techwood w/ techwood edge
15" Deep Quarter-Round Shape Corner Counter Worksurface 	15"	14 ^{13/16"}	15"	1 ^{1/4"}	D1R 1515C	\$253.	\$281.	\$306.	\$1,023.
15" Deep Square-Shape Corner Counter Worksurface 	15"	14 ^{13/16"}	15"	1 ^{1/4"}	D1R 1515S	232.	258.	281.	640.
15" Deep Rectangular Counter Worksurface 	24"	23 ^{13/16"}	15"	1 ^{1/4"}	D1R 2415	341.	372.	407.	774.
	30"	29 ^{13/16"}	15"	1 ^{1/4"}	D1R 3015	368.	405.	439.	810.
	36"	35 ^{13/16"}	15"	1 ^{1/4"}	D1R 3615	375.	415.	452.	847.
	42"	41 ^{13/16"}	15"	1 ^{1/4"}	D1R 4215	376.	416.	455.	878.
	48"	47 ^{13/16"}	15"	1 ^{1/4"}	D1R 4815	376.	416.	455.	916.
	54"	54 ^{13/16"}	15"	1 ^{1/4"}	D1R 5415	393.	428.	474.	947.
	60"	59 ^{13/16"}	15"	1 ^{1/4"}	D1R 6015	416.	460.	503.	984.
	66"	65 ^{13/16"}	15"	1 ^{1/4"}	D1R 6615	428.	475.	520.	1,018.
	72"	71 ^{13/16"}	15"	1 ^{1/4"}	D1R 7215	472.	520.	567.	1,054.
	78"	77 ^{13/16"}	15"	1 ^{1/4"}	D1R 7815	503.	550.	601.	1,086.
	84"	83 ^{13/16"}	15"	1 ^{1/4"}	D1R 8415	525.	579.	633.	1,122.
	90"	89 ^{13/16"}	15"	1 ^{1/4"}	D1R 9015	553.	607.	661.	1,161.
	96"	95 ^{13/16"}	15"	1 ^{1/4"}	D1R 9615	579.	639.	694.	1,192.



w* = nominal width

Dimensions listed under w d are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
15"D Counter Worksurface 1. Pattern Number 2. Top Finish Type 3. Edge Finish 4. Counter Worksurface Bracket Finish	15"D Counter Worksurface <i>Example:</i> D1R 3615, 117, 117, 117 D1R 3615 Pattern Number 117 Soft Grey Laminate 117 Soft Grey Edge Band 117 Soft Grey Bracket Finish	15"D Counter Worksurface • Four counter worksurface brackets • Attachment hardware	15"D Counter Worksurface • Woodgrain ABS edge • Metal edge • Techwood edge
Square-Shape Corner Counter Worksurface 1. Pattern Number 2. Top Finish Type 3. Edge Finish	Square-Shape Counter Worksurface <i>Example:</i> D1R 1515S, 117, 117 D1R Pattern Number 1515S 117 Soft Grey Laminate 117 Soft Grey Edge Band	Square-Shape Counter Worksurface • Three counter worksurface flat brackets • Attachment hardware	Square-Shape Counter Worksurface • Woodgrain ABS edge • Metal edge • Techwood edge
Quarter-Round Shape Counter Worksurface 1. Pattern Number 2. Top Finish Type 3. Edge Finish	Quarter-Round Shape Counter Worksurface <i>Example:</i> D1R 1515C, 117, 117 D1R Pattern Number 1515C 117 Soft Grey Laminate 117 Soft Grey Edge Band	Quarter-Round Shape Counter Worksurface • Two counter worksurface flat brackets • Attachment hardware Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.	Quarter-Round Shape Counter Worksurface • Woodgrain ABS edge • Metal edge • Techwood edge

Rectangular with Cascade Edge 24" and 30" Deep

Dividends Horizon

description	w	d	t	pattern no.	Solid	Woodgrain
24" D Rectangular 	24"	24"	1 1/4"	DCE1R2424N	\$259.	\$296.
	30"	24"	1 1/4"	DCE1R3024N	296.	341.
	36"	24"	1 1/4"	DCE1R3624N	325.	375.
	42"	24"	1 1/4"	DCE1R4224N	375.	432.
	48"	24"	1 1/4"	DCE1R4824N	422.	486.
	54"	24"	1 1/4"	DCE1R5424N	453.	521.
	60"	24"	1 1/4"	DCE1R6024N	493.	566.
	66"	24"	1 1/4"	DCE1R6624N	531.	609.
	72"	24"	1 1/4"	DCE1R7224N	556.	639.
	78"	24"	1 1/4"	DCE1R7824N	598.	686.
	84"	24"	1 1/4"	DCE1R8424N	631.	724.
	90"	24"	1 1/4"	DCE1R9024N	712.	817.
	96"	24"	1 1/4"	DCE1R9624N	777.	893.
30" D Rectangular 	24"	30"	1 1/4"	DCE1R2430N	326.	377.
	30"	30"	1 1/4"	DCE1R3030N	367.	422.
	36"	30"	1 1/4"	DCE1R3630N	409.	471.
	42"	30"	1 1/4"	DCE1R4230N	445.	509.
	48"	30"	1 1/4"	DCE1R4830N	493.	566.
	54"	30"	1 1/4"	DCE1R5430N	557.	641.
	60"	30"	1 1/4"	DCE1R6030N	613.	704.
	66"	30"	1 1/4"	DCE1R6630N	683.	785.
	72"	30"	1 1/4"	DCE1R7230N	712.	817.
	78"	30"	1 1/4"	DCE1R7830N	759.	872.
	84"	30"	1 1/4"	DCE1R8430N	806.	928.
	90"	30"	1 1/4"	DCE1R9030N	868.	999.
	96"	30"	1 1/4"	DCE1R9630N	928.	1,066.
Sample 	12"	12"	1 1/4"	DCE1R1212G	159.	185.

Ordering Information

1. Pattern Number
2. Top Finish Type

Order Code

Worksurfaces	
Example: DCE1R4824N, 118	
DCE1	Dividends Cascade Edge Worksurface
R	Rectangular
48	Width
24	Depth
N	No Grommet
118	Bright White finish

Included with:

Specify worksurface supports separately.

Available Colors:

Solid:

- 114 Folkstone Grey
- 117 Soft Grey
- 118 Bright White
- 119 Pumice

Woodgrain:

- 124 Medium Cherry
- 125 Natural Maple
- 126 Natural Cherry
- 127 Walnut


Options

Worksurfaces

- Center-Located Edge Grommet
To specify, replace the "N" suffix from the pattern number with "G".

Add \$22.

Shaded area on worksurface drawings represents cascade edge detail.

description	A	B	C	pattern no.	Solid	Woodgrain
	36"	24"	24"	DCE1L3636SSN	\$643.	\$741.
	42"	24"	24"	DCE1L4242SSN	777.	893.
	42"	24"	30"	DCE1L4242SDN	923.	1,059.
	42"	30"	24"	DCE1L4242DSN	923.	1,059.
	48"	24"	24"	DCE1L4848SSN	872.	1,004.
	48"	24"	30"	DCE1L4848SDN	1,046.	1,202.
	48"	30"	24"	DCE1L4848DSN	1,046.	1,202.
	48"	30"	30"	DCE1L4848DDN	936.	1,078.

Ordering Information

1. Pattern Number
2. Top Finish Type

Order Code

Worksurfaces

Example: **DCE1BD7248SL, 118**

DCE1	Dividends Cascade Edge worksurface
BD	Blended “D”
72	Width
48	Depth
S	24”d return
L	Extended Left
118	Bright White

Included with:

Available Colors:

Solid:

114	Folkstone Grey
117	Soft Grey
118	Bright White
119	Pumice

Woodgrain:

124	Medium Cherry
125	Natural Maple
126	Natural Cherry
127	Walnut

Options

Worksurfaces


- Center-Located Edge Grommet (Blended “L” only) To specify, replace the “N” suffix from the pattern number with “G”.
Add \$44.

Note: Support column and panel-to-worksurface brackets must be ordered separately.

Shaded area on worksurface drawings represents cascade edge detail.

Note: When wood grain or brushed laminates are specified on Cascade corner worksurfaces with two “A” sides of equal length, one of three grain direction options must be specified. Insert the desired grain direction option (L,R or D) after the laminate code. Please add \$26 to the list price for diagonal grain (D) selection.

description	Width B	Width C	Width A	Width D	t	pattern no.	Solid	Woodgrain
Blended “L”	42"	60"	24"	24"	1 1/4"	DCE1L4260SSN	\$1,066.	\$1,226.
	42"	66"	24"	24"	1 1/4"	DCE1L4266SSN	1,093.	1,261.
	42"	72"	24"	24"	1 1/4"	DCE1L4272SSN	1,135.	1,307.
	42"	78"	24"	24"	1 1/4"	DCE1L4278SSN	1,149.	1,319.
	48"	60"	24"	24"	1 1/4"	DCE1L4860SSN	1,080.	1,240.
	48"	60"	24"	30"	1 1/4"	DCE1L4860SDN	1,059.	1,220.
	48"	60"	30"	24"	1 1/4"	DCE1L4860DSN	1,059.	1,220.
	48"	66"	24"	24"	1 1/4"	DCE1L4866SSN	1,119.	1,285.
	48"	66"	24"	30"	1 1/4"	DCE1L4866SDN	1,115.	1,282.
	48"	66"	30"	24"	1 1/4"	DCE1L4866DSN	1,115.	1,282.
	48"	72"	24"	24"	1 1/4"	DCE1L4872SSN	1,160.	1,333.
	48"	72"	24"	30"	1 1/4"	DCE1L4872SDN	1,166.	1,343.
	48"	72"	30"	24"	1 1/4"	DCE1L4872DSN	1,166.	1,343.
	48"	78"	24"	24"	1 1/4"	DCE1L4878SSN	1,278.	1,470.
	48"	84"	24"	24"	1 1/4"	DCE1L4884SSN	1,437.	1,653.
	60"	42"	24"	24"	1 1/4"	DCE1L6042SSN	1,066.	1,226.
	60"	48"	24"	24"	1 1/4"	DCE1L6048SSN	1,080.	1,240.
	60"	48"	24"	30"	1 1/4"	DCE1L6048SDN	1,059.	1,220.
	60"	48"	30"	24"	1 1/4"	DCE1L6048DSN	1,059.	1,220.
	66"	42"	24"	24"	1 1/4"	DCE1L6642SSN	1,093.	1,261.
	66"	48"	24"	24"	1 1/4"	DCE1L6648SSN	1,119.	1,285.
	66"	48"	24"	30"	1 1/4"	DCE1L6648SDN	1,115.	1,282.
	66"	48"	30"	24"	1 1/4"	DCE1L6648DSN	1,115.	1,282.
	72"	42"	24"	24"	1 1/4"	DCE1L7242SSN	1,135.	1,307.
	72"	48"	24"	24"	1 1/4"	DCE1L7248SSN	1,160.	1,333.
	72"	48"	24"	30"	1 1/4"	DCE1L7248SDN	1,166.	1,343.
	72"	48"	30"	24"	1 1/4"	DCE1L7248DSN	1,166.	1,343.
	78"	42"	24"	24"	1 1/4"	DCE1L7842SSN	1,149.	1,319.
	78"	48"	24"	24"	1 1/4"	DCE1L7848SSN	1,278.	1,470.
	84"	48"	24"	24"	1 1/4"	DCE1L8448SSN	1,437.	1,653.



Ordering Information

1. Pattern Number
2. Top Finish Type

Order Code

Worksurfaces

Example: DCE1L4872SDG,114

DCE1 Dividends Cascade

Edge worksurface

L Blended “L”

48 Width

72 Depth

S 24”d, left side

D 30”d, right side

G Grommet

114 Folkstone Grey

Included with:

Available Colors:

Solid:

114 Folkstone Grey

117 Soft Grey

118 Bright White

119 Pumice

Woodgrain:

124 Medium Cherry

125 Natural Maple

126 Natural Cherry

127 Walnut


Options

Worksurfaces

- Center-Located Edge Grommet
To specify, replace the “N” suffix from the pattern number with “G”.
Add \$44.

Note: Specify the panel-to-worksurface brackets separately.

Shaded area on worksurface drawings represents cascade edge detail.

description	w	d	t	pattern no.	Solid	Woodgrain
 Half Round	48"	18"	1 1/4"	DCE1H4818	\$556.	\$639.
	48"	18"	1 1/4"	DCE1H4818P	556.	639.
	60"	24"	1 1/4"	DCE1H6024	764.	880.
	60"	24"	1 1/4"	DCE1H6024P	764.	880.
 LH Corner Round	24"	24"	1 1/4"	DCE1CR24L	296.	341.
 RH Corner Round	24"	24"	1 1/4"	DCE1CR24R	296.	341.
 Notched Corner Round	24"	24"	1 1/4"	DCE1CR24N	296.	341.

Ordering Information

1. Pattern Number
2. Top Finish Type

Order Code

Worksurfaces	
Example:	DCE1H4818P,117
DCE1	Dividends Cascade Edge worksurface
H	Half Round
48	Width
18	Depth
P	Notched for panel
117	Soft Grey

Included with:


Available Colors:	
Solid:	
114	Folkstone Grey
117	Soft Grey
118	Bright White
119	Pumice
Woodgrain:	
124	Medium Cherry
125	Natural Maple
126	Natural Cherry
127	Walnut

Options


P= Notched for panel

Note: Specify all support brackets separately.

Shaded area on worksurface drawings represents cascade edge detail.

description	1	2	3	A	B	t	pattern no.	Solid	Woodgrain
Wave End, RH 	36"	30"	24"	3"	15"	1 1/4"	DCE1W362430N	\$692.	\$795.
	42"	30"	24"	9"	15"	1 1/4"	DCE1W422430N	725.	836.
	48"	30"	24"	15"	15"	1 1/4"	DCE1W482430N	778.	895.
	72"	30"	24"	30 1/2"	23 1/2"	1 1/4"	DCE1W722430N	989.	1,137.

shown with grommet

Wave End, LH 	36"	24"	30"	15"	3"	1 1/4"	DCE1W363024N	692.	795.
	42"	24"	30"	15"	9"	1 1/4"	DCE1W423024N	725.	836.
	48"	24"	30"	15"	15"	1 1/4"	DCE1W483024N	778.	895.
	72"	24"	30"	23 1/2"	30 1/2"	1 1/4"	DCE1W723024N	989.	1,137.

Ordering Information

1. Pattern Number
2. Top Finish Type

Order Code

Worksurfaces	
Example:	DCE1W483024N,118
DCE1	Dividends Cascade Edge worksurface
W	Wave End
48	Width
30	30"d, left side
24	24"d, right side
N	No grommet
118	Bright White

Included with:

Available Colors:	
Solid:	
114	Folkstone Grey
117	Soft Grey
118	Bright White
119	Pumice
Woodgrain:	
124	Medium Cherry
125	Natural Maple
126	Natural Cherry
127	Walnut

Options

Worksurfaces


- Center-Located Edge Grommet
To specify, replace the "N" suffix from the pattern number with "G".
Add \$21.

Note: Specify all support brackets separately.

Shaded area on worksurface drawings represents cascade edge detail.

Postformed Worksurfaces, 1 3/4" 18" Deep

Dividends Horizon



description	type	w	d	h	pattern no.	lam.	V1	V2
Straight, 18"D 	No grommet	30"	17 3/8"	1 3/4"	MW2-S3018-B-()	\$569.	\$837.	\$1,177.
	No grommet	36"	17 3/8"	1 3/4"	MW2-S3618-B-()	625.	898.	1,267.
	No grommet	42"	17 3/8"	1 3/4"	MW2-S4218-B-()	689.	982.	1,410.
	No grommet	48"	17 3/8"	1 3/4"	MW2-S4818-B-()	772.	1,061.	1,528.
	No grommet	54"	17 3/8"	1 3/4"	MW2-S5418-B-()	827.	1,155.	1,645.
	No grommet	60"	17 3/8"	1 3/4"	MW2-S6018-B-()	853.	1,206.	1,763.
	No grommet	66"	17 3/8"	1 3/4"	MW2-S6618-B-()	947.	1,355.	1,968.
	No grommet	72"	17 3/8"	1 3/4"	MW2-S7218-B-()	1,030.	1,505.	2,147.

Postformed

Order Code	Specification Information	Application Notes
Example: MW2-S3618-B-117	B: Worksurface does not include grommets	18"D worksurfaces are used interchangeably in desk and panel system applications as shallow main surfaces, extensions, or credenza tops. They must be supported at each end by a pedestal, end panel, end support cantilever or cantilever bridging bracket with a maximum span of 60" between supports.
MW2 Worksurface 1 3/4" thick	Specify surface finish	All worksurfaces have threaded metal inserts at all end panel, desk support and bracket locations and pilot holes at pedestal locations.
S Worksurface type	All worksurfaces are U.L.-listed.	MW2- worksurfaces are supported by brackets with machine screws.
36 Width		Panel supported worksurfaces over 60" must be mid-span supported by MB2-C18 bracket, specified separately.
18 Depth		18"D worksurfaces with desk supports or filler panels do not accept pedestals.
B No grommets		
117 Surface finish		

Postformed Worksurfaces, 1 3/4" 24" Deep



Dividends Horizon

description	type	w	d	h	pattern no.	lam.	V1	V2
Straight, 24"D 	Grommets	24"	23 3/8"	1 3/4"	MW2-S2424-A-()	\$692.	\$1,041.	\$1,410.
	Grommets	30"	23 3/8"	1 3/4"	MW2-S3024-A-()	749.	1,072.	1,468.
	Grommets	36"	23 3/8"	1 3/4"	MW2-S3624-A-()	809.	1,130.	1,531.
	Grommets	42"	23 3/8"	1 3/4"	MW2-S4224-A-()	896.	1,184.	1,649.
	Grommets	48"	23 3/8"	1 3/4"	MW2-S4824-A-()	951.	1,303.	1,827.
	Grommets	54"	23 3/8"	1 3/4"	MW2-S5424-A-()	1,009.	1,416.	1,975.
	Grommets	60"	23 3/8"	1 3/4"	MW2-S6024-A-()	1,091.	1,509.	2,088.
	Grommets	66"	23 3/8"	1 3/4"	MW2-S6624-A-()	1,178.	1,649.	2,297.
	Grommets	72"	23 3/8"	1 3/4"	MW2-S7224-A-()	1,295.	1,792.	2,533.
	Grommets	78"	23 3/8"	1 3/4"	MW2-S7824-A-()	1,407.	1,936.	2,704.
	Grommets	84"	23 3/8"	1 3/4"	MW2-S8424-A-()	1,490.	2,081.	2,910.
	Grommets	90"	23 3/8"	1 3/4"	MW2-S9024-A-()	1,604.	2,254.	3,176.
	Grommets	96"	23 3/8"	1 3/4"	MW2-S9624-A-()	1,755.	2,485.	3,470.
Straight, 24"D - No grommets 	No grommets	24"	23 3/8"	1 3/4"	MW2-S2424-B-()	569.	920.	1,293.
	No grommets	30"	23 3/8"	1 3/4"	MW2-S3024-B-()	625.	953.	1,354.
	No grommets	36"	23 3/8"	1 3/4"	MW2-S3624-B-()	689.	1,010.	1,410.
	No grommets	42"	23 3/8"	1 3/4"	MW2-S4224-B-()	772.	1,061.	1,528.
	No grommets	48"	23 3/8"	1 3/4"	MW2-S4824-B-()	827.	1,180.	1,706.
	No grommets	54"	23 3/8"	1 3/4"	MW2-S5424-B-()	893.	1,297.	1,854.
	No grommets	60"	23 3/8"	1 3/4"	MW2-S6024-B-()	969.	1,390.	1,968.
	No grommets	66"	23 3/8"	1 3/4"	MW2-S6624-B-()	1,058.	1,528.	2,175.
	No grommets	72"	23 3/8"	1 3/4"	MW2-S7224-B-()	1,169.	1,675.	2,413.
	No grommets	78"	23 3/8"	1 3/4"	MW2-S7824-B-()	1,286.	1,815.	2,590.
	No grommets	84"	23 3/8"	1 3/4"	MW2-S8424-B-()	1,375.	1,959.	2,793.
	No grommets	90"	23 3/8"	1 3/4"	MW2-S9024-B-()	1,482.	2,136.	3,055.
	No grommets	96"	23 3/8"	1 3/4"	MW2-S9624-B-()	1,629.	2,367.	3,351.

Order Code	Specification Information	Application Notes
Example: MW2-S7224-A-117	<i>Grommets / no grommets:</i>	24"D worksurfaces are used interchangeably as shallow main surfaces, extensions or credenza tops. They must be supported at each end by a pedestal, end panel, end support cantilever or cantilever bridging bracket with a maximum span of 60" between supports.
MW2 Worksurface 1 3/4" thick	A: Worksurface includes 3" grommet in each back corner leading into desk support or wire manager.	All straight worksurfaces are 3/8" less than nominal depth for rear wire clearance or privacy screens.
S Worksurface type	B: Worksurface does not include grommets	Plastic laminate worksurfaces are post-formed top and bottom, front and back.
72 Width	Specify surface finish	Worksurfaces with grommets are bored to accept and are shipped with wire manager clips.
24 Depth	All worksurfaces are U.L.-listed.	Panel supported worksurfaces over 60" must be mid-span supported by MB2-C18 bracket, specified separately.
A Grommets		
117 Surface finish		
		All worksurfaces have threaded metal inserts at all end panel, desk support and bracket locations and pilot holes at pedestal locations.
		MW2- worksurfaces are supported by brackets with machine screws.
		Use 18"D pedestals with 24"D worksurface for full wire management capability in desk or panel applications.
		18"D worksurfaces with desk supports or filler panels do not accept pedestals.

Postformed Worksurfaces, 1 3/4" 30" Deep

Dividends Horizon



description	type	w	d	h	pattern no.	lam.	V1	V2
Straight, 30"D 	Grommets	30"	29 5/8"	1 3/4"	MW2-S3030-A-()	\$833.	\$1,159.	\$1,621.
	Grommets	36"	29 5/8"	1 3/4"	MW2-S3630-A-()	921.	1,244.	1,740.
	Grommets	42"	29 5/8"	1 3/4"	MW2-S4230-A-()	977.	1,333.	1,854.
	Grommets	48"	29 5/8"	1 3/4"	MW2-S4830-A-()	1,061.	1,447.	1,997.
	Grommets	54"	29 5/8"	1 3/4"	MW2-S5430-A-()	1,116.	1,560.	2,111.
	Grommets	60"	29 5/8"	1 3/4"	MW2-S6030-A-()	1,178.	1,649.	2,297.
	Grommets	66"	29 5/8"	1 3/4"	MW2-S6630-A-()	1,268.	1,764.	2,498.
	Grommets	72"	29 5/8"	1 3/4"	MW2-S7230-A-()	1,407.	1,936.	2,704.
	Grommets	78"	29 5/8"	1 3/4"	MW2-S7830-A-()	1,522.	2,111.	2,938.
	Grommets	84"	29 5/8"	1 3/4"	MW2-S8430-A-()	1,636.	2,285.	3,208.
	Grommets	90"	29 5/8"	1 3/4"	MW2-S9030-A-()	1,782.	2,509.	3,557.
	Grommets	96"	29 5/8"	1 3/4"	MW2-S9630-A-()	1,951.	2,744.	3,908.
Straight, 30"D - no grommets 	No Grommets	30"	29 5/8"	1 3/4"	MW2-S3030-B-()	719.	1,040.	1,505.
	No Grommets	36"	29 5/8"	1 3/4"	MW2-S3630-B-()	803.	1,127.	1,620.
	No Grommets	42"	29 5/8"	1 3/4"	MW2-S4230-B-()	853.	1,206.	1,739.
	No Grommets	48"	29 5/8"	1 3/4"	MW2-S4830-B-()	944.	1,320.	1,880.
	No Grommets	54"	29 5/8"	1 3/4"	MW2-S5430-B-()	1,001.	1,444.	1,994.
	No Grommets	60"	29 5/8"	1 3/4"	MW2-S6030-B-()	1,058.	1,528.	2,175.
	No Grommets	66"	29 5/8"	1 3/4"	MW2-S6630-B-()	1,148.	1,645.	2,381.
	No Grommets	72"	29 5/8"	1 3/4"	MW2-S7230-B-()	1,286.	1,815.	2,590.
	No Grommets	78"	29 5/8"	1 3/4"	MW2-S7830-B-()	1,404.	1,994.	2,819.
	No Grommets	84"	29 5/8"	1 3/4"	MW2-S8430-B-()	1,518.	2,163.	3,084.
	No Grommets	90"	29 5/8"	1 3/4"	MW2-S9030-B-()	1,660.	2,389.	3,443.
	No Grommets	96"	29 5/8"	1 3/4"	MW2-S9630-B-()	1,825.	2,615.	3,790.

Postformed

Order Code	Specification Information	Application Notes
Example: MW2-S4230-A-117	<i>Grommets / no grommets:</i>	30"D worksurfaces are used interchangeably in desk and panel system applications as main surfaces, extensions, or credenza tops. They must be supported at each end by a pedestal, end panel, end support cantilever or cantilever bridging bracket with a maximum span of 60" between supports.
MW2 Worksurface 1 3/4" thick	A: Worksurface includes 3" grommet in each back corner leading into desk support or wire manager.	Panel supported worksurfaces over 60" must be mid-span supported by MB2-C18 bracket, specified separately.
S Worksurface type	B: Worksurface does not include grommets	Plastic laminate worksurfaces are post-formed top and bottom, front and back.
42 Width	Specify surface finish	
30 Depth	All worksurfaces are U.L.-listed.	All straight worksurfaces are 3/8" less than nominal depth for rear wire clearance or privacy screens.
A Grommets		MW2- worksurfaces are supported by brackets with machine screws.
117 Surface finish		

Postformed Worksurfaces, 1 3/4" 36" Deep



Dividends Horizon

description	type	w	d	h	pattern no.	lam.	V1	V2
Straight, 36"D 	Recessed Grommet	66"	35 3/4"	1 3/4"	MW2-S6636-R-()	\$1,547.	\$2,081.	\$2,853.
	Recessed Grommet	72"	35 3/4"	1 3/4"	MW2-S7236-R-()	1,636.	2,254.	3,176.
	Recessed Grommet	78"	35 3/4"	1 3/4"	MW2-S7836-R-()	1,782.	2,458.	3,379.
Straight, 36"D - no grommets 	No Grommets	66"	35 3/4"	1 3/4"	MW2-S6636-B-()	1,426.	1,959.	2,736.
	No Grommets	72"	35 3/4"	1 3/4"	MW2-S7836-B-()	1,518.	2,136.	3,055.
	No Grommets	78"	35 3/4"	1 3/4"	MW2-S7236-B-()	1,660.	2,340.	3,263.

Order Code	Specification Information	Application Notes
Example: MW2-S3636-R-117	<i>Grommet / no grommets:</i>	36"D desk may be planned with 6" recessed desk support and 24"D pedestals or end panels, or 29" or 35"W universal end panels with kneehole filler. 36"D worksurfaces do not accept privacy screens.
MW2 Worksurface 1 3/4" thick	B: worksurface does not include grommets	Plastic laminate worksurfaces are post-formed top and bottom, front and back.
S Worksurface type	R: worksurface includes 3" grommets recessed for use with 6" recessed desk support	All straight worksurfaces are 3/8" less than nominal depth for rear wire clearance or privacy screens.
36 Width	Specify surface finish	MW2- worksurfaces are supported by brackets with machine screws.
36 Depth	All worksurfaces are U.L.-listed.	
R Recessed grommets		
117 Surface finish		

Postformed Worksurfaces, 1 3/4" VDT corners

Dividends Horizon

description	type	w	d	h	pattern no.	lam.	V1	V2
Corner 	Corner grommet only	35 5/8"	17 3/8"	1 3/4"	MW2-V3618-A-()	\$1,468.	\$1,840.	\$2,597.
	Corner grommet only	35 5/8"	23 5/8"	1 3/4"	MW2-V3624-A-()	1,528.	1,865.	2,658.
	Corner grommet only	41 5/8"	23 5/8"	1 3/4"	MW2-V4224-A-()	1,582.	1,954.	2,769.
	Corner grommet only	41 5/8"	29 5/8"	1 3/4"	MW2-V4230-A-()	1,672.	2,069.	2,938.
	Corner grommet only	47 5/8"	23 5/8"	1 3/4"	MW2-V4824-A-()	1,868.	2,234.	3,263.
	Corner grommet only	47 5/8"	29 5/8"	1 3/4"	MW2-V4830-A-()	1,957.	2,404.	3,431.
Corner - 3 grommets 	3 Grommets	35 5/8"	23 3/8"	1 3/4"	MW2-V3624-C-()	1,649.	1,991.	2,770.
	3 Grommets	41 5/8"	23 5/8"	1 3/4"	MW2-V4224-C-()	1,702.	2,073.	2,891.
	3 Grommets	41 5/8"	29 5/8"	1 3/4"	MW2-V4230-C-()	1,792.	2,186.	3,061.
	3 Grommets	47 5/8"	23 5/8"	1 3/4"	MW2-V4824-C-()	1,984.	2,354.	3,379.
	3 Grommets	47 5/8"	29 5/8"	1 3/4"	MW2-V4830-C-()	2,078.	2,529.	3,553.

Postformed

Order Code	Specification Information	Application Notes
Example: MW2-V4830-C-117		
MW2 Worksurface 1 3/4" thick	<i>Grommets/no grommets:</i>	All VDT corner worksurfaces are bored to accept and are shipped with wire manager clips.
V VDT corner	A- VDT corner includes 3" grommet in back corner.	
48 Width	C- VDT corner includes 3" grommet in all three back corners.	
30 Depth of return	Specify surface finish.	VDT corners may be used interchangeably in desk and panel system applications. They must be supported by VDT support brackets on each back edge or cantilever bridging brackets on each side edge and a cantilever bracket on the back corner.
C Three grommets	VDT worksurfaces have threaded metal inserts at all desk support and bracket locations.	
117 Surface finish	MW2- worksurfaces are supported by brackets with machine screws.	
	All worksurfaces are U.L.-listed.	36"W x 18"D VDT corners accept 18"D returns, 36", 42", and 48"W x 24"D VDT corners accept 24"D returns, 42" and 48"W x 30"D VDT corners accept 30"D returns.


VDT corners are 3/8" less than nominal depth for rear wire clearance or privacy screens.

Plastic laminate worksurfaces are post-formed on front and back edges. 48" x 24" VDT corners have an inside radius, T-mold front edge that curves into an optimal 45° straight keyboard location.


Postformed Worksurfaces, 1 3/4" Rounded end, 30" deep

Dividends Horizon

description	type	w	d	h	pattern no.	lam.	V1	V2
30"D - End grommets		63"	30"	1 3/4"	MW2-R6330E()	\$2,291.	\$3,004.	\$4,265.
		75"	30"	1 3/4"	MW2-R7530E()	2,379.	3,133.	4,385.
		87"	30"	1 3/4"	MW2-R8730E()	2,545.	3,236.	4,594.




30"D - No grommets		63"	30"	1 3/4"	MW2-R6330B()(L/R)	2,164.	2,884.	4,143.
		75"	30"	1 3/4"	MW2-R7530B()(L/R)	2,253.	3,000.	4,260.
		87"	30"	1 3/4"	MW2-R8730B()(L/R)	2,425.	3,117.	4,470.



Order Code	Specification Information	Application Notes
Example: MW2-R8730E-117	<i>Grommets/no grommets:</i>	
MW2	Worksurface, 1 3/4" thick	
R	Rounded end	
87	Width	
30	Depth	
E	End grommets	
117	Surface finish	
	B- worksurface does not include grommets.	
	E- rounded end worksurface includes 3" grommet in each straight end corner.	
	R- rounded end worksurface includes 3" grommets recessed for use with 6" recessed desk support.	
	Specify surface finish.	
	Rounded end worksurfaces with recessed or no grommets are specified left or right to determine position of grommets and pedestal drilling. Rounded end when seated at desk defines L/R hand (Right hand shown above). All worksurfaces are U.L.-listed.	
	Recessed grommets align with desk support recessed 6".	
		Rounded end worksurfaces may be used to create fully enclosed desks or open table/desks with support column. For front modesty, use 48"W desk support with 63" rounded end, 60"W desk support with 75" rounded end; 72"W desk support with 87" rounded end.
		Use 18"D pedestal or end panel each end with 30"D rounded end with recessed grommets. Rounded end worksurfaces with end grommets are supported by 30"W or 36"W desk support and support column.
		Worksurfaces with grommets are bored to accept and are shipped with wire manager clips.
		Worksurfaces with end grommets may not be supported by conference end panels.
		Plastic laminate worksurfaces have radiused T-mold edge.
		Rounded end worksurfaces have threaded metal inserts for desk support, end panel each end, and at all bracket locations. End grommet worksurfaces have no pedestal inserts.
		MW2- worksurfaces are supported by brackets with machine screws.

Postformed Worksurfaces, 1 1/4" 18" Deep

Dividends Horizon



description	type	w	d	h	pattern no.	lam.	V1	V2
Straight, 18"D 	No grommet	30"	17 5/8"	1 1/4"	MU1-S3018-B-()	\$442.	\$684.	\$1,001.
	No grommet	36"	17 5/8"	1 1/4"	MU1-S3618-B-()	489.	737.	1,078.
	No grommet	42"	17 5/8"	1 1/4"	MU1-S4218-B-()	511.	799.	1,191.
	No grommet	48"	17 5/8"	1 1/4"	MU1-S4818-B-()	601.	882.	1,305.
	No grommet	54"	17 5/8"	1 1/4"	MU1-S5418-B-()	625.	934.	1,388.
	No grommet	60"	17 5/8"	1 1/4"	MU1-S6018-B-()	654.	990.	1,502.
	No grommet	66"	17 5/8"	1 1/4"	MU1-S6618-B-()	707.	1,103.	1,662.
	No grommet	72"	17 5/8"	1 1/4"	MU1-S7218-B-()	788.	1,235.	1,832.

Postformed

Order Code	Specification Information	Application Notes
Example: MU1-S4818-B-117	B: Worksurface does not include grommets.	18"D worksurfaces are used interchangeably in desk and panel system applications as shallow main surfaces, extensions, or credenza tops. They may be supported at each end by an 18" end support bracket, 18" cantilever bracket, 18"W conference end panel, 18"D pedestal, or 12"W end panel (MN2-E12) in conjunction with a desk support.
MU1 Worksurface 1 1/4" thick	Specify surface finish.	18"D worksurfaces with desk supports do not accept pedestals.
S Worksurface type	1 1/4" worksurfaces are 3-ply, solid core construction with threaded metal inserts at all end panel, desk support and bracket locations and pilot holes at pedestal locations.	All worksurfaces are 3/8" less than nominal depth for rear wire clearance or privacy screens.
48 Width	All worksurfaces are U.L.-listed.	Panel-supported 1 1/4" worksurfaces over 48" must be mid-span supported by MB2-C18 bracket, specified separately.
18 Depth	MU1- worksurfaces are supported by brackets with machine screws.	Suspended pedestals may not be used with 1 1/4" worksurfaces.
B No grommets		
117 Surface finish		

Postformed Worksurfaces, 1 1/4" 24" Deep



Dividends Horizon

description	type	w	d	h	pattern no.	lam.	V1	V2
Straight, 24"D 	Grommets	24"	23 5/8"	1 1/4"	MU1-S2424-A-()	\$559.	\$893.	\$1,228.
	Grommets	30"	23 5/8"	1 1/4"	MU1-S3024-A-()	607.	917.	1,284.
	Grommets	36"	23 5/8"	1 1/4"	MU1-S3624-A-()	633.	940.	1,311.
	Grommets	42"	23 5/8"	1 1/4"	MU1-S4224-A-()	719.	998.	1,417.
	Grommets	48"	23 5/8"	1 1/4"	MU1-S4824-A-()	741.	1,076.	1,588.
	Grommets	54"	23 5/8"	1 1/4"	MU1-S5424-A-()	803.	1,184.	1,699.
	Grommets	60"	23 5/8"	1 1/4"	MU1-S6024-A-()	852.	1,243.	1,782.
	Grommets	66"	23 5/8"	1 1/4"	MU1-S6624-A-()	934.	1,386.	1,976.
	Grommets	72"	23 5/8"	1 1/4"	MU1-S7224-A-()	1,018.	1,487.	2,172.
	Grommets	78"	23 5/8"	1 1/4"	MU1-S7824-A-()	1,107.	1,620.	2,322.
	Grommets	84"	23 5/8"	1 1/4"	MU1-S8424-A-()	1,179.	1,737.	2,492.
	Grommets	90"	23 5/8"	1 1/4"	MU1-S9024-A-()	1,253.	1,846.	2,658.
	Grommets	96"	23 5/8"	1 1/4"	MU1-S9624-A-()	1,369.	2,020.	2,910.
Straight, 24"D - No grommets 	No grommets	24"	23 5/8"	1 1/4"	MU1-S2424-B-()	442.	772.	1,112.
	No grommets	30"	23 5/8"	1 1/4"	MU1-S3024-B-()	489.	799.	1,168.
	No grommets	36"	23 5/8"	1 1/4"	MU1-S3624-B-()	511.	827.	1,191.
	No grommets	42"	23 5/8"	1 1/4"	MU1-S4224-B-()	601.	882.	1,305.
	No grommets	48"	23 5/8"	1 1/4"	MU1-S4824-B-()	625.	962.	1,472.
	No grommets	54"	23 5/8"	1 1/4"	MU1-S5424-B-()	682.	1,073.	1,585.
	No grommets	60"	23 5/8"	1 1/4"	MU1-S6024-B-()	736.	1,127.	1,662.
	No grommets	66"	23 5/8"	1 1/4"	MU1-S6624-B-()	816.	1,268.	1,862.
	No grommets	72"	23 5/8"	1 1/4"	MU1-S7224-B-()	901.	1,376.	2,052.
	No grommets	78"	23 5/8"	1 1/4"	MU1-S7824-B-()	980.	1,502.	2,203.
	No grommets	84"	23 5/8"	1 1/4"	MU1-S8424-B-()	1,059.	1,619.	2,377.
	No grommets	90"	23 5/8"	1 1/4"	MU1-S9024-B-()	1,132.	1,731.	2,541.
	No grommets	96"	23 5/8"	1 1/4"	MU1-S9624-B-()	1,246.	1,898.	2,793.

Order Code	Specification Information	Application Notes
Example: MU1-S3024-B-117	<i>Grommets/no grommets:</i>	24"D worksurfaces are used interchangeably as shallow main surfaces, extensions or credenza tops. They can be supported at each end by 24" end support bracket, 24" cantilever bracket, 24"W end panel, 18"D pedestal or end panel in conjunction with desk support.
MU1 Worksurface, 1 1/4" thick	A- Worksurfaces include 3" grommet in each back corner leading into desk support or wire manager.	Use 18"D pedestals with 24"D worksurfaces for full wire management capability in desk or panel applications.
S Straight worksurface	B- Worksurface does not include grommets.	All straight worksurfaces are 3/8" less than nominal depth for rear wire clearance or privacy screens.
30 Width	Specify surface finish.	Panel-supported 1 1/4" worksurfaces over 48" must be mid-span supported by MB2-C18 bracket, specified separately.
24 Depth	1 1/4" worksurfaces are 3-ply, solid core construction with threaded metal inserts at all end panel, desk support and bracket locations and pilot holes at pedestal locations.	Suspended pedestals may not be used with 1 1/4" worksurfaces.
B No grommets	Worksurfaces with grommets are bored to accept and are shipped with wire manager clips.	
117 Surface finish	All worksurfaces are U.L.-listed.	
	MU1- worksurfaces are supported by brackets with machine screws.	

Postformed Worksurfaces, 1 1/4" 30" Deep

Dividends Horizon



description	type	w	d	h	pattern no.	lam.	V1	V2
Straight, 30"D 	Grommets	30"	29 5/8"	1 1/4"	MU1-S3030-A-()	\$666.	\$967.	\$1,393.
	Grommets	36"	29 5/8"	1 1/4"	MU1-S3630-A-()	719.	1,026.	1,480.
	Grommets	42"	29 5/8"	1 1/4"	MU1-S4230-A-()	774.	1,109.	1,588.
	Grommets	48"	29 5/8"	1 1/4"	MU1-S4830-A-()	826.	1,184.	1,699.
	Grommets	54"	29 5/8"	1 1/4"	MU1-S5430-A-()	882.	1,295.	1,839.
	Grommets	60"	29 5/8"	1 1/4"	MU1-S6030-A-()	934.	1,386.	1,976.
	Grommets	66"	29 5/8"	1 1/4"	MU1-S6630-A-()	985.	1,464.	2,143.
	Grommets	72"	29 5/8"	1 1/4"	MU1-S7230-A-()	1,094.	1,601.	2,307.
	Grommets	78"	29 5/8"	1 1/4"	MU1-S7830-A-()	1,181.	1,737.	2,542.
	Grommets	84"	29 5/8"	1 1/4"	MU1-S8430-A-()	1,276.	1,872.	2,747.
	Grommets	90"	29 5/8"	1 1/4"	MU1-S9030-A-()	1,349.	1,988.	2,926.
	Grommets	96"	29 5/8"	1 1/4"	MU1-S9630-A-()	1,466.	2,160.	3,180.
Straight, 30"D - no grommets 	No Grommets	30"	29 5/8"	1 1/4"	MU1-S3030-B-()	549.	848.	1,279.
	No Grommets	36"	29 5/8"	1 1/4"	MU1-S3630-B-()	601.	908.	1,365.
	No Grommets	42"	29 5/8"	1 1/4"	MU1-S4230-B-()	654.	990.	1,472.
	No Grommets	48"	29 5/8"	1 1/4"	MU1-S4830-B-()	707.	1,073.	1,585.
	No Grommets	54"	29 5/8"	1 1/4"	MU1-S5430-B-()	758.	1,178.	1,725.
	No Grommets	60"	29 5/8"	1 1/4"	MU1-S6030-B-()	816.	1,268.	1,862.
	No Grommets	66"	29 5/8"	1 1/4"	MU1-S6630-B-()	867.	1,342.	2,026.
	No Grommets	72"	29 5/8"	1 1/4"	MU1-S7230-B-()	977.	1,483.	2,189.
	No Grommets	78"	29 5/8"	1 1/4"	MU1-S7830-B-()	1,061.	1,619.	2,425.
	No Grommets	84"	29 5/8"	1 1/4"	MU1-S8430-B-()	1,155.	1,752.	2,627.
	No Grommets	90"	29 5/8"	1 1/4"	MU1-S9030-B-()	1,236.	1,874.	2,809.
	No Grommets	96"	29 5/8"	1 1/4"	MU1-S9630-B-()	1,345.	2,042.	3,065.

Postformed

Order Code	Specification Information	Application Notes
Example: MU1-S3030B-117		
MU1 Worksurface, 1 1/4" thick		
S Straight worksurface		
30 Width		
30 Depth		
B No grommets		
117 Surface finish		
	<i>Grommets/no grommets:</i> A- Worksurfaces include 3" grommet in each back corner leading into desk support or wire manager. B- Worksurface does not include grommets. Specify surface finish. 1 1/4" worksurfaces are 3-ply, solid core construction with threaded metal inserts at all end panel, desk support and bracket locations and pilot holes at pedestal locations. Worksurfaces with grommets are bored to accept and are shipped with wire manager clips. All worksurfaces are U.L.-listed. MU1- worksurfaces are supported by brackets with machine screws.	Plastic laminate worksurfaces are post-formed top and bottom, front and back. 30"D worksurfaces are used interchangeably in desk and panel system applications as main surfaces, extensions or credenza tops. They can be supported at each end by 30" end support bracket, 30" cantilever bracket, 30" flat bracket, 30"W end panel, 24"D pedestal or end panel in conjunction with desk support, or 30"D pedestal. All straight worksurfaces are 3/8" less than nominal depth for rear wire clearance or privacy screens. Panel-supported 1 1/4" worksurfaces over 48" must be mid-span supported by MB2-C18 bracket, specified separately. Worksurfaces with grommets are bored to accept and are shipped with wire manager clips. Suspended pedestals may not be used with 1 1/4" worksurfaces.

Postformed Worksurfaces, 1 1/4" VDT corners



Dividends Horizon

description	type	w	d	h	pattern no.	lam.	V1	V2
Corner 	Corner grommet only	35 5/8"	17 5/8"	1 1/4"	MU1-V3618-A()	\$1,131.	\$1,483.	\$2,179.
	Corner grommet only	35 5/8"	23 5/8"	1 1/4"	MU1-V3624-A()	1,160.	1,511.	2,206.
	Corner grommet only	41 5/8"	23 5/8"	1 1/4"	MU1-V4224-A()	1,207.	1,565.	2,317.
	Corner grommet only	41 5/8"	29 5/8"	1 1/4"	MU1-V4230-A()	1,274.	1,646.	2,428.
	Corner grommet only	47 5/8"	23 5/8"	1 1/4"	MU1-V4824-A()	1,429.	1,776.	2,720.
	Corner grommet only	47 5/8"	29 5/8"	1 1/4"	MU1-V4830-A()	1,485.	1,916.	2,858.
Corner - 3 grommets 	3 Grommets	35 5/8"	23 5/8"	1 1/4"	MU1-V3624-C()	1,283.	1,628.	2,324.
	3 Grommets	41 5/8"	23 5/8"	1 1/4"	MU1-V4224-C()	1,332.	1,680.	2,434.
	3 Grommets	41 5/8"	29 5/8"	1 1/4"	MU1-V4230-C()	1,389.	1,760.	2,543.
	3 Grommets	47 5/8"	23 5/8"	1 1/4"	MU1-V4824-C()	1,544.	1,897.	2,844.
	3 Grommets	47 5/8"	29 5/8"	1 1/4"	MU1-V4830-C()	1,603.	2,030.	2,980.

Order Code	Specification Information	Application Notes	
Example: MU1-V4830-C-117	<i>Grommets/no grommets:</i>	VDT corners may be used interchangeably in desk and panel system applications. They may be supported by VDT end support brackets on each back edge; they may be supported by flat bracket or bridging bracket on each side edge.	VDT corners are 3/8" less than nominal depth for rear wire clearance or privacy screens.
MU1	Worksurface, 1 1/4" thick	A- VDT corner includes 3" grommet in back corner.	
V	VDT corner	C- VDT corner includes 3" grommet in all three back corners.	48" x 24" VDT corners have an inside radius, T-mold front edge that curves into an optimal 45° straight keyboard location.
48	Width	Specify surface finish.	
30	Depth of return	1 1/4" VDT corners are solid core construction with threaded metal inserts at desk support and all bracket locations.All worksurfaces are U.L.-listed.	
C	Three grommets		
117	Surface finish	MU1- worksurfaces are supported by brackets with machine screws.	Corner worksurfaces with equal rear edges have diagonal grain direction.

Postformed Worksurfaces, 1 1/4" split top VDT corners

Dividends Horizon

description	type	w	d	h	pattern no.	lam.	V1	V2
	Corner grommet only	41 5/8"	23 5/8"	1 1/4"	MU1-V42SS-A()	\$3,068.	\$3,404.	\$4,155.
	Corner grommet only	47 5/8"	23 5/8"	1 1/4"	MU1-V48SS-A()	3,282.	3,619.	4,562.
	Corner grommet only	47 5/8"	29 5/8"	1 1/4"	MU1-V48DS-A()	3,342.	3,756.	4,696.
	3 Grommets	41 5/8"	23 5/8"	1 1/4"	MU1-V42SS-C()	3,184.	3,520.	4,272.
	3 Grommets	47 5/8"	23 5/8"	1 1/4"	MU1-V48SS-C()	3,404.	3,736.	4,678.
	3 Grommets	47 5/8"	29 5/8"	1 1/4"	MU1-V48DS-C()	3,461.	3,877.	4,814.

Postformed

Order Code	Specification Information	Application Notes
Example: MU1-V48SS-A-117	<i>VDT Corner Depth:</i>	Split top worksurfaces include counterbalanced adjustable keyboard/ mouse support with fingertip control.
MU1 Worksurface, 1 1/4" thick	S- 24"D sides	
V VDT corner	D- 30"D sides	
48 Width		
S Depth	<i>Grommets/no grommets:</i>	Front surface adjusts from 5" below back surface to 7" above, and adjusts in tilt from -10° to +10°.
S Split top	A- Grommets in back corners of straight tops, one back corner of VDT	Split top surfaces may be panel supported or desk supported with standard brackets.
A Grommet	C- Grommets in all three back corners of VDT	
117 Surface finish	Specify surface finish. 1 1/4" VDT corners are solid core construction with threaded metal inserts at desk support and all bracket locations. All worksurfaces are U.L.-listed. MU1- worksurfaces are supported by brackets with machine screws.	Specify 18"D cantilever brackets with 23 5/8" split corners, and 24"D cantilever or bridging brackets with 29 5/8" D split corners.

48"W split-top VDT corners must be supported by VDT-end support kits in conjunction with cantilever brackets at side edges.


Corner worksurfaces with equal rear edges have diagonal grain direction.

Postformed Worksurfaces, 1 1/4"


Rounded end worksurfaces

Dividends Horizon

description	type	w	d	h	pattern no.	lam.	V1	V2
30"D rounded end - No grommets		62 5/8"	30"	1 1/4"	MU1-R6330B() (L/R)	\$1,649.	\$2,340.	\$3,502.
		74 5/8"	30"	1 1/4"	MU1-R7530B() (L/R)	1,704.	2,417.	3,576.



30"D rounded end - End grommets		62 5/8"	30"	1 1/4"	MU1-R6330E()	1,765.	2,458.	3,619.
		74 5/8"	30"	1 1/4"	MU1-R7530E()	1,825.	2,540.	3,701.



Order Code	Specification Information		Application Notes
Example: MU1-R6330E-117	<i>Grommets/no grommets:</i>		Rounded end worksurfaces are used interchangeably in desk and panel system applications as main surfaces or extensions. They may be supported by 30" end support brackets, 30" cantilever bracket, 30" flat bracket or 30" conference end panel, and by a support column at the rounded end.
MU1	Worksurface, 1 1/4" thick	E- rounded end worksurface includes 3" grommet in each straight end corner.	
R	Rounded end	R- rounded end worksurface includes 3" grommets recessed for use with 6" recessed desk support.	
63	Width	B- rounded end worksurface does not include grommets	
30	Depth		Use 18"D pedestal or end panel with desk support under rounded end worksurfaces with recessed grommets. Use 48"D desk support with 63" rounded end and 60"W desk support with 75" rounded end.
E	End grommets		
117	Surface finish		
	Specify surface finish. Rounded end worksurfaces with recessed or no grommets are specified left or right to determine position of grommets and pedestal drilling. Rounded end when seated at desk defines L/R hand (Right hand shown above).		Worksurfaces with end grommets may not be supported by conference end panel.
	1 1/4" worksurfaces are 3-ply, solid core construction with threaded metal inserts at all end panel, desk support and bracket locations and pilot holes at pedestal locations.		Suspended pedestals may not be used with 1 1/4" worksurfaces.
	MU1- worksurfaces are supported by brackets with machine screws.		Rounded end worksurfaces have threaded metal inserts for desk support, end panel each end, and at all bracket locations. End grommet worksurfaces have no pedestal inserts.
	All worksurfaces are U.L.-listed.		

Postformed Worksurfaces, 1 1/4" conference shapes

Dividends Horizon

description	type	w	d	h	pattern no.	lam.	V1	V2
Half round - Standard		30"	48"	1 1/4"	MU1-R3048-B-()	\$1,203.	\$1,719.	\$2,445.
								
Half round - With vertical panel		50 3/8"	48"	1 1/4"	MU1-R3050-B-()	1,336.	1,885.	2,695.
								

Postformed


Order Code	Specification Information	Application Notes
Example: MU1-R3050B-117		
MU1 Worksurface, 1 1/4" thick	<i>Grommets/no grommets:</i>	
R Rounded end	B- worksurface does not include grommets.	
30 Width	Specify surface finish.	
50 Depth		
B No grommet	1 1/4" worksurfaces are 3-ply, solid core construction with threaded metal inserts at all end panel, desk support and bracket locations and pilot holes at pedestal locations.	Half-round and extended half-round are used with back-to-back 24"D straight or VDT corner worksurfaces. Half round with vertical panel attaches to 24"D straight or VDT corner worksurfaces supported by vertical panel.
117 Surface finish	MU1- worksurfaces are supported by brackets with machine screws.	Conference worksurfaces must be supported by support column and flat bracket or bridging bracket to adjacent worksurface.
	Plastic laminate worksurfaces have radiused T mold edge.	
	All worksurfaces are U.L.-listed.	

Postformed Worksurfaces, 1 1/4"


P-shape curvilinear

Dividends Horizon

description	type	w	d	h	pattern no.	lam.	V1	V2
Rounded end left	24" D return	48"	72"	1 1/4"	MU1-P72SA()L	\$3,072.	\$3,946.	\$5,530.
	30" D return	48"	78"	1 1/4"	MU1-P78DA()L	3,201.	4,118.	5,766.



Rounded end right	24" D return	48"	72"	1 1/4"	MU1-P72SA()R	3,072.	3,946.	5,530.
	30" D return	48"	78"	1 1/4"	MU1-P78DA()R	3,201.	4,118.	5,766.







Order Code	Specification Information	Application Notes
Example: MU1-P72SA-117L	S- 24"D side edge	P-shape curvilinear worksurfaces may be used interchangeably in desk and panel system applications. They may be supported by a 48" VDT support bracket kit, or 48" desk support and 6" end panel, in conjunction with rounded end support column. Use flat bracket or bridging bracket to join to adjacent 1 1/4" work surface.
MU1 Worksurface, 1 1/4"	D- 30"D side edge	
P P-shape curvilinear	Specify surface finish.	
72 Overall length	1 1/4" curvilinear surfaces are solid core construction with threaded metal inserts at desk support and all bracket locations.	
S Depth of return	MU1- worksurfaces are supported by brackets with machine screws.	
A Grommets	All worksurfaces are U.L.-listed.	P-shape laminate surfaces have continuous T-mold edge in profile to match adjacent 1 1/4" worksurfaces.
117 Surface finish	All P-shape worksurfaces have 2 grommets at 48" end for use with 48" desk and overhead supports.	
L Rounded end left		

Postformed Worksurfaces, 1 1/4"

L-shape curvilinear


Dividends Horizon

description	type	w	d	h	pattern no.	lam.	V1	V2
24" D returns left and right 	3 grommet	42"	42"	1 1/4"	MU1-C4242SS()	\$1,406.	\$1,811.	\$2,537.
	3 grommet	48"	48"	1 1/4"	MU1-C4848SS()	1,532.	1,976.	2,760.
	3 grommet	48"	60"	1 1/4"	MU1-C4860SS()	1,742.	2,238.	3,138.
	3 grommet	48"	72"	1 1/4"	MU1-C4872SS()	1,997.	2,576.	3,613.
	3 grommet	60"	48"	1 1/4"	MU1-C6048SS()	1,742.	2,238.	3,138.
	3 grommet	72"	48"	1 1/4"	MU1-C7248SS()	1,997.	2,576.	3,613.
24" D return left, 30" D right 	3 grommet	48"	48"	1 1/4"	MU1-C4848SD()	1,532.	1,976.	2,760.
	3 grommet	48"	60"	1 1/4"	MU1-C4860SD()	1,742.	2,238.	3,138.
	3 grommet	48"	72"	1 1/4"	MU1-C4872SD()	1,997.	2,576.	3,613.
	3 grommet	60"	48"	1 1/4"	MU1-C6048SD()	1,742.	2,238.	3,138.
	3 grommet	72"	48"	1 1/4"	MU1-C7248SD()	1,997.	2,576.	3,613.
30" D return left, 24" D right 	3 grommet	48"	48"	1 1/4"	MU1-C4848DS()	1,532.	1,976.	2,760.
	3 grommet	48"	60"	1 1/4"	MU1-C4860DS()	1,742.	2,238.	3,138.
	3 grommet	48"	72"	1 1/4"	MU1-C4872DS()	1,997.	2,576.	3,613.
	3 grommet	60"	48"	1 1/4"	MU1-C6048DS()	1,742.	2,238.	3,138.
	3 grommet	72"	48"	1 1/4"	MU1-C7248DS()	1,997.	2,576.	3,613.
30" D returns left and right 	3 grommet	48"	48"	1 1/4"	MU1-C4848DD()	1,532.	1,976.	2,760.

Order Code	Specification Information	Application Notes
Example: MU1-C4860SD-117 MU1 Worksurface, 1 1/4" C L-shape curvilinear 48 Width left 60 Width right S Depth of left return D Depth of right return 117 Surface finish	Width dimension (W) refers to width of left-side back edge; depth dimension (D) indicates width of right-side back edge. S- 24"D side edge D- 30"D side edge Specify surface finish. 1 1/4" curvilinear surfaces are solid core construction with threaded metal inserts at desk support and all bracket locations. MU1- worksurfaces are supported by brackets with machine screws. All worksurfaces are U.L.-listed. All L-shape curvilinear worksurfaces have three grommets. Corner worksurfaces with equal rear edges have diagonal grain direction.	L-shape worksurfaces have grain direction along the longer back edge. L-shape curvilinear worksurfaces may be used interchangeably in desk and panel system applications. They may be supported by corner desk supports or by VDT end support bracket kit. Use cantilever bridging brackets or flat brackets to join to adjacent worksurfaces. L-shape surfaces may also be supported by MN1- end panel in conjunction with desk support, or cantilever bracket in panel planning. L-shape surfaces are veneer or post-formed plastic laminate on both back edges, matching profile T-mold on curvilinear front, and self-edge on sides. Curvilinear worksurfaces are available only in 1 1/4" thickness. L-shape surfaces are 3/8" less than nominal depth for rear wire clearance or privacy screens. If specifying privacy screens on both back edges, one or both must be 48" back-of-VDT type.

120° corners

90° return


description	w	return	h	pattern no.	lam.	V1	V2
90° return Left hand - grommet	36"	24"	1 1/4"	MU1-Y36S-AL-() ()	\$1,058.	\$1,482.	\$1,801.
	42"	24"	1 1/4"	MU1-Y42S-AL-() ()	1,114.	1,793.	2,369.
	48"	24"	1 1/4"	MU1-Y48S-AL-() ()	1,240.	1,975.	2,967.
	60"	24"	1 1/4"	MU1-Y60S-AL-() ()	1,508.	n/a	n/a
90° return Right hand - grommet	36"	24"	1 1/4"	MU1-Y36S-AR-() ()	1,058.	1,482.	1,801.
	42"	24"	1 1/4"	MU1-Y42S-AR-() ()	1,114.	1,793.	2,369.
	48"	24"	1 1/4"	MU1-Y48S-AR-() ()	1,240.	1,975.	2,967.
	60"	24"	1 1/4"	MU1-Y60S-AR-() ()	1,508.	n/a	n/a
Transitional 	24"		1 1/4"	MU1-YTS-() ()	839.	1,103.	1,431.

Order Code	Specification Information	Application Notes
Example: MU1-Y48S-A-R-L-117	Width dimension (w) refers to width of both back edges.	Worksurfaces are 3/8" less than nominal depth for rear wire clearance or privacy screens.
MU1 Worksurface, 1 1/4" thick	Specify surface finish.	
Y 120° corner, 90° returns	1 1/4" worksurfaces are solid core construction with threaded metal inserts at desk supports and all standard bracket locations.	120° worksurfaces with 90° returns are used mainly in panel system applications. They can be supported at each end with 24" end support brackets, 24" cantilever bracket, 24"W end panel, 18"D and 24"D pedestal or end panel in conjunction with desk supports.
48 Width		Use cantilever bridging brackets to join to adjacent worksurface or to transitional 120° worksurface.
S 24"D return		Transitional worksurfaces connect two 120° corner tops with 90° returns.
A Grommets		Corner worksurfaces have diagonal grain direction.
R Right hand		
L Laminate	MU1- worksurfaces are supported by brackets with machine screws.	
117 Surface finish	Grommets/no grommets:	
	A- worksurface includes 2 grommets in 2 back corners, creating Left- and Right-hand applications (see illustration).	120° corner is supported by a standard (90°) 24"D cantilever bracket.
	B- worksurface does not include grommets. Worksurfaces with no grommets are not handed.	


120° corners

Meeting Corners

description	w	return	h	pattern no.	lam.
Meeting corner Left hand - grommet	48"	24"	1 1/4"	MU1-M48S-AL-() ()	\$1,279.



Meeting corner Right hand - grommet	48"	24"	1 1/4"	MU1-M48S-AR-() ()	1,279.
--	-----	-----	--------	----------------------------	--------





Postformed

Order Code	Specification Information	Application Notes
Example: MU1-M48S-A-L-L-117	Width dimension (w) refers to width of smaller back edge. Total width of back edge with rounded meeting area is 62 1/2".	Worksurfaces are 3/8" less than nominal depth for rear wire clearance or privacy screens.
MU1 Worksurface, 1 1/4" thick		
M Meeting corner		120° meeting worksurfaces are used mainly in panel system applications. Support at the rounded meeting end with a support column, specified separately. They can be supported at the other end by 24" end support brackets, 24" cantilever bracket, 24"W end panel, 18"D and 24"D pedestal or end panel in conjunction with desk supports. Network straight desk support may be used under the 48W back edge.
48 Width	Specify surface finish.	120° corner is supported by 24"D cantilever bracket.
S 24"D return		Use 24"D cantilever bridging brackets to join to adjacent worksurfaces.
A Grommets	1 1/4" worksurfaces are solid core construction with threaded metal inserts at desk supports and all standard bracket locations.	
L Left hand		
L Laminate	MU1- worksurfaces are supported by brackets with machine screws.	
117 Surface finish	Grommets/no grommets:	
	A- worksurface includes 2 grommets in 2 back corners.	
	B- worksurface does not include grommets.	

Postformed Options worksurfaces 1 1/4" 18" Deep

Dividends Horizon



description	w	d	h	pattern no.	lam.	V1	V2
Straight, 18"D - Grommet 	30"	17 5/8"	1 1/4"	LU1-S3018-A-()	\$359.	\$601.	\$898.
	36"	17 5/8"	1 1/4"	LU1-S3618-A-()	379.	623.	950.
	42"	17 5/8"	1 1/4"	LU1-S4218-A-()	426.	699.	1,074.
	48"	17 5/8"	1 1/4"	LU1-S4818-A-()	472.	737.	1,143.
	54"	17 5/8"	1 1/4"	LU1-S5418-A-()	514.	814.	1,243.
	60"	17 5/8"	1 1/4"	LU1-S6018-A-()	564.	887.	1,372.
	66"	17 5/8"	1 1/4"	LU1-S6618-A-()	607.	979.	1,520.
	72"	17 5/8"	1 1/4"	LU1-S7218-A-()	652.	1,076.	1,646.
	78"	17 5/8"	1 1/4"	LU1-S7818-A-()	698.	1,131.	1,735.
	84"	17 5/8"	1 1/4"	LU1-S8418-A-()	741.	1,188.	1,820.
	90"	17 5/8"	1 1/4"	LU1-S9018-A-()	787.	1,268.	1,940.
	96"	17 5/8"	1 1/4"	LU1-S9618-A-()	833.	1,336.	2,049.
	108"	17 5/8"	1 1/4"	LU1-S10818-A-()	902.	1,431.	2,191.
	120"	17 5/8"	1 1/4"	LU1-S12018-A-()	985.	1,543.	2,377.
Straight, 18"D - No Grommet 	30"	17 5/8"	1 1/4"	LU1-S3018-B-()	314.	557.	849.
	36"	17 5/8"	1 1/4"	LU1-S3618-B-()	339.	580.	902.
	42"	17 5/8"	1 1/4"	LU1-S4218-B-()	379.	652.	1,028.
	48"	17 5/8"	1 1/4"	LU1-S4818-B-()	427.	699.	1,103.
	54"	17 5/8"	1 1/4"	LU1-S5418-B-()	472.	772.	1,200.
	60"	17 5/8"	1 1/4"	LU1-S6018-B-()	515.	842.	1,325.
	66"	17 5/8"	1 1/4"	LU1-S6618-B-()	564.	935.	1,474.
	72"	17 5/8"	1 1/4"	LU1-S7218-B-()	607.	1,030.	1,601.
	78"	17 5/8"	1 1/4"	LU1-S7818-B-()	653.	1,090.	1,686.
	84"	17 5/8"	1 1/4"	LU1-S8418-B-()	698.	1,145.	1,776.
	90"	17 5/8"	1 1/4"	LU1-S9018-B-()	745.	1,226.	1,895.
	96"	17 5/8"	1 1/4"	LU1-S9618-B-()	787.	1,293.	2,010.
	108"	17 5/8"	1 1/4"	LU1-S10818-B-()	857.	1,388.	2,148.
	120"	17 5/8"	1 1/4"	LU1-S12018-B-()	947.	1,505.	2,332.

Order Code	Specification Information	Application Notes
Example: LU1-S4818-B-117	<i>Grommet/no grommet:</i>	18"D worksurfaces are used in panel system applications as shallow main surfaces, extensions or credenza tops. They may be supported at each end by an 18" end support bracket, 18" cantilever bracket, 18"W desk end panel or 18"D pedestal.
LU1 Worksurface, 1 1/4" thick	A- worksurface includes one edge grommet	
S Straight worksurface	B- worksurface does not include grommet	Options worksurfaces cannot be used in conjunction with Network desk supports.
48 Width		
18 Depth		All straight worksurfaces are 3/8" less than nominal depth for rear wire clearance.
B No grommet		
117 Surface finish		Panel-supported 1 1/4" worksurfaces over 48" must be mid-span supported by MB2-C18 bracket, specified separately.
	Specify surface finish.	Panel-supported 1 1/4" worksurfaces over 96" must be pedestal or MB2-C24 cantilever bracket supported every 48".
	1 1/4" Options worksurfaces are 3-ply, solid core construction with pilot holes at all pedestal, end panel, and bracket locations.	
	Edge grommets are centered at rear of worksurface.	Suspended pedestals may not be used with 1 1/4" worksurfaces.
	LU1- worksurfaces are supported by brackets with wood screws.	

Postformed Options worksurfaces 1 1/4" 24" Deep

Dividends Horizon



Postformed

description	w	d	h	pattern no.	lam.	V1	V2
Straight, 24"D - Grommet 	120"	23 5/8"	1 1/4"	LU1-S12024-A-()	\$1,082.	\$1,717.	\$2,608.
	24"	23 5/8"	1 1/4"	LU1-S2424-A-()	404.	722.	1,041.
	30"	23 5/8"	1 1/4"	LU1-S3024-A-()	426.	746.	1,073.
	36"	23 5/8"	1 1/4"	LU1-S3624-A-()	451.	776.	1,093.
	42"	23 5/8"	1 1/4"	LU1-S4224-A-()	495.	800.	1,168.
	48"	23 5/8"	1 1/4"	LU1-S4824-A-()	542.	860.	1,320.
	54"	23 5/8"	1 1/4"	LU1-S5424-A-()	585.	957.	1,444.
	60"	23 5/8"	1 1/4"	LU1-S6024-A-()	632.	1,006.	1,516.
	66"	23 5/8"	1 1/4"	LU1-S6624-A-()	678.	1,108.	1,669.
	72"	23 5/8"	1 1/4"	LU1-S7224-A-()	722.	1,175.	1,823.
	78"	23 5/8"	1 1/4"	LU1-S7824-A-()	762.	1,209.	1,899.
	84"	23 5/8"	1 1/4"	LU1-S8424-A-()	813.	1,316.	2,003.
	90"	23 5/8"	1 1/4"	LU1-S9024-A-()	853.	1,403.	2,131.
	96"	23 5/8"	1 1/4"	LU1-S9624-A-()	902.	1,481.	2,250.
	108"	23 5/8"	1 1/4"	LU1-S10824-A-()	985.	1,572.	2,410.
Straight, 24"D - No Grommet 	120"	23 5/8"	1 1/4"	LU1-S12024-B-()	1,034.	1,671.	2,563.
	24"	23 5/8"	1 1/4"	LU1-S2424-B-()	359.	676.	1,006.
	30"	23 5/8"	1 1/4"	LU1-S3024-B-()	379.	704.	1,026.
	36"	23 5/8"	1 1/4"	LU1-S3624-B-()	407.	729.	1,049.
	42"	23 5/8"	1 1/4"	LU1-S4224-B-()	451.	754.	1,121.
	48"	23 5/8"	1 1/4"	LU1-S4824-B-()	495.	815.	1,279.
	54"	23 5/8"	1 1/4"	LU1-S5424-B-()	543.	916.	1,399.
	60"	23 5/8"	1 1/4"	LU1-S6024-B-()	585.	960.	1,470.
	66"	23 5/8"	1 1/4"	LU1-S6624-B-()	633.	1,060.	1,626.
	72"	23 5/8"	1 1/4"	LU1-S7224-B-()	678.	1,130.	1,781.
	78"	23 5/8"	1 1/4"	LU1-S7824-B-()	722.	1,166.	1,857.
	84"	23 5/8"	1 1/4"	LU1-S8424-B-()	765.	1,272.	1,959.
	90"	23 5/8"	1 1/4"	LU1-S9024-B-()	813.	1,364.	2,086.
	96"	23 5/8"	1 1/4"	LU1-S9624-B-()	857.	1,434.	2,207.
	108"	23 5/8"	1 1/4"	LU1-S10824-B-()	947.	1,527.	2,366.

Order Code	Specification Information	Application Notes
Example: LU1-S3024-B-117	<i>Grommet/no grommet:</i>	Options worksurfaces cannot be used in conjunction with Network desk supports.
LU1 Worksurface, 1 1/4" thick	A- worksurface includes one edge grommet	All straight worksurfaces are 3/8" less than nominal depth for rear wire clearance.
S Straight worksurface	B- worksurface does not include grommet	
30 Width	Specify surface finish.	Panel-supported 1 1/4" worksurfaces over 48" must be mid-span supported by MB2-C18 bracket, specified separately.
24 Depth	1 1/4" Options worksurfaces are 3-ply, solid core construction with pilot holes at all pedestal, end panel, and bracket locations.	Panel-supported 1 1/4" worksurfaces over 96" must be pedestal or MB2-C24 cantilever bracket supported every 48".
B No grommet	Edge grommets are centered at rear of worksurface.	Suspended pedestals may not be used with 1 1/4" worksurfaces.
117 Surface finish	LU1- worksurfaces are supported by brackets with wood screws.	

Postformed Options worksurfaces 1 1/4" 30" Deep

Dividends Horizon





description	w	d	h	pattern no.	lam.	V1	V2
Straight, 30"D - Grommet 	30"	29 5/8"	1 1/4"	LU1-S3030-A-()	\$472.	\$756.	\$1,169.
	36"	29 5/8"	1 1/4"	LU1-S3630-A-()	514.	813.	1,240.
	42"	29 5/8"	1 1/4"	LU1-S4230-A-()	564.	887.	1,338.
	48"	29 5/8"	1 1/4"	LU1-S4830-A-()	607.	956.	1,439.
	54"	29 5/8"	1 1/4"	LU1-S5430-A-()	652.	1,053.	1,566.
	60"	29 5/8"	1 1/4"	LU1-S6030-A-()	698.	1,127.	1,689.
	66"	29 5/8"	1 1/4"	LU1-S6630-A-()	741.	1,192.	1,843.
	72"	29 5/8"	1 1/4"	LU1-S7230-A-()	813.	1,289.	1,962.
	78"	29 5/8"	1 1/4"	LU1-S7830-A-()	853.	1,347.	2,063.
	84"	29 5/8"	1 1/4"	LU1-S8430-A-()	902.	1,421.	2,175.
	90"	29 5/8"	1 1/4"	LU1-S9030-A-()	947.	1,495.	2,270.
	96"	29 5/8"	1 1/4"	LU1-S9630-A-()	985.	1,572.	2,388.
Straight, 30"D - No grommet 	30"	29 5/8"	1 1/4"	LU1-S3030-B-()	427.	721.	1,123.
	36"	29 5/8"	1 1/4"	LU1-S3630-B-()	472.	770.	1,196.
	42"	29 5/8"	1 1/4"	LU1-S4230-B-()	515.	842.	1,295.
	48"	29 5/8"	1 1/4"	LU1-S4830-B-()	564.	912.	1,395.
	54"	29 5/8"	1 1/4"	LU1-S5430-B-()	607.	1,012.	1,522.
	60"	29 5/8"	1 1/4"	LU1-S6030-B-()	653.	1,082.	1,649.
	66"	29 5/8"	1 1/4"	LU1-S6630-B-()	698.	1,150.	1,798.
	72"	29 5/8"	1 1/4"	LU1-S7230-B-()	765.	1,244.	1,922.
	78"	29 5/8"	1 1/4"	LU1-S7830-B-()	813.	1,310.	2,022.
	84"	29 5/8"	1 1/4"	LU1-S8430-B-()	857.	1,380.	2,133.
	90"	29 5/8"	1 1/4"	LU1-S9030-B-()	902.	1,452.	2,230.
	96"	29 5/8"	1 1/4"	LU1-S9630-B-()	947.	1,527.	2,346.

Order Code	Specification Information	Application Notes
Example: LU1-S3030B-117	<i>Grommets/no grommets:</i>	30"D worksurfaces are used in panel system applications as main surfaces, extensions or credenza tops. They can be supported at each end by 30" end support bracket, 30" cantilever bracket or 30"W end panel.
LU1 Worksurface, 1 1/4" thick	A- worksurface includes one edge grommet	Options worksurfaces cannot be used in conjunction with Network desk supports.
S Straight worksurface	B- worksurface does not include grommets	
30 Width		
30 Depth	Specify surface finish.	All straight worksurfaces are 3/8" less than nominal depth for rear wire clearance.
B No grommets	1 1/4" Options worksurfaces are 3-ply, solid core construction with pilot holes at all pedestal, end panel, and bracket locations.	Panel-supported 1 1/4" worksurfaces over 48" must be mid-span supported by MB2-C24 bracket, specified separately.
117 Surface finish	Edge grommets are centered at rear of worksurface.	Suspended pedestals may not be used with 1 1/4" worksurfaces.
	LU1- worksurfaces are supported by brackets with wood screws.	

Postformed Options worksurfaces 1 1/4"

Trapezoidal

Dividends Horizon

description	w	d	h	pattern no.	lam.	V1	V2
Right hand - grommet 	48"	30"/24"	1 1/4"	LU1-T48A-R-()	\$762.	\$1,088.	\$1,521.
	54"	30"/24"	1 1/4"	LU1-T54A-R-()	970.	1,381.	1,932.
	60"	30"/24"	1 1/4"	LU1-T60A-R-()	1,177.	1,675.	2,346.
	72"	30"/24"	1 1/4"	LU1-T72A-R-()	1,386.	1,969.	2,752.
Left hand - grommet 	48"	30"/24"	1 1/4"	LU1-T48A-L-()	762.	1,088.	1,521.
	54"	30"/24"	1 1/4"	LU1-T54A-L-()	970.	1,381.	1,932.
	60"	30"/24"	1 1/4"	LU1-T60A-L-()	1,177.	1,675.	2,346.
	72"	24"/30"	1 1/4"	LU1-T72A-L-()	1,386.	1,969.	2,752.
Right hand - no grommet 	48"	30"/24"	1 1/4"	LU1-T48B-R-()	723.	1,028.	1,434.
	54"	30"/24"	1 1/4"	LU1-T54B-R-()	926.	1,320.	1,850.
	60"	30"/24"	1 1/4"	LU1-T60B-R-()	1,132.	1,619.	2,256.
	72"	30"/24"	1 1/4"	LU1-T72B-R-()	1,339.	1,905.	2,671.
Left hand - no grommet 	48"	30"/24"	1 1/4"	LU1-T48B-L-()	723.	1,028.	1,434.
	54"	30"/24"	1 1/4"	LU1-T54B-L-()	926.	1,320.	1,850.
	60"	30"/24"	1 1/4"	LU1-T60B-L-()	1,132.	1,619.	2,256.
	72"	30"/24"	1 1/4"	LU1-T72B-L-()	1,339.	1,905.	2,671.


Postformed

Order Code	Specification Information	Application Notes
Example: LU1-T48B-R-117		
LU1 Worksurface, 1 1/4" thick	Grommets/ no grommets	1 1/4" Options worksurfaces are 3-ply solid core construction with pilot holes at all pedestal, end panel and bracket locations.
T Trapezoidal	A- worksurface includes one edge grommet	
48 Width	B- worksurface does not include grommets	LU1- worksurfaces are supported by brackets with wood screws.
B No grommets	Specify surface finish.	Trapezoidal worksurfaces must be supported at each end by a pedestal, cantilever or cantilever bridging bracket with a maximum span of 48" between supports. Panel-supported worksurfaces over 48" must be mid-span supported by MB2-C18 brackets, specified separately.
R Right hand	Edge grommets are centered at rear of worksurface. Right-and-Left and are defined by applying trapezoidal tops as returns from rectilinear worksurfaces.	Options worksurfaces cannot be used in conjunction with Network desk supports.
117 Surface finish	R- Right hand 30" D Left, 24" D Right edge L- Left hand 24" D Left, 30" D Right edge	All worksurfaces are 3/8" less than nominal depth for rear wire clearance or privacy screens.

Postformed Options worksurfaces 1 1/4"

VDT corners and split-top surfaces

Dividends Horizon





description	type	w	d	h	pattern no.	lam.	V1	V2
Corner 	Corner grommet only	36"	17 5/8"	1 1/4"	LU1-V3618-A()	\$857.	\$1,192.	\$1,856.
	Corner grommet only	36"	23 5/8"	1 1/4"	LU1-V3624-A()	878.	1,214.	1,876.
	Corner grommet only	42"	23 5/8"	1 1/4"	LU1-V4230-A()	923.	1,264.	1,978.
	Corner grommet only	42"	29 5/8"	1 1/4"	LU1-V4224-A()	970.	1,332.	2,073.
	Corner grommet only	48"	23 5/8"	1 1/4"	LU1-V4824-A()	1,087.	1,416.	2,317.
	Corner grommet only	48"	29 5/8"	1 1/4"	LU1-V4830-A()	1,127.	1,537.	2,438.

Order Code	Specification Information	Application Notes
Example: LU1-V4830-A-117		
LU1 Worksurface, 1 1/4" thick	Grommet/no grommet: A- VDT corner includes one edge grommet in back corner. Straight split top has one center back edge grommet. Specify surface finish. 1 1/4" Options worksurfaces are solid core construction with pilot holes at all bracket locations. LU1- worksurfaces are supported by brackets with wood screws.	VDT corners and split top straight surfaces are used in panel system applications. Options VDT corners may be supported by left or right hand 24" cantilever brackets at the rear corner, and cantilever bridging bracket on each side edge (see page 0). Options straight split top should be supported by 18"D cantilever bracket. 48"W split-top corners must be supported by VDT- end support brackets kits in conjunction with cantilever brackets at side edges.
V VDT corner		
48 Width		
30 Depth of return		
A Corner grommet		
117 Specify finish		36"W x 18"D VDT corners accept 18"D returns, 36", 42", and 48"W x 24"D VDT corners accept 24"D returns, 42" and 48"W x 30"D VDT corners accept 30"D returns. VDT corners are 3/8" less than nominal depth for rear wire clearance. Split top corners have counterbalanced adjustable keyboard/mouse surface with fingertip control. Front surface adjusts from 5" below to 7" above back surface, and adjusts in tilt from -10° to +10°.
		Corner worksurfaces with equal rear edges have diagonal grain direction.

Postformed Options worksurfaces 1 1/4"

L-shape curvilinear

Dividends Horizon

description	type	w	d	h	pattern no.	lam.	V1	V2
24" D returns left and right 	2 grommet	48"	60"	1 1/4"	LU1-C4872SS()	\$1,523.	\$2,075.	\$3,057.
	2 grommet	48"	72"	1 1/4"	LU1-C4860SS()	1,325.	1,801.	2,658.
	2 grommet	60"	48"	1 1/4"	LU1-C7248SS()	1,523.	2,075.	3,057.
	2 grommet	72"	48"	1 1/4"	LU1-C6048SS()	1,325.	1,801.	2,658.
	Corner grommet	42"	42"	1 1/4"	LU1-C4242SS()	1,072.	1,462.	2,147.
	Corner grommet	48"	48"	1 1/4"	LU1-C4848SS()	1,169.	1,591.	2,340.
24" D returns left, 30" D right 	2 grommets	48"	60"	1 1/4"	LU1-C4860SD()	1,325.	1,801.	2,658.
	2 grommets	48"	72"	1 1/4"	LU1-C4872SD()	1,523.	2,075.	3,057.
	2 grommets	60"	48"	1 1/4"	LU1-C6048SD()	1,325.	1,801.	2,658.
	2 grommets	72"	48"	1 1/4"	LU1-C7248SD()	1,523.	2,075.	3,057.
	Corner grommet	48"	48"	1 1/4"	LU1-C4848SD()	1,169.	1,591.	2,340.
30" D returns left and right 	Corner grommet	48"	48"	1 1/4"	LU1-C4848DD()	1,169.	1,591.	2,340.
30" D returns left, 24" D right 	2 grommets	48"	60"	1 1/4"	LU1-C4860DS()	1,325.	1,801.	2,658.
	2 grommets	48"	72"	1 1/4"	LU1-C4872DS()	1,523.	2,075.	3,057.
	2 grommets	60"	48"	1 1/4"	LU1-C6048DS()	1,325.	1,801.	2,658.
	2 grommets	72"	48"	1 1/4"	LU1-C7248DS()	1,523.	2,075.	3,057.
	Corner grommet	48"	48"	1 1/4"	LU1-C4848DS()	1,169.	1,591.	2,340.


Postformed

Order Code	Specification Information	Application Notes
Example: LU1-C4860SD-117		
LU1 Options worksurface, 1 1/4"	Width dimension (W) refers to width of left-side back edge; depth dimension (D) indicates width of right-side back edge.	Options L-shaped curvilinear worksurfaces may be supported by left- or right-hand cantilever brackets at the rear corner and cantilever bridging bracket on each side edge. Use mid-span support whenever Options worksurfaces span more than 48".
C L-shape curvilinear		
48 Width left	S- 24"D side edge D- 30"D side edge	
60 Width right		
S Depth of left return	Specify surface finish.	
D Depth of right return	1 1/4" curvilinear surfaces are solid core construction with pilot holes at all bracket locations.	L-shape surfaces are veneer or post-formed plastic laminate on both back edges, matching profile T-mold on curvilinear front, and self-edge on sides.
117 Surface finish	LU1- worksurfaces are supported by brackets with wood screws.	
	Corner worksurfaces with equal rear edges have diagonal grain direction.	
		Curvilinear worksurfaces are available only in 1 1/4" thickness.
		L-shape surfaces are 3/8" less than nominal depth for rear wire clearance or privacy screens.

Postformed Options worksurfaces 1 1/4"

Rounded end and conference shapes

Dividends Horizon





description	type	w	d	h	pattern no.	lam.	V1	V2
Half round 	With vertical panel	30"	50 5/8"	1 1/4"	LU1-R3050-B-()	\$921.	\$1,406.	\$2,102.
30"D rounded end 	No grommets	62 5/8"	30"	1 1/4"	LU1-R6330B()(L/R)	1,253.	1,909.	3,038.
	No grommets	74 5/8"	30"	1 1/4"	LU1-R7530B()(L/R)	1,298.	1,979.	3,086.

Order Code	Specification Information	Application Notes
Example: LU1-R6330B-117-L		
LU1 Options worksurface, 1 1/4" thick	<i>Grommets/no grommets:</i> B- worksurface does not include grommets.	Rounded end worksurfaces are specified left or right to determine position of pedestal drilling. Rounded end when seated at desk defines L/R hand (Right hand shown above). All worksurfaces are U.L.-listed.
R Rounded end	Specify surface finish.	Rounded end worksurfaces may be supported by 30" end support brackets, 30" flat bracket or 30" conference end panel, and by a support column at the rounded end.
63 Width	1 1/4" worksurfaces are 3-ply, solid core construction. Plastic laminate worksurfaces have radiused T mold edge.	Suspended pedestals may not be used with 1 1/4" worksurfaces.
30 Depth	Rounded end worksurfaces have a flat self-edge in the straight end.	Conference worksurfaces must be supported by support column and flat bracket or bridging bracket to adjacent desk.
B No grommets	LU1- worksurfaces are supported by brackets with wood screws.	Half round with vertical panel attaches to 24"D straight or VDT corner worksurfaces supported by vertical panel.
117 Surface finish		
L Left hand		

Postformed Options worksurfaces 1 1/4"

Wave-end surfaces

Dividends Horizon

description	w	d	h	pattern no.	lam.
Left wave-end - Grommet 	36"	29 5/8"	1 1/4"	LU1-W36AL ()	\$1,103.
	42"	29 5/8"	1 1/4"	LU1-W42AL ()	1,169.
	48"	29 5/8"	1 1/4"	LU1-W48AL ()	1,238.
Left wave-end - No grommets 	36"	29 5/8"	1 1/4"	LU1-W36BL ()	1,082.
	42"	29 5/8"	1 1/4"	LU1-W42BL ()	1,146.
	48"	29 5/8"	1 1/4"	LU1-W48BL ()	1,218.
Right wave-end - Grommet 	36"	29 5/8"	1 1/4"	LU1-W36AR ()	1,103.
	42"	29 5/8"	1 1/4"	LU1-W42AR ()	1,169.
	48"	29 5/8"	1 1/4"	LU1-W48AR ()	1,238.
Right wave-end - No grommets 	36"	29 5/8"	1 1/4"	LU1-W36BR ()	1,082.
	42"	29 5/8"	1 1/4"	LU1-W42BR ()	1,146.
	48"	29 5/8"	1 1/4"	LU1-W48BR ()	1,218.

Postformed



Order Code	Specification Information	Application Notes
Example: LU1-W48AL-117	1 1/4" curvilinear surfaces are solid core construction with pilot holes at bracket and pedestal locations.	Options wave-end curvilinear worksurfaces are for panel planning only and cannot be used in conjunction with Network desk supports.
LU1 Options worksurface, 1 1/4"		
W Wave-end curvilinear	LU1- worksurfaces are supported by brackets with wood screws.	Use cantilever bridging bracket to join to adjacent 1 1/4" worksurface.
48 Width		
A With grommets	<i>Grommets/no grommets:</i>	Wave-end surfaces are post-formed on back edge, matching profile T-mold on curvilinear front, and self-edge on sides.
L Left	A- Worksurface includes one edge grommet	
117 Surface finish	B- Worksurface does not include grommets	Wave-end surfaces are available only in plastic laminate, 1 1/4" thickness.
	Specify surface finish.	Wave-end surfaces are nominal 30"D at left or right, and align with 24"D surface at the other end.
	Edge grommets are centered at rear of worksurface.	

Postformed Options worksurfaces 1 1/4"

Dividends Horizon

120° corners

90° return


description	w	return	h	pattern no.	lam.	V1	V2
 90° return	36"	24"	1 1/4"	LU1-Y36S-B()	\$992.	\$1,399.	\$1,697.
	42"	24"	1 1/4"	LU1-Y42S-B()	1,049.	1,697.	2,237.
	48"	24"	1 1/4"	LU1-Y48S-B()	1,162.	1,862.	2,803.
	60"	24"	1 1/4"	LU1-Y60S-B()	1,418.	n/a	n/a
 Diamond	36"	24"	1 1/4"	LU1-D36S-B()	980.	1,415.	1,746.
	42"	24"	1 1/4"	LU1-D42S-B()	1,089.	1,729.	2,331.
	48"	24"	1 1/4"	LU1-D48S-B()	1,192.	1,935.	2,936.
 Transitional	24"	24"	1 1/4"	LU1-YTS-()	762.	1,001.	1,299.

Order Code	Specification Information	Application Notes
Example: LU1-Y48S-B-L-L-117	Width dimensions (w) refers to width of both back edges.	Worksurfaces are 3/8" less than nominal depth for rear wire clearance.
LU1 Options worksurface, 1 1/4" thick	Specify surface finish.	
Y 120° corner, 90° returns	1 1/4" Options worksurfaces are solid core construction with pilot holes at standard support locations.	120° Postformed Options worksurfaces with 90° returns are used in panel system applications only. They can be supported at each end by 24" end support brackets, 24" cantilever bracket or 18"D and 24"D pedestals. 120° corner is supported by standard (90°) 24"D cantilever bracket.
48 Width	120° Options worksurfaces are available without grommets only.	Order brackets with wood screws for Postformed Options worksurfaces.
S 24"D return	LU1- worksurfaces are supported by brackets with wood screws.	Corner worksurfaces have diagonal grain direction.
B No Grommets		
L Left hand		
L Laminate		
117 Surface finish		


120° corners

Meeting Corners

description	w	return	h	pattern no.	lam.	V1	V2
Meeting corner Right hand - no grommets	48"	24"	1 1/4"	LU1-M48S-BRL()	\$1,197.	n/a	n/a



Meeting corner Left hand - no grommets	48"	24"	1 1/4"	LU1-M48S-BLL()	1,197.	n/a	n/a
---	-----	-----	--------	------------------------	--------	-----	-----



Postformed

Order Code	Specification Information	Application Notes
Example: LU1-M48S-B-L-L-117		
LU1 Options worksurface, 1 1/4" thick	Width dimension (w) refers to width of smaller back edge. Total width of back edge with rounded meeting area is 62 1/2".	Worksurfaces are 3/8" less than nominal depth for rear wire clearance or privacy screens.
M Meeting corner	Specify surface finish.	Postformed Options 120° meeting worksurfaces are used in panel system application only. They are supported at the rounded meeting end by a Postformed support column, specified separately. They can be supported at the other end by 24" end support brackets, 24" cantilever bracket or 18"D and 24"D pedestals.
48 Width	1 1/4" worksurfaces are solid core construction with pilot holes at all support locations.	120° corner is supported by 24"D cantilever bracket.
S 24"D return		Use 24"D cantilever bridging brackets to join to adjacent worksurfaces.
B No Grommets		
L Left hand		
L Laminate	120° Options worksurfaces are available without grommets only.	
117 Surface finish	LU1- worksurfaces are supported by brackets with wood screws.	

Worksurface Supports

Worksurfaces are shipped without supports which must be ordered separately.

A variety of worksurface supports are available. They include:

- Cantilevers
- Flat brackets
- Panel-to-worksurface brackets

In addition, freestanding pedestals and end units can also be used for worksurface support.

Cantilevers and panel-to-worksurface brackets are used strictly in panel-mount applications while flat brackets, pedestals and end units can be used in both panel-mounted and freestanding applications.

Cantilevers

Cantilevers provide panel-hung worksurface support when the worksurface width runs parallel to the panel run.

Primary cantilever applications include:

- Corner worksurfaces
- Worksurface mid-span support
- 18" and 24" deep rectangular worksurface support in moderate load situations

Note: For heavy load applications, panel-to-worksurface brackets, freestanding pedestal, panel-mount C-leg, or open support leg is recommended. In applications involving 30" deep worksurfaces, cantilevers are only recommended for mid-span support.

Cantilevers are left- and right-handed and are available in three depths (18", 24" and 30") to support 18", 24" and 30" deep worksurfaces.

Note: 36" deep worksurfaces cannot be supported by cantilevers.

- **Attachment:** Cantilevers lock into the panel's slotted standard and adjust vertically in 1 1/2" increments. Cantilevers are left- or right-handed

- **Construction:** 14-gauge, black painted steel

Flat Brackets

Flat brackets are used to join a primary worksurface with an adjacent return or bridge unit worksurface at the same height.

Flat brackets are available in three depths to support 18", 24" and 30" deep worksurface returns.

- **Attachment:** Flat brackets attach to pre-drilled positions on the undersides of worksurfaces with provided screws

- **Construction:** 14-gauge painted steel

Shared Cantilevers

Adjacent worksurfaces can share a single cantilever if the appropriate flat bracket is used in conjunction with the appropriate cantilever (i.e. 18" cantilever with 18" flat bracket).

Panel-to-Worksurface Brackets, Worksurface Support

Panel-to-worksurface brackets are used to:

- Mount worksurfaces perpendicular to panels
- Anchor the rear corner of corner worksurfaces to panels
- Secure a panel to a pedestal

Panel-to-worksurface brackets provide the most secure panel-hung support for heavily loaded worksurfaces.

Panel worksurface brackets are handed left or right.

Note: The panel width must match the worksurface depth for panel-to-worksurface brackets to connect worksurfaces perpendicular to panels.

- **Attachment:** Panel-to-worksurface brackets lock into the panel's slotted standard and adjust vertically in 1 1/2" increments

- **Construction:** 14-gauge painted steel

Panel-to-Worksurface Brackets, Stabilizing Support

Panel-to-worksurface brackets are also used in conjunction with pedestals to stabilize panel runs.

In applications where the worksurface is "wrapped" with a return panel and a pedestal is installed below the worksurface at the "wrapped" end, a panel-to-worksurface bracket is used at the front corner of the worksurface. In pedestal applications, the panel-to-worksurface bracket connects the pedestal at the rear corner of the pedestal to the panel (as shown in the illustration below) or front corner of the pedestal to the panel when a return wing panel is used.


Panel-to-Worksurface Brackets, Off-Module Support

For applications where the width of the panel exceeds the depth of the worksurface, specify off-module panel-to-worksurface brackets which allow off module worksurface support.


Worksurface Reinforcement

Worksurface reinforcements are required for worksurface spans greater than 48 inches. This includes freestanding desk worksurfaces over 48 inches using desk end units. Worksurface reinforcements have a black paint finish.


Panel Mounted Worksurface Bracket Application



Flat Bracket Application




Shared Cantilever Application




Stabilizing Support




Off-Module Support



Worksurface Reinforcement Panel Hung Application



Cantilevers, Flat Brackets and Panel-to-Worksurface Brackets

description	type	w	d	h	pattern no.	black	P1	P2	P3
Cantilever Bracket Left or Right (Left Shown) (package of 10) 	For 18"D WS	1 ⁵ / ₁₆ "	12 ³ / ₁₆ "	11 ¹³ / ₁₆ "	DB1C 18 (L or R) 10	\$468.	\$492.	\$512.	\$537.
	For 24"D WS	1 ⁵ / ₁₆ "	20 ⁵ / ₈ "	10 ¹ / ₂ "	DB1C 24 (L or R) 10	582.	611.	640.	670.
	For 30"D WS	1 ⁵ / ₁₆ "	26 ¹⁵ / ₁₆ "	10 ¹ / ₂ "	DB1C 30 (L or R) 10	831.	873.	913.	956.
Cantilever Brackets, Left or Right (Left Shown) (single pack) 	For 30"D WS	1 ⁵ / ₁₆ "	26 ¹⁵ / ₁₆ "	10 ¹ / ₂ "	DB1C30 (L or R)	102.	108.	114.	120.
	For 18"D WS	1 ⁵ / ₁₆ "	12 ³ / ₁₆ "	11 ¹³ / ₁₆ "	DB1C18 (L or R)	57.	59.	62.	63.
	For 24"D WS	1 ⁵ / ₁₆ "	20 ⁵ / ₈ "	10 ¹ / ₂ "	DB1C24 (L or R)	73.	79.	84.	86.
Cantilever Brackets for 120° Planning (Left Shown)(single pack) 		20 ⁵ / ₈ "		1 ⁵ / ₁₆ "	DB120C (L or R)	73.	79.	84.	86.
Flat Bracket (single pack) 	For 18"D WS	3 ³ / ₄ "	8 ³ / ₁₆ "		DB1F18SP	29.	n/a	n/a	n/a
	For 24"D WS	3 ³ / ₄ "	14 ⁵ / ₈ "		DB1F24SP	33.	n/a	n/a	n/a
	For 30"D WS	3 ³ / ₄ "	20 ¹⁵ / ₁₆ "		DB1F30SP	38.	n/a	n/a	n/a
Flat Bracket (package of 10) 	For 18"D WS	3 ³ / ₄ "	8 ³ / ₁₆ "		DB1F18TP	158.	n/a	n/a	n/a
	For 24"D WS	3 ³ / ₄ "	14 ³ / ₁₆ "		DB1F24TP	263.	n/a	n/a	n/a
	For 30"D WS	3 ³ / ₄ "	20 ⁵ / ₁₆ "		DB1F30TP	302.	n/a	n/a	n/a
Worksurface Reinforcement 		54"	4"		DB1WR54	77.	n/a	n/a	n/a
		60"	4"		DB1WR60	78.	n/a	n/a	n/a
		66"	4"		DB1WR66	81.	n/a	n/a	n/a
		72"	4"		DB1WR72	84.	n/a	n/a	n/a
Panel-to-Worksurface Brackets 	Pair	3"	3"	4 ¹¹ / ₁₆ "	DB1PWSP	20.	20.	24.	29.
	Left (Shown)	3"	3"	4 ¹¹ / ₁₆ "	DB1PWSL	9.	9.	10.	11.
	Right	3"	3"	4 ¹¹ / ₁₆ "	DB1PWSR	9.	9.	10.	11.

Ordering Information

Panel-to-Worksurface Bracket,
Off Module

1. Pattern Number
2. Trim Finish

Order Code

Panel-to-Worksurface Bracket,
Off ModuleExample: **DB1P WS36, 113****DB1P** Pattern Number**WS36****113** Dark Grey Finish

Included with:

Panel-to-Worksurface Bracket,
Off Module

- Trim finish mounting rail
- Worksurface brackets

Options

Panel-to-Worksurface Bracket,
Off Module

Cantilevers, Flat Brackets and Panel-to-Worksurface Brackets


description	type	w	d	h	pattern no.	black	P1	P2	P3
Panel-to-Worksurface Brackets (package of 10)	Left (Shown)	3"	3"	4 ^{11/16"}	DB1PWSL10	\$87.	\$87.	\$98.	\$111.
	Right	3"	3"	4 ^{11/16"}	DB1PWSR10	87.	87.	98.	111.




Panel-to-Worksurface Brackets for use with Worksurface Height Panels ONLY	Left	3"	3"	4 ^{11/16"}	DB1PWSLWH	29.	31.	33.	35.
	Right	3"	3"	4 ^{11/16"}	DB1PWSRWH	29.	31.	33.	35.
	Pair	3"	3"	4 ^{11/16"}	DB1PWSPWH	54.	58.	63.	70.



Panel-to-Worksurface Brackets (Off Module)	For 24" Wide Panel				DB1PWS24	n/a	81.	87.	89.
	For 30" Wide Panel				DB1PWS30	n/a	85.	91.	96.
	For 36" Wide Panel				DB1PWS36	n/a	88.	96.	100.
	For 42" Wide Panel				DB1PWS42	n/a	94.	105.	113.
	For 48" Wide Panel				DB1PWS48	n/a	100.	113.	117.



Layered Cantilever Assembly Left or Right					DBVDC (L or R)	103.	109.	116.	121.
---	--	--	--	--	-----------------------	------	------	------	------




Right hand shown

Ordering Information	Order Code	Included with:	Options
Panel-to-Worksurface Bracket, Off Module	Panel-to-Worksurface Bracket, Off Module	Panel-to-Worksurface Bracket, Off Module	Panel-to-Worksurface Bracket, Off Module
1. Pattern Number	<i>Example:</i> DB1P WS36, 113	• Trim finish mounting rail	
2. Trim Finish	DB1P Pattern Number	• Worksurface brackets	
	WS36		
	113 Dark Grey Finish		

Panel Mounted Worksurface Brackets

Currents worksurfaces for Dividends Horizon Stiffeners

Dividends Horizon

description	type	w	d	h	pattern no.	list
 Stiffener for straight and corner worksurfaces	36"	20"	1/2"	2"	AWM1 S36	\$76.
	42"	26"	1/2"	2"	AWM1 S42	81.
	48"	32"	1/2"	2"	AWM1 S48	83.
	60"	44"	1/2"	2"	AWM1 S60	85.
	66"	50"	1/2"	2"	AWM1 S66	89.
	72"	56"	1/2"	2"	AWM1 S72	93.
	78"	62"	1/2"	2"	AWM1 S78	98.
	84"	68"	1/2"	2"	AWM1 S84	100.

Ordering Information	Order Code	Application Notes	Specification Information
1. Pattern Number	Stiffener <i>Example:</i> AWM1 S48 AW1 Worksurface S Stiffener 48 Type	Currents worksurfaces for Dividends Horizon require stiffener when the span between structural supports exceeds 36". Specify worksurface stiffeners and supports separately. When using Dividends Horizon end support brackets, order MB3-EC18, 24 or 30. For 90" application span, use two AWM1-S42 stiffeners. For 96" application span, use two AWM1-S48 stiffeners.	Stiffener mounts 18" from front edge of worksurface and will interfere with mobile or floorstanding pedestals greater than 18" deep. To accommodate a floorstanding pedestal greater than 18" deep at one end of worksurface, specify stiffener for 12" narrower worksurface. To accommodate two floorstanding pedestals or double-wide at one end of worksurface, specify stiffener for 24" narrower worksurface.

Panel Mounted Worksurface Brackets

Flat Brackets

Dividends Horizon

description	type	w	d	h	pattern no.	list
Flat brackets with machine screws 	18" surface	3 1/2"	8"		MB3-F18M	\$51.
	24" surface	3 1/2"	14"		MB3-F24M	55.
	30"/36" surface	3 1/2"	20"		MB3-F30M	63.
Flat brackets with wood screws 	18" surface	3 1/2"	8"		MB3-F18W	51.
	24" surface	3 1/2"	14"		MB3-F24W	55.
	30"/36" surface	3 1/2"	20"		MB3-F30W	63.

Ordering Information

Flat Brackets

1. Pattern Number

Order Code

Flat Brackets

Example: **MB3-F24M**

MB3	Bracket
F	Bracket type
24	Bracket depth
M	Machine screws

Application Notes

Flat bridging brackets attach two worksurfaces at the same height in 90° "L", VDT or end-to-end applications (in conjunction with floorstanding pedestal support)

Flat bridging brackets are universal for freestanding or panel based planning.




Brackets with machine screws (suffix-M) are used with MW2- and MU1- worksurfaces.

Brackets with wood screws (suffix-W) are used with LU1- and AWM2- worksurfaces.

Network Privacy screens

back screens

Dividends Horizon


description	type	w	d	h	pattern no.	10	15	20	30	40	45
 Back of worksurface screens to 42"H		30"	3/4"	15"	MZ1-B3015-()	\$337.	\$379.	\$390.	\$426.	\$478.	\$532.
		36"	3/4"	15"	MZ1-B3615-()	405.	442.	452.	496.	545.	587.
		42"	3/4"	15"	MZ1-B4215-()	496.	519.	534.	589.	642.	686.
		48"	3/4"	15"	MZ1-B4815-()	557.	580.	598.	654.	734.	783.
		54"	3/4"	15"	MZ1-B5415-()	650.	669.	689.	761.	830.	880.
		60"	3/4"	15"	MZ1-B6015-()	717.	729.	756.	874.	923.	981.
		66"	3/4"	15"	MZ1-B6615-()	*	786.	*	*	*	*
		72"	3/4"	15"	MZ1-B7215-()	*	874.	*	*	*	*
		78"	3/4"	15"	MZ1-B7815-()	*	957.	*	*	*	*
 Back of worksurface screens to overhead support height, 46"H		30"	3/4"	19"	MZ1-B3019-()	427.	467.	478.	525.	576.	627.
		36"	3/4"	19"	MZ1-B3619-()	528.	556.	570.	630.	670.	712.
		42"	3/4"	19"	MZ1-B4219-()	625.	640.	653.	724.	800.	846.
		48"	3/4"	19"	MZ1-B4819-()	710.	727.	745.	820.	948.	966.
		54"	3/4"	19"	MZ1-B5419-()	810.	814.	843.	924.	992.	1,056.
		60"	3/4"	19"	MZ1-B6019-()	874.	897.	923.	1,022.	1,084.	1,157.
		60"	3/4"	19"	MZ1-B6619-()	874.	897.	923.	1,022.	1,084.	1,157.
		66"	3/4"	19"	MZ1-B6619-()	*	982.	*	*	*	*
		72"	3/4"	19"	MZ1-B7219-()	*	1,074.	*	*	*	*
		78"	3/4"	19"	MZ1-B7819-()	*	1,165.	*	*	*	*
 Back of worksurface screens, to Reuter overhead support height, 49"H		30"	3/4"	22"	MZ1-B3022-()	525.	551.	564.	627.	670.	717.
		36"	3/4"	22"	MZ1-B3622-()	649.	669.	689.	758.	813.	843.
		42"	3/4"	22"	MZ1-B4222-()	745.	758.	783.	861.	957.	1,002.
		48"	3/4"	22"	MZ1-B4822-()	874.	875.	901.	996.	1,062.	1,158.
		54"	3/4"	22"	MZ1-B5422-()	958.	960.	996.	1,103.	1,172.	1,236.
		60"	3/4"	22"	MZ1-B6022-()	1,022.	1,070.	1,103.	1,214.	1,286.	1,332.
		66"	3/4"	22"	MZ1-B6622-()	*	1,188.	*	*	*	*
		72"	3/4"	22"	MZ1-B7222-()	*	1,274.	*	*	*	*
		78"	3/4"	22"	MZ1-B7822-()	*	1,372.	*	*	*	*

Order Code	Specification Information	Application Notes												
Example: MZ1-B6619-15 MZ1 Network privacy screen B Back of worksurface 66 Width 19 Height 15 Surface type and group no. W210 Upholstery	<i>Surface type:</i> <table><tr><td>10-</td><td>Fabric group 10</td></tr><tr><td>15-</td><td>Fabric group 15</td></tr><tr><td>20-</td><td>Fabric group 20</td></tr><tr><td>30-</td><td>Fabric group 30</td></tr><tr><td>40-</td><td>Fabric group 40</td></tr><tr><td>45-</td><td>Fabric group 45</td></tr></table> Network screens may be used with Plannable Upstart tables. Refer to front of Upstart price book for planning information. * Screens 66"w and wider are available with fabric railroaded to fit the screens' width. Please contact Knoll Custom Product Development to establish pattern numbers.	10-	Fabric group 10	15-	Fabric group 15	20-	Fabric group 20	30-	Fabric group 30	40-	Fabric group 40	45-	Fabric group 45	Back of worksurface screens provide visual barrier and tackable surface from underside of worksurface to a height of 42", 46" or 49". Screen widths should correspond to straight worksurface width, or sum of VDT corner and return widths. Use back of worksurface screen for VDT applications where one side is backed by a vertical panel. VDT worksurfaces will accept back screens on only one back edge. Back screens may not be used at the end of a straight worksurface; use end screens in this application. Privacy screens are not available in a combination of fabrics. Back of worksurface screens are full dimension: two smaller screens may be substituted for a larger one. For example, if using fabric grades 20-70, specify two 36" screens for a 72" surface. Between back-to-back straight or VDT worksurfaces specify a single 3/4" back screen. This allows back-to-back 23 7/8"D or 29 7/8"D worksurfaces to plan on a precise 6" module. 15" high screens are used for a 42" horizon. 19"H screens are used to fill in space between worksurface and overhead. 22"H screens fill the space between worksurface and Reuter overhead. All but shared end screens start at the bottom of the worksurface. Privacy screens are supported by brackets fastened at worksurface inserts. Privacy screens include mounting brackets, insert kit, and stiffener clip. For replacement screen stiffeners see Accessories page. Privacy screens may be specified to achieve ASTM E-84 Class "A" flamespread rating.
10-	Fabric group 10													
15-	Fabric group 15													
20-	Fabric group 20													
30-	Fabric group 30													
40-	Fabric group 40													
45-	Fabric group 45													

Network Privacy screens

VDT Screens



Dividends Horizon

description	type	w	d	h	pattern no.	10	15	20	30	40	45
 Back of VDT screens	To 42"H	35 7/8"	3/4"	15"	MZ1-V3615-()	\$405.	\$442.	\$452.	\$478.	\$532.	\$587.
	To 42"H	41 7/8"	3/4"	15"	MZ1-V4215-()	496.	519.	534.	576.	627.	686.
	To 42"H	47 7/8"	3/4"	15"	MZ1-V4815-()	557.	580.	598.	642.	712.	783.
	To 42"H	59 7/8"	3/4"	15"	MZ1-V6015-()	707.	734.	758.	811.	896.	970.
	To 42"H	71 7/8"	3/4"	15"	MZ1-V7215-()	*	882.	*	*	*	*
	To 46"H	35 7/8"	3/4"	19"	MZ1-V3619-()	533.	553.	570.	607.	651.	712.
	To 46"H	41 7/8"	3/4"	19"	MZ1-V4219-()	625.	640.	653.	699.	783.	846.
	To 46"H	47 7/8"	3/4"	19"	MZ1-V4819-()	710.	729.	756.	804.	875.	966.
	To 46"H	59 7/8"	3/4"	19"	MZ1-V6019-()	893.	921.	956.	1,034.	1,146.	1,240.
	To 46"H	71 7/8"	3/4"	19"	MZ1-V7219-()	*	1,113.	*	*	*	*
	To 49"H	35 7/8"	3/4"	22"	MZ1-V3622-()	649.	669.	689.	736.	783.	843.
	To 49"H	41 7/8"	3/4"	22"	MZ1-V4222-()	745.	758.	783.	820.	936.	1,002.
	To 49"H	47 7/8"	3/4"	22"	MZ1-V4822-()	874.	877.	903.	960.	966.	1,158.
	To 49"H	59 7/8"	3/4"	22"	MZ1-V6022-()	1,033.	1,073.	1,107.	1,205.	1,327.	1,440.
	To 49"H	71 7/8"	3/4"	22"	MZ1-V7222-()	*	1,286.	*	*	*	*

Order Code	Specification Information	Application Notes
Example: MZ1-V4822-15 MZ1 Network privacy screen V VDT 48 Width 22 Height 15 Surface type and group no. W210 Upholstery	<i>Surface type:</i> 10- Fabric group 10 15- Fabric group 15 20- Fabric group 20 30- Fabric group 30 40- Fabric group 40 45- Fabric group 45 VDT worksurfaces will not accept back screens on both back edges. Use VDT screens on at least one back edge. VDT screens are not in pairs; specify one for each back edge or one VDT screen and one back screen. * Screens 66" w and wider are available with fabric railroaded to fit the screens' width. Please contact Knoll Custom Product Development to establish pattern numbers.	Privacy screens are supported by brackets fastened at worksurface inserts. Privacy screens include mounting brackets, insert kit and stiffener clip. 15" high screens are used for a 42" horizon. 19"H screens are used to fill in space between worksurface and desk mounted Network overheads. 22"H screens fill the space between worksurface and desk mounted Reuter overheads. Privacy screens may be specified to achieve ASTM E-84 Class "A" flamespread rating.

Network Privacy screens end screens

Dividends Horizon

description	type	w	d	h	pattern no.	10	15	20	30	40	45
	To 42"H	24"	3/4"	15"	MZ1-E2415-W/U-()	\$320.	\$366.	\$376.	\$394.	\$455.	\$519.
	To 42"H	30"	3/4"	15"	MZ1-E3015-W/U-()	358.	391.	405.	436.	487.	553.
	To 46"H	24"	3/4"	19"	MZ1-E2419-W/U-()	389.	423.	427.	470.	519.	581.
	To 46"H	30"	3/4"	19"	MZ1-E3019-W/U-()	448.	486.	496.	532.	581.	649.
	To 49"H	24"	3/4"	22"	MZ1-E2422-W/U-()	455.	483.	493.	528.	584.	647.
	To 49"H	30"	3/4"	22"	MZ1-E3022-W/U-()	545.	576.	585.	630.	682.	744.
	To 42"H	24"	3/4"	13"	MZ1-S2415-W/U-()	309.	352.	364.	380.	442.	497.
	To 42"H	30"	3/4"	13"	MZ1-S3015-W/U-()	337.	379.	390.	419.	469.	532.
	To 46"H	24"	3/4"	17"	MZ1-S2419-W/U-()	371.	405.	419.	447.	497.	561.
	To 46"H	30"	3/4"	17"	MZ1-S3019-W/U-()	427.	467.	478.	511.	561.	627.
	To 49"H	24"	3/4"	20"	MZ1-S2422-W/U-()	436.	465.	472.	509.	562.	625.
	To 49"H	30"	3/4"	20"	MZ1-S3022-W/U-()	525.	551.	564.	607.	651.	717.

Worksurface Supports

Order Code	Specification Information	Application Notes
Example: MZ1-S3019W15		
MZ1 Network privacy screen	<i>Surface type:</i>	End screens must be used at the end of straight or rounded end workspaces.
S Shared	10- Fabric group 10	
30 Width	15- Fabric group 15	End screens for outside application cover the end of the worksurface and align with adjacent back screens. End screens for shared application begin above the worksurface to allow modular planning when straight workspaces are end-to-end.
19 Height	20- Fabric group 20	
W For 1 3/4" worksurface	30- Fabric group 30	When specifying end screens under 64"H panel mounted Network overheads with task lights, only screens to 42"H will fit.
15 Surface type and group no.	40- Fabric group 40	With 64"H panel-mounted Reuter overheads any screen up to 49"H may be planned perpendicular to storage.
W210 Upholstery	45- Fabric group 45	
	<i>End screens specify:</i>	
	W- For use with 1 3/4" thick workspaces	Privacy screens are supported by brackets fastened at worksurface inserts. Privacy screens include mounting brackets, insert kit and stiffener clip.
	U- For use with 1 1/4" thick workspaces	15" high screens are used for a 42" horizon.
		19"H screens are used to fill in space between worksurface and desk mounted Network overheads.
		22"H screens fill the space between worksurface and desk mounted Reuter overheads.
		All but shared end screens start at the bottom of the worksurface.
		Privacy screens may be specified to achieve ASTM E-84 Class "A" flamespread rating.

Screen-to-Worksurface Brackets, Worksurface Support

Screen-to-worksurface brackets are used to:

- Mount worksurfaces perpendicular to screens
- Anchor the rear corner of corner worksurfaces to screens


Screen-to-worksurface brackets provide the most secure screen-hung support for heavily loaded worksurfaces.

Screen worksurface brackets are handed left or right.


Note: The screen width must match the worksurface depth for screen-to-worksurface brackets to connect worksurfaces perpendicular to screens.

- **Attachment:** Screen-to-worksurface brackets lock into the screen's slotted standard and adjust vertically in 1 1/2" increments
- **Construction:** 14-gauge painted steel

Screen-to-Worksurface Support Application



Screen-to-Worksurface Brackets



Screen-to-Worksurface Brackets

Screen mid-span worksurface support

Dividends Horizon

description	type	w	d	h	pattern no.	P1	P2	P3
Screen-to-Worksurface Brackets (Individual)	Left				DB1SWSL	\$7.	\$9.	\$12.
	Right				DB1SWSR	7.	9.	12.



Left hand shown

Screen-to-Worksurface Brackets (Pair)	Left/Right				DB1SWSP	35.	38.	41.
---------------------------------------	------------	--	--	--	----------------	-----	-----	-----

Screen Mid-Span Worksurface Support	left hand				DBSMLH	31.	32.	33.
	right hand				DBSMRH	31.	32.	33.



Left hand shown

Worksurface Supports

Ordering Information	Order Code	Included with:	Options
Panel-to-Worksurface Bracket, Off Module	Panel-to-Worksurface Bracket, Off Module	Panel-to-Worksurface Bracket, Off Module	Panel-to-Worksurface Bracket, Off Module
1. Pattern Number	<i>Example:</i> DB1P WS36, 113	• Trim finish mounting rail	
2. Trim Finish	DB1P Pattern Number	• Worksurface brackets	
	WS36		
	113 Dark Grey Finish		

Panel-Mounted C-Legs, Open Support Legs, and Worksurface End Panels

Panel-mounted C-legs, open support legs, and worksurface end panels provide panel-hung worksurface support when the worksurface width runs parallel to the panel run.

Primary panel-mounted support applications include:

- Rectangular worksurface end support for 24" and 30" depth worksurfaces
- Mid span worksurface support for 24" and 30" depth worksurfaces
- Corner and split top corner worksurface support
- Support for heavier worksurface load applications
- Shared support between two adjacent worksurfaces

Note: 18" deep and 36" worksurface may not be used with panel-mounted C-leg worksurface support.

Construction

C-leg support:

- Support foot: die cast aluminum
- Support leg: extruded aluminum
- Mounting bracket: $\frac{3}{16}$ " steel plate

Open Support Leg:

- Vertical members: extruded aluminum
- Top plate and spanner bar: 0.025" cold rolled steel
- Mounting brackets: $\frac{3}{16}$ " steel plate

Worksurface End Panel:


- Panel: 20 gauge steel
- Mounting brackets: 14 gauge steel

Note: Open support legs and worksurface end panels are only available in Knoll Core finishes


Note: The shared open support leg is designed for use where 2 panels meet. It cannot be used on the end of a panel run.

Note: Worksurface end panels are for use with panels only and are non-handed.


Panel-Mounted C-Leg Support




Panel-Mounted C-Leg Support (radiused foot)



Open Support Leg







Worksurface End Panel



Panel Mounted Worksurface Supports

Open Support Leg, C-Leg and Worksurface End Panel

Dividends Horizon

description	type	w	d	h	pattern no.	P1	P2	P3
Panel Mounted C-Leg Worksurface Support (Left-hand shown) 	Left-hand C-Leg			26 ⁷ / ₈ "	DB1CL24L	\$404.	\$444.	\$461.
	Right-hand C-Leg			26 ⁷ / ₈ "	DB1CL 24R	404.	444.	461.
	Shared C-Leg			26 ⁷ / ₈ "	DB1CL24S	426.	470.	494.
Panel Mounted C-Leg Worksurface Support Radiused Foot (Right-hand shown) 	LH Shared Worksurface C-Leg			26 ⁷ / ₈ "	DB2CL24LS	506.	560.	582.
	LH Single Worksurface C-Leg			26 ⁷ / ₈ "	DB2CL24L	480.	527.	552.
	RH Shared Worksurface C-Leg			26 ⁷ / ₈ "	DB2CL24RS	506.	560.	582.
	RH Single Worksurface C-Leg			26 ⁷ / ₈ "	DB2CL24R	480.	527.	552.
Open Support Leg Panel Attachment 		3"	15"	26 ⁷ / ₈ "	DB1LSP15()	386.	409.	425.
		3"	18"	26 ⁷ / ₈ "	DB1LSP18()	386.	409.	425.
		3"	24"	26 ⁷ / ₈ "	DB1LSP24()	379.	402.	421.
		3"	30"	26 ⁷ / ₈ "	DB1LSP30()	400.	418.	441.
		3"	36"	26 ⁷ / ₈ "	DB1LSP36()	422.	444.	461.
Open Support Leg Screen Attachment 		3"	15"	26 ⁷ / ₈ "	DB1LSS15()	386.	409.	425.
		3"	18"	26 ⁷ / ₈ "	DB1LSS18()	386.	409.	425.
		3"	24"	26 ⁷ / ₈ "	DB1LSS24()	379.	402.	421.
		3"	30"	26 ⁷ / ₈ "	DB1LSS30()	400.	418.	441.
		3"	36"	26 ⁷ / ₈ "	DB1LSS36()	422.	444.	461.
Worksurface End Panel Panel Attachment 		1 1/4"	15"	26 ⁷ / ₈ "	DB1PSP15	352.	384.	406.
		1 1/4"	18"	26 ⁷ / ₈ "	DB1PSP18	366.	404.	421.
		1 1/4"	19"	26 ⁷ / ₈ "	DB1PSP19	383.	415.	434.
		1 1/4"	24"	26 ⁷ / ₈ "	DB1PSP24	402.	443.	460.
		1 1/4"	30"	26 ⁷ / ₈ "	DB1PSP30	430.	476.	498.
		1 1/4"	36"	26 ⁷ / ₈ "	DB1PSP36	459.	506.	528.

Ordering Information	Order Code	Included with:	Options
Panel-Mounted C-Leg Worksurface Support 1. Pattern Number 2. Paint Finish	Panel Mounted C-Leg Worksurface Support <i>Example:</i> DB1 CL24R, 117 DB1 Pattern Number CL24R 117 Soft Grey finish	Panel-Mounted C-Leg Worksurface Support • C-leg foot • C-leg column • Panel attachment bracket • C-leg flat bracket • Leveling glides	Open Support Leg Option (R) = Right-hand leg (L) = Left-hand leg (S) = Shared leg Note: Worksurface end panels are for use with panels only.
Worksurface End Panel 1. Pattern Number 2. Paint Finish	Worksurface End Panel <i>Example:</i> DB1 PSP 24 DB1 PSP Pattern Number 24 117 Soft Grey finish	Worksurface End Panel • Panel attachment bracket • Leveling glides	
Open Support Leg 1. Pattern Number 2. Paint Finish		Note: Open Support Legs are only available in Knoll core finishes. Note: The shared open support leg is designed for use where 2 panels meet. It cannot be used at the end of a panel run.	

Round Support Column

4" diameter round column may be used to support the rounded end of panel-mounted curvilinear half-round, "D", "P", "9", and blended "D" peninsula tops. Column is available in all Knoll core paint finishes

Construction

- Material: 4" diameter steel tube
- Mounting bracket: heavy gauge steel plate, 6 x 6

T-Support Column

The T-support column may be used to support the rounded end of a panel-mounted curvilinear half-round, "D", "P", "9", and blended "D" peninsula tops. The T-support column is recommended for use with "D" peninsula worksurfaces used in freestanding applications. The T-support column is available in all Dividends paint finishes.

Construction

T-support column specifications:

- Support foot: die cast aluminum
- Support leg: extruded aluminum
- Mounting bracket: heavy gauge steel plate

T-End Unit

The T-end unit is used on the end of a freestanding "D" peninsula worksurface top. The T-end is available in a depth of 24" and 30" for use with "D", "P" and "9" top depths of 24" and 30".

Construction

- Outer skin: 21-gauge steel
- Inner frame: 20-gauge steel
- Mounting brackets: 11-gauge steel

A Leg


An A leg may be used to support panel mounted curvilinear half-round, "D", "P", "9" and blended "D" peninsula tops. A legs are available in any Knoll Core paint finish.

Construction


- Vertical members: extruded aluminum
- Top plate and spanner bar: 0.025" cold rolled steel
- Mounting brackets: 14 gauge steel

Note: A legs are only available in Knoll Core finishes


Round Column with Panel
"D" Worksurface




T-Support Base with Panel
"D" Worksurface



T-End Unit with Freestanding
"D" Worksurface



A-Leg with Panel
"D" Worksurface



Peninsula Worksurface Supports

Round Support Column, T-Support Base and A Leg

Dividends Horizon

description	w	d	h	pattern no.	P1	P2	P3
 T-End Unit	21 ¹³ / ₁₆ "	12"	26 ⁷ / ₈ "	DD1TEU24	\$379.	\$420.	\$441.
	27 ¹³ / ₁₆ "	12"	26 ⁷ / ₈ "	DD1TEU30	418.	457.	479.
 T-Support Base	23 ¹ / ₂ "	12"	26 ⁷ / ₈ "	DB1TB	360.	397.	413.
 Round Support Column	4"	4"	26 ⁷ / ₈ "	DB1S CR	310.	324.	348.
 A Leg	3"	15"	26 ⁷ / ₈ "	DB1LS15A	408.	449.	465.
	3"	18"	26 ⁷ / ₈ "	DB1LS18A	421.	461.	481.
	3"	24"	26 ⁷ / ₈ "	DB1LS24A	434.	478.	498.
	3"	30"	26 ⁷ / ₈ "	DB1LS30A	450.	494.	511.
	3"	36"	26 ⁷ / ₈ "	DB1LS36A	459.	506.	526.
 2.5" Round Support Column				DBSCR	310.	324.	348.

Worksurface Supports

Dimensions listed under w d t are actual to the nearest ¹/₁₆"

Ordering Information	Order Code	Included with:	Options
T-End Unit 1. Pattern Number 2. Paint Finish	T-End Unit <i>Example:</i> DD1TEU24, 115 DD1TEU24 Pattern Number 115 Medium Grey Paint Finish	T-End Unit • Worksurface	T-End Unit T-Support Base A Leg Round Support Column
T-Support Base 1. Pattern Number 2. Paint Finish	T-Support Base <i>Example:</i> DB1TB, 115 DB1TB Pattern Number 115 Medium Grey Paint Finish	T-Support Base Note: The A leg is for use in peninsula worksurface applications only. It is not to be used in freestanding applications.	
A Leg 1. Pattern Number 2. Paint Finish		Note: A Legs are only available in Knoll core finishes.	
Round Support Column 1. Pattern Number 2. Paint Finish	Round Support Column <i>Example:</i> DB1SCR, 118 DB1SCR Pattern Number 118 Bright White Paint Finish		

Y Leg Tables

Freestanding and Credenza Supported Specifications

Dividends Horizon

Dividends Horizon Tables

The design details of Dividends Horizon tables are consistent with the scale and visual language of the Dividends Horizon system. This design consistency makes Dividends Horizon tables appropriate for use in conference, meeting, private office and open plan office applications.

Dividends Horizon Y Leg tables are available in two versions:

- Freestanding Y Leg
- Credenza Supported Y Leg

Freestanding Y Leg Tables

Freestanding Y Leg tables include a worksurface and base assembly. All freestanding table sizes are available with two Y legs and a horizontal stretcher connecting the two columns.

In addition, 24 and 30 inch deep tables are available without a stretcher. Tables without stretcher include an integral worksurface support plate. 36 and 42 inch deep tables are available only with a stretcher.

Available Sizes

- Width: 60-96 inches
- Depth: 24-42 inches
- Height: 28-1/2 inches

Credenza Supported Y Leg Tables

The unique Dividends Horizon Credenza Supported Y Leg tables are designed to be used in concert with Dividends Horizon low credenzas, specified separately.

Credenza Supported Tables include one Y Leg, credenza support spacer, and a worksurface with integral stiffening plate.

Note: Credenza supported tables may be used with laminate or veneer top credenzas only, and are not compatible with steel top credenzas.

Available Sizes

- Width: 60-96 inches
- Depth: 24-36 inches
- Height: 28-1/2 inches

Optional Edge Grommet

Edge grommets are optional and can be factory installed centered along the rear edge of rectangular or racetrack freestanding or credenza supported Y Leg tables.

Construction

- Worksurface:
 - Material: 0.028 inch thick laminate or 0.6mm thick veneer on 1-1/8" particle board core
 - Edge: plastic laminate tops have a 2mm edgeband; Techwood tops have a 3/16 inch thick Techwood edge
- Bases:
 - Stretcher: extruded aluminum
 - Stiffening plate: 4 inch deep 12 gauge steel plate (length varies)
 - Foot: die cast aluminum
 - Column: extruded aluminum with 3/16 inch thick structural plate
 - Credenza support spacer:
 - 2-15/16 inches high x 9-5/8 inches wide x 1-9/16 inches deep steel box with a flat bracket on top


Note: Dividends Horizon tables are only available in Knoll Core paint, laminate, and Techwood finishes. Legacy finishes are not available. All paint finishes have the Dividends Horizon textured paint finish; this includes 613 Silver, which is a smooth paint on all other Dividends Horizon products.

Note: The stiffening plate on tables without a stretcher prevents the field installation of a grommet or plexus box. (see illustration below)


24" Deep Freestanding Racetrack Y Leg Table with Stretcher



24" Deep Credenza Supported Racetrack Y Leg Table



24" Deep Freestanding Racetrack Y Leg Table without Stretcher




Y Leg Tables

Freestanding Rectangular Table Top


24" and 30" Deep

description	w*	w	d	t	h	pattern no.	Laminate Top P1 Paint	Laminate Top P2 Paint	Laminate Top P3 Paint	Techgrain Top P1 Paint	Techgrain Top P2 Paint	Techgrain Top P3 Paint
24" Deep Rectangular with (2) Y-Legs, No Grommet	60"	59 ^{13/16"}	23 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY6024NS	\$1,882.	\$2,073.	\$2,155.	\$2,157.	\$2,372.	\$2,470.
	66"	65 ^{13/16"}	23 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY6624NS	1,904.	2,096.	2,178.	2,190.	2,413.	2,510.
	72"	71 ^{13/16"}	23 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY7224NS	1,924.	2,119.	2,204.	2,228.	2,450.	2,549.
	78"	77 ^{13/16"}	23 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY7824NS	1,947.	2,140.	2,226.	2,265.	2,492.	2,592.
	84"	83 ^{13/16"}	23 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY8424NS	1,983.	2,179.	2,268.	2,303.	2,532.	2,633.
	90"	89 ^{13/16"}	23 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY9024NS	2,016.	2,221.	2,308.	2,336.	2,572.	2,672.
	96"	95 ^{13/16"}	23 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY9624NS	2,052.	2,259.	2,348.	2,370.	2,608.	2,715.



(with stretcher shown)

30" Deep Rectangular with (2) Y-Legs, No Grommet	60"	59 ^{13/16"}	29 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY6030NS	1,931.	2,125.	2,211.	2,206.	2,425.	2,521.
	66"	65 ^{13/16"}	29 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY6630NS	1,958.	2,155.	2,242.	2,247.	2,471.	2,570.
	72"	71 ^{13/16"}	29 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY7230NS	1,985.	2,182.	2,272.	2,287.	2,517.	2,619.
	78"	77 ^{13/16"}	29 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY7830NS	2,011.	2,215.	2,304.	2,331.	2,563.	2,666.
	84"	83 ^{13/16"}	29 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY8430NS	2,050.	2,257.	2,345.	2,370.	2,608.	2,715.
	90"	89 ^{13/16"}	29 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY9030NS	2,088.	2,298.	2,389.	2,414.	2,653.	2,761.
	96"	95 ^{13/16"}	29 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY9630NS	2,126.	2,339.	2,432.	2,457.	2,701.	2,809.



(with stretcher shown)

w* = nominal width

Dimensions listed under w d t h are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Freestanding Y Leg Table:	Freestanding Y Leg Table:	Freestanding Y Leg Table:	Grommet Option:
1. Pattern number	<i>Example:</i> DT1ARY6024NS, 114, 114	(2) Y Legs - Hardware kit - Table top - Stretcher or stiffening plate	To specify an edge grommet, replace the "N" suffix from the pattern number with an "E" and add \$18.
2. Base/Stretcher Paint Finish	DT1 Dividends Horizon Table	Note: Y Leg tables are finished with textured paint, including 613 Silver.	Stretcher Option:
3. Top Finish	A 2 Leg table assembly	Note: Y Leg Tables are only available in Knoll core finishes.	A stretcher is optional on 24" and 30" deep tables ONLY. To specify a table without a stretcher replace the "S" suffix from the pattern number with an "N". Stretchers are required on 36" and 42" depths.
4. Edge Finish	R Rectangular shape		
	Y Y Leg Base		
	60 Overall width in inches		
	24 Overall depth in inches		
	N No grommet		
	S Stretcher		
	114 Base/ stretcher paint finish		
	114 Laminate top finish		
	114 Edgeband finish		


Y Leg Tables

Freestanding Rectangular Table Top


36" and 42" Deep

Dividends Horizon

description	w*	w	d	t	h	pattern no.	Laminate Top P1 Paint	Laminate Top P2 Paint	Laminate Top P3 Paint	Techgrain Top P1 Paint	Techgrain Top P2 Paint	Techgrain Top P3 Paint
36" Deep Rectangular with (2) Y-Legs, No Grommet	60"	59 ^{13/16"}	35 1/2"	1 1/4"	28 1/2"	DT1ARY6036N	\$1,996.	\$2,192.	\$2,281.	\$2,304.	\$2,534.	\$2,633.
	66"	65 ^{13/16"}	35 1/2"	1 1/4"	28 1/2"	DT1ARY6636N	2,032.	2,232.	2,323.	2,346.	2,583.	2,685.
	72"	71 ^{13/16"}	35 1/2"	1 1/4"	28 1/2"	DT1ARY7236N	2,064.	2,272.	2,363.	2,392.	2,632.	2,737.
	78"	77 ^{13/16"}	35 1/2"	1 1/4"	28 1/2"	DT1ARY7836N	2,099.	2,310.	2,402.	2,437.	2,682.	2,789.
	84"	83 ^{13/16"}	35 1/2"	1 1/4"	28 1/2"	DT1ARY8436N	2,133.	2,348.	2,442.	2,484.	2,731.	2,839.
	90"	89 ^{13/16"}	35 1/2"	1 1/4"	28 1/2"	DT1ARY9036N	2,169.	2,386.	2,483.	2,529.	2,783.	2,891.
	96"	95 ^{13/16"}	35 1/2"	1 1/4"	28 1/2"	DT1ARY9636N	2,206.	2,425.	2,521.	2,574.	2,832.	2,942.



42" Deep Rectangular with (2) Y-Legs, No Grommet	84"	83 ^{13/16"}	41 1/2"	1 1/4"	28 1/2"	DT1ARY8442N	2,187.	2,410.	2,508.	2,778.	3,055.	3,180.
	90"	89 ^{13/16"}	41 1/2"	1 1/4"	28 1/2"	DT1ARY9042N	2,235.	2,460.	2,558.	2,817.	3,099.	3,223.
	96"	95 ^{13/16"}	41 1/2"	1 1/4"	28 1/2"	DT1ARY9642N	2,271.	2,498.	2,597.	2,855.	3,140.	3,265.



w* = nominal width

Dimensions listed under w d t h are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Freestanding Y Leg Table: 1. Pattern number 2. Base/Stretcher Paint Finish 3. Top Finish 4. Edge Finish	Freestanding Y Leg Table: <i>Example:</i> DT1ARY6024NS, 114, 114 DT1 Dividends Horizon Table A 2 Leg table assembly R Rectangular shape Y Y Leg Base 60 Overall width in inches 24 Overall depth in inches N No grommet S Stretcher 114 Base/ stretcher paint finish 114 Laminate top finish 114 Edgeband finish	Freestanding Y Leg Table: (2) Y Legs - Hardware kit - Table top - Stretcher or stiffening plate Note: Y Leg tables are finished with textured paint, including 613 Silver. Note: Y Leg Tables are only available in Knoll core finishes.	Grommet Option: - To specify an edge grommet, replace the "N" suffix from the pattern number with an "E" and add \$18. Stretcher Option: - A stretcher is optional on 24" and 30" deep tables ONLY. To specify a table without a stretcher replace the "S" suffix from the pattern number with an "N". Stretchers are required on 36" and 42" depths.

Y Leg Tables

Freestanding Racetrack Table Top

24" and 30" Deep

description	w*	w	d	t	h	pattern no.	Laminate Top P1 Paint	Laminate Top P2 Paint	Laminate Top P3 Paint	Techgrain Top P1 Paint	Techgrain Top P2 Paint	Techgrain Top P3 Paint
24" Deep Racetrack with (2) Y-Legs, No Grommet	60"	59 ^{13/16"}	23 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY6024NS	\$1,881.	\$2,072.	\$2,154.	\$3,360.	\$3,694.	\$3,845.
	66"	65 ^{13/16"}	23 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY6624NS	1,942.	2,133.	2,221.	3,392.	3,729.	3,879.
	72"	71 ^{13/16"}	23 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY7224NS	1,998.	2,199.	2,285.	3,420.	3,766.	3,915.
	78"	77 ^{13/16"}	23 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY7824NS	2,056.	2,262.	2,352.	3,453.	3,801.	3,949.
	84"	83 ^{13/16"}	23 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY8424NS	2,092.	2,302.	2,392.	3,482.	3,831.	3,985.
	90"	89 ^{13/16"}	23 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY9024NS	2,126.	2,339.	2,432.	3,515.	3,866.	4,022.
	96"	95 ^{13/16"}	23 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY9624NS	2,163.	2,379.	2,475.	3,547.	3,899.	4,057.



(with stretcher shown)

30" Deep Racetrack with (2) Y-Legs, No Grommet	60"	59 ^{13/16"}	29 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY6030NS	1,956.	2,150.	2,237.	3,410.	3,752.	3,902.
	66"	65 ^{13/16"}	29 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY6630NS	2,010.	2,213.	2,302.	3,444.	3,787.	3,940.
	72"	71 ^{13/16"}	29 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY7230NS	2,066.	2,272.	2,363.	3,475.	3,823.	3,978.
	78"	77 ^{13/16"}	29 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY7830NS	2,121.	2,332.	2,425.	3,510.	3,862.	4,017.
	84"	83 ^{13/16"}	29 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY8430NS	2,160.	2,377.	2,471.	3,546.	3,898.	4,055.
	90"	89 ^{13/16"}	29 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY9030NS	2,200.	2,419.	2,516.	3,578.	3,935.	4,092.
	96"	95 ^{13/16"}	29 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY9630NS	2,238.	2,464.	2,561.	3,610.	3,972.	4,132.



(with stretcher shown)

w* = nominal width

Dimensions listed under w d t h are actual to the nearest 1/16"

Ordering Information	Order Code	Included With	Options
Freestanding Y Leg Table:	Freestanding Y Leg Table:	Freestanding Y Leg Table:	Grommet Option:
1. Pattern number	<i>Example:</i> DT1ATY6024NS, 114, 114	• (2) Y Legs	• To specify an edge grommet, replace the "N" suffix from the pattern number with an "E" and add \$18.
2. Base/Stretcher Paint Finish	DT1 Dividends Horizon Table	• Hardware kit	
3. Top Finish	A 2 Leg table assembly	• Table top	
4. Edge Finish	T Racetrack shape	• Stretcher or stiffening plate	
	Y Y Leg Base	Note: Y Leg tables are finished with textured paint, including 613 Silver.	Stretcher Option:
	60 Overall width in inches	Note: Y Leg Tables are only available in Knoll core finishes.	• A stretcher is optional on 24" and 30" deep tables ONLY. To specify a table without a stretcher replace the "S" suffix from pattern number with an "N". Stretchers are required on 36" and 42" depths.
	24 Overall depth in inches		
	N No grommet		
	S Stretcher		
	114 Base/ stretcher paint finish		
	114 Laminate top finish		
	114 Edgeband finish		

Y Leg Tables

Freestanding Racetrack Table Top


36" and 42" Deep

Dividends Horizon

description	w*	w	d	t	h	pattern no.	Laminate Top P1 Paint	Laminate Top P2 Paint	Laminate Top P3 Paint	Techgrain Top P1 Paint	Techgrain Top P2 Paint	Techgrain Top P3 Paint
36" Deep Racetrack with (2) Y-Legs, No Grommet	60"	59 ^{13/16"}	35 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY6036N	\$2,022.	\$2,226.	\$2,314.	\$3,459.	\$3,807.	\$3,959.
	66"	65 ^{13/16"}	35 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY6636N	2,087.	2,295.	2,386.	3,498.	3,845.	3,999.
	72"	71 ^{13/16"}	35 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY7236N	2,148.	2,364.	2,459.	3,531.	3,884.	4,042.
	78"	77 ^{13/16"}	35 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY7836N	2,213.	2,432.	2,531.	3,568.	3,925.	4,083.
	84"	83 ^{13/16"}	35 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY8436N	2,247.	2,472.	2,570.	3,605.	3,964.	4,126.
	90"	89 ^{13/16"}	35 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY9036N	2,282.	2,511.	2,609.	3,639.	4,007.	4,167.
	96"	95 ^{13/16"}	35 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY9636N	2,316.	2,548.	2,650.	3,677.	4,046.	4,208.



42" Deep Racetrack with (2) Y-Legs, No Grommet	84"	83 ^{13/16"}	41 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY8442N	2,302.	2,531.	2,631.	3,668.	4,036.	4,195.
	90"	89 ^{13/16"}	41 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY9042N	2,344.	2,581.	2,683.	3,708.	4,078.	4,238.
	96"	95 ^{13/16"}	41 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ATY9642N	2,386.	2,627.	2,730.	3,742.	4,119.	4,285.



w* = nominal width


Dimensions listed under w d t h are actual to the nearest 1/16"

Ordering Information	Order Code	Included With	Options
Freestanding Y Leg Table:	Freestanding Y Leg Table:	Freestanding Y Leg Table:	Grommet Option:
1. Pattern number	<i>Example:</i> DT1ATY6024NS, 114, 114	• (2) Y Legs • Hardware kit • Table top • Stretcher or stiffening plate	• To specify an edge grommet, replace the "N" suffix from the pattern number with an "E" and add \$18.
2. Base/Stretcher Paint Finish	DT1 Dividends Horizon Table	Note: Y Leg tables are finished with textured paint, including 613 Silver.	Stretcher Option:
3. Top Finish	A 2 Leg table assembly	Note: Y Leg Tables are only available in Knoll core finishes.	• A stretcher is optional on 24" and 30" deep tables ONLY. To specify a table without a stretcher replace the "S" suffix from pattern number with an "N". Stretchers are required on 36" and 42" depths.
4. Edge Finish	T Racetrack shape		
	Y Y Leg Base		
	60 Overall width in inches		
	24 Overall depth in inches		
	N No grommet		
	S Stretcher		
	114 Base/ stretcher paint finish		
	114 Laminate top finish		
	114 Edgeband finish		

Y Leg Tables


Credenza Supported Rectangular Table Top
24", 30" and 36" deep

description	w*	w	d	t	h	pattern no.	Laminate Top P1 Paint	Laminate Top P2 Paint	Laminate Top P3 Paint	Techgrain Top P1 Paint	Techgrain Top P2 Paint	Techgrain Top P3 Paint
24" Deep Rectangular with (1) Y-Leg and (1) Spacer - No Grommet	60"	59 ¹³ / ₁₆ "	23 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1CRY6024N	\$1,573.	\$1,732.	\$1,801.	\$1,845.	\$2,031.	\$2,109.
	66"	65 ¹³ / ₁₆ "	23 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1CRY6624N	1,593.	1,753.	1,825.	1,879.	2,068.	2,149.
	72"	71 ¹³ / ₁₆ "	23 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1CRY7224N	1,615.	1,776.	1,849.	1,915.	2,105.	2,189.
	78"	77 ¹³ / ₁₆ "	23 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1CRY7824N	1,634.	1,799.	1,871.	1,953.	2,147.	2,232.
	84"	83 ¹³ / ₁₆ "	23 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1CRY8424N	1,670.	1,837.	1,911.	1,989.	2,184.	2,274.
	90"	89 ¹³ / ₁₆ "	23 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1CRY9024N	1,709.	1,876.	1,953.	2,022.	2,226.	2,313.
	96"	95 ¹³ / ₁₆ "	23 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1CRY9624N	1,743.	1,916.	1,994.	2,059.	2,265.	2,356.




(credenza not included)

30" Deep Rectangular with (1) Y-Leg and (1) Spacer - No Grommet	60"	59 ¹³ / ₁₆ "	29 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1CRY6030N	1,620.	1,780.	1,852.	1,893.	2,080.	2,164.
	66"	65 ¹³ / ₁₆ "	29 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1CRY6630N	1,645.	1,809.	1,881.	1,934.	2,127.	2,213.
	72"	71 ¹³ / ₁₆ "	29 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1CRY7230N	1,672.	1,838.	1,913.	1,977.	2,174.	2,260.
	78"	77 ¹³ / ₁₆ "	29 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1CRY7830N	1,699.	1,869.	1,946.	2,016.	2,221.	2,308.
	84"	83 ¹³ / ₁₆ "	29 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1CRY8430N	1,739.	1,911.	1,989.	2,059.	2,265.	2,356.
	90"	89 ¹³ / ₁₆ "	29 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1CRY9030N	1,776.	1,955.	2,035.	2,100.	2,311.	2,402.
	96"	95 ¹³ / ₁₆ "	29 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1CRY9630N	1,815.	1,998.	2,077.	2,141.	2,357.	2,449.



(credenza not included)

36" Deep Rectangular with (1) Y-Leg and (1) Spacer - No Grommet	60"	59 ¹³ / ₁₆ "	35 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1CRY6036N	1,718.	1,890.	1,962.	2,021.	2,225.	2,313.
	66"	65 ¹³ / ₁₆ "	35 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1CRY6636N	1,748.	1,922.	2,001.	2,064.	2,272.	2,361.
	72"	71 ¹³ / ₁₆ "	35 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1CRY7236N	1,781.	1,959.	2,038.	2,104.	2,315.	2,410.
	78"	77 ¹³ / ₁₆ "	35 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1CRY7836N	1,814.	1,996.	2,075.	2,148.	2,363.	2,458.
	84"	83 ¹³ / ₁₆ "	35 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1CRY8436N	1,858.	2,045.	2,126.	2,187.	2,408.	2,504.
	90"	89 ¹³ / ₁₆ "	35 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1CRY9036N	1,904.	2,095.	2,178.	2,232.	2,456.	2,552.
	96"	95 ¹³ / ₁₆ "	35 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1CRY9636N	1,951.	2,145.	2,229.	2,274.	2,500.	2,600.



(credenza not included)

w* = nominal width

Dimensions listed under w d t h are actual to the nearest 1/16"

Ordering Information	Order Code	Included with	Options
Credenza Supported Y Leg Table:	Credenza Supported Y Leg Table:	Credenza Supported Y leg Table:	Grommet Option:
1. Pattern number	<i>Example:</i> DT1CRY6024N, 114, 114	(1) Y Leg (1) Credenza support spacer - Hardware kit - Table top - Stiffening plate	To specify an edge grommet, replace the "N" suffix from the pattern number with an "E" and add \$18.
2. Base/Stretcher Paint Finish	DT1 Dividends Horizon Table	Credenza must be specified separately	Note: Credenza supported tables may be used with laminate or veneer top credenzas only and are not compatible with steel top credenzas.
3. Top Finish	C Credenza support assembly		
4. Edge Finish	R Rectangular shape		
	Y Y Leg Base		
	60 Overall width in inches		
	24 Overall depth in inches	Note: Y Leg tables are finished with textured paint, including 613 Silver.	
	N No grommet	Note: Y Leg Tables are only available in Knoll core finishes.	
	114 Base/ stretcher paint finish		
	114 Laminate top finish		
	114 Edgeband finish		


Y Leg Tables

Dividends Horizon

Credenza Supported Racetrack Table Top


24", 30" and 36" deep

description	w*	w	d	h	pattern no.	Laminate Top P1 Paint	Laminate Top P2 Paint	Laminate Top P3 Paint	Techgrain Top P1 Paint	Techgrain Top P2 Paint	Techgrain Top P3 Paint
24" Deep Racetrack with (1) Y-Leg and (1) Spacer - No Grommet	60"	59 ^{13/16"}	23 ^{1/2"}	28 ^{1/2"}	DT1CTY6024N	\$1,571.	\$1,728.	\$1,799.	\$3,076.	\$3,382.	\$3,474.
	66"	65 ^{13/16"}	23 ^{1/2"}	28 ^{1/2"}	DT1CTY6624N	1,629.	1,792.	1,864.	3,093.	3,403.	3,504.
	72"	71 ^{13/16"}	23 ^{1/2"}	28 ^{1/2"}	DT1CTY7224N	1,688.	1,856.	1,929.	3,108.	3,420.	3,528.
	78"	77 ^{13/16"}	23 ^{1/2"}	28 ^{1/2"}	DT1CTY7824N	1,745.	1,918.	1,997.	3,128.	3,441.	3,556.
	84"	83 ^{13/16"}	23 ^{1/2"}	28 ^{1/2"}	DT1CTY8424N	1,766.	1,942.	2,017.	3,142.	3,459.	3,582.
	90"	89 ^{13/16"}	23 ^{1/2"}	28 ^{1/2"}	DT1CTY9024N	1,783.	1,961.	2,040.	3,161.	3,476.	3,608.
	96"	95 ^{13/16"}	23 ^{1/2"}	28 ^{1/2"}	DT1CTY9624N	1,802.	1,984.	2,061.	3,179.	3,499.	3,635.




(credenza not included)

30" Deep Racetrack with (1) Y-Leg and (1) Spacer - No Grommet	60"	59 ^{13/16"}	29 ^{1/2"}	28 ^{1/2"}	DT1CTY6030N	1,645.	1,809.	1,881.	3,095.	3,404.	3,518.
	66"	65 ^{13/16"}	29 ^{1/2"}	28 ^{1/2"}	DT1CTY6630N	1,700.	1,871.	1,947.	3,130.	3,443.	3,560.
	72"	71 ^{13/16"}	29 ^{1/2"}	28 ^{1/2"}	DT1CTY7230N	1,755.	1,929.	2,007.	3,162.	3,479.	3,605.
	78"	77 ^{13/16"}	29 ^{1/2"}	28 ^{1/2"}	DT1CTY7830N	1,809.	1,992.	2,072.	3,197.	3,518.	3,645.
	84"	83 ^{13/16"}	29 ^{1/2"}	28 ^{1/2"}	DT1CTY8430N	1,850.	2,035.	2,118.	3,233.	3,556.	3,688.
	90"	89 ^{13/16"}	29 ^{1/2"}	28 ^{1/2"}	DT1CTY9030N	1,890.	2,077.	2,160.	3,265.	3,596.	3,732.
	96"	95 ^{13/16"}	29 ^{1/2"}	28 ^{1/2"}	DT1CTY9630N	1,926.	2,121.	2,207.	3,301.	3,631.	3,776.



(credenza not included)

36" Deep Racetrack with (1) Y-Leg and (1) Spacer - No Grommet	60"	59 ^{13/16"}	35 ^{1/2"}	28 ^{1/2"}	DT1CTY6036N	1,742.	1,915.	1,993.	3,112.	3,423.	3,560.
	66"	65 ^{13/16"}	35 ^{1/2"}	28 ^{1/2"}	DT1CTY6636N	1,802.	1,984.	2,061.	3,165.	3,480.	3,621.
	72"	71 ^{13/16"}	35 ^{1/2"}	28 ^{1/2"}	DT1CTY7236N	1,864.	2,050.	2,132.	3,216.	3,538.	3,679.
	78"	77 ^{13/16"}	35 ^{1/2"}	28 ^{1/2"}	DT1CTY7836N	1,924.	2,119.	2,204.	3,269.	3,597.	3,736.
	84"	83 ^{13/16"}	35 ^{1/2"}	28 ^{1/2"}	DT1CTY8436N	1,969.	2,166.	2,255.	3,319.	3,653.	3,801.
	90"	89 ^{13/16"}	35 ^{1/2"}	28 ^{1/2"}	DT1CTY9036N	2,013.	2,216.	2,305.	3,371.	3,710.	3,858.
	96"	95 ^{13/16"}	35 ^{1/2"}	28 ^{1/2"}	DT1CTY9636N	2,058.	2,264.	2,355.	3,422.	3,767.	3,918.



(credenza not included)

w* = nominal width

Dimensions listed under w d t h are actual to the nearest 1/16"

Ordering Information	Order Code	Included with	Options
Credenza Supported Y Leg Table:	Credenza Supported Y Leg Table:	Credenza Supported Y Leg Table:	Grommet Option:
1. Pattern number	<i>Example:</i> DT1CTY6024N, 114, 114	(1) Y Leg (1) Credenza support spacer - Hardware kit - Table top - Stiffening plate	To specify an edge grommet, replace the "N" suffix from the pattern number with an "E" and add \$18.
2. Base/Stretcher Paint Finish	DT1 Dividends Horizon Table	Credenza must be specified separately	Note: Credenza supported tables may be used with laminate or veneer top credenzas only and are not compatible with steel top credenzas.
3. Top Finish	C Credenza support assembly		
4. Edge Finish	T Racetrack shape		
	Y Y Leg Base		
	60 Overall width in inches		
	24 Overall depth in inches	Note: Y Leg tables are finished with textured paint, including 613 Silver.	
	N No grommet	Note: Y Leg Tables are only available in Knoll core finishes.	
	114 Base/ stretcher paint finish		
	114 Laminate top finish		
	114 Edgeband finish		

This page intentionally left blank

X Base Tables

Table Supports

Specifications

X Base Tables

Dividends Horizon X base tables are designed to be used along with the Dividends Horizon system to create a consistent aesthetic throughout the entire office. With various height and width options, X base tables can be used in a multitude of applications, including collaboration areas in the open plan, break rooms, and lounge areas.

Available with a round, square or rounded square top shape with either a laminate or veneer finish, a Dividends Horizon X base table is appropriate for use in a vast array of applications from the private office to the open plan and even to lounge areas. The five height options allow for the same table base to be used in various applications while maintaining visual consistency throughout the space.

X base tables include a top, support column, and X base.

Available Sizes

- Width: 30 - 48 inches
- Depth: 30 - 48 inches
- Heights: 17, 21, 28-1/2, 36, and 42 inches

Construction

• Worksurface:

- Material: 0.028" thick laminate or 0.6mm thick veneer on 1-1/8" particle board core
- Edge: plastic laminate tops have a 2mm edgeband; Techwood tops have a 3/16" thick Techwood edge.

• Base:

- Foot: die cast aluminum
- Column: extruded aluminum with 3/16" thick structural plate

Table Supports

X bases may be specified separately for use with an alternative table top. The appropriate X base size must be selected according to the width of the table top being used. X bases are available in five heights and may be used with table tops that are 30 to 48 inches wide.

Available Sizes

Heights: 17, 21, 28-1/2, 36, and 42 inches


Construction

• Base:

- Foot: die cast aluminum
- Column: extruded aluminum with 3/16" thick structural plate

Note: Dividends Horizon tables are only available in Knoll Core paint and laminate finishes. Legacy finishes are not available. All paint finishes have the Dividends Horizon textured paint finish; this includes 613 Silver, which is a smooth paint on all other Dividends Horizon products.

Square X Base Table



Round X Base Table



Rounded Square X Base Table



X Base Tables

Square Table Tops

17", 21", 28", 36" and 42" High

Dividends Horizon

description	w*	w	d	t	h	pattern no.	Laminate Top P1 Paint	Laminate Top P2 Paint	Laminate Top P3 Paint	Techgrain Top P1 Paint	Techgrain Top P2 Paint	Techgrain Top P3 Paint
	30"	29 ^{13/16"}	29 ^{13/16"}	1 ^{1/4"}	17"	DT1ASX303017	\$1,144.	\$1,263.	\$1,314.	\$1,691.	\$1,869.	\$1,945.
	36"	35 ^{13/16"}	35 ^{13/16"}	1 ^{1/4"}	17"	DT1ASX363617	1,194.	1,319.	1,372.	1,786.	1,967.	2,047.
	42"	41 ^{13/16"}	41 ^{13/16"}	1 ^{1/4"}	17"	DT1ASX424217	1,327.	1,461.	1,518.	1,892.	2,081.	2,166.
	48"	47 ^{13/16"}	47 ^{13/16"}	1 ^{1/4"}	17"	DT1ASX484817	1,390.	1,535.	1,594.	1,966.	2,165.	2,255.

	30"	29 ^{13/16"}	29 ^{13/16"}	1 ^{1/4"}	21"	DT1ASX303021	1,144.	1,263.	1,314.	1,691.	1,869.	1,945.
	36"	35 ^{13/16"}	35 ^{13/16"}	1 ^{1/4"}	21"	DT1ASX363621	1,194.	1,319.	1,372.	1,786.	1,967.	2,047.
	42"	41 ^{13/16"}	41 ^{13/16"}	1 ^{1/4"}	21"	DT1ASX424221	1,327.	1,461.	1,518.	1,892.	2,081.	2,166.
	48"	47 ^{13/16"}	47 ^{13/16"}	1 ^{1/4"}	21"	DT1ASX484821	1,390.	1,535.	1,594.	1,966.	2,165.	2,255.

	30"	29 ^{13/16"}	29 ^{13/16"}	1 ^{1/4"}	28 ^{1/2"}	DT1ASX3030	1,173.	1,290.	1,340.	1,718.	1,895.	1,969.
	36"	35 ^{13/16"}	35 ^{13/16"}	1 ^{1/4"}	28 ^{1/2"}	DT1ASX3636	1,222.	1,343.	1,396.	1,813.	1,994.	2,074.
	42"	41 ^{13/16"}	41 ^{13/16"}	1 ^{1/4"}	28 ^{1/2"}	DT1ASX4242	1,350.	1,489.	1,546.	1,916.	2,107.	2,190.
	48"	47 ^{13/16"}	47 ^{13/16"}	1 ^{1/4"}	28 ^{1/2"}	DT1ASX4848	1,416.	1,559.	1,622.	1,993.	2,189.	2,279.

	30"	29 ^{13/16"}	29 ^{13/16"}	1 ^{1/4"}	36"	DT1ASX303036	1,237.	1,354.	1,407.	1,781.	1,959.	2,035.
	36"	35 ^{13/16"}	35 ^{13/16"}	1 ^{1/4"}	36"	DT1ASX363636	1,287.	1,409.	1,462.	1,876.	2,058.	2,138.
	42"	41 ^{13/16"}	41 ^{13/16"}	1 ^{1/4"}	36"	DT1ASX424236	1,415.	1,550.	1,612.	1,983.	2,174.	2,258.
	48"	47 ^{13/16"}	47 ^{13/16"}	1 ^{1/4"}	36"	DT1ASX484836	1,482.	1,624.	1,687.	2,057.	2,257.	2,343.

	30"	29 ^{13/16"}	29 ^{13/16"}	1 ^{1/4"}	42"	DT1ASX303042	1,262.	1,380.	1,430.	1,807.	1,986.	2,059.
	36"	35 ^{13/16"}	35 ^{13/16"}	1 ^{1/4"}	42"	DT1ASX363642	1,310.	1,435.	1,490.	1,903.	2,084.	2,164.
	42"	41 ^{13/16"}	41 ^{13/16"}	1 ^{1/4"}	42"	DT1ASX424242	1,444.	1,579.	1,636.	2,007.	2,200.	2,282.
	48"	47 ^{13/16"}	47 ^{13/16"}	1 ^{1/4"}	42"	DT1ASX484842	1,508.	1,648.	1,714.	2,081.	2,281.	2,368.

w* = nominal width

Dimensions listed under w d t h are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
X Base Table:	X Base Table:	X Base Table:	
1. Pattern number	<i>Example:</i> DT1ASX3030, 114, 114,	• (1) X Base	
2. Base Paint Finish	114	• Hardware kit	
3. Top Finish	DT1 Dividends Horizon	• Table top	
4. Edge Finish	A Table assembly	Note: X Base Tables are finished	
	S Square shape	with textured paint, including 613	
	X X Base	Silver.	
	30 Overall width in inches	Note: X Base Tables are only	
	30 Overall depth in inches	available in Knoll core finishes.	
	114 Base finish		
	114 Laminate top finish		
	114 Edgeband finish		

X Base Tables

Round Table Tops


17", 21", 28", 36" and 42" High


Dividends Horizon

description	w*	w	d	t	h	pattern no.	Laminate Top P1 Paint	Laminate Top P2 Paint	Laminate Top P3 Paint	Techgrain Top P1 Paint	Techgrain Top P2 Paint	Techgrain Top P3 Paint
	30"	29 ^{13/16"}	29 ^{13/16"}	1 ^{1/4"}	17"	DT1ACX3017	\$1,157.	\$1,277.	\$1,329.	\$2,584.	\$2,843.	\$2,959.
	36"	35 ^{13/16"}	35 ^{13/16"}	1 ^{1/4"}	17"	DT1ACX3617	1,205.	1,328.	1,381.	2,686.	2,958.	3,077.
	42"	41 ^{13/16"}	41 ^{13/16"}	1 ^{1/4"}	17"	DT1ACX4217	1,332.	1,467.	1,529.	2,813.	3,099.	3,224.
	48"	47 ^{13/16"}	47 ^{13/16"}	1 ^{1/4"}	17"	DT1ACX4817	1,396.	1,540.	1,600.	2,891.	3,183.	3,312.

	30"	29 ^{13/16"}	29 ^{13/16"}	1 ^{1/4"}	21"	DT1ACX3021	1,157.	1,277.	1,329.	2,584.	2,843.	2,959.
	36"	35 ^{13/16"}	35 ^{13/16"}	1 ^{1/4"}	21"	DT1ACX3621	1,205.	1,328.	1,381.	2,686.	2,958.	3,077.
	42"	41 ^{13/16"}	41 ^{13/16"}	1 ^{1/4"}	21"	DT1ACX4221	1,332.	1,467.	1,529.	2,813.	3,099.	3,224.
	48"	47 ^{13/16"}	47 ^{13/16"}	1 ^{1/4"}	21"	DT1ACX4821	1,396.	1,540.	1,600.	2,891.	3,183.	3,312.

	30"	29 ^{13/16"}	29 ^{13/16"}	1 ^{1/4"}	28 ^{1/2"}	DT1ACX30	1,184.	1,302.	1,354.	2,608.	2,869.	2,986.
	36"	35 ^{13/16"}	35 ^{13/16"}	1 ^{1/4"}	28 ^{1/2"}	DT1ACX36	1,230.	1,352.	1,408.	2,711.	2,985.	3,101.
	42"	41 ^{13/16"}	41 ^{13/16"}	1 ^{1/4"}	28 ^{1/2"}	DT1ACX42	1,357.	1,495.	1,553.	2,841.	3,125.	3,252.
	48"	47 ^{13/16"}	47 ^{13/16"}	1 ^{1/4"}	28 ^{1/2"}	DT1ACX48	1,424.	1,565.	1,628.	2,917.	3,209.	3,337.

	30"	29 ^{13/16"}	29 ^{13/16"}	1 ^{1/4"}	36"	DT1ACX3036	1,247.	1,367.	1,417.	2,673.	2,931.	3,049.
	36"	35 ^{13/16"}	35 ^{13/16"}	1 ^{1/4"}	36"	DT1ACX3636	1,294.	1,416.	1,470.	2,776.	3,048.	3,166.
	42"	41 ^{13/16"}	41 ^{13/16"}	1 ^{1/4"}	36"	DT1ACX4236	1,423.	1,558.	1,618.	2,905.	3,190.	3,315.
	48"	47 ^{13/16"}	47 ^{13/16"}	1 ^{1/4"}	36"	DT1ACX4836	1,490.	1,630.	1,693.	2,981.	3,274.	3,402.

	30"	29 ^{13/16"}	29 ^{13/16"}	1 ^{1/4"}	42"	DT1ACX3042	1,274.	1,391.	1,447.	2,700.	2,959.	3,076.
	36"	35 ^{13/16"}	35 ^{13/16"}	1 ^{1/4"}	42"	DT1ACX3642	1,322.	1,446.	1,499.	2,803.	3,074.	3,192.
	42"	41 ^{13/16"}	41 ^{13/16"}	1 ^{1/4"}	42"	DT1ACX4242	1,450.	1,585.	1,642.	2,929.	3,214.	3,341.
	48"	47 ^{13/16"}	47 ^{13/16"}	1 ^{1/4"}	42"	DT1ACX4842	1,513.	1,655.	1,719.	3,008.	3,300.	3,425.

w* = nominal width

Dimensions listed under w d t h are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
X Base Table:	X Base Table:	X Base Table:	
1. Pattern number	<i>Example:</i> DT1ACX3030, 114, 114,	• (1) X Base	
2. Base Paint Finish	114	• Hardware kit	
3. Top Finish	DT1 Dividends Horizon	• Table top	
4. Edge Finish	A Table assembly	Note: X Base Tables are finished	
	C Round shape	with textured paint, including 613	
	X X Base	Silver.	
	30 Overall width in inches	Note: X Base Tables are only	
	30 Overall depth in inches	available in Knoll core finishes.	
	114 Base finish		
	114 Laminate top finish		
	114 Edgeband finish		

X Base Tables

Rounded Square Table Tops

17", 21", 28", 36" and 42" High

Dividends Horizon

							Laminate Top P1 Paint	Laminate Top P2 Paint	Laminate Top P3 Paint	Techgrain Top P1 Paint	Techgrain Top P2 Paint	Techgrain Top P3 Paint	
description	w*	w	d	t	h	pattern no.							
	17" High Rounded Square X Base Table	30"	29 ^{13/16"}	29 ^{13/16"}	1 ^{1/4"}	17"	DT1ADX303017	\$1,157.	\$1,277.	\$1,329.	\$2,584.	\$2,843.	\$2,959.
		36"	35 ^{13/16"}	35 ^{13/16"}	1 ^{1/4"}	17"	DT1ADX363617	1,205.	1,328.	1,381.	2,686.	2,958.	3,077.
		42"	41 ^{13/16"}	41 ^{13/16"}	1 ^{1/4"}	17"	DT1ADX424217	1,332.	1,467.	1,529.	2,813.	3,099.	3,224.
		48"	47 ^{13/16"}	47 ^{13/16"}	1 ^{1/4"}	17"	DT1ADX484817	1,396.	1,540.	1,600.	2,891.	3,183.	3,312.



21" High Rounded Square X Base Table	30"	29 ^{13/16"}	29 ^{13/16"}	1 ^{1/4"}	21"	DT1ADX303021	1,157.	1,277.	1,329.	2,584.	2,843.	2,959.
	36"	35 ^{13/16"}	35 ^{13/16"}	1 ^{1/4"}	21"	DT1ADX363621	1,205.	1,328.	1,381.	2,686.	2,958.	3,077.
	42"	41 ^{13/16"}	41 ^{13/16"}	1 ^{1/4"}	21"	DT1ADX424221	1,332.	1,467.	1,529.	2,813.	3,099.	3,224.
	48"	47 ^{13/16"}	47 ^{13/16"}	1 ^{1/4"}	21"	DT1ADX484821	1,396.	1,540.	1,600.	2,891.	3,183.	3,312.



28" High Rounded Square X Base Table	30"	29 ^{13/16"}	29 ^{13/16"}	1 ^{1/4"}	28 ^{1/2"}	DT1ADX3030	1,184.	1,302.	1,354.	2,608.	2,869.	2,986.
	36"	35 ^{13/16"}	35 ^{13/16"}	1 ^{1/4"}	28 ^{1/2"}	DT1ADX3636	1,230.	1,352.	1,408.	2,711.	2,985.	3,101.
	42"	41 ^{13/16"}	41 ^{13/16"}	1 ^{1/4"}	28 ^{1/2"}	DT1ADX4242	1,357.	1,495.	1,553.	2,841.	3,125.	3,252.
	48"	47 ^{13/16"}	47 ^{13/16"}	1 ^{1/4"}	28 ^{1/2"}	DT1ADX4848	1,424.	1,565.	1,628.	2,917.	3,209.	3,337.



36" High Rounded Square X Base Table	30"	29 ^{13/16"}	29 ^{13/16"}	1 ^{1/4"}	36"	DT1ADX303036	1,247.	1,367.	1,417.	2,673.	2,931.	3,049.
	36"	35 ^{13/16"}	35 ^{13/16"}	1 ^{1/4"}	36"	DT1ADX363636	1,294.	1,416.	1,470.	2,776.	3,048.	3,166.
	42"	41 ^{13/16"}	41 ^{13/16"}	1 ^{1/4"}	36"	DT1ADX424236	1,423.	1,558.	1,618.	2,905.	3,190.	3,315.
	48"	47 ^{13/16"}	47 ^{13/16"}	1 ^{1/4"}	36"	DT1ADX484836	1,490.	1,630.	1,693.	2,981.	3,274.	3,402.



Tables

w* = nominal width

Dimensions listed under w d t h are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
X Base Table:	X Base Table:	X Base Table:	
1. Pattern number	<i>Example:</i> DT1ADX3030, 114, 114,	• (1) X Base	
2. Base Paint Finish	114	• Hardware kit	
3. Top Finish	DT1 Dividends Horizon	• Table top	
4. Edge Finish	A Table assembly	Note: X Base Tables are finished	
	D Rounded Square shape	with textured paint, including 613	
	X X Base	Silver.	
	30 Overall width in inches	Note: X Base Tables are only	
	30 Overall depth in inches	available in Knoll core finishes.	
	114 Base finish		
	114 Laminate top finish		
	114 Edgeband finish		

X Base Tables

Rounded Square Table Tops

17", 21", 28", 36" and 42" High

Dividends Horizon

description	w*	w	d	t	h	pattern no.	Laminate Top	Laminate Top	Laminate Top	Techgrain Top	Techgrain Top	Techgrain Top
							P1 Paint	P2 Paint	P3 Paint	P1 Paint	P2 Paint	P3 Paint
42" High Rounded Square X Base Table	30"	29 13/16"	29 13/16"	1 1/4"	42"	DT1ADX303042	\$1,274.	\$1,391.	\$1,447.	\$2,700.	\$2,959.	\$3,076.
	36"	35 13/16"	35 13/16"	1 1/4"	42"	DT1ADX363642	1,322.	1,446.	1,499.	2,803.	3,074.	3,192.
	42"	41 13/16"	41 13/16"	1 1/4"	42"	DT1ADX424242	1,450.	1,585.	1,642.	2,929.	3,214.	3,341.
	48"	47 13/16"	47 13/16"	1 1/4"	42"	DT1ADX484842	1,513.	1,655.	1,719.	3,008.	3,300.	3,425.



w* = nominal width

Dimensions listed under w d t h are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
X Base Table:	X Base Table:	X Base Table:	
1. Pattern number	<i>Example:</i> DT1ADX3030, 114, 114,	• (1) X Base	
2. Base Paint Finish	114	• Hardware kit	
3. Top Finish	DT1 Dividends Horizon	• Table top	
4. Edge Finish	A Table assembly	Note: X Base Tables are finished	
	D Rounded Square shape	with textured paint, including 613	
	X X Base	Silver.	
	30 Overall width in inches	Note: X Base Tables are only	
	30 Overall depth in inches	available in Knoll core finishes.	
	114 Base finish		
	114 Laminate top finish		
	114 Edgeband finish		

Table Supports

X Bases

Credenza Support Spacer

Dividends Horizon

description	w	h	d	pattern no.	P1	P2	P3
Small X-Base, for use with 30" or 36" wide round, square or rounded square table tops		17"		DT1BXS17	\$615.	\$680.	\$709.
		21"		DT1BXS21	615.	680.	709.
		28"		DT1BXS	640.	707.	735.
		36"		DT1BXS36	707.	769.	799.
		42"		DT1BXS42	731.	797.	824.



Large X Base, for use with 42" or 48" wide round, square or rounded square table tops		17"		DT1BXL17	679.	749.	779.
		21"		DT1BXL21	679.	749.	779.
		28"		DT1BXL	706.	774.	806.
		36"		DT1BXL36	768.	839.	870.
		42"		DT1BXL42	795.	866.	896.



Credenza Support Spacer For use with Dividends Horizon Credenza	9 ⁵ / ₈ "	2 ¹⁵ / ₁₆ "	1 ⁹ / ₁₆ "	DT1S	183.	203.	211.
--	---------------------------------	-----------------------------------	----------------------------------	-------------	------	------	------



Small T-Base, for use with 24" or 30" deep tops	28"			DT1BTS	640.	707.	735.
---	-----	--	--	---------------	------	------	------



Large T-Base, for use with 36" or 48" deep tops	28"			DT1BTL	706.	774.	806.
---	-----	--	--	---------------	------	------	------



Ordering Information	Order Code	Included with:	Options
Table Supports:	X Base:	X Base:	Casters are designed for use on X- and Y-bases only.
1. Pattern number	<i>Example:</i> DT1BXS, 114	• X Base	
2. Paint Finish	DT1 Dividends Horizon Table	• Hardware kit	Tables with casters may not exceed 28"h, 84"w or 42"d.
	B Base	T Base:	
	S X Shape	• T Base	
	114 Paint finish	• Hardware kit	
	Credenza Support Spacer:	Credenza Support spacer:	
	<i>Example:</i> DT1S, 114	• Support spacer	
	DT1 Dividends Horizon Table	• Hardware Kit	
	S Support Spacer	Note: X and T bases are painted with textured paint, including 613 Silver.	
	114 Paint finish	Note: Table supports are only available in Knoll core finishes.	

Table Supports
X Bases
Credenza Support Spacer

Dividends Horizon

description	w	h	d	pattern no.	P1	P2	P3
Caster Kit (set of 4) black only    		1"		DT1CK4	\$44.	\$0.	\$0.

Ordering Information	Order Code	Included with:	Options
Table Supports: 1. Pattern number 2. Paint Finish	X Base: <i>Example:</i> DT1BXS, 114 DT1 Dividends Horizon Table B Base S X Shape 114 Paint finish Credenza Support Spacer: <i>Example:</i> DT1S, 114 DT1 Dividends Horizon Table S Support Spacer 114 Paint finish 	X Base: • X Base • Hardware kit T Base: • T Base • Hardware kit Credenza Support spacer: • Support spacer • Hardware Kit Note: X and T bases are painted with textured paint, including 613 Silver. Note: Table supports are only available in Knoll core finishes.	Casters are designed for use on X- and Y-bases only. Tables with casters may not exceed 28"h, 84"w or 42"d.

This page intentionally left blank

Dividends Horizon Conference Tables

Dividends Horizon conference tables are designed with a scale and visual language consistent with the full scope of Dividends Horizon products. This design consistency makes Dividends Horizon tables appropriate for use in conference, meeting, private office and open plan office applications.

Dividends Horizon conference tables are available in racetrack, rectangular, or boat shape and in all standard Dividends Horizon finishes.

Conference tables include a table top and base assembly. A conference table base assembly includes two Y legs, one center support T base, and two horizontal stretchers that connect the three bases. All conference table tops are produced in two pieces. Grain patterns on woodgrain laminates and veneer tops will not match at the seam in the middle of the conference tables.

Available Sizes

Width: 102- 144 inches

Depth: 36- 48 inches

Height: 28-1/2 inches

Construction

Worksurface:

- Material: 0.028 inch thick laminate or 0.6mm thick veneer on 1-1/8 inch thick particle board core
- Edge: plastic laminate tops have a 2mm edgeband; Techwood tops have a 3/16" thick Techwood edge


Base:

- Stretcher: extruded aluminum
- Foot: die cast aluminum
- Column: extruded aluminum with 3/16 inch thick structural plate


Note: Dividends Horizon conference tables are only available in Knoll Core paint, laminate, and Techwood finishes. Legacy finishes are not available. All paint finishes have the Dividends Horizon textured paint finish; this includes 613 Silver, which is a smooth paint on all other Dividends Horizon products.

Note: Grain patterns on woodgrain laminate and veneer tops will not match at the seam in the middle of conference tables.

Rectangular Conference Table



Racetrack Conference Table



Boat Shape Conference Table




Conference Tables


Rectangular Table Top

36", 42" and 48" deep


description	w*	w	d	t	h	pattern no.	Laminate Top P1 Paint	Laminate Top P2 Paint	Laminate Top P3 Paint	Techgrain Top P1 Paint	Techgrain Top P2 Paint	Techgrain Top P3 Paint
36" Deep Rectangular Conference Table	102"	101 ^{13/16"}	35 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY10236N	\$2,714.	\$2,777.	\$2,843.	\$3,100.	\$3,231.	\$3,490.
	108"	107 ^{13/16"}	35 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY10836N	2,777.	2,843.	2,908.	3,165.	3,480.	3,623.



42" Deep Rectangular Conference Table	102"	101 ^{13/16"}	41 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY10242N	2,777.	2,843.	2,908.	3,165.	3,294.	3,554.
	108"	107 ^{13/16"}	41 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY10842N	2,843.	2,908.	2,972.	3,197.	3,554.	3,729.
	120"	119 ^{13/16"}	41 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY12042N	3,041.	3,102.	3,167.	3,320.	3,654.	3,802.
	132"	131 ^{13/16"}	41 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY13242N	3,167.	3,233.	3,298.	3,862.	4,248.	4,421.
	144"	143 ^{13/16"}	41 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY14442N	3,298.	3,362.	3,424.	4,400.	4,844.	5,034.



48" Deep Rectangular Conference Table	102"	101 ^{13/16"}	47 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY10248N	2,843.	2,908.	2,972.	3,231.	3,422.	3,682.
	108"	107 ^{13/16"}	47 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY10848N	2,908.	2,972.	3,038.	3,327.	3,649.	3,812.
	120"	119 ^{13/16"}	47 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY12048N	3,111.	3,176.	3,243.	3,418.	3,763.	3,910.
	132"	131 ^{13/16"}	47 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY13248N	3,243.	3,307.	3,370.	3,968.	4,366.	4,541.
	144"	143 ^{13/16"}	47 ^{1/2"}	1 ^{1/4"}	28 ^{1/2"}	DT1ARY14448N	3,370.	3,433.	3,501.	4,516.	4,968.	5,170.



w* = nominal width

Dimensions listed under w d t h are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Conference Tables:	Conference Table:	Conference Table:	Conference Tables
1. Pattern number	<i>Example:</i> DT1ARY10836N	• (2) Y Legs	
2. Base/Stretcher Paint Finish	DT1 Dividends Horizon Table	• (1) T leg	
3. Top Finish	A Table Assembly	• (2) Stretchers	
4. Edge Finish	R Rectangular shape	• Table Top	
	Y Y Leg Base	• Hardware Kit	
	108 Overall width in inches		
	36 Overall depth in inches		
	N No grommet		
	114 Base/ stretcher paint finish		
	114 Laminate top finish		
	114 Edgeband finish		


Conference Tables

Racetrack Table Top


36", 42" and 48" deep

Dividends Horizon


description	w*	w	d	t	h	pattern no.	Laminate Top	Laminate Top	Laminate Top	Techgrain Top	Techgrain Top	Techgrain Top
							P1 Paint	P2 Paint	P3 Paint	P1 Paint	P2 Paint	P3 Paint
36" Deep Racetrack Conference Table	102"	101 ¹³ / ₁₆ "	35 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1ATY10236N	\$2,714.	\$2,777.	\$2,843.	\$4,007.	\$4,393.	\$4,523.
	108"	107 ¹³ / ₁₆ "	35 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1ATY10836N	2,777.	2,843.	2,908.	4,063.	4,471.	4,648.



42" Deep Racetrack Conference Table	102"	101 ¹³ / ₁₆ "	41 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1ATY10242N	2,777.	2,843.	2,908.	4,038.	4,456.	4,650.
	108"	107 ¹³ / ₁₆ "	41 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1ATY10842N	2,843.	2,908.	2,972.	4,134.	4,523.	4,715.
	120"	119 ¹³ / ₁₆ "	41 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1ATY12042N	3,041.	3,102.	3,167.	4,220.	4,642.	4,827.
	132"	131 ¹³ / ₁₆ "	41 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1ATY13242N	3,167.	3,233.	3,298.	4,846.	5,327.	5,543.
	144"	143 ¹³ / ₁₆ "	41 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1ATY14442N	3,298.	3,362.	3,424.	5,468.	6,014.	6,257.



48" Deep Racetrack Conference Table	102"	101 ¹³ / ₁₆ "	47 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1ATY10248N	2,843.	2,908.	2,972.	4,134.	4,489.	4,684.
	108"	107 ¹³ / ₁₆ "	47 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1ATY10848N	2,908.	2,972.	3,038.	4,265.	4,587.	4,781.
	120"	119 ¹³ / ₁₆ "	47 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1ATY12048N	3,111.	3,176.	3,243.	4,314.	4,745.	4,936.
	132"	131 ¹³ / ₁₆ "	47 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1ATY13248N	3,243.	3,307.	3,370.	4,949.	5,444.	5,665.
	144"	143 ¹³ / ₁₆ "	47 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1ATY14448N	3,370.	3,433.	3,501.	5,587.	6,143.	6,389.



w* = nominal width

Dimensions listed under w d t h are actual to the nearest ¹/₁₆"


Ordering Information	Order Code	Included with:	Options
Conference Tables:	Conference Table:	Conference Table:	Conference Tables
1. Pattern number	<i>Example:</i> DT1ARY10836N		
2. Base/Stretcher Paint Finish	DT1 Dividends Horizon Table	• (2) Y Legs	
3. Top Finish	A Table Assembly	• (1) T leg	
4. Edge Finish	R Rectangular shape	• (2) Stretchers	
	Y Y Leg Base	• Table Top	
	108 Overall width in inches	• Hardware Kit	
	36 Overall depth in inches		
	N No grommet		
	114 Base/ stretcher paint finish		
	114 Laminate top finish		
	114 Edgeband finish		

Conference Tables


Boat Shape Table Top

42" and 48" deep

description	w*	w	d	t	h	pattern no.	Laminate Top P1 Paint	Laminate Top P2 Paint	Laminate Top P3 Paint	Techgrain Top P1 Paint	Techgrain Top P2 Paint	Techgrain Top P3 Paint
42" Deep Boat Shape Conference Table	102"	101 ¹³ / ₁₆ "	41 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1ABY10242N	\$2,777.	\$2,843.	\$2,908.	\$4,038.	\$4,456.	\$4,650.
	108"	107 ¹³ / ₁₆ "	41 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1ABY10842N	2,843.	2,908.	2,972.	4,134.	4,523.	4,715.
	120"	119 ¹³ / ₁₆ "	41 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1ABY12042N	3,041.	3,102.	3,167.	4,220.	4,642.	4,827.
	132"	131 ¹³ / ₁₆ "	41 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1ABY13242N	3,167.	3,233.	3,298.	4,846.	5,327.	5,543.
	144"	143 ¹³ / ₁₆ "	41 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1ABY14442N	3,298.	3,362.	3,424.	5,468.	6,014.	6,257.




48" Deep Boat Shape Conference Table	102"	101 ¹³ / ₁₆ "	47 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1ABY10248N	2,843.	2,908.	2,972.	4,134.	4,489.	4,684.
	108"	107 ¹³ / ₁₆ "	47 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1ABY10848N	2,908.	2,972.	3,038.	4,265.	4,587.	4,781.
	120"	119 ¹³ / ₁₆ "	47 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1ABY12048N	3,111.	3,176.	3,243.	4,314.	4,745.	4,936.
	132"	131 ¹³ / ₁₆ "	47 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1ABY13248N	3,243.	3,307.	3,370.	4,949.	5,444.	5,665.
	144"	143 ¹³ / ₁₆ "	47 ¹ / ₂ "	1 ¹ / ₄ "	28 ¹ / ₂ "	DT1ABY14448N	3,370.	3,433.	3,501.	5,587.	6,143.	6,389.





w* = nominal width

Dimensions listed under w d t h are actual to the nearest ¹/₁₆"

Ordering Information	Order Code	Included with:	Options
Conference Tables:	Conference Table:	Conference Table:	Conference Tables
1. Pattern number	<i>Example:</i> DT1ARY10836N	• (2) Y Legs	
2. Base/Stretcher Paint Finish	DT1 Dividends Horizon Table	• (1) T leg	
3. Top Finish	A Table Assembly	• (2) Stretchers	
4. Edge Finish	R Rectangular shape	• Table Top	
	Y Y Leg Base	• Hardware Kit	
	108 Overall width in inches		
	36 Overall depth in inches		
	N No grommet		
	114 Base/ stretcher paint finish		
	114 Laminate top finish		
	114 Edgeband finish		


description	surface	type	w	d	h	pattern no.	P1	P2	P3
	Laminate		29 3/4"	29 3/4"	29"	ET1RT30	\$940.	\$989.	\$1,034.
	Laminate		35 3/4"	35 3/4"	29"	ET1RT36	1,010.	1,058.	1,112.
	Laminate		41 3/4"	41 3/4"	29"	ET1RT42	1,343.	1,415.	1,478.
	Laminate	4 columns - 4 legs	59 3/4"	59 3/4"	29"	ET1RT60	2,973.	3,128.	3,276.
	Laminate	5 legs	47 3/4"	47 3/4"	29"	ET1RT48	1,676.	1,758.	1,839.
	Laminate	with casters	35 3/4"	35 3/4"	29"	ET1RT36C	1,327.	1,396.	1,460.

	Laminate		24"	24"	16"	ET1ST2416	680.	713.	747.
	Laminate		29 3/4"	29 3/4"	29"	ET1ST30	899.	944.	989.
	Laminate		35 3/4"	35 3/4"	29"	ET1ST36	958.	1,007.	1,052.
	Laminate		41 3/4"	41 3/4"	29"	ET1ST42	1,279.	1,341.	1,406.
	Laminate	4 columns - 4 legs	59 1/2"	59 1/2"	29"	ET1ST60	2,831.	2,972.	3,114.
	Laminate	6 legs	47 3/4"	47 3/4"	29"	ET1ST48	1,593.	1,670.	1,749.
	Laminate	with caster	22 1/4"	22 1/4"	26 3/8"	ET1ST22C	1,089.	1,141.	1,194.

	Laminate		47 3/4"	29 3/4"	29"	ET1RCT3048	1,568.	1,646.	1,725.
	Laminate		58 1/2"	35 1/2"	29"	ET1RCT3660	2,259.	2,369.	2,486.
	Laminate		59 3/4"	29 3/4"	29"	ET1RCT3060	1,913.	2,010.	2,107.
	Laminate		71 3/4"	29 3/4"	29"	ET1RCT3072	2,259.	2,369.	2,486.
	Laminate		71 3/4"	35 3/4"	29"	ET1RCT3672	2,675.	2,808.	2,944.
	Laminate		83 3/4"	41 3/4"	29"	ET1RCT4284	3,581.	3,758.	3,937.
	Laminate	4 columns	95 3/4"	47 3/4"	29"	ET1RCT4896	4,617.	4,848.	5,077.
	Laminate	Accepts Equity drawers	69 1/4"	34"	29"	ET1RCT3469	3,399.	3,568.	3,736.
	Laminate	Accepts Equity drawers	79 1/4"	34"	29"	ET1RCT3479	3,399.	3,568.	3,736.

Order Code	Specification Information	Application Notes
Example: ET1RCT3060, 117, 117, 117	Specify surface, trim and hardware trim color.	Stretchers are used between two or more hubs. Two column tables have one stretcher; four column tables use four stretchers; and six column tables use seven.
ET1RCT Rectangular table	If a polished chrome base is desired, add a "P" suffix and add \$11 to the P1 list price.	ET10T60144 top ships in two sections. Hidden fasteners join sections.
30 Depth	Tables are only available in EW1 profile.	Note: Add 10% to the list price of any table when specifying a legacy laminate.
60 Width		
117 Soft Grey laminate		
117 Soft Grey edge		
117 Soft Grey trim		

description	surface	type	w	d	h	pattern no.	P1	P2	P3
oval table	Laminate		71 3/4"	35 3/4"	29"	ET1OT3672	\$3,535.	\$3,711.	\$3,890.
	Laminate	4 columns	95 3/4"	47"	29"	ET1OT4896	5,798.	6,092.	6,381.
	Laminate	6 columns	119 3/4"	47"	29"	ET1OT48120	7,092.	7,445.	7,801.
	Laminate	6 columns	119 3/4"	53 3/4"	29"	ET1OT54120	7,905.	8,300.	8,696.
	Laminate	6 columns	143 3/4"	59 3/4"	29"	ET1OT60144	10,324.	10,838.	11,355.



Order Code	Specification Information		Application Notes
Example: ET1RCT3060, 117, 117, 117	Specify surface, trim and hardware trim color.		Stretchers are used between two or more hubs. Two column tables have one stretcher; four column tables use four stretchers; and six column tables use seven. ET1OT60144 top ships in two sections. Hidden fasteners join sections. Note: Add 10% to the list price of
ET1RCT	Rectangular table	If a polished chrome base is desired, add a “P” suffix and add \$11 to the P1 list price.	
30	Depth		
60	Width	Tables are only available in EW1 profile.	
117	Soft Grey laminate		
117	Soft Grey edge		
117	Soft Grey trim		

Preconfigured Desks

Series 2 Single and Double Pedestal Specifications

Series 2 Single and Double Pedestal Desks

Series 2 freestanding single and double pedestal desks can be specified "Preconfigured" or by component for "Build-to-Spec" applications.

These applications include when a different pedestal drawer configuration is required, or when back panels are not needed.

"Preconfigured" single pedestal desks consist of a worksurface, Series 2 box/box/file pedestal, "L" shaped end panel and full height back panel.

"Preconfigured" double pedestal desks consist of a worksurface, two pedestals (file/file and box/ box/file) and full height back panel.

Available Sizes

- Height: 28½"
- Depths: 24", 30" and 36"
(double pedestal desk only)
- Widths: 60", 66" and 72"
- Worksurface thickness: 1¼"

"Build-to-Spec" Desks

For "Build-to-Spec" desks specify by component. Refer to individual component category for information.

Construction

All freestanding desks match the aesthetics and dimensions of Dividends Horizon panel components.

Drawers overlay the cabinet front and feature softly-radiused integral pulls, drawer fronts and drawer trim. Series 2 desks include full-height modesty panels.

Worksurface support is provided by pedestals and end units which are non-handed and shipped knocked down. This allows pedestals and end units to be positioned at either end of worksurfaces.

Optional Edge Grommets

Edge grommets are optional for all desks except overhang desks and can be specified factory-installed, centered along the rear edge of worksurfaces. Grommets can also be ordered as a kit (pattern number D1WSG) for field installation in any position along the rear edge of the worksurface. When grommets are specified, a reveal of ½" is provided between the rear of the worksurface and the back panel for repositioning cables anywhere along the back panel.

Locks


Desk pedestals can be ordered with or without locks. When specified without locks, a lock plug is included. An optional lock retrofit kit is available for field-installation of locks at a later date if required. Locks are keyed randomly unless otherwise specified. Other keying options include keyed alike or keyed with lock cores K001-K250.

All locks are factory-installed and have a black finish.


Desk Accessory

All Series 2 pedestal accessories including the hanging file bar must be specified separately.


Series 2 Single Pedestal Desk




Series 2 Double Pedestal Desk



Series 2 Desk Components



Optional Edge Grommet



Series 2 Freestanding Desk Configurations




	24D	30D
60W		
66W		
72W		

Preconfigured Desks

Series 2 Single and Double Pedestal

24", 30" and 36" Deep

Dividends Horizon

description	w*	w	d	h	pattern no.	P1	P2	P3
 Single Pedestal Desk with Locks	60"	59 ^{13/16"}	23 ^{1/2"}	28 ^{1/2"}	DD2S L6024N	\$1,908.	\$2,063.	\$2,134.
	60"	59 ^{13/16"}	29 ^{1/2"}	28 ^{1/2"}	DD2S L6030N	2,092.	2,251.	2,331.
	66"	65 ^{13/16"}	23 ^{1/2"}	28 ^{1/2"}	DD2S L6624N	1,954.	2,107.	2,184.
	66"	65 ^{13/16"}	29 ^{1/2"}	28 ^{1/2"}	DD2S L6630N	2,160.	2,323.	2,402.
	72"	71 ^{13/16"}	23 ^{1/2"}	28 ^{1/2"}	DD2S L7224N	1,988.	2,142.	2,219.
	72"	71 ^{13/16"}	29 ^{1/2"}	28 ^{1/2"}	DD2S L7230N	2,197.	2,360.	2,440.
 Double Pedestal Desk with Locks	60"	59 ^{13/16"}	23 ^{1/2"}	28 ^{1/2"}	DD2D L6024N	2,196.	2,376.	2,465.
	60"	59 ^{13/16"}	29 ^{1/2"}	28 ^{1/2"}	DD2D L6030N	2,369.	2,556.	2,648.
	66"	65 ^{13/16"}	23 ^{1/2"}	28 ^{1/2"}	DD2D L6624N	2,244.	2,424.	2,516.
	66"	65 ^{13/16"}	29 ^{1/2"}	28 ^{1/2"}	DD2D L6630N	2,440.	2,630.	2,723.
	72"	71 ^{13/16"}	23 ^{1/2"}	28 ^{1/2"}	DD2D L7224N	2,275.	2,458.	2,550.
	72"	71 ^{13/16"}	29 ^{1/2"}	28 ^{1/2"}	DD2D L7230N	2,477.	2,664.	2,761.
 Double Pedestal Desk with Locks and 6" Front Overhang	60"	59 ^{13/16"}	35 ^{1/2"}	28 ^{1/2"}	DD2O L6036N	2,513.	2,697.	2,793.
	66"	65 ^{13/16"}	35 ^{1/2"}	28 ^{1/2"}	DD2O L6636N	2,593.	2,784.	2,875.
	72"	71 ^{13/16"}	35 ^{1/2"}	28 ^{1/2"}	DD2O L7236N	2,680.	2,870.	2,961.

w* = nominal width

Dimensions listed under w d h are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Single Pedestal Desk 1. Pattern Number 2. Laminate Finish 3. Edge Band Finish 4. Paint Finish	Single Pedestal Desk <i>Example:</i> DD2S L7230N, 117, 117, 117 DD2S Pattern Number L7230N 117 Soft Grey laminate 117 Soft Grey edge finish 117 Soft Grey paint finish	Single Pedestal Desk Double Pedestal Desk Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.	Single Pedestal Desk - To specify desk with center located edge grommet, replace the suffix letter "N" with a "G". Add \$19 (Grommets not available for overhang desks) - To specify pedestals without locks, replace the fifth character "L" with an "N". Deduct \$20.
Double Pedestal Desk 1. Pattern Number 2. Laminate Finish 3. Edge Band Finish 4. Paint Finish	Double Pedestal Desk <i>Example:</i> DD2D L7230N, 117, 117, 117 DD2D Pattern Number L7230N 117 Soft Grey laminate 117 Soft Grey edge finish 117 Soft Grey paint finish		Double Pedestal Desk - To specify desk with center located edge grommet, replace the suffix letter "N" with a "G". Add \$19 (Grommets not available for overhang desks) - To specify pedestals without locks, replace the fifth character "L" with an "N". Deduct \$40.

Preconfigured Desks

Single and Double Pedestals

Specifications

Dividends Horizon

Single and Double Pedestal Desks

Dividends freestanding single and double pedestal desks can be specified "Preconfigured" or by component for "Build-to-Spec" applications. These applications include when a different pedestal drawer configuration is required, or when back panels are not needed. "Preconfigured" single pedestal desks consist of a worksurface, box/box/file pedestal, "L" shaped end panel and half-height back panel.

"Preconfigured" double pedestal desks consist of a worksurface, two pedestals (file/file and box/ box/file) and half-height back panel.

Available Sizes

- Height: 28½"
- Depths: 24", 30" and 36"
(Double pedestal desk only)
- Widths: 60", 66" and 72"
- Worksurface thickness: 1¼"

"Build-to-Spec" Desks

For "Build-to-Spec" desks specify by component. Refer to individual component category for information.

Construction

All freestanding desks match the aesthetics and dimensions of Dividends panel components.

Drawers overlay the cabinet front and feature softly-radiused pulls, drawer fronts and drawer trim.

Half-height back panels extend 11" from the bottom of the worksurface, are inset ¾" from the pedestal backs and match the softly-radiused aesthetics of other Dividends components.

Worksurface support is provided by pedestals and end units which are non-handed and shipped knocked down. This allows pedestals and end units to be positioned at either end of worksurfaces.


Locks

Desk pedestals can be ordered with or without locks. When specified without locks, a lock plug is included. An optional lock retrofit kit is available for field-installation of locks at a later date if required. Locks are keyed randomly unless otherwise specified. Other keying options include keyed alike or keyed with lock cores K001-K250 All locks are factory-installed and have a black finish.


Accessory

Hanging file bars for front-to-back or side-to-side filing are included with pedestals.


Single Pedestal Desk




Double Pedestal Desk



Desk Components



Optional Edge Grommet



Freestanding Desk Configurations


	24D	30D
60W		
66W		
72W		


Preconfigured Desks


Single and Double Pedestals

24", 30" and 36" Deep

Dividends Horizon

description	w*	w	d	h	pattern no.	P1	P2	P3
Single Pedestal Desk with Locks 	60"	59 ¹³ / ₁₆ "	23 ¹ / ₂ "	28 ¹ / ₂ "	DD1S L6024N	\$1,908.	\$2,063.	\$2,134.
	60"	59 ¹³ / ₁₆ "	29 ¹ / ₂ "	28 ¹ / ₂ "	DD1S L6030N	2,092.	2,251.	2,331.
	66"	65 ¹³ / ₁₆ "	23 ¹ / ₂ "	28 ¹ / ₂ "	DD1S L6624N	1,954.	2,107.	2,184.
	66"	65 ¹³ / ₁₆ "	29 ¹ / ₂ "	28 ¹ / ₂ "	DD1S L6630N	2,160.	2,323.	2,402.
	72"	71 ¹³ / ₁₆ "	23 ¹ / ₂ "	28 ¹ / ₂ "	DD1S L7224N	1,988.	2,142.	2,219.
	72"	71 ¹³ / ₁₆ "	29 ¹ / ₂ "	28 ¹ / ₂ "	DD1S L7230N	2,197.	2,360.	2,440.

Double Pedestal Desk with Locks 	60"	59 ¹³ / ₁₆ "	23 ¹ / ₂ "	28 ¹ / ₂ "	DD1D L6024N	2,196.	2,376.	2,465.
	60"	59 ¹³ / ₁₆ "	29 ¹ / ₂ "	28 ¹ / ₂ "	DD1D L6030N	2,369.	2,556.	2,648.
	66"	65 ¹³ / ₁₆ "	23 ¹ / ₂ "	28 ¹ / ₂ "	DD1D L6624N	2,244.	2,424.	2,516.
	66"	65 ¹³ / ₁₆ "	29 ¹ / ₂ "	28 ¹ / ₂ "	DD1D L6630N	2,440.	2,630.	2,723.
	72"	71 ¹³ / ₁₆ "	23 ¹ / ₂ "	28 ¹ / ₂ "	DD1D L7224N	2,275.	2,458.	2,550.
	72"	71 ¹³ / ₁₆ "	29 ¹ / ₂ "	28 ¹ / ₂ "	DD1D L7230N	2,477.	2,664.	2,761.

Double Pedestal Desk with Locks and 6" Front Overhang 	60"	59 ¹³ / ₁₆ "	35 ¹ / ₂ "	28 ¹ / ₂ "	DD1O L6036N	2,513.	2,697.	2,793.
	66"	65 ¹³ / ₁₆ "	35 ¹ / ₂ "	28 ¹ / ₂ "	DD1O L6636N	2,593.	2,784.	2,875.
	72"	71 ¹³ / ₁₆ "	35 ¹ / ₂ "	28 ¹ / ₂ "	DD1O L7236N	2,680.	2,870.	2,961.

w* = nominal width

Dimensions listed under w d h are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Single Pedestal Desk 1. Pattern Number 2. Laminate Finish 3. Edge Band Finish 4. Paint Finish	Single Pedestal Desk <i>Example:</i> DD1S L7230N, 117, 117, 117 DD1S L7230N Pattern Number 117 Soft Grey laminate 117 Soft Grey edge finish 117 Soft Grey paint finish	Single Pedestal Desk Double Pedestal Desk Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.	Single Pedestal Desk • To specify desk with center located edge grommet, replace the suffix letter "N" with a "G". Add \$19 (Grommets not available for overhang desks) • To specify pedestals without locks, replace the fifth character "L" with an "N". Deduct \$20.
Double Pedestal Desk 1. Pattern Number 2. Laminate Finish 3. Edge Band Finish 4. Paint Finish	Double Pedestal Desk <i>Example:</i> DD1D L7230N, 117, 117, 117 DD1D L7230N Pattern Number 117 Soft Grey laminate 117 Soft Grey edge finish 117 Soft Grey paint finish		Double Pedestal Desk • To specify desk with center located edge grommet, replace the suffix letter "N" with a "G". Add \$19 (Grommets not available for overhang desks) • To specify pedestals without locks, replace the fifth character "L" with an "N". Deduct \$40.

Preconfigured Desks

Series 2 Freestanding Corner Unit

Specifications

Dividends Horizon

Series 2 Freestanding Corner Units (Assembly)

Dividends Horizon Series 2 freestanding corner units are available "Preconfigured" and can also be specified by component for "Build-to-Spec" applications.

"Preconfigured" freestanding corners consist of a worksurface, three "L" shaped end units and two full height back panels.

Available Sizes

- Height: 28½"
- Widths: 36", 42" and 48"
- Returns: 24" depth

Construction

Corner Unit:

- Worksurface: 1¼" thick, 45 lb. density particle board core with laminate surface and 2mm vinyl edge banding
- Back panels: 20-gauge steel
- Series 2 Freestanding Corner Units include full height back panels

Rear Corner End Unit

- Outer skin: 21-gauge steel
- Inner frame: 20-gauge steel
- Leveling glide: ⅜" 16-gauge steel with 1½" of height adjustment
- Attachment bracket: 11-gauge steel

Side Corner End Unit

- Outer skin: 21-gauge
- Inner frame: 20-gauge
- Leveling glide: ⅜" 16-gauge steel with 1½" of height adjustment
- Attachment bracket: 11-gauge steel


Freestanding Corner End Units (Components)

Freestanding corner end units have mounting brackets that allow attachment to corner worksurfaces. A 6" wide rear corner end unit is used in the rear corner to support the worksurface top. A 12" wide non-handed side corner end unit is attached to both sides of a corner worksurface for support.


Optional Edge Grommets

Edge grommets are optional and can be specified factory-installed on center on both edges along the rear edge of the worksurface. Grommets can also be ordered as a kit (pattern number D1WSG) for field installation in any position along the rear edge of the worksurface.


Series 2 Freestanding Corner Unit Components



Edge Grommet Locations



Series 2 Freestanding Corner Unit Attached to Return to Form a "L" Shaped Workstation



Preconfigured Desks

Series 2 Freestanding Corner Unit

24" Deep

Dividends Horizon

description	type	w *	w	d	h	pattern no.	P1	P2	P3
 Freestanding Corner Unit (Assembly)		36"	35 1/2"	23 1/2"	28 1/2"	DD2VD 3624 N	\$1,613.	\$1,775.	\$1,856.
		42"	41 1/2"	23 1/2"	28 1/2"	DD2VD 4224 N	1,667.	1,835.	1,919.
		48"	47 1/2"	23 1/2"	28 1/2"	DD2VD 4824 N	1,749.	1,925.	2,012.
 Freestanding Curved Corner Unit (Assembly)		36"	35 1/2"	23 1/2"	28 1/2"	DD2VL 3624 N	1,648.	1,812.	1,897.
		42"	41 1/2"	23 1/2"	28 1/2"	DD2VL 4224 N	1,748.	1,924.	2,011.
		48"	47 1/2"	23 1/2"	28 1/2"	DD2VL 4824 N	1,826.	2,011.	2,098.
 Freestanding Corner End Unit (Component)			6 9/16"	6 9/16"	26 7/8"	DD1R CU6	339.	373.	390.

w* = nominal width
Dimensions listed under w d h are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Freestanding Corner 1. Pattern Number 2. Laminate Finish 3. Edge Band Finish 4. Paint Finish	Freestanding Corner <i>Example:</i> DD2VD 3624 N, 117, 117 DD2VD Pattern Number 3624 N No Grommets 117 Soft Grey laminate 117 Soft Grey edge finish 117 Soft Grey paint finish Freestanding Corner End Unit <i>Example:</i> DD1RCU6, 117 DD1RCU6 Pattern Number 117 Soft Grey paint finish	Freestanding Corner • Corner supports (3) • Back panels (2) • Corner worksurface • Connecting hardware Freestanding Corner End Unit Note: Series 2 freestanding corner units have full height modesty panels. Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.	Freestanding Corner • To specify two center-mounted edge grommets, replace the suffix letter "N" with a "G". Add \$29. Freestanding Corner End Unit

Preconfigured Desks

Freestanding Corner Unit

Specifications

Dividends Horizon

Freestanding Corner Units (Assembly)

Dividends freestanding corner units are available "Preconfigured" and can also be specified by component for "Build-to-Spec" applications. "Preconfigured" freestanding corners consist of a worksurface, three "L" shaped end units and two 11" high back panels.

Available Sizes

- Height: 28½"
- Widths: 36", 42" and 48"
- Returns: 24" depth

Construction

Corner Unit Specifications

- Worksurface: 1¼" thick, 45 lb. density particle board core with laminate surface and 2mm vinyl edge banding
- Back panels: 20-gauge steel

Rear Corner End Unit

- Outer skin: 21-gauge steel
- Inner frame: 20-gauge steel
- Leveling glide: ⅜" 16-gauge steel with 1½" of height adjustment
- Attachment bracket: 11-gauge steel

Side Corner End Unit

- Outer skin: 21-gauge steel
- Inner frame: 20-gauge steel
- Leveling glide: ⅜" 16-gauge steel
- Attachment bracket: 11-gauge steel


Freestanding Corner End Units (Components)

Freestanding corner end units have mounting brackets that allow attachment to corner worksurfaces. A 6" wide rear corner end unit is used in the rear corner to support the worksurface top. A 12" wide non-handed side corner end unit is attached to both sides of a corner worksurface for support.


Optional Edge Grommets

Edge grommets are optional and can be specified factory-installed on center on both edges along the rear edge of the worksurface. Grommets can also be ordered as a kit (pattern number D1WSG) for field installation in any position along the rear edge of the worksurface.


Freestanding Corner Unit Components



Edge Grommet Locations



Freestanding Corner Unit attached to returns to form an "L" shaped workstation



Preconfigured Desks

Freestanding Corner Unit

24" Deep

Dividends Horizon

description	type	w *	w	d	h	pattern no.	P1	P2	P3
 Freestanding Corner Unit (Assembly)		36"	35 1/2"	23 1/2"	28 1/2"	DD1VD 3624 N	\$1,613.	\$1,775.	\$1,856.
		42"	41 1/2"	23 1/2"	28 1/2"	DD1VD 4224 N	1,667.	1,835.	1,919.
		48"	47 1/2"	23 1/2"	28 1/2"	DD1VD 4824 N	1,749.	1,925.	2,012.

	Freestanding Curved Corner Unit (Assembly)		36"	35 1/2"	23 1/2"	28 1/2"	DD1VL 3624 N	1,648.	1,812.	1,897.
			42"	41 1/2"	23 1/2"	28 1/2"	DD1VL 4224 N	1,748.	1,924.	2,011.
			48"	47 1/2"	23 1/2"	28 1/2"	DD1VL 4824 N	1,826.	2,011.	2,098.

Freestanding Corner End Unit (Component)			6 9/16"	6 9/16"	26 7/8"	DD1R CU6	339.	373.	390.
--	--	--	---------	---------	---------	-----------------	------	------	------

Freestanding Corner Unit (Component)			6 9/16"	12 9/16"	26 7/8"	DD1S CU12	400.	440.	458.
--------------------------------------	--	--	---------	----------	---------	------------------	------	------	------

	Back Panels for Freestanding Corner Unit (Component)	full height	36"	20 15/16"	26 5/8"	DD1 FBPV36	240.	263.	274.
		full height	42"	26 15/16"	26 5/8"	DD1 FBPV42	242.	266.	279.
		full height	48"	32 15/16"	26 5/8"	DD1 FBPV48	245.	271.	283.
		half height	36"	20 15/16"	11"	DD1 BPV36	202.	219.	230.
		half height	42"	26 15/16"	11"	DD1 BPV42	212.	233.	242.
		half height	48"	32 15/16"	11"	DD1 BPV48	220.	244.	258.

w* = nominal width

Dimensions listed under w d h are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Freestanding Corner 1. Pattern Number 2. Laminate Finish 3. Edge Band Finish 4. Paint Finish	Freestanding Corner <i>Example:</i> DD1VD 3624 N, 117, 117 DD1VD Pattern Number 3624 N No Grommets 117 Soft Grey laminate 117 Soft Grey edge finish 117 Soft Grey paint finish Freestanding Corner End Unit <i>Example:</i> DD1RCU6, 117 DD1RCU6 Pattern Number 117 Soft Grey paint finish	Freestanding Corner • Corner supports (3) • Back panels (2) • Corner worksurface • Connecting hardware Freestanding Corner End Unit Note: Series 2 freestanding corner units have full height modesty panels. Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.	Freestanding Corner • To specify two center-mounted edge grommets, replace the suffix letter "N" with a "G". Add \$29. Freestanding Corner End Unit Freestanding Corner Back Panel

Preconfigured Desks

Series 2 Returns and Bridge Units

Specifications

Dividends Horizon

Series 2 End Panel and Pedestal Returns

Dividends Horizon freestanding returns can be specified "Preconfigured" or can be ordered by component for "Build-to-Spec" applications. These applications include when a different pedestal drawer combination is required or when back panels are not needed.

"Preconfigured" pedestal returns consist of a worksurface, file/file pedestal, and full-height back panel. "Preconfigured" end panel returns consist of a worksurface, "L" shaped end panel and full height back panel.

Available Sizes

- Height: 28 1/2"
- Widths: 36", 42" and 48"
- Depths: 18" and 24"

Attachment

Returns attach to adjacent desks or freestanding corner units with flat brackets, which are included.

Construction

All freestanding returns match the aesthetics of the Dividends Horizon panel system.

Drawers overlay the cabinet front and feature softly-radiused integral pulls, drawer fronts and drawer trim. Series 2 Desk components include full-height back panels.

Worksurface support is provided by pedestals and end units which are non-handed and shipped knocked down. This allows pedestals and end units to be positioned at either end of worksurfaces.

"Build-to-Spec" Returns and Bridges

For "Build-to-Spec" returns and bridges, specify by component. Refer to the individual component categories for information.

Accessory

Hanging file bars for front-to-back or side-to-side filing are included with pedestals.


Bridge Units

Bridge units are used to form freestanding "U" shaped workstations.


Bridge units consist of a worksurface and back panel and connect to adjacent freestanding components with flat brackets which are included.

Available Sizes


- Height: 28 1/2"
- Widths: 30", 36", 42" and 48"
- Depths: 18" and 24"



Pedestal Return



End Panel Return



Bridge Unit


Series 2 Return Sizes Available

	18"D	24"D
30"W		
42"W		
48"W		

Series 2 Bridge Unit Sizes Available

30"W		
42"W		
42"W		
48"W		

Series 2 Desk Configurations



Preconfigured Desks

Series 2 Returns and Bridge Units

18" and 24" Deep

Dividends Horizon

description	w *	w	d	h	pattern no.	P1	P2	P3
 End Panel Return	36"	35 ¹³ / ₁₆ "	17 ¹ / ₂ "	28 ¹ / ₂ "	DD2E 3618N	\$890.	\$957.	\$984.
	36"	35 ¹³ / ₁₆ "	23 ¹ / ₂ "	28 ¹ / ₂ "	DD2E 3624N	974.	1,041.	1,077.
	42"	41 ¹³ / ₁₆ "	17 ¹ / ₂ "	28 ¹ / ₂ "	DD2E 4218N	936.	1,003.	1,036.
	42"	41 ¹³ / ₁₆ "	23 ¹ / ₂ "	28 ¹ / ₂ "	DD2E 4224N	1,019.	1,089.	1,126.
 Pedestal Return	36"	35 ¹³ / ₁₆ "	17 ¹ / ₂ "	28 ¹ / ₂ "	DD2P (L)3618N	1,151.	1,243.	1,288.
	36"	35 ¹³ / ₁₆ "	23 ¹ / ₂ "	28 ¹ / ₂ "	DD2P (L)3624N	1,259.	1,354.	1,403.
	42"	41 ¹³ / ₁₆ "	17 ¹ / ₂ "	28 ¹ / ₂ "	DD2P (L)4218N	1,202.	1,292.	1,334.
	42"	41 ¹³ / ₁₆ "	23 ¹ / ₂ "	28 ¹ / ₂ "	DD2P (L)4224N	1,308.	1,406.	1,451.
	48"	47 ¹³ / ₁₆ "	17 ¹ / ₂ "	28 ¹ / ₂ "	DD2P (L)4818N	1,246.	1,334.	1,382.
	48"	47 ¹³ / ₁₆ "	23 ¹ / ₂ "	28 ¹ / ₂ "	DD2P (L)4824N	1,358.	1,458.	1,509.
 Bridge Unit	30"	29 ¹³ / ₁₆ "	17 ¹ / ₂ "	28 ¹ / ₂ "	DD2B 3018N	434.	454.	460.
	36"	35 ¹³ / ₁₆ "	17 ¹ / ₂ "	28 ¹ / ₂ "	DD2B 3618N	479.	501.	510.
	36"	35 ¹³ / ₁₆ "	23 ¹ / ₂ "	28 ¹ / ₂ "	DD2B 3624N	512.	534.	545.
	42"	41 ¹³ / ₁₆ "	17 ¹ / ₂ "	28 ¹ / ₂ "	DD2B 4218N	519.	542.	552.
	42"	41 ¹³ / ₁₆ "	23 ¹ / ₂ "	28 ¹ / ₂ "	DD2B 4224N	563.	584.	594.
	48"	47 ¹³ / ₁₆ "	17 ¹ / ₂ "	28 ¹ / ₂ "	DD2B 4818N	563.	584.	594.
	48"	47 ¹³ / ₁₆ "	23 ¹ / ₂ "	28 ¹ / ₂ "	DD2B 4824N	613.	636.	647.

w* = nominal width

Dimensions listed under w d h are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Pedestal Return 1. Pattern Number 2. Laminate Finish 3. Edge Band Finish 4. Paint Finish	Pedestal Return <i>Example:</i> DD2P L4824N, 117, 117, 117 DP2P Pattern Number L4824N 117 Soft Grey laminate 117 Soft Grey edge finish 117 Soft Grey paint finish End Panel Return or Bridge Unit <i>Example:</i> DD2B 4224N, 117, 117, 117 DD2B Pattern Number 4424 117 Soft Grey laminate 117 Soft Grey finish 117 Soft Grey finish	Pedestal Return • Worksurface • Pedestal • Back panel • Half height flat bracket (1) • Connecting hardware End Panel Return or Bridge Unit • Worksurface • Back panel • Half height flat brackets (2) • Connecting hardware Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.	Pedestal Return • To specify center-mounted edge grommet, replace the "N" suffix from the pattern number with "G". Add \$19 • To specify pedestal without locks, replace the 5th digit "L" from the pattern number with "N". Deduct \$20. End Panel Return or Bridge Unit • To specify center-mounted edge grommet, replace the "N" suffix from the pattern number with "G". Add \$19

Preconfigured Desks

Return and Bridge Units

Specifications

Dividends Horizon

End Panel and Pedestal Returns

Dividends freestanding returns can be specified "Preconfigured" or can be ordered by component for "Build-to-Spec" applications. These applications include when a different pedestal drawer combination is required or when back panels are not needed.

"Preconfigured" pedestal returns consist of a worksurface, file/file pedestal, and half-height back panel. "Preconfigured" end panel returns consist of a worksurface, "L" shaped end panel and half-height back panel.

Available Sizes

- Height: 28 1/2"
- Widths: 36", 42" and 48"
- Depths: 18" and 24"

Attachment

Returns attach to adjacent desks or freestanding corner units with flat brackets, which are included.

Construction

All freestanding returns match the aesthetics of the Dividends panel system.

Drawers overlay the cabinet front and feature softly-radiused pulls, drawer fronts and drawer trim.

Half-height back panels extend 11" from the bottom of the worksurface, are inset 3/4" from the pedestal backs and match the softly radiused aesthetics of other Dividends components.

Worksurface support is provided by pedestals and end units which are non-handed and shipped knocked down. This allows pedestals and end units to be positioned at either end of worksurfaces.

"Build-to-Spec" Returns and Bridges

For "Build-to-Spec" returns and bridges, specify by component. Refer to the individual component categories for information.

Accessory

Hanging file bars for front-to-back or side-to-side filing are included with pedestals.

Bridge Units


Bridge units are used to form freestanding "U" shaped workstations.

Bridge units consist of a worksurface and back panel and connect to adjacent freestanding components with flat brackets which are included.


Available Sizes

- Height: 28 1/2"
- Widths: 30", 36", 42" and 48"
- Depths: 18" and 24"

Pedestal Return



End Panel Return



Bridge Unit





Return Sizes Available

	18D	24D
30W		
30W		
42W		
42W		
48W		

Bridge Unit Sizes Available

30W		
42W		
42W		
48W		

Freestanding Configuration





Preconfigured Desks

Return and Bridge Units

18" and 24" Deep

Dividends Horizon

description	w *	w	d	h	pattern no.	P1	P2	P3
 End Panel Return	36"	35 ¹³ / ₁₆ "	17 ¹ / ₂ "	28 ¹ / ₂ "	DD1E 3618N	\$890.	\$957.	\$984.
	36"	35 ¹³ / ₁₆ "	23 ¹ / ₂ "	28 ¹ / ₂ "	DD1E 3624N	974.	1,041.	1,077.
	42"	41 ¹³ / ₁₆ "	17 ¹ / ₂ "	28 ¹ / ₂ "	DD1E 4218N	936.	1,003.	1,036.
	42"	41 ¹³ / ₁₆ "	23 ¹ / ₂ "	28 ¹ / ₂ "	DD1E 4224N	1,019.	1,089.	1,126.
 Pedestal Return	36"	35 ¹³ / ₁₆ "	17 ¹ / ₂ "	28 ¹ / ₂ "	DD1P (L)3618N	1,151.	1,243.	1,288.
	36"	35 ¹³ / ₁₆ "	23 ¹ / ₂ "	28 ¹ / ₂ "	DD1P (L)3624N	1,259.	1,354.	1,403.
	42"	41 ¹³ / ₁₆ "	17 ¹ / ₂ "	28 ¹ / ₂ "	DD1P (L)4218N	1,202.	1,292.	1,334.
	42"	41 ¹³ / ₁₆ "	23 ¹ / ₂ "	28 ¹ / ₂ "	DD1P (L)4224N	1,308.	1,406.	1,451.
	48"	47 ¹³ / ₁₆ "	17 ¹ / ₂ "	28 ¹ / ₂ "	DD1P (L)4818N	1,246.	1,334.	1,382.
	48"	47 ¹³ / ₁₆ "	23 ¹ / ₂ "	28 ¹ / ₂ "	DD1P (L)4824N	1,358.	1,458.	1,509.
 Bridge Unit	30"	29 ¹³ / ₁₆ "	17 ¹ / ₂ "	28 ¹ / ₂ "	DD1B 3018N	434.	454.	460.
	36"	35 ¹³ / ₁₆ "	17 ¹ / ₂ "	28 ¹ / ₂ "	DD1B 3618N	479.	501.	510.
	36"	35 ¹³ / ₁₆ "	23 ¹ / ₂ "	28 ¹ / ₂ "	DD1B 3624N	512.	534.	545.
	42"	41 ¹³ / ₁₆ "	17 ¹ / ₂ "	28 ¹ / ₂ "	DD1B 4218N	519.	542.	552.
	42"	41 ¹³ / ₁₆ "	23 ¹ / ₂ "	28 ¹ / ₂ "	DD1B 4224N	563.	584.	594.
	48"	47 ¹³ / ₁₆ "	17 ¹ / ₂ "	28 ¹ / ₂ "	DD1B 4818N	563.	584.	594.
	48"	47 ¹³ / ₁₆ "	23 ¹ / ₂ "	28 ¹ / ₂ "	DD1B 4824N	613.	636.	647.

w* = nominal width

Dimensions listed under w d h are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Pedestal Return 1. Pattern Number 2. Laminate Finish 3. Edge Band Finish 4. Paint Finish	Pedestal Return <i>Example:</i> DD1P L4824N, 117, 117, 117 DP1P Pattern Number L4824N 117 Soft Grey laminate 117 Soft Grey edge finish 117 Soft Grey paint finish End Panel Return or Bridge Unit <i>Example:</i> DD1B 4224N, 117, 117, 117 DD1B Pattern Number 4424 117 Soft Grey laminate 117 Soft Grey finish 117 Soft Grey finish	Pedestal Return • Worksurface • Pedestal • Back panel • Half height flat bracket (1) • Connecting hardware End Panel Return or Bridge Unit • Worksurface • Back panel • Half height flat brackets (2) • Connecting hardware Note: An upcharge applies when specifying Legacy laminates. See Legacy finish page.	Pedestal Return • To specify center-mounted edge grommet, replace the "N" suffix from the pattern number with "G". Add \$19 • To specify pedestal without locks, replace the 5th digit "L" from the pattern number with "N". Deduct \$20. End Panel Return or Bridge Unit • To specify center-mounted edge grommet, replace the "N" suffix from the pattern number with "G". Add \$19

Desk Components

End Units

Planning Guidelines

Desk End Units

Dividends desk end units are an "L" shaped, non-handed design that can be used on either end of a worksurface in freestanding and panel applications. Desk end units have the same footprint (outside dimension) as pedestals and can be interchanged with pedestals.

End units are used in "Preconfigured" single pedestal desks and end panel returns.

They can also be specified by component for "Build-to-Spec" applications.

These include when an end panel is required on one end and a desk integration unit is required on the other, or when an end unit is required on both ends of the worksurface.

Available Sizes

Depths: 18", 24" and 30"

Width: 15"

Height: 26⁷/₈"

Desk End Unit Attachment

Desk end units have mounting brackets that allow attachment to worksurfaces with supplied screws. Dividends worksurfaces are pre-drilled for end unit attachment.

Construction

End unit specifications:

- Outer skin: 21-gauge steel
- Inner frame: 20-gauge steel
- Leveling glides: ³/₈" 16-gauge steel with 1¹/₂" of height adjustment
- Attachment bracket: 11-gauge steel

Desk Integration End Units

If a back panel (modesty) is required in a systems application, a desk integration end unit can be used in place of an end unit.

Panel-to-worksurface brackets are included and make the connection between the worksurface and Dividends Horizon panels. Desk integration end units are 15" wide.

Note: The desk integration end unit is a non-structural support. Panel-to-work surface brackets provide the actual support for the worksurface.

Note: Panel width must match the depth of the connecting worksurface.

Construction

Desk integration end unit specifications:

- Outer skin: 20-gauge steel
- Panel-to-worksurface brackets: 14-gauge steel

Intermediate End Units

Intermediate end units are freestanding "T" shaped end units used to support two desks in an in-line configuration.

Units attach to 18", 24" and 30" deep worksurfaces in place of desk end units. Mounting brackets and a front worksurface alignment plate are included with intermediate end units.

Available Size


- Depth: 14"
- Width: 30"
- Height: 26⁷/₈"

Construction


Intermediate end unit specifications:

- Outer skin: 20-gauge steel
- Inner frame: 20-gauge steel
- Mounting brackets: 11-gauge steel


Desk End Unit




Intermediate End Unit




Desk Integration End Unit (Non-structural)




Desk End Unit Available Sizes



End Unit Configurations



Desk Integration End Unit



Intermediate End Unit

*End Units**Desk End, Desk Integration and Intermediate*

description	d *	d	w	h	pattern no.	P1	P2	P3
	18"	16 ³ / ₈ "	14 ⁷ / ₈ "	26 ⁷ / ₈ "	DD1 EU18	\$425.	\$469.	\$493.
	24"	22 ³ / ₈ "	14 ⁷ / ₈ "	26 ⁷ / ₈ "	DD1 EU24	470.	515.	541.
	30"	28 ³ / ₈ "	14 ⁷ / ₈ "	26 ⁷ / ₈ "	DD1 EU30	511.	561.	589.
Desk Integration End Unit (Non-structural)	1 ¹ / ₂ "	1 ¹ / ₂ "	14 ⁷ / ₈ "	26 ⁷ / ₈ "	DD1 DIEU	237.	259.	269.
								
Intermediate End Unit	14"	12"	31 ⁹ / ₁₆ "	26 ⁷ / ₈ "	DD1 IE30	425.	469.	493.
								

d* = nominal depth

Dimensions listed under d w h are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Desk End Unit	Desk End Unit	Desk End Unit	Desk End Unit
1. Pattern Number	<i>Example:</i> DD1 EU18, 117		
2. Paint Finish	DD1 EU18 Pattern Number	Desk Integration End Unit	Desk Integration End Unit
	117 Soft Grey Paint Finish	• Panel-to-Worksurface Brackets (2)	Intermediate End Unit
Desk Integration End Unit	Desk Integration End Unit	Intermediate End Unit	
1. Pattern Number	<i>Example:</i> DD1 DIEU, 117		
2. Paint Finish	DD1 DIEU Pattern Number		
	117 Soft Grey Paint Finish		
Intermediate End Unit	Intermediate End Unit		
1. Pattern Number	<i>Example:</i> DD1 IE30, 117		
2. Paint Finish	DD1 IE30 Pattern Number		
	117 Soft Grey Paint Finish		

Desk Components

Half Height Back Panels

Planning Guidelines

Dividends Horizon

Half Height Back Panels

Dividends back panels extend between pedestals, end units or desk integration end units in freestanding desks. They also extend between end units in returns and along the rear surface of bridge units. Back panels are softly-radiused to match the aesthetics of the Dividends Horizon system and extend 11" down from the worksurface to provide a half-height modesty.

Back panels are used in "Preconfigured" desks or can be specified separately by component for "Build-to-Spec" applications.

Available Sizes

- Widths: 19⁵/₈" to 48¹/₄" see compatibility chart (below)
- Height: 11"

Back Panel Attachment

Back panels attach to the undersides of worksurfaces with mounting brackets and do not require attachment to adjacent pedestals or end units. Dividends Horizon worksurfaces are pre-drilled for back panel attachment.

Construction

Back panel specifications:

- Outer skin: 22-gauge steel
- Mounting Brace: 16-gauge


Back Panel Compatibility

The chart below shows which back panels are specified for various configurations.

Optional Grommets/Wire Management

When installed, back panels provide a 1/2" reveal between the back panel and worksurface for wire management. Optional edge grommets are required to provide access.

Desk Configurations



Back Panel Compatibility

Product	Work-surface Width	Back Panel Width	Back Panel Pattern No.	No. of Required Peds/End Units
Desks	54	23 ⁷ / ₈ "	DD1 BPD54	2
	60	29 ⁷ / ₈ "	DD1 BPD60	2
	66	35 ⁷ / ₈ "	DD1 BPD66	2
	72	41 ⁷ / ₈ "	DD1 BPD72	2
Returns	36	21 ⁵ / ₈ "	DD1 BPR36	1
	42	27 ⁵ / ₈ "	DD1 BPR42	1
	48	33 ⁵ / ₈ "	DD1 BPR48	1
	60	45 ⁵ / ₈ "	DD1 BPR60	1
Bridge Units	30	31 ³ / ₈ "	DD1 BPB30	0
	36	37 ³ / ₈ "	DD1 BPB36	0
	42	43 ³ / ₈ "	DD1 BPB42	0
	48	49 ³ / ₈ "	DD1 BPB48	0
"U" Credenza w/2 peds	72	26 ¹⁵ / ₁₆ "	DD1 BPU72	3
Freestanding	36	20 ¹⁵ / ₁₆ "	DD1 BPV36	3
Corner Unit (needs two back panels)	42	26 ¹⁵ / ₁₆ "	DD1 BPV42	3
	48	32 ¹⁵ / ₁₆ "	DD1 BPV48	3

Note: Specify "desk" back panels from category (above) for use with desk integration end units and intermediate end units.

Desk Components

Half Height Back Panels

For Desks, Returns, Bridges and 2 Pedestal Configuration

Dividends Horizon

description	top width	w *	h	pattern no.	P1	P2	P3
Half Height Back panels for Desks 	54"	29 7/8"	11"	DD1 BPD54	\$238.	\$260.	\$271.
	60"	29 7/8"	11"	DD1 BPD60	249.	274.	286.
	66"	35 7/8"	11"	DD1 BPD66	263.	289.	300.
	72"	41 7/8"	11"	DD1 BPD72	276.	302.	319.
Half Height Back panels for Returns 	36"	21 5/8"	11"	DD1 BPR36	212.	233.	242.
	42"	27 5/8"	11"	DD1 BPR42	219.	242.	256.
	48"	33 5/8"	11"	DD1 BPR48	237.	259.	269.
	60"	45 5/8"	11"	DD1 BPR60	263.	289.	300.
Half Height Back panels for Bridges 	30"	31 3/8"	11"	DD1 BPB30	187.	206.	216.
	36"	37 3/8"	11"	DD1 BPB36	202.	219.	230.
	42"	43 3/8"	11"	DD1 BPB42	212.	233.	242.
	48"	49 3/8"	11"	DD1 BPB48	222.	245.	259.
Half Height Back panels for 2 Pedestal "U" Credenza 	72"	26 15/16"	11"	DD1 BPU72	212.	233.	242.

Freestanding Desks

Dimensions listed under w h are actual to the nearest 1/16"

Ordering Information	Order Code	Included with:	Options
Back Panels for Bridges	Back Panels for Bridges	Back Panels for Bridges	Back Panels for Bridges
1. Pattern Number	<i>Example:</i> DD1 BPB36 , 117	• Attachment Hardware	
2. Paint Finish	DD1 Pattern Number		
	BPB36		
	117 Soft Grey Paint Finish		

Desk Components

Full Back Panels

Planning Guidelines

Dividends Horizon

Full Back Panels

Dividends full back panels extend between pedestals, end units or desk integration end units in freestanding desks. They also extend between end units in returns and along the rear surface of bridge units.

Full back panels are specified separately by component for "Build-to-Spec" applications.

Available Sizes

- Widths: 19⁵/₈" to 48¹/₄" see compatibility chart (above)
- Height: 26⁵/₈"

Full Back Panel Attachment

Back panels attach to the undersides of pedestals or end units with mounting brackets.

Construction

Back panel specifications:

- Outer skin: 20-gauge steel
- Mounting Brace: 16-gauge


Back Panel Compatibility

The chart below shows which back panels are specified for various configurations.

Optional Grommets/Wire Management

When installed, back panels provide a 1/2" reveal between the back panel and worksurface for wire management. Optional edge grommets are required to provide access.

Desk Configurations



Back Panel Compatibility

Product	Work-surface Width	Back Panel Width	Back Panel Pattern No.	No. of Required Peds/End Units
Desks	54	23 7/8"	DD1 FFBPD54	2
	60	29 7/8"	DD1 FFBPD60	2
	66	35 7/8"	DD1 FBPD66	2
	72	41 7/8"	DD1 FBPD72	2
Returns	36	21 5/8"	DD1 FBPR36	1
	42	27 5/8"	DD1 FBPR42	1
	48	33 5/8"	DD1 FBPR48	1
	60	45 5/8"	DD1 FBPR60	1
Bridge Units	30	31 5/8"	DD1 FBPB30	0
	36	37 5/8"	DD1 FBPB36	0
	42	43 5/8"	DD1 FBPB42	0
	48	49 5/8"	DD1 FBPB48	0
"U" Credenza w/2 peds	72	26 15/16"	DD1 FBPU72	3
Freestanding	36	20 15/16"	DD1 FBPV36	3
Corner Unit (needs	42	26 15/16"	DD1 FBPV42	3
two back panels)	48	32 15/16"	DD1 FBPV48	3

Note: Specify "desk" back panels from category (above) for use with desk integration end units and intermediate end units.

*Full Back Panels**For Desks, Returns, Bridges and 2 Pedestal Configuration*

description	top width	w *	h	pattern no.	P1	P2	P3
Full Back panels for Desks 	54"	23 ⁷ / ₈ "	26 ⁵ / ₈ "	DD1 FBPD54	\$282.	\$310.	\$324.
	60"	29 ⁷ / ₈ "	26 ⁵ / ₈ "	DD1 FBPD60	287.	316.	330.
	66"	35 ⁷ / ₈ "	26 ⁵ / ₈ "	DD1 FBPD66	295.	325.	336.
	72"	41 ⁷ / ₈ "	26 ⁵ / ₈ "	DD1 FBPD72	304.	334.	350.
Full Back panels for Returns 	36"	21 ⁵ / ₈ "	26 ⁵ / ₈ "	DD1 FBPR36	265.	290.	304.
	42"	27 ⁵ / ₈ "	26 ⁵ / ₈ "	DD1 FBPR42	271.	297.	311.
	48"	33 ⁵ / ₈ "	26 ⁵ / ₈ "	DD1 FBPR48	283.	311.	325.
	60"	45 ⁵ / ₈ "	26 ⁵ / ₈ "	DD1 FBPR60	310.	337.	359.
Full Back panels for Bridges 	30"	31 ³ / ₈ "	26 ⁵ / ₈ "	DD1 FBPB30	248.	272.	284.
	36"	37 ³ / ₈ "	26 ⁵ / ₈ "	DD1 FBPB36	261.	287.	298.
	42"	43 ³ / ₈ "	26 ⁵ / ₈ "	DD1 FBPB42	283.	311.	325.
	48"	49 ³ / ₈ "	26 ⁵ / ₈ "	DD1 FBPB48	290.	320.	334.
Full Back panels for 2 Pedestal "U" Credenza 	72"	26 ¹⁵ / ₁₆ "	26 ⁵ / ₈ "	DD1 FBPU72	271.	297.	311.

Dimensions listed under w h are actual to the nearest ¹/₁₆"

Ordering Information	Order Code	Included with:	Options
Back Panels for Bridges 1. Pattern Number 2. Paint Finish	Back Panels for Bridges <i>Example:</i> DD1 FBPB36 , 117 DD1 Pattern Number FBPB36 117 Soft Grey Paint Finish	Back Panels for Bridges • Attachment Hardware	Back Panels for Bridges

Pencil Tray

Five section tray rides on drawer sides of box drawers. Plastic injection molded construction. 13¹/₄ wide, 5⁷/₁₆ deep and ⁷/₈ high. Black or clear finish available.

Hanging File Bar

Allows for side-to-side hanging folders. 20-gauge steel construction. Set of two. Black finish.

Note: A hanging file bar is included with each file drawer when ordering desks or DS1 style pedestals.

Drawer Dividers

Two styles available: box drawer and file drawer sizes. 18-gauge steel construction. Black finish.

Stationery Inserts

Set of four trays for use in box drawers. 18-gauge steel construction. Can accommodate letter-and legal-sized stationery. Black finish.

Pencil Drawer

For use with freestanding desks or panel-mounted worksurfaces with depths of 24 or more. 24 wide, 17⁵/₈ deep and 2 high. Black finish.

Attachment: Mounts on underside of worksurface with included mounting hardware

Pedestal Lock Retrofit Kit

Allows existing nonlocking pedestals to be field-retrofitted with locks. Includes lock housing, lock core (keyed randomly unless specified keyed alike) and lock rod assembly (must be specified box/box/file or file/file).

Flat Brackets

Allow same-height worksurfaces to be joined in perpendicular configurations. All flat brackets are 3³/₄ wide. Black finish.

Three sizes available to support the following worksurface depths:

- 18 deep worksurfaces
- 24 deep worksurfaces
- 30 deep worksurfaces
- Construction: 14-gauge steel
- Attachment: Mounts on underside of worksurfaces in pre-drilled locations with included mounting hardware

Worksurface Cable Management Clips

Self-adhesive, injection-molded clips adhere to any flat, nonporous surface to route cables along and beneath worksurfaces. ³/₄ x 1¹/₂ internal dimension.

Worksurface Cable Management Basket


Steel wire basket attaches to the underside of worksurfaces to provide management of excess cords and cables. Once installed, the cable basket slides forward to a position abutting the panel face to allow the passage of cords and cables. Black finish.

Worksurface Edge Grommet


Available factory-installed when ordering worksurfaces or as a kit for field installation. Can be installed in any location along the rear edge of worksurfaces. Includes a cutting template, grommet and cover. Dark grey finish.

Worksurface Reinforcement


Worksurface reinforcements are required for worksurface spans greater than 48 inches. This includes freestanding desk worksurfaces over 48 inches using desk end units. Worksurface reinforcements have a black paint finish.




Pencil Tray




Pencil Drawer




Stationery Inserts




Worksurface Cable Management Clip




Hanging File Bar




Drawer Divider,
File Drawer




Flat Bracket




Worksurface Cable Management Basket



Drawer Divider,
Box Drawer




Worksurface Reinforcement
Panel Hung Application



Worksurface
Edge Grommet


Drawer Organizers, Cable Management and Grommet Kits

description	type	w	d	h	pattern no.	list
 Pencil Tray	Black finish	13 1/4"	5 7/8"	7/8"	DS2PPTN	\$48.
	Clear finish	13 1/4"	5 7/8"	7/8"	DS2PPTC	55.
 Hanging File Bar		12 3/16"	2 5/16"	1/2"	DS1PFS	42.
 Drawer Divider, Box		12 3/8"	3"	3 1/8"	DS1PBD	42.
 Drawer Divider, File		10	3 5/8"	6 3/8"	DS1PFD	42.
 Stationary Inserts, box (4 trays)		13	15 1/16"	8 7/8"	DS1PST	220.
 Pencil Drawer		24"	17 5/8"	2"	DS1PCD	293.
 Workspace Cable Management Clip	Package of 10	3/4"	1/2"		D1WC	49.
 Workspace Cable Management Basket	19 1/2" wide	16 1/2"	3 1/2"	1 1/2"	D1WB20	51.
	25 1/2" wide	25 1/2"	3 1/2"	1 1/2"	D1WB26	53.
	31 1/2" wide	31 1/2"	3 1/2"	1 1/2"	D1WB32	67.
	35" wide	35"	3 1/2"	1 1/2"	D1WB36	74.
	41" wide	41"	3 1/2"	1 1/2"	D1WB42	79.
 Workspace Grommet Kit (Dark Grey)		2 3/16"	2 5/16"	1 3/8"	D1WSG	30.

Ordering Information	Order Code	Included with:	Options
Pencil Tray 1. Pattern Number	Pencil Tray Example: DS1 PPT DS1 PPT Pattern Number	Pencil Tray	

Desk Accessories

Flat Brackets and Worksurface Reinforcements

description	w	d	pattern no.	black
Flat Bracket (single pack) 	3 3/4"	14 5/8"	DB1F24SP	\$33.
	3 3/4"	20 15/16"	DB1F30SP	38.
	3 3/4"	8 5/16"	DB1F18SP	29.
Flat Bracket (package of 10) 	3 3/4"	14 5/16"	DB1F24TP	263.
	3 3/4"	20 5/16"	DB1F30TP	302.
	3 3/4"	8 3/16"	DB1F18TP	158.
Worksurface Reinforcement 	54"	4"	DB1WR54	77.
	60"	4"	DB1WR60	78.
	66"	4"	DB1WR66	81.
	72"	4"	DB1WR72	84.

Ordering Information	Order Code	Included with:	Options
Flat Bracket 1. Pattern Number	Flat Bracket <i>Example:</i> DB1PWSP DB1PWSP Pattern Number	Flat Bracket	Flat Bracket

Wall Mounting Suggestions

The following information is provided only as a guide, and represents minimum recommendations only. Knoll does not accept responsibility for the attachment of any Knoll product to a Customer's site wall. Wall specification/construction is the responsibility of the Customer and its structural engineer/architect. Failure to properly attach Knoll products to adequate wall structures can lead to property damage and/or personal injury.

You should consult your own structural engineers and/or architects and must not rely on the information provided herein.

It is the responsibility of the Customer and its structural engineers/architects to verify that the permanent structural walls (studs, blocks, solid masonry, etc.) on which the Knoll products are intended to be mounted are designed appropriately to support the product weight, PLUS 3 lbs. per linear inch for each useable shelf length

NOTE: A cabinet's top is considered a "useable shelf" and MUST be included in the calculation of the total load for an overhead cabinet.

It is the responsibility of the Customer and its structural engineer/architects to specify the fasteners and method for attaching the Knoll supplied wall mounting cleat, bracket, frame, etc. to the supporting wall and to confirm that the installers have adhered to these specifications. For all local building standards and codes, and additional requirements (including, but not limited to, seismic conditions) the Customer should always consult local code agencies.

		EXISTING CONSTRUCTION				
	NEW CONSTRUCTION	Cinder Block or Poured Concrete Masonry Wall	Wood Stud Wall, the studs being FULL HEIGHT to the roof/floor above	Wood Stud Wall, the studs being only Ceiling Height	Steel Stud Wall, the studs being FULL HEIGHT to the roof/floor above	Steel Stud Wall, the studs being only Ceiling Height
Stud Specification	Wood studs, grade #2 or better, 3 1/2" minimum width, OR Metal studs, minimum 25 gage thickness, 3 5/8" minimum width	The wall must be a minimum of 6" thick, and must be full height to the roof/ floor structure above	Wood studs must be Grade #2, or better, 3 1/2" minimum width	Wood studs must be Grade #2, or better, 3 1/2" minimum width	Metal studs must be minimum 25 gage thickness, 3 5/8" minimum width	Metal studs must be minimum 25 gage thickness, 3 5/8" minimum width
Stud Centers	Metal and wood studs must be spaced at 16" c/c maximum	N/A	Wood studs must be spaced at 16" c/c maximum	Wood studs must be spaced at 16" c/c maximum	Metal studs must be spaced at 16" c/c maximum	Metal studs must be spaced at 16" c/c maximum
Stud Height	Metal and wood studs must extend upwards, and be securely attached to the roof/ floor structure above			Wood studs must be braced above the ceiling, and be securely attached to the roof/floor structure above Affix #2 grade 'cap' across the top of the studs, then place diagonal studs from the top cap up to underside of the roof/ floor structure above		Metal studs must be braced above the ceiling, and be securely attached to the roof/floor structure above Affix metal bracing 'cap' across the top of the studs, then place diagonal studs from the top cap up to underside of the roof / floor structure above
Mounting the Knoll Supplied Cleat, Bracket, Frame, etc*	Insert a 2" X 6" wood block, #2 grade or better, [or a Danback™ flexible wood backing system] horizontally between each of the studs to accommodate the full width of the cabinet, and beyond to the next stud. Fasten the wood block to each stud using three screws at the ends of each block. (Fasten the Danback™ as directed by the manufacturer) Fasten the Knoll supplied wall mounting cleat, bracket, frame, etc directly to each wood block every 6" For wall mounting structures that have a rectangular frame-like configuration: fasten the top horizontal element of the frame to the wood blocking every 6", and fasten the lower horizontal element to each wall stud, using one fastener per stud.	Fasten the Knoll supplied cabinet wall mounting cleat, bracket, frame, etc. directly to the masonry wall every 6" For wall mounting structures that have a rectangular frame-like configuration: fasten the top horizontal element of the frame to the wall every 6", and fasten the lower horizontal element to the wall every 16" Replace the drywall and repair as desired. Fasten the Knoll supplied wall mounting cleat, rail, frame, etc directly to the wood block every 6" For wall mounting structures that have a rectangular frame-like configuration: fasten the top horizontal element of the frame to the wood blocking every 6", and fasten the lower horizontal element to each wall stud, using one fastener per stud.	In the desired location of the cabinet mounting rail, remove an 8" high section of drywall the width of the cabinet, and beyond to the next stud. Insert a 2" X 6" wood block, #2 grade or better, horizontally between each of the exposed studs. Fasten the wood block to each stud using three screws at the ends of each block. Replace the drywall and repair as desired. Fasten the Knoll supplied wall mounting cleat, rail, frame, etc directly to the wood block every 6" For wall mounting structures that have a rectangular frame-like configuration: fasten the top horizontal element of the frame to the wood blocking every 6", and fasten the lower horizontal element to each wall stud, using one fastener per stud.	In the desired location of the cabinet mounting rail, remove an 8" high section of drywall the width of the cabinet, and beyond to the next stud. Insert a 2" X 6" wood block, #2 grade or better, horizontally between each of the exposed studs. Fasten the wood block to each stud using three screws at the ends of each block. Replace the drywall and repair as desired. Fasten the Knoll supplied wall mounting cleat, rail, frame, etc directly to the wood block every 6" For wall mounting structures that have a rectangular frame-like configuration: fasten the top horizontal element of the frame to the wood blocking every 6", and fasten the lower horizontal element to each wall stud, using one fastener per stud.	In the desired location of the cabinet mounting rail, remove an 8" high section of drywall the width of the cabinet, and beyond to the next stud. Insert a 2" X 6" wood block, #2 grade or better, [or a Danback™ flexible wood backing system] horizontally between each of the exposed studs. Fasten the wood block to each stud using three screws at the ends of each block. Replace the drywall and repair as desired. Fasten the Knoll supplied wall mounting cleat, rail, frame, etc directly to the wood block every 6" For wall mounting structures that have a rectangular frame-like configuration: fasten the top horizontal element of the frame to the wood blocking every 6", and fasten the lower horizontal element to each wall stud, using one fastener per stud.	In the desired location of the cabinet mounting rail, remove an 8" high section of drywall the width of the cabinet, and beyond to the next stud. Insert a 2" X 6" wood block, #2 grade or better, [or a Danback™ flexible wood backing system] horizontally between each of the exposed studs. Fasten the wood block to each stud using three screws at the ends of each block. Replace the drywall and repair as desired. Fasten the Knoll supplied wall mounting cleat, rail, frame, etc directly to the wood block every 6" For wall mounting structures that have a rectangular frame-like configuration: fasten the top horizontal element of the frame to the wood blocking every 6", and fasten the lower horizontal element to each wall stud, using one fastener per stud.
*Graham Wall Hung Shelf	The Graham Wall Hung Shelf Bracket (and others like it) requires full support behind the full height of the bracket This should be accomplished by insertion of additional 2"X 6" wood blocking between the studs as defined above	Fasten the Knoll supplied wall mounting brackets directly to the masonry wall, using the holes provided in each bracket	The Graham Wall Hung Shelf Bracket (and others like it) requires full support behind the full height of the bracket This should be accomplished by insertion of additional 2"X 6" wood blocking between the studs as defined above	The Graham Wall Hung Shelf Bracket (and others like it) requires full support behind the full height of the bracket This should be accomplished by insertion of additional 2"X 6" wood blocking between the studs as defined above	The Graham Wall Hung Shelf Bracket (and others like it) requires full support behind the full height of the bracket This should be accomplished by insertion of additional 2"X 6" wood blocking between the studs as defined above	The Graham Wall Hung Shelf Bracket (and others like it) requires full support behind the full height of the bracket This should be accomplished by insertion of additional 2"X 6" wood blocking between the studs as defined above
Fasten the Knoll supplied wall cleat with...	#10 x 2 1/2" Grabber Woodys Screws or equiv. @ 6" c/c, screwed directly into the wood blocking	3/16" x 3 1/2" Tapcon Masonry Screws or equiv. @ 6" c/c with 1-1/4" embedment, screwed directly into the masonry wall	#10 x 2 1/2" Grabber Woodys Screws or equiv. @ 6" c/c, screwed directly into the wood blocking	#10 x 2 1/2" Grabber Woodys Screws or equiv. @ 6" c/c, screwed directly into the wood blocking	#10 x 2 1/2" Grabber Woodys Screws or equiv. @ 6" c/c, screwed directly into the wood blocking	#10 x 2 1/2" Grabber Woodys Screws or equiv. @ 6" c/c, screwed directly into the wood blocking

Alpha-Numeric Index

<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>
AWM1 S36	391	D1D 5430N	349	D1L 6042SSN	344	D1R 4215	355
AWM1 S42	391	D1D 5436N	349	D1L 6048DSN	347	D1R 4218N	319
AWM1 S48	391	D1D 6024N	349	D1L 6048SDN	347	D1R 4224N	320
AWM1 S60	391	D1D 6030N	349	D1L 6048SSN	344	D1R 4230N	325
AWM1 S66	391	D1D 6036N	349	D1L 6642SSN	344	D1R 4518N	319
AWM1 S72	391	D1D 6624N	349	D1L 6648DSN	347	D1R 4524N	320
AWM1 S78	391	D1D 6630N	349	D1L 6648SDN	347	D1R 4530N	325
AWM1 S84	391	D1D 6636N	349	D1L 6648SSN	344	D1R 4815	355
D19 5430N	350	D1D 7224N	349	D1L 7236SSN	344	D1R 4818N	319
D19 6030N	351	D1D 7230N	349	D1L 7242SSN	344	D1R 4824N	320
D19 6630N	351	D1D 7236N	349	D1L 7248DSN	347	D1R 4830N	325
D19 7230N	351	D1D 7824N	349	D1L 7248SDN	347	D1R 5118N	319
D19 7830N	351	D1D 7830N	349	D1L 7248SSN	344	D1R 5124N	320
D19 7836N	351	D1D 7836N	349	D1L 7836SSN	344	D1R 5130N	325
D19 8430N	351	D1D 8424N	349	D1L 7842SSN	344	D1R 5415	355
D19 9030N	351	D1D 8430N	349	D1L 7848SSN	344	D1R 5418N	319
D1BD6048SL	349	D1D 8436N	349	D1L 8442SSN	344	D1R 5424N	320
D1BD6048SR	350	D1D 9624N	349	D1L 8448SSN	344	D1R 5430N	325
D1BD6648DL	349	D1D 9630N	349	D1L 9648SSN	344	D1R 5718N	319
D1BD6648DR	350	D1D 9636N	349	D1P 5430N	350	D1R 5724N	320
D1BD6648SL	349	D1H4818	353	D1P 6030N	350	D1R 5730N	325
D1BD6648SR	350	D1H5118P	353	D1P 6630N	350	D1R 6015	355
D1BD7242DL	350	D1H6024	353	D1P 7230N	350	D1R 6018N	319
D1BD7242DR	350	D1H6324P	353	D1P 7830N	350	D1R 6024N	320
D1BD7242SL	349	D1L 3636SSN	343	D1P 7836N	350	D1R 6030N	325
D1BD7242SR	350	D1L 3648SSN	343	D1P 8430N	350	D1R 6036N	326
D1BD7248DL	350	D1L 3654SSN	343	D1P 9030N	350	D1R 6318N	319
D1BD7248DR	350	D1L 3660SSN	343	D1R 10224N	320	D1R 6324N	320
D1BD7248SL	349	D1L 3672SSN	343	D1R 10230N	325	D1R 6330N	325
D1BD7248SR	350	D1L 3678SSN	343	D1R 10824N	320	D1R 6615	355
D1BD7848DL	350	D1L 4242SSN	343	D1R 10830N	325	D1R 6618N	319
D1BD7848DR	350	D1L 4248SSN	343	D1R 11430N	325	D1R 6624N	320
D1BD7848SL	349	D1L 4254SSN	343	D1R 12024N	320	D1R 6630N	325
D1BD7848SR	350	D1L 4260SSN	343	D1R 12030N	325	D1R 6636N	326
D1BD8448DL	350	D1L 4266SSN	343	D1R 1515C	355	D1R 6918N	319
D1BD8448DR	350	D1L 4272SSN	343	D1R 1515S	355	D1R 6924N	320
D1BD8448SL	349	D1L 4278SSN	343	D1R 1818N	319	D1R 6930N	325
D1BD8448SR	350	D1L 4284SSN	343	D1R 1824N	320	D1R 7215	355
D1C 3618N	341	D1L 4836SSN	343	D1R 2118N	319	D1R 7218N	319
D1C 3624N	341	D1L 4842SSN	343	D1R 2124N	320	D1R 7224N	320
D1C 422430N	341	D1L 4848DDN	347	D1R 2415	355	D1R 7230N	325
D1C 4224N	341	D1L 4848DSN	347	D1R 2418N	319	D1R 7236N	326
D1C 423024N	341	D1L 4848SDN	347	D1R 2424N	320	D1R 7518N	319
D1C 482430N	341	D1L 4848SSN	343	D1R 2430N	325	D1R 7524N	320
D1C 4824N	341	D1L 4854SSN	343	D1R 2718N	319	D1R 7530N	325
D1C 483024N	341	D1L 4860DSN	347	D1R 2724N	320	D1R 7815	355
D1C 4830N	341	D1L 4860SDN	347	D1R 2730N	325	D1R 7818N	319
D1CRL24	353	D1L 4860SSN	343	D1R 3015	355	D1R 7824N	320
D1CRN24	353	D1L 4866DSN	347	D1R 3018N	319	D1R 7830N	325
D1CRR24	353	D1L 4866SDN	347	D1R 3024N	320	D1R 7836N	326
D1CRR30	353	D1L 4866SSN	343	D1R 3030N	325	D1R 8118N	319
D1CS 4224N	341	D1L 4872DSN	347	D1R 3318N	319	D1R 8124N	320
D1CS 4824N	341	D1L 4872SDN	347	D1R 3324N	320	D1R 8130N	325
D1CS 4830N	341	D1L 4872SSN	343	D1R 3330N	325	D1R 8415	355
D1D 3024N	349	D1L 4878SSN	343	D1R 3615	355	D1R 8418N	319
D1D 3030N	349	D1L 4884SSN	343	D1R 3618N	319	D1R 8424N	320
D1D 3624N	349	D1L 4896SSN	343	D1R 3624N	320	D1R 8430N	325
D1D 3630N	349	D1L 5436SSN	343	D1R 3630N	325	D1R 8436N	326
D1D 4824N	349	D1L 5442SSN	343	D1R 3918N	319	D1R 8718N	319
D1D 4830N	349	D1L 5448SSN	343	D1R 3924N	320	D1R 8724N	320
D1D 5424N	349	D1L 6036SSN	344	D1R 3930N	325	D1R 8730N	325

<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>
D1R 9015	355	D1W S781824N	330	DB1C24 (L or R)	389	DCE1CR24R	359
D1R 9018N	319	D1W S781830N	330	DB1C30 (L or R)	389	DCE1H4818	359
D1R 9024N	320	D1W S782418N	330	DB1CL 24R	399	DCE1H4818P	359
D1R 9030N	325	D1W S782430N	330	DB1CL24L	399	DCE1H6024	359
D1R 9036N	326	D1W S783018N	330	DB1CL24S	399	DCE1H6024P	359
D1R 9318N	319	D1W S783024N	330	DB1F18SP	389, 444	DCE1L3636SSN	357
D1R 9324N	320	D1W S841824N	330	DB1F18TP	389, 444	DCE1L4242DSN	357
D1R 9330N	325	D1W S841830N	330	DB1F24SP	389, 444	DCE1L4242SDN	357
D1R 9615	355	D1W S842418N	330	DB1F24TP	389, 444	DCE1L4242SSN	357
D1R 9618N	319	D1W S842430N	330	DB1F30SP	389, 444	DCE1L4260SSN	358
D1R 9624N	320	D1W S843018N	330	DB1F30TP	389, 444	DCE1L4266SSN	358
D1R 9630N	325	D1W S843024N	330	DB1LS15A	401	DCE1L4272SSN	358
D1R 9636N	326	D1W T482430N	338	DB1LS18A	401	DCE1L4278SSN	358
D1R 9918N	319	D1W T483024N	338	DB1LS24A	401	DCE1L4848DDN	357
D1R 9924N	320	D1W T602430N	338	DB1LS30A	401	DCE1L4848DSN	357
D1R 9930N	325	D1W T603024N	338	DB1LS36A	401	DCE1L4848SDN	357
D1R2419N	323	D1W T662430N	338	DB1LSP15	399	DCE1L4848SSN	357
D1R3019N	323	D1W T663024N	338	DB1LSP18	399	DCE1L4860DSN	358
D1R3619N	323	D1W T722430N	338	DB1LSP24	399	DCE1L4860SDN	358
D1R4219N	323	D1W T723024N	338	DB1LSP30	399	DCE1L4860SSN	358
D1R4819N	323	D1WB20	243, 443	DB1LSP36	399	DCE1L4866DSN	358
D1R5419N	323	D1WB26	243, 443	DB1LSS15	399	DCE1L4866SDN	358
D1R6019N	323	D1WB32	243, 443	DB1LSS18	399	DCE1L4866SSN	358
D1R6619N	323	D1WB36	243, 443	DB1LSS24	399	DCE1L4872DSN	358
D1R7219N	323	D1WB42	243, 443	DB1LSS30	399	DCE1L4872SDN	358
D1R7819N	323	D1WC	243, 443	DB1LSS36	399	DCE1L4872SSN	358
D1R8419N	323	D1WSC	277, 443	DB1PSP15	399	DCE1L4878SSN	358
D1R9019N	323	D1WT218	207	DB1PSP18	399	DCE1L4884SSN	358
D1R9619N	323	D1WT224	207	DB1PSP19	399	DCE1L6042SSN	358
D1W 362430N	329	D1WT324	207	DB1PSP24	399	DCE1L6048DSN	358
D1W 363024N	329	D1WT424	207	DB1PSP30	399	DCE1L6048SDN	358
D1W 422430N	329	D1WT518	207	DB1PSP36	399	DCE1L6048SSN	358
D1W 423024N	329	D1WT524	207	DB1PWS24	390	DCE1L6642SSN	358
D1W 482430N	329	D1WW11481824	207	DB1PWS30	390	DCE1L6648DSN	358
D1W 483024N	329	D1WW11482418	207	DB1PWS36	390	DCE1L6648SDN	358
D1W 721830N	329	D1WW12481824	207	DB1PWS42	390	DCE1L6648SSN	358
D1W 722430N	329	D1WW12482418	207	DB1PWS48	390	DCE1L7242SSN	358
D1W 722436N	329	D1WW124824L	207	DB1PWSL	389	DCE1L7248DSN	358
D1W 723018N	329	D1WW124824R	207	DB1PWSL10	390	DCE1L7248SDN	358
D1W 723024N	329	D1WW13481824	207	DB1PWSLWH	390	DCE1L7248SSN	358
D1W 723624N	329	D1WW13482418	207	DB1PWSP	389	DCE1L7842SSN	358
D1W S481824N	330	D1WW134824L	207	DB1PWSPWH	390	DCE1L7848SSN	358
D1W S481830N	330	D1WW134824R	207	DB1PWSR	389	DCE1L8448SSN	358
D1W S482418N	330	D1WW34824	207	DB1PWSR10	390	DCE1R1212G	356
D1W S482430N	330	D1WW44824	207	DB1PWSRWH	390	DCE1R2424N	356
D1W S483018N	330	D1WW54824L	207	DB1S CR	401	DCE1R2430N	356
D1W S483024N	330	D1WW54824R	207	DB1SWSL	397	DCE1R3024N	356
D1W S601824N	330	D1WW64824L	207	DB1SWSP	397	DCE1R3030N	356
D1W S601830N	330	D1WW64824R	207	DB1SWSR	397	DCE1R3624N	356
D1W S602418N	330	D1WW74824L	207	DB1TB	401	DCE1R3630N	356
D1W S602430N	330	D1WW74824R	207	DB1U18	263, 268	DCE1R4224N	356
D1W S603018N	330	D2H4824	353	DB1WR54	389, 444	DCE1R4230N	356
D1W S603024N	330	D2H4836	353	DB1WR60	389, 444	DCE1R4824N	356
D1W S661824N	330	D2H4848	353	DB1WR66	389, 444	DCE1R4830N	356
D1W S661830N	330	D2H5124P	353	DB1WR72	389, 444	DCE1R5424N	356
D1W S662418N	330	D2H5136P	353	DB2CL24L	399	DCE1R5430N	356
D1W S662430N	330	D2H5148P	353	DB2CL24LS	399	DCE1R6024N	356
D1W S663018N	330	D2P1	85	DB2CL24R	399	DCE1R6030N	356
D1W S663024N	330	DB120C (L or R)	389	DB2CL24RS	399	DCE1R6624N	356
D1W S721824N	330	DB1BD48SL	350	DBSCR	401	DCE1R6630N	356
D1W S721830N	330	DB1BD48SR	350	DBSMLH	397	DCE1R7224N	356
D1W S722418N	330	DB1C 18 (L or R) 10	389	DBSMRH	397	DCE1R7230N	356
D1W S722430N	330	DB1C 24 (L or R) 10	389	DBVDC (L or R)	390	DCE1R7824N	356
D1W S723018N	330	DB1C 30 (L or R) 10	389	DCE1CR24L	359	DCE1R7830N	356
D1W S723024N	330	DB1C18 (L or R)	389	DCE1CR24N	359	DCE1R8424N	356

<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>
DCE1R8430N	356	DD1E 4218N	435	DD2S L7230N	425	DE1E BI56	239
DCE1R9024N	356	DD1E 4224N	435	DD2VD 3624 N	429	DE1E BI56(L/R)	235
DCE1R9030N	356	DD1O L6036N	427	DD2VD 4224 N	429	DE1E CI144	235
DCE1R9624N	356	DD1O L6636N	427	DD2VD 4824 N	429	DE1E CI288	237
DCE1R9630N	356	DD1O L7236N	427	DD2VL 3624 N	429	DE1E ERE56	237
DCE1W362430N	360	DD1P (L)3618N	435	DD2VL 4224 N	429	DE1E RBI144	235
DCE1W363024N	360	DD1P (L)3624N	435	DD2VL 4824 N	429	DE1E RBI156	235
DCE1W422430N	360	DD1P (L)4218N	435	DD3 PS36	292	DE1E RBI216	235
DCE1W423024N	360	DD1P (L)4224N	435	DD3 PS42	292	DE1E RBI288	235
DCE1W482430N	360	DD1P (L)4818N	435	DD3 PS48	292	DE1E RBI56	235
DCE1W483024N	360	DD1P (L)4824N	435	DD3 PS54	292	DE1E RBI56SF	239
DCE1W722430N	360	DD1R CU6	429, 431	DD3 PS60	292	DE1(E,8,T) PCNP	214
DCE1W723024N	360	DD1S CU12	431	DD3 PS66	292	DE1(E,8,T) PCWP	214
DD1 BPB30	439	DD1S L6024N	427	DD3 PS72	292	DE1(E,8,T,2V) PC21M	214, 232
DD1 BPB36	439	DD1S L6030N	427	DE1	232, 233	DE1(E,8,T,2V) PJ15NP	214
DD1 BPB42	439	DD1S L6624N	427	DE1 FDP	224	DE1(E,8,T,2V) PJ15WP	214
DD1 BPB48	439	DD1S L6630N	427	DE12V BI156(L/R)	235	DE1(E,8,T,2V) PJ18NP	214
DD1 BPD54	439	DD1S L7224N	427	DE12V BI56(L/R)	235	DE1(E,8,T,2V) PJ18WP	214
DD1 BPD60	439	DD1S L7230N	427	DE12V ERE56	237	DE1(E,8,T,2V) PJ24NP	214
DD1 BPD66	439	DD1TEU24	401	DE1(2V) PCNPM	214	DE1(E,8,T,2V) PJ24WP	214
DD1 BPD72	439	DD1TEU30	401	DE1(2V) PCWPM	214	DE1(E,8,T,2V) PJ30NP	214
DD1 BPR36	439	DD1VD 3624 N	431	DE12V RBI156	235	DE1(E,8,T,2V) PJ30WP	214
DD1 BPR42	439	DD1VD 4224 N	431	DE12V RBI56	235	DE1(E,8,T,2V) PJ36NP	214
DD1 BPR48	439	DD1VD 4824 N	431	DE18 B1NY1	239	DE1(E,8,T,2V) PJ36WP	214
DD1 BPR60	439	DD1VL 3624 N	431	DE18 BI144(L/R)	235	DE1(E,8,T,2V) PJ42NP	214
DD1 BPU72	439	DD1VL 4224 N	431	DE18 BI156(L/R)	235	DE1(E,8,T,2V) PJ42WP	214
DD1 BPV36	431	DD1VL 4824 N	431	DE18 BI216(L/R)	235	DE1(E,8,T,2V) PJ48NP	214
DD1 BPV42	431	DD2B 3018N	433	DE18 BI288(L/R)	235	DE1(E,8,T,2V) PJ48WP	214, 222, 233
DD1 BPV48	431	DD2B 3618N	433	DE18 BI56	239	DE1(E,8,T,2V) PJ54WP	215, 222, 233
DD1 DIEU	437	DD2B 3624N	433	DE18 BI56(L/R)	235	DE1(E,8,T,2V) PJ60WP	215, 222, 233
DD1 EU18	437	DD2B 4218N	433	DE18 CI144	235	DE1(E,8,T,2V) PJ66WP	215, 222
DD1 EU24	437	DD2B 4224N	433	DE18 CI288	237	DE1(E,8,T,2V) PJ72WP	215, 222
DD1 EU30	437	DD2B 4818N	433	DE18 ERE56	237	DE1(E,8,T,2V) PJ78WP	215, 222
DD1 FBPB30	441	DD2B 4824N	433	DE18 RBI144	235	DE1(E,8,T,2V) PJ84WP	215, 222
DD1 FBPB36	441	DD2D L6024N	425	DE18 RBI156	235	DE1(E,8,T,2V) PJ96WP	215
DD1 FBPB42	441	DD2D L6030N	425	DE18 RBI216	235	DE1(E,8,T,2V) PM24	214
DD1 FBPB48	441	DD2D L6624N	425	DE18 RBI288	235	DE1(E,8,T,2V) PM30	214
DD1 FBPD54	441	DD2D L6630N	425	DE18 RBI56	235	DE1(E,8,T,2V) PM36	214
DD1 FBPD60	441	DD2D L7224N	425	DE18 RBI56SF	239	DE1(E,8,T,2V) PM42	214
DD1 FBPD66	441	DD2D L7230N	425	DE1DATSHD	243	DE1(E,8,T,2V) PM48	214
DD1 FBPD72	441	DD2E 3618N	433	DE1DATSHDF	243	DE1(E,8,T,2V) PM60	214
DD1 FBPR36	441	DD2E 3624N	433	DE1DOR4	217	DE1(E,8,T,2V) PMS24	214
DD1 FBPR42	441	DD2E 4218N	433	DE1DOR5	217	DE1(E,8,T,2V) PMS30	214
DD1 FBPR48	441	DD2E 4224N	433	DE1DOR6	217	DE1(E,8,T,2V) PMS36	214
DD1 FBPR60	441	DD2O L6036N	425	DE1DR1	217	DE1(E,8,T,2V) PMS42	214
DD1 FBPU72	441	DD2O L6636N	425	DE1DR12V	217	DE1(E,8,T,2V) PMS48	214
DD1 FBPV36	431	DD2O L7236N	425	DE1DR1C	217	DE1(E,8,T,2V) PMS60	214
DD1 FBPV42	431	DD2OD 36L	291	DE1DR2	217	DE1HPA	232
DD1 FBPV48	431	DD2OD 42L	291	DE1DR22V	217	DE1SPA	232
DD1 IE30	437	DD2OD 48L	291	DE1DR2C	217	DE1T B1NY1	239
DD1B 3018N	435	DD2OD 54L	291	DE1DR3	217	DE1T BI144(L/R)	235
DD1B 3618N	435	DD2OD 60L	291	DE1DR32V	217	DE1T BI156(L/R)	235
DD1B 3624N	435	DD2OD 66L	291	DE1DR3C	217	DE1T BI216(L/R)	235
DD1B 4218N	435	DD2OD 72L	291	DE1DR4	217	DE1T BI288(L/R)	235
DD1B 4224N	435	DD2P (L)3618N	433	DE1DR42V	217	DE1T BI56	239
DD1B 4818N	435	DD2P (L)3624N	433	DE1DR4C	217	DE1T BI56(L/R)	235
DD1B 4824N	435	DD2P (L)4218N	433	DE1DR5	217	DE1T CI144	235
DD1D L6024N	427	DD2P (L)4224N	433	DE1DR5C	217	DE1T CI288	237
DD1D L6030N	427	DD2P (L)4818N	433	DE1DR6	217	DE1T ERE56	237
DD1D L6624N	427	DD2P (L)4824N	433	DE1DR6C	217	DE1T RBI144	235
DD1D L6630N	427	DD2S L6024N	425	DE1E B1NY1	239	DE1T RBI156	235
DD1D L7224N	427	DD2S L6030N	425	DE1E BI144(L/R)	235	DE1T RBI216	235
DD1D L7230N	427	DD2S L6624N	425	DE1E BI156(L/R)	235	DE1T RBI288	235
DD1E 3618N	435	DD2S L6630N	425	DE1E BI216(L/R)	235	DE1T RBI56	235
DD1E 3624N	435	DD2S L7224N	425	DE1E BI288(L/R)	235	DE1T RBI56SF	239

<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>
DE1USB1H	218	DE6 VDR3	223	DPIAR0747W	129	DPIAR0780H	194
DE1USB1V	218	DE6 VDR3C	224	DPIAR0748E	131	DPIAR0780W	196
DE1USB2H	218	DE6 VDR4	223	DPIAR0748H	127	DPIAR0781E	198
DE1USB2V	218	DE6 VDR4C	224	DPIAR0748W	129	DPIAR0781H	194
DE1USB3H	218	DE6 VDR5	223	DPIAR0750E	198	DPIAR0781W	196
DE1USB3V	218	DE6 VDR5C	224	DPIAR0750H	194	DPIAR0783E	131
DE1USB4H	218	DE6 VDR6	223	DPIAR0750W	196	DPIAR0783H	127
DE1USB4V	218	DE6 VDR6C	224	DPIAR0751E	198	DPIAR0783W	129
DE1USB5H	218	DE6 VPM	223	DPIAR0751H	194	DPIAR0784E	131
DE1USB5V	218	DFFCUS	107	DPIAR0751W	196	DPIAR0784H	127
DE1USB6H	218	DFFELS	107	DPIAR0753E	131	DPIAR0784W	129
DE1USB6V	218	DFFERS	107	DPIAR0753H	127	DPIAR0786E	198
DE1X ERE56	237	DFFEUD	107	DPIAR0753W	129	DPIAR0786H	194
DE2	232	DFFEUS	107	DPIAR0754E	131	DPIAR0786W	196
DE2KC10	77, 217	DFFSSS	107	DPIAR0754H	127	DPIAR0787E	198
DE2V CI144	235	DL3TC	271	DPIAR0754W	129	DPIAR0787H	194
DE4CL202120(BB/W/W/WS)	227	DL4L17	271	DPIAR0756E	198	DPIAR0787W	196
DE4CL20272(BB/W/W/WS)	227	DL4L31	271	DPIAR0756H	194	DPIAR0789E	131
DE4CL202H(BB/W/W/WS)	227	DL4L44	271	DPIAR0756W	196	DPIAR0789H	127
DE4CL210120(BB/W/W/WS)	227	DL4L58	271	DPIAR0757E	198	DPIAR0789W	129
DE4CL21072(BB/W/W/WS)	227	DP 109, 110, 147, 148, 153, 154, 157		DPIAR0757H	194	DPIAR0790E	131
DE4CL210H(BB/W/W/WS)	227	DP1	83	DPIAR0757W	196	DPIAR0790H	127
DE4CL311120(BB/W/W/WS)	227	DP1 CG	163	DPIAR0759E	131	DPIAR0790W	129
DE4CL31172(BB/W/W/WS)	227	DP1 CHB	163	DPIAR0759H	127	DPIAR0792E	198
DE4CL311H(BB/W/W/WS)	227	DP1 CHP	163	DPIAR0759W	129	DPIAR0792H	194
DE4CLA12120(BB/W/W/WS)	227	DP1 TKC	243	DPIAR0760E	131	DPIAR0792W	196
DE4CL41272(BB/W/W/WS)	227	DP1 VWG	243	DPIAR0760H	127	DPIAR0793E	198
DE4CL412H(BB/W/W/WS)	227	DPIAR0714E	131	DPIAR0760W	129	DPIAR0793H	194
DE4OC202120 (BB/W/W/WS)	228	DPIAR0714H	127	DPIAR0762E	198	DPIAR0793W	196
DE4OC20272 (BB/W/W/WS)	228	DPIAR0714W	129	DPIAR0762H	194	DPIAR0795E	131
DE4OC202H (BB/W/W/WS)	228	DPIAR0715E	131	DPIAR0762W	196	DPIAR0795H	127
DE4OC210120 (BB/W/W/WS)	228	DPIAR0715H	127	DPIAR0763E	198	DPIAR0795W	129
DE4OC21072 (BB/W/W/WS)	228	DPIAR0715W	129	DPIAR0763H	194	DPIAR0796E	131
DE4OC210H (BB/W/W/WS)	228	DPIAR0717E	131	DPIAR0763W	196	DPIAR0796H	127
DE4OC311120 (BB/W/W/WS)	228	DPIAR0717H	127	DPIAR0765E	131	DPIAR0796W	129
DE4OC31172 (BB/W/W/WS)	228	DPIAR0717W	129	DPIAR0765H	127	DPIAR0798E	198
DE4OC311H (BB/W/W/WS)	228	DPIAR0718E	131	DPIAR0765W	129	DPIAR0798H	194
DE4OC412120 (BB/W/W/WS)	228	DPIAR0718H	127	DPIAR0766E	131	DPIAR0798W	196
DE4OC41272 (BB/W/W/WS)	228	DPIAR0718W	129	DPIAR0766H	127	DPIAR0799E	198
DE4OC412H (BB/W/W/WS)	228	DPIAR0723E	131	DPIAR0766W	129	DPIAR0799H	194
DE4TU202120(BB/W/W/WS)	226	DPIAR0723H	127	DPIAR0768E	198	DPIAR0799W	196
DE4TU20272(BB/W/W/WS)	226	DPIAR0723W	129	DPIAR0768H	194	DPIAR1414E	132
DE4TU202H(BB/W/W/WS)	226	DPIAR0724E	131	DPIAR0768W	196	DPIAR1414H	128
DE4TU210120(BB/W/W/WS)	226	DPIAR0724H	127	DPIAR0769E	198	DPIAR1414W	130
DE4TU21072(BB/W/W/WS)	226	DPIAR0724W	129	DPIAR0769H	194	DPIAR1415E	132
DE4TU210H(BB/W/W/WS)	226	DPIAR0729E	131	DPIAR0769W	196	DPIAR1415H	128
DE4TU311120(BB/W/W/WS)	226	DPIAR0729H	127	DPIAR0771E	131	DPIAR1415W	130
DE4TU31172(BB/W/W/WS)	226	DPIAR0729W	129	DPIAR0771H	127	DPIAR1417E	132
DE4TU311H(BB/W/W/WS)	226	DPIAR0730E	131	DPIAR0771W	129	DPIAR1417H	128
DE4TU412120(BB/W/W/WS)	226	DPIAR0730H	127	DPIAR0772E	131	DPIAR1417W	130
DE4TU41272(BB/W/W/WS)	226	DPIAR0730W	129	DPIAR0772H	127	DPIAR1418E	132
DE4TU412H(BB/W/W/WS)	226	DPIAR0735E	131	DPIAR0772W	129	DPIAR1418H	128
DE4WSMC	229	DPIAR0735H	127	DPIAR0774E	198	DPIAR1418W	130
DE4WSME108	229	DPIAR0735W	129	DPIAR0774H	194	DPIAR1423E	132
DE4WSME72	229	DPIAR0736E	131	DPIAR0774W	196	DPIAR1423H	128
DE4WSMED108	229	DPIAR0736H	127	DPIAR0775E	198	DPIAR1423W	130
DE4WSMED72	229	DPIAR0736W	129	DPIAR0775H	194	DPIAR1424E	132
DE6 D FD P	225	DPIAR0741E	131	DPIAR0775W	196	DPIAR1424H	128
DE6 D VPM	225	DPIAR0741H	127	DPIAR0777E	131	DPIAR1424W	130
DE6 FDP	222	DPIAR0741W	129	DPIAR0777H	127	DPIAR1429E	132
DE6 FDPF	224	DPIAR0742E	131	DPIAR0777W	129	DPIAR1429H	128
DE6 VDR1	223	DPIAR0742H	127	DPIAR0778E	131	DPIAR1429W	130
DE6 VDR1C	224	DPIAR0742W	129	DPIAR0778H	127	DPIAR1430E	132
DE6 VDR2	223	DPIAR0747E	131	DPIAR0778W	129	DPIAR1430H	128
DE6 VDR2C	224	DPIAR0747H	127	DPIAR0780E	198	DPIAR1430W	130

<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>
DP1AR1435E	132	DP1AR1472W	130	DP1AU0741	125	DP1AU1469	193
DP1AR1435H	128	DP1AR1474E	199	DP1AU0742	125	DP1AU1471	126
DP1AR1435W	130	DP1AR1474H	195	DP1AU0747	125	DP1AU1472	126
DP1AR1436E	132	DP1AR1474W	197	DP1AU0748	125	DP1AU1474	193
DP1AR1436H	128	DP1AR1475E	199	DP1AU0750	192	DP1AU1475	193
DP1AR1436W	130	DP1AR1475H	195	DP1AU0751	192	DP1AU1477	126
DP1AR1441E	132	DP1AR1475W	197	DP1AU0753	125	DP1AU1478	126
DP1AR1441H	128	DP1AR1477E	132	DP1AU0754	125	DP1AU1480	193
DP1AR1441W	130	DP1AR1477H	128	DP1AU0756	192	DP1AU1481	193
DP1AR1442E	132	DP1AR1477W	130	DP1AU0757	192	DP1AU1483	126
DP1AR1442H	128	DP1AR1478E	132	DP1AU0759	125	DP1AU1484	126
DP1AR1442W	130	DP1AR1478H	128	DP1AU0760	125	DP1AU1486	193
DP1AR1447E	132	DP1AR1478W	130	DP1AU0762	192	DP1AU1487	193
DP1AR1447H	128	DP1AR1480E	199	DP1AU0763	192	DP1AU1489	126
DP1AR1447W	130	DP1AR1480H	195	DP1AU0765	125	DP1AU1490	126
DP1AR1448E	132	DP1AR1480W	197	DP1AU0766	125	DP1AU1492	193
DP1AR1448H	128	DP1AR1481E	199	DP1AU0768	192	DP1AU1493	193
DP1AR1448W	130	DP1AR1481H	195	DP1AU0769	192	DP1AU1495	126
DP1AR1450E	199	DP1AR1481W	197	DP1AU0771	125	DP1AU1496	126
DP1AR1450H	195	DP1AR1483E	132	DP1AU0772	125	DP1AU1498	193
DP1AR1450W	197	DP1AR1483H	128	DP1AU0774	192	DP1AU1499	193
DP1AR1451E	199	DP1AR1483W	130	DP1AU0775	192	DP1AUECTP	126, 193
DP1AR1451H	195	DP1AR1484E	132	DP1AU0777	125	DP1BCT18	244
DP1AR1451W	197	DP1AR1484H	128	DP1AU0778	125	DP1BCT24	244
DP1AR1453E	132	DP1AR1484W	130	DP1AU0780	192	DP1BCT30	244
DP1AR1453H	128	DP1AR1486E	199	DP1AU0781	192	DP1BCT36	244
DP1AR1453W	130	DP1AR1486H	195	DP1AU0783	125	DP1BCT42	244
DP1AR1454E	132	DP1AR1486W	197	DP1AU0784	125	DP1BCT48	244
DP1AR1454H	128	DP1AR1487E	199	DP1AU0786	192	DP1BCT60	244
DP1AR1454W	130	DP1AR1487H	195	DP1AU0787	192	DP1MBT24	89
DP1AR1456E	199	DP1AR1487W	197	DP1AU0789	125	DP1MBT30	89
DP1AR1456H	195	DP1AR1489E	132	DP1AU0790	125	DP1MBT36	89
DP1AR1456W	197	DP1AR1489H	128	DP1AU0792	192	DP1MBT42	89
DP1AR1457E	199	DP1AR1489W	130	DP1AU0793	192	DP1MBT48	89
DP1AR1457H	195	DP1AR1490E	132	DP1AU0795	125	DP1PT3	157
DP1AR1457W	197	DP1AR1490H	128	DP1AU0796	125	DP1PT4	157
DP1AR1459E	132	DP1AR1490W	130	DP1AU0798	192	DP1SO0818	77
DP1AR1459H	128	DP1AR1492E	199	DP1AU0799	192	DP1SO0824	77
DP1AR1459W	130	DP1AR1492H	195	DP1AU1414	126	DP1SO0830	77
DP1AR1460E	132	DP1AR1492W	197	DP1AU1415	126	DP1SO0836	77
DP1AR1460H	128	DP1AR1493E	199	DP1AU1417	126	DP1SO0842	77
DP1AR1460W	130	DP1AR1493H	195	DP1AU1418	126	DP1SO0848	77
DP1AR1462E	199	DP1AR1493W	197	DP1AU1423	126	DP1SO0860	77
DP1AR1462H	195	DP1AR1495E	132	DP1AU1424	126	DP1SO1015	69
DP1AR1462W	197	DP1AR1495H	128	DP1AU1429	126	DP1SO1018	69
DP1AR1463E	199	DP1AR1495W	130	DP1AU1430	126	DP1SO1018F	78
DP1AR1463H	195	DP1AR1496E	132	DP1AU1435	126	DP1SO1024	69
DP1AR1463W	197	DP1AR1496H	128	DP1AU1436	126	DP1SO1024F	78
DP1AR1465E	132	DP1AR1496W	130	DP1AU1441	126	DP1SO1030	69
DP1AR1465H	128	DP1AR1498E	199	DP1AU1442	126	DP1SO1030F	78
DP1AR1465W	130	DP1AR1498H	195	DP1AU1447	126	DP1SO1036	69
DP1AR1466E	132	DP1AR1498W	197	DP1AU1448	126	DP1SO1036F	78
DP1AR1466H	128	DP1AR1499E	199	DP1AU1450	193	DP1SO1042	69
DP1AR1466W	130	DP1AR1499H	195	DP1AU1451	193	DP1SO1042F	78
DP1AR1468E	199	DP1AR1499W	197	DP1AU1453	126	DP1SO1048	69
DP1AR1468H	195	DP1AU0714	125	DP1AU1454	126	DP1SO1048F	78
DP1AR1468W	197	DP1AU0715	125	DP1AU1456	193	DP1SO1060	69
DP1AR1469E	199	DP1AU0717	125	DP1AU1457	193	DP1SO1060F	78
DP1AR1469H	195	DP1AU0718	125	DP1AU1459	126	DP1SO1415	69
DP1AR1469W	197	DP1AU0723	125	DP1AU1460	126	DP1SO1418	69
DP1AR1471E	132	DP1AU0724	125	DP1AU1462	193	DP1SO1424	69
DP1AR1471H	128	DP1AU0729	125	DP1AU1463	193	DP1SO1430	69
DP1AR1471W	130	DP1AU0730	125	DP1AU1465	126	DP1SO1436	69
DP1AR1472E	132	DP1AU0735	125	DP1AU1466	126	DP1SO1442	69
DP1AR1472H	128	DP1AU0736	125	DP1AU1468	193	DP1SO1448	69

<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>
DP1SO1460	69	DP1SO5018CCF	185	DP1SO748	69	DP1WTBTC18	160
DP1SO2115	70	DP1SO5024	60, 181	DP1SO760	69	DP1WTBTC24	160
DP1SO2118	70	DP1SO5024CCF	185	DP1SO7815	61	DP1WTBTC30	160
DP1SO2124	70	DP1SO5030	60, 181	DP1SO7818	61	DP1WTBTC36	160
DP1SO2130	70	DP1SO5030CCF	185	DP1SO7824	61	DP1WTBTC42	160
DP1SO2136	70	DP1SO5030EPEF	189	DP1SO7830	61	DP1WTBTC48	160
DP1SO2142	70	DP1SO5036	60, 181	DP1SO7836	61	DP1WTET57	160
DP1SO2148	70	DP1SO5036CCF	185	DP1SO7842	61	DP1WTET64	160
DP1SO2160	70	DP1SO5036EPEF	189	DP1SO7848	61	DP1WTET71	160
DP1SO2418	77	DP1SO5042	60, 181	DP1SOS15	71	DP1WTET78	160
DP1SO2424	77	DP1SO5042CCF	185	DP1SOS18	71	DP1WTTTC15	160
DP1SO2430	77	DP1SO5048	60, 181	DP1SOS24	71	DP1WTTTC18	160
DP1SO2436	77	DP1SO5048CCF	185	DP1SOS30	71	DP1WTTTC24	160
DP1SO2442	77	DP1SO5048EPEF	189	DP1SOS36	71	DP1WTTTC30	160
DP1SO2448	77	DP1SO5060	60, 181	DP1SOS42	71	DP1WTTTC36	160
DP1SO2460	77	DP1SO5060CCF	185	DP1SOS48	71	DP1WTTTC42	160
DP1SO2815	59, 70, 180	DP1SO5060EPEF	189	DP1SOS60	71	DP1WTTTC48	160
DP1SO2815CCF	184	DP1SO5072RR*	60	DP1SOWH15	59, 180	DP1WTTTC54	160
DP1SO2818	59, 70, 180	DP1SO5084RR*	60	DP1SOWH15CCF	184	DP1WTTTC60	160
DP1SO2818CCF	184	DP1SO5096RR*	60	DP1SOWH18	59, 180	DP1WTTTC66	160
DP1SO2824	59, 70, 180	DP1SO5715	61, 181	DP1SOWH18CCF	184	DP1WTTTC72	160
DP1SO2824CCF	184	DP1SO5715CCF	185	DP1SOWH24	59, 180	DP1WTTTC78	160
DP1SO2830	59, 70, 180	DP1SO5718	61, 181	DP1SOWH24CCF	184	DP1WTTTC84	160
DP1SO2830CCF	184	DP1SO5718CCF	185	DP1SOWH30	59, 180	DP1WTTTC90	160
DP1SO2830EPEF	188	DP1SO5724	61, 181	DP1SOWH30CCF	184	DP1WTTTC96	160
DP1SO2836	59, 70, 180	DP1SO5724CCF	185	DP1SOWH30EPEF	188	DP1WTTTSB	161
DP1SO2836CCF	184	DP1SO5730	61, 181	DP1SOWH36	59, 180	DP2 STFL1418	55
DP1SO2836EPEF	188	DP1SO5730CCF	185	DP1SOWH36CCF	184	DP2 STFL1424	55
DP1SO2842	59, 70, 180	DP1SO5730EPEF	189	DP1SOWH36EPEF	188	DP2 STFL1430	55
DP1SO2842CCF	184	DP1SO5736	61, 181	DP1SOWH42	59, 180	DP2 STFL1436	55
DP1SO2848	59, 70, 180	DP1SO5736CCF	185	DP1SOWH42CCF	184	DP2 STFL1442	55
DP1SO2848CCF	184	DP1SO5736EPEF	189	DP1SOWH48	59, 180	DP2 STFL1448	55
DP1SO2848EPEF	188	DP1SO5742	61, 181	DP1SOWH48CCF	184	DP2CHTP	163
DP1SO2860	59, 70, 180	DP1SO5742CCF	185	DP1SOWH48EPEF	188	DP2PMS36	157
DP1SO2860CCF	184	DP1SO5748	61, 181	DP1SOWH60	59, 180	DP2PMS42	157
DP1SO2860EPEF	188	DP1SO5748CCF	185	DP1SOWH60CCF	184	DP2PMS50	157
DP1SO2872RR*	59	DP1SO5748EPEF	189	DP1SOWH60EPEF	188	DP2PMS57	157
DP1SO2884RR*	59	DP1SO5760	61, 181	DP1SOWH72RR*	59	DP2PMS64	157
DP1SO2896RR*	59	DP1SO5760CCF	185	DP1SOWH84RR*	59	DP2PMS78	157
DP1SO4215	59, 180	DP1SO5760EPEF	189	DP1SOWH96RR*	59	DP2PRFIC15	163
DP1SO4215CCF	184	DP1SO6415	61, 181	DP1SW0724	101	DP2PRFN15	163
DP1SO4218	59, 180	DP1SO6415CCF	185	DP1SW0730	101	DP2PRFW15	163
DP1SO4218CCF	184	DP1SO6418	61, 181	DP1SW0736	101	DP2SOS15	71
DP1SO4224	59, 180	DP1SO6418CCF	185	DP1SW0742	101	DP2SOS18	71
DP1SO4224CCF	184	DP1SO6424	61, 181	DP1SW0748	101	DP2SOS24	71
DP1SO4230	59, 180	DP1SO6424CCF	185	DP1SW1424	101	DP2SOS30	71
DP1SO4230CCF	184	DP1SO6430	61, 181	DP1SW1430	101	DP2SOS36	71
DP1SO4230EPEF	188	DP1SO6430CCF	185	DP1SW1436	101	DP2SOS42	71
DP1SO4236	59, 180	DP1SO6430EPEF	189	DP1SW1442	101	DP2SOS48	71
DP1SO4236CCF	184	DP1SO6436	61, 181	DP1SW1448	101	DP2SOS60	71
DP1SO4236EPEF	188	DP1SO6436CCF	185	DP1SW2124	101	DP2SOSC	71
DP1SO4242	59, 180	DP1SO6436EPEF	189	DP1SW2130	101	DP2STF 2118	55
DP1SO4242CCF	184	DP1SO6442	61, 181	DP1SW2136	101	DP2STF 2124	55
DP1SO4248	59, 180	DP1SO6442CCF	185	DP1SW2142	101	DP2STF 2130	55
DP1SO4248CCF	184	DP1SO6448	61, 181	DP1SW2148	101	DP2STF 2136	55
DP1SO4248EPEF	188	DP1SO6448CCF	185	DP1SW2824	101	DP2STF 2142	55
DP1SO4260	59, 180	DP1SO6448EPEF	189	DP1SW2830	101	DP2STF 2148	55
DP1SO4260CCF	184	DP1SO6460	61, 181	DP1SW2836	101	DP2S(T/N)F 1418	55
DP1SO4260EPEF	188	DP1SO6460CCF	185	DP1SW2842	101	DP2S(T/N)F 1424	55
DP1SO4272RR*	59	DP1SO715	69	DP1SW2848	101	DP2S(T/N)F 1430	55
DP1SO4284RR*	59	DP1SO718	69	DP1WT57	160	DP2S(T/N)F 1436	55
DP1SO4296RR*	59	DP1SO724	69	DP1WT64	160	DP2S(T/N)F 1442	55
DP1SO5015	60, 181	DP1SO730	69	DP1WT71	160	DP2S(T/N)F 1448	55
DP1SO5015CCF	185	DP1SO736	69	DP1WT78	160	DP2S(T/N)F 2818	55
DP1SO5018	60, 181	DP1SO742	69	DP1WTBTC15	160	DP2S(T/N)F 2824	55

<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>
DP2S(T/N)F 2830	55	DP3L12830EPEF	190	DP3L15048EPEF	191	DP3PWS64	157
DP2S(T/N)F 2836	55	DP3L12830F	64, 74	DP3L15048F	66	DP3PWS78	157
DP2S(T/N)F 2842	55	DP3L12836	63, 73, 182	DP3L15060EPEF	191	DP3SS	79, 91, 92, 93
DP2S(T/N)F 2848	55	DP3L12836CCF	186	DP3L15072EPEF	191	DP5(C/V/U)PT29CP	177
DP3ESB	79, 97, 98, 99	DP3L12836EPEF	190	DP3L15084EPEF	191	DP5(C/V/U)PT30CP	177
DP3L10715	73	DP3L12836F	64, 74	DP3L15715	65, 183	DP5(C/V/U)PT35CP	177
DP3L10718	73	DP3L12842	63, 73, 182	DP3L15715CCF	187	DP5(C/V/U)PT36CP	177
DP3L10724	73	DP3L12842CCF	186	DP3L15715F	66	DP5(C/V/U)PT47CP	177
DP3L10730	73	DP3L12842F	64, 74	DP3L15718	65, 183	DP5(C/V/U)PT48CP	177
DP3L10736	73	DP3L12848	63, 73, 182	DP3L15718CCF	187	DP5(C/V/U)PT59CP	177
DP3L10742	73	DP3L12848CCF	186	DP3L15718F	66	DP5(C/V/U)PT60CP	177
DP3L10748	73	DP3L12848EPEF	190	DP3L15724	65, 183	DP5(C/V/U)PT71CP	177
DP3L11015	73	DP3L12848F	64, 74	DP3L15724CCF	187	DP5(C/V/U)PT72CP	177
DP3L11018	73	DP3L12860EPEF	190	DP3L15724F	66	DP5(C/V/U)PT83CP	177
DP3L11024	73	DP3L12872EPEF	190	DP3L15730	65, 183	DP5(C/V/U)PT84CP	177
DP3L11030	73	DP3L12884EPEF	190	DP3L15730CCF	187	DP5(C/V/U)PT95CP	177
DP3L11036	73	DP3L14215	63, 182	DP3L15730EPEF	191	DP5(C/V/U)PT96CP	177
DP3L11042	73	DP3L14215CCF	186	DP3L15730F	66	DP5PEG36F	147
DP3L11048	73	DP3L14215F	64	DP3L15736	65, 183	DP5PEG42	147
DP3L11415	73	DP3L14218	63, 182	DP3L15736CCF	187	DP5PEG50	147
DP3L11415F	74	DP3L14218CCF	186	DP3L15736EPEF	191	DP5PEG57	147
DP3L11418	73	DP3L14218F	64	DP3L15736F	66	DP5PEG78	147
DP3L11418F	74	DP3L14224	63, 182	DP3L15742	65, 183	DP5PEGG08	150
DP3L11424	73	DP3L14224CCF	186	DP3L15742CCF	187	DP5PEGG14	150
DP3L11424F	74	DP3L14224F	64	DP3L15742F	66	DP5PEGG22	150
DP3L11430	73	DP3L14230	63, 182	DP3L15748	65, 183	DP5PEGG28	150
DP3L11430F	74	DP3L14230CCF	186	DP3L15748CCF	187	DP5PEGG36	150
DP3L11436	73	DP3L14230EPEF	190	DP3L15748EPEF	191	DP5PEGG42H	150
DP3L11436F	74	DP3L14230F	64	DP3L15748F	66	DP5PEGGWH36	150
DP3L11442	73	DP3L14236	63, 182	DP3L15760EPEF	191	DP5PEGGWH42	150
DP3L11442F	74	DP3L14236CCF	186	DP3L15772EPEF	191	DP5PEGGWH50	150
DP3L11448	73	DP3L14236EPEF	190	DP3L15784EPEF	191	DP5PEGGWH57	150
DP3L11448F	74	DP3L14236F	64	DP3L1WH15	63, 182	DP5PEGGWH64	150
DP3L12115	73	DP3L14242	63, 182	DP3L1WH15CCF	186	DP5PEGGWH78	150
DP3L12118	73	DP3L14242CCF	186	DP3L1WH15F	64	DP5PEGN08	149
DP3L12124	73	DP3L14242F	64	DP3L1WH18	63, 182	DP5PEGN14	149
DP3L12130	73	DP3L14248	63, 182	DP3L1WH18CCF	186	DP5PEGN22	149
DP3L12136	73	DP3L14248CCF	186	DP3L1WH18F	64	DP5PEGN28	149
DP3L12142	73	DP3L14248EPEF	190	DP3L1WH24	63, 182	DP5PEGN36	149
DP3L12148	73	DP3L14248F	64	DP3L1WH24CCF	186	DP5PEGN42H	149
DP3L12415	80	DP3L14260EPEF	190	DP3L1WH24F	64	DP5PEGNWH36	149
DP3L12415F	80	DP3L14272EPEF	190	DP3L1WH30	63, 182	DP5PEGNWH42	149
DP3L12418	80	DP3L14284EPEF	190	DP3L1WH30CCF	186	DP5PEGNWH50	149
DP3L12418F	80	DP3L15015	65, 183	DP3L1WH30EPEF	190	DP5PEGNWH57	149
DP3L12424	80	DP3L15015CCF	187	DP3L1WH30F	64	DP5PEGNWH64	149
DP3L12424F	80	DP3L15015F	66	DP3L1WH36	63, 182	DP5PEGNWH78	149
DP3L12430	80	DP3L15018	65, 183	DP3L1WH36CCF	186	DP5PEGWH	147
DP3L12430F	80	DP3L15018CCF	187	DP3L1WH36EPEF	190	DP5PEGWHS14	147
DP3L12436	80	DP3L15018F	66	DP3L1WH36F	64	DP5PEGWHS21	147
DP3L12436F	80	DP3L15024	65, 183	DP3L1WH42	63, 182	DP5PEGWHS28	147
DP3L12442	80	DP3L15024CCF	187	DP3L1WH42CCF	186	DP5PENG08	151
DP3L12442F	80	DP3L15024F	66	DP3L1WH42F	64	DP5PENG14	151
DP3L12448	80	DP3L15030	65, 183	DP3L1WH48	63, 182	DP5PENG22	151
DP3L12448F	80	DP3L15030CCF	187	DP3L1WH48CCF	186	DP5PENG28	151
DP3L12815	63, 73, 182	DP3L15030EPEF	191	DP3L1WH48EPEF	190	DP5PENG42H	151
DP3L12815CCF	186	DP3L15030F	66	DP3L1WH48F	64	DP5PENGG36	151
DP3L12815F	64, 74	DP3L15036	65, 183	DP3L1WH60EPEF	190	DP5PENGWH36	151
DP3L12818	63, 73, 182	DP3L15036CCF	187	DP3L1WH72EPEF	190	DP5PENGWH42	151
DP3L12818CCF	186	DP3L15036EPEF	191	DP3L1WH84EPEF	190	DP5PENGWH50	151
DP3L12818F	64, 74	DP3L15036F	66	DP3MB	88, 89	DP5PENGWH57	151
DP3L12824	63, 73, 182	DP3L15042	65, 183	DP3PSB	79, 94, 95, 96	DP5PENGWH64	151
DP3L12824CCF	186	DP3L15042CCF	187	DP3PWS36	157	DP5PENGWH78	151
DP3L12824F	64, 74	DP3L15042F	66	DP3PWS42	157	DP5PG64	147
DP3L12830	63, 73, 182	DP3L15048	65, 183	DP3PWS50	157	DP6PE08	152
DP3L12830CCF	186	DP3L15048CCF	187	DP3PWS57	157	DP6PE14	152

<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>
DP6PE22	152	DP7PP42S	236	DP8CBBFR5048	45	DP8CMMFR4218	20
DP6PE28	152	DP7PP42T	236	DP8CBBFR5060	45	DP8CMMFR4224	20
DP6PE36	152	DP7PP50S	236	DP8CBBFR5718	46	DP8CMMFR4230	20
DP6PE36F	152	DP7PP50T	236	DP8CBBFR5724	46	DP8CMMFR4236	20
DP6PE42	152	DP7PP57S	236	DP8CBBFR5730	46	DP8CMMFR4242	20
DP6PE42H	152	DP7PP57T	236	DP8CBBFR5736	46	DP8CMMFR4248	20
DP6PE50	152	DP7PP64S	236	DP8CBBFR5742	46	DP8CMMFR4260	20
DP6PE57	152	DP7PP64T	236	DP8CBBFR5748	46	DP8CMMFR5015	21
DP6PE64	152	DP7PP78S	236	DP8CBBFR5760	46	DP8CMMFR5018	21
DP6PE78	152	DP7PP78T	236	DP8CBBFR6418	46	DP8CMMFR5024	21
DP6PEWH	152	DP7RCCH24	240	DP8CBBFR6424	46	DP8CMMFR5030	21
DP6PEWH36	152	DP7RCCH30	240	DP8CBBFR6430	46	DP8CMMFR5036	21
DP6PEWH42	152	DP7RCCH36	240	DP8CBBFR6436	46	DP8CMMFR5042	21
DP6PEWH50	152	DP7RCCH42	240	DP8CBBFR6442	46	DP8CMMFR5048	21
DP6PEWH57	152	DP7RCCH48	240	DP8CBBFR6448	46	DP8CMMFR5060	21
DP6PEWH64	152	DP7RCCH60	240	DP8CBBFR6460	46	DP8CMMFR5715	21
DP6PEWH78	152	DP7S	115, 116, 117, 118	DP8CBBFR7818	47	DP8CMMFR5718	21
DP6PEWHS14	152	DP7SS	121, 123	DP8CBBFR7824	47	DP8CMMFR5724	21
DP6PEWHS21	152	DP7SWTFK24	114	DP8CBBFR7830	47	DP8CMMFR5730	21
DP6PEWHS28	152	DP7SWTFK30	114	DP8CBBFR7836	47	DP8CMMFR5736	21
DP6TF	103	DP7SWTFK36	114	DP8CBBFR7842	47	DP8CMMFR5742	21
DP6TS	104	DP7SWTFK42	114	DP8CBBFR7848	47	DP8CMMFR5748	21
DP71RCT18	244	DP7SWTFK48	114	DP8CBBRR4218	43	DP8CMMFR5760	21
DP71RCT24	244	DP7SWTFKD	114	DP8CBBRR4224	43	DP8CMMFR6415	21
DP71RCT30	244	DP8	50, 51, 52	DP8CBBRR4230	43	DP8CMMFR6418	21
DP71RCT36	244	DP8120PC08S	205	DP8CBBRR4236	43	DP8CMMFR6424	21
DP71RCT42	244	DP8120PC14S	205	DP8CBBRR4242	43	DP8CMMFR6430	21
DP71RCT48	244	DP8120PC22S	205	DP8CBBRR4248	43	DP8CMMFR6436	21
DP71RCT60	244	DP8120PC28S	205	DP8CBBRR4260	43	DP8CMMFR6442	21
DP72RCT18	244	DP8120PC36S	205	DP8CBBRR5018	43	DP8CMMFR6448	21
DP72RCT24	244	DP8120PC36SF	205	DP8CBBRR5024	43	DP8CMMFR6460	21
DP72RCT30	244	DP8120PC42S	205	DP8CBBRR5030	43	DP8CMMFR7815	22
DP72RCT36	244	DP8120PC42SH	205	DP8CBBRR5036	43	DP8CMMFR7818	22
DP72RCT42	244	DP8120PC50S	205	DP8CBBRR5042	43	DP8CMMFR7824	22
DP72RCT48	244	DP8120PC57S	205	DP8CBBRR5048	43	DP8CMMFR7830	22
DP72RCT60	244	DP8120PC64S	205	DP8CBBRR5060	43	DP8CMMFR7836	22
DP7BF	143	DP8120PC78S	205	DP8CBBRR5718	44	DP8CMMFR7842	22
DP7CERK	239	DP8120PO36	205	DP8CBBRR5724	44	DP8CMMFR7848	22
DP7HIRKD24	240	DP8120PO42	205	DP8CBBRR5730	44	DP8CMMFRWH15	20
DP7HIRKD30	240	DP8120PO50	205	DP8CBBRR5736	44	DP8CMMFRWH18	20
DP7HIRKD36	240	DP8120PO57	205	DP8CBBRR5742	44	DP8CMMFRWH24	20
DP7HIRKD42	240	DP8120PO64	205	DP8CBBRR5748	44	DP8CMMFRWH30	20
DP7HIRKD48	240	DP8120PO78	205	DP8CBBRR5760	44	DP8CMMFRWH36	20
DP7HIRKD60	240	DP8120SPO 14	204	DP8CBBRR6418	44	DP8CMMFRWH42	20
DP7HIRKS24	240	DP8120SPO 21	204	DP8CBBRR6424	44	DP8CMMFRWH48	20
DP7HIRKS30	240	DP8120SPO 28	204	DP8CBBRR6430	44	DP8CMMFRWH60	20
DP7HIRKS36	240	DP8BC18K	77	DP8CBBRR6436	44	DP8CMMMLL3618	18
DP7HIRKS42	240	DP8BC24K	77	DP8CBBRR6442	44	DP8CMMMLL3624	18
DP7HIRKS48	240	DP8BC30K	77	DP8CBBRR6448	44	DP8CMMMLL3630	18
DP7HIRKS60	240	DP8BC36K	77	DP8CBBRR6460	44	DP8CMMMLL3636	18
DP7HLCWH	142	DP8BC42K	77	DP8CBBRR7818	44	DP8CMMMLL3642	18
DP7HRRKD24	240	DP8BC48K	77	DP8CBBRR7824	44	DP8CMMMLL3648	18
DP7HRRKD30	240	DP8BC60K	77	DP8CBBRR7830	44	DP8CMMMLL3660	18
DP7HRRKD36	240	DP8CBBFR4218	45	DP8CBBRR7836	44	DP8CMMMLL4218	18
DP7HRRKD42	240	DP8CBBFR4224	45	DP8CBBRR7842	44	DP8CMMMLL4224	18
DP7HRRKD48	240	DP8CBBFR4230	45	DP8CBBRR7848	44	DP8CMMMLL4230	18
DP7HRRKD60	240	DP8CBBFR4236	45	DP8CMMFR3615	20	DP8CMMMLL4236	18
DP7HRRKS24	240	DP8CBBFR4242	45	DP8CMMFR3618	20	DP8CMMMLL4242	18
DP7HRRKS30	240	DP8CBBFR4248	45	DP8CMMFR3624	20	DP8CMMMLL4248	18
DP7HRRKS36	240	DP8CBBFR4260	45	DP8CMMFR3630	20	DP8CMMMLL4260	18
DP7HRRKS42	240	DP8CBBFR5018	45	DP8CMMFR3636	20	DP8CMMMLL5018	18
DP7HRRKS48	240	DP8CBBFR5024	45	DP8CMMFR3642	20	DP8CMMMLL5024	18
DP7HRRKS60	240	DP8CBBFR5030	45	DP8CMMFR3648	20	DP8CMMMLL5030	18
DP7PP36S	236	DP8CBBFR5036	45	DP8CMMFR3660	20	DP8CMMMLL5036	18
DP7PP36T	236	DP8CBBFR5042	45	DP8CMMFR4215	20	DP8CMMMLL5042	18

<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>
DP8CMMMLL5048	18	DP8CMMRR5730	17	DP8CPPFR5042	39	DP8CPPRR4242	33
DP8CMMMLL5060	18	DP8CMMRR5736	17	DP8CPPFR5048	39	DP8CPPRR4248	33
DP8CMMMLL5718	19	DP8CMMRR5742	17	DP8CPPFR5060	39	DP8CPPRR4260	33
DP8CMMMLL5724	19	DP8CMMRR5748	17	DP8CPPFR5715	40	DP8CPPRR5015	33
DP8CMMMLL5730	19	DP8CMMRR5760	17	DP8CPPFR5718	40	DP8CPPRR5018	33
DP8CMMMLL5736	19	DP8CMMRR6415	17	DP8CPPFR5724	40	DP8CPPRR5024	33
DP8CMMMLL5742	19	DP8CMMRR6418	17	DP8CPPFR5730	40	DP8CPPRR5030	33
DP8CMMMLL5748	19	DP8CMMRR6424	17	DP8CPPFR5736	40	DP8CPPRR5036	33
DP8CMMMLL5760	19	DP8CMMRR6430	17	DP8CPPFR5742	40	DP8CPPRR5042	33
DP8CMMMLL6418	19	DP8CMMRR6436	17	DP8CPPFR5748	40	DP8CPPRR5048	33
DP8CMMMLL6424	19	DP8CMMRR6442	17	DP8CPPFR5760	40	DP8CPPRR5060	33
DP8CMMMLL6430	19	DP8CMMRR6448	17	DP8CPPFR6415	40	DP8CPPRR5715	34
DP8CMMMLL6436	19	DP8CMMRR6460	17	DP8CPPFR6418	40	DP8CPPRR5718	34
DP8CMMMLL6442	19	DP8CMMRR7815	17	DP8CPPFR6424	40	DP8CPPRR5724	34
DP8CMMMLL6448	19	DP8CMMRR7818	17	DP8CPPFR6430	40	DP8CPPRR5730	34
DP8CMMMLL6460	19	DP8CMMRR7824	17	DP8CPPFR6436	40	DP8CPPRR5736	34
DP8CMMMLL7818	19	DP8CMMRR7830	17	DP8CPPFR6442	40	DP8CPPRR5742	34
DP8CMMMLL7824	19	DP8CMMRR7836	17	DP8CPPFR6448	40	DP8CPPRR5748	34
DP8CMMMLL7830	19	DP8CMMRR7842	17	DP8CPPFR6460	40	DP8CPPRR5760	34
DP8CMMMLL7836	19	DP8CMMRR7848	17	DP8CPPFR7815	41	DP8CPPRR6415	34
DP8CMMMLL7842	19	DP8CMMRRWH15	15	DP8CPPFR7818	41	DP8CPPRR6418	34
DP8CMMMLL7848	19	DP8CMMRRWH18	15	DP8CPPFR7824	41	DP8CPPRR6424	34
DP8CMMMLLWH18	18	DP8CMMRRWH24	15	DP8CPPFR7830	41	DP8CPPRR6430	34
DP8CMMMLLWH24	18	DP8CMMRRWH30	15	DP8CPPFR7836	41	DP8CPPRR6436	34
DP8CMMMLLWH30	18	DP8CMMRRWH36	15	DP8CPPFR7842	41	DP8CPPRR6442	34
DP8CMMMLLWH36	18	DP8CMMRRWH42	15	DP8CPPFR7848	41	DP8CPPRR6448	34
DP8CMMMLLWH42	18	DP8CMMRRWH48	15	DP8CPPLL4218	36	DP8CPPRR6460	34
DP8CMMMLLWH48	18	DP8CMMRRWH60	15	DP8CPPLL4224	36	DP8CPPRR7815	35
DP8CMMMLLWH60	18	DP8CMMRRWH72RR*	15	DP8CPPLL4230	36	DP8CPPRR7818	35
DP8CMMRR3615	15	DP8CMMRRWH84RR*	15	DP8CPPLL4236	36	DP8CPPRR7824	35
DP8CMMRR3618	15	DP8CMMRRWH96RR*	15	DP8CPPLL4242	36	DP8CPPRR7830	35
DP8CMMRR3624	15	DP8CPAG3625	136	DP8CPPLL4248	36	DP8CPPRR7836	35
DP8CMMRR3630	15	DP8CPAG3635	136	DP8CPPLL4260	36	DP8CPPRR7842	35
DP8CMMRR3636	15	DP8CPAG3645	136	DP8CPPLL5018	36	DP8CPPRR7848	35
DP8CMMRR3642	15	DP8CPAG4225	136	DP8CPPLL5024	36	DP8CPTCPG5	176
DP8CMMRR3648	15	DP8CPAG4235	136	DP8CPPLL5030	36	DP8CPTCPHG5	176
DP8CMMRR3660	15	DP8CPAG4245	136	DP8CPPLL5036	36	DP8CPTG15	143
DP8CMMRR3672RR*	15	DP8CPAG5025	136	DP8CPPLL5042	36	DP8CPTG25	143
DP8CMMRR3684RR*	15	DP8CPAG5035	136	DP8CPPLL5048	36	DP8CPTG35	143
DP8CMMRR3696RR*	15	DP8CPAG5045	136	DP8CPPLL5060	36	DP8CPTG45	143
DP8CMMRR4215	16	DP8CPAG5725	136	DP8CPPLL5718	37	DP8CPTG55	143
DP8CMMRR4218	16	DP8CPAG5735	136	DP8CPPLL5724	37	DP8CTTFR3615	30
DP8CMMRR4224	16	DP8CPAG5745	136	DP8CPPLL5730	37	DP8CTTFR3618	30
DP8CMMRR4230	16	DP8CPAG6425	136	DP8CPPLL5736	37	DP8CTTFR3624	30
DP8CMMRR4236	16	DP8CPAG6435	136	DP8CPPLL5742	37	DP8CTTFR3630	30
DP8CMMRR4242	16	DP8CPAG6445	136	DP8CPPLL5748	37	DP8CTTFR3636	30
DP8CMMRR4248	16	DP8CPAG7825	136	DP8CPPLL5760	37	DP8CTTFR3642	30
DP8CMMRR4260	16	DP8CPAG7835	136	DP8CPPLL6418	37	DP8CTTFR3648	30
DP8CMMRR4272RR*	16	DP8CPAG7845	136	DP8CPPLL6424	37	DP8CTTFR3660	30
DP8CMMRR4284RR*	16	DP8CPAGWH25	136	DP8CPPLL6430	37	DP8CTTFR4215	30
DP8CMMRR4296RR*	16	DP8CPAGWH35	136	DP8CPPLL6436	37	DP8CTTFR4218	30
DP8CMMRR5015	16	DP8CPAGWH45	136	DP8CPPLL6442	37	DP8CTTFR4224	30
DP8CMMRR5018	16	DP8CPPFR4215	39	DP8CPPLL6448	37	DP8CTTFR4230	30
DP8CMMRR5024	16	DP8CPPFR4218	39	DP8CPPLL6460	37	DP8CTTFR4236	30
DP8CMMRR5030	16	DP8CPPFR4224	39	DP8CPPLL7818	38	DP8CTTFR4242	30
DP8CMMRR5036	16	DP8CPPFR4230	39	DP8CPPLL7824	38	DP8CTTFR4248	30
DP8CMMRR5042	16	DP8CPPFR4236	39	DP8CPPLL7830	38	DP8CTTFR4260	30
DP8CMMRR5048	16	DP8CPPFR4242	39	DP8CPPLL7836	38	DP8CTTFR5015	31
DP8CMMRR5060	16	DP8CPPFR4248	39	DP8CPPLL7842	38	DP8CTTFR5018	31
DP8CMMRR5072RR*	16	DP8CPPFR4260	39	DP8CPPLL7848	38	DP8CTTFR5024	31
DP8CMMRR5084RR*	16	DP8CPPFR5015	39	DP8CPPRR4215	33	DP8CTTFR5030	31
DP8CMMRR5096RR*	16	DP8CPPFR5018	39	DP8CPPRR4218	33	DP8CTTFR5036	31
DP8CMMRR5715	17	DP8CPPFR5024	39	DP8CPPRR4224	33	DP8CTTFR5042	31
DP8CMMRR5718	17	DP8CPPFR5030	39	DP8CPPRR4230	33	DP8CTTFR5048	31
DP8CMMRR5724	17	DP8CPPFR5036	39	DP8CPPRR4236	33	DP8CTTFR5060	31

<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>
DP8CTTFR5715	31	DP8CTTFR3618	26	DP8(C/V/U)120PAG573	203	DP8(C/V/U)POWHS	141
DP8CTTFR5718	31	DP8CTTFR3624	26	DP8(C/V/U)120PAG642	203	DP8(C/V/U)PT1	142
DP8CTTFR5724	31	DP8CTTFR3630	26	DP8(C/V/U)120PAG643	203	DP8(C/V/U)PT2	142
DP8CTTFR5730	31	DP8CTTFR3636	26	DP8(C/V/U)120PAG782	203	DP8(C/V/U)PT3	142
DP8CTTFR5736	31	DP8CTTFR3642	26	DP8(C/V/U)120PAG783	203	DP8(C/V/U)PT4	142
DP8CTTFR5742	31	DP8CTTFR3648	26	DP8(C/V/U)120PT1	205	DP8(C/V/U)PTCP	176
DP8CTTFR5748	31	DP8CTTFR3660	26	DP8(C/V/U)120PT2	205	DP8(C/V/U)PTCPH	176
DP8CTTFR5760	31	DP8CTTFR4215	26	DP8(C/V/U)120PT3	205	DP8(C/V/U)PTS	142
DP8CTTFR6415	32	DP8CTTFR4218	26	DP8(C/V/U)120PTG1	205	DP8HLC	143
DP8CTTFR6418	32	DP8CTTFR4224	26	DP8(C/V/U)120PTG2	205	DP8PBR	53
DP8CTTFR6424	32	DP8CTTFR4230	26	DP8(C/V/U)120PTG3	205	DP8PBRN15	53
DP8CTTFR6430	32	DP8CTTFR4236	26	DP8(C/V/U)PA362	135	DP8PC07	144
DP8CTTFR6436	32	DP8CTTFR4242	26	DP8(C/V/U)PA363	135	DP8PC07UH	145
DP8CTTFR6442	32	DP8CTTFR4248	26	DP8(C/V/U)PA364	135	DP8PC14	144
DP8CTTFR6448	32	DP8CTTFR4260	26	DP8(C/V/U)PA422	135	DP8PC14UH	145
DP8CTTFR6460	32	DP8CTTFR5015	26	DP8(C/V/U)PA423	135	DP8PC21	144
DP8CTTFR7815	32	DP8CTTFR5018	26	DP8(C/V/U)PA424	135	DP8PC21UH	145
DP8CTTFR7818	32	DP8CTTFR5024	26	DP8(C/V/U)PA502	135	DP8PC28	144
DP8CTTFR7824	32	DP8CTTFR5030	26	DP8(C/V/U)PA503	135	DP8PC28UH	145
DP8CTTFR7830	32	DP8CTTFR5036	26	DP8(C/V/U)PA504	135	DP8PC36	144
DP8CTTFR7836	32	DP8CTTFR5042	26	DP8(C/V/U)PA572	135	DP8PC362	144
DP8CTTFR7842	32	DP8CTTFR5048	26	DP8(C/V/U)PA573	135	DP8PC36U	145
DP8CTTFR7848	32	DP8CTTFR5060	26	DP8(C/V/U)PA574	135	DP8PC42	144
DP8CTTLL3618	28	DP8CTTFR5715	27	DP8(C/V/U)PA642	135	DP8PC422	144
DP8CTTLL3624	28	DP8CTTFR5718	27	DP8(C/V/U)PA643	135	DP8PC42U	145
DP8CTTLL3630	28	DP8CTTFR5724	27	DP8(C/V/U)PA644	135	DP8PC50	144
DP8CTTLL3636	28	DP8CTTFR5730	27	DP8(C/V/U)PA782	135	DP8PC502	144
DP8CTTLL3642	28	DP8CTTFR5736	27	DP8(C/V/U)PA783	135	DP8PC50U	145
DP8CTTLL3648	28	DP8CTTFR5742	27	DP8(C/V/U)PA784	135	DP8PC57	144
DP8CTTLL3660	28	DP8CTTFR5748	27	DP8(C/V/U)PAWH2	135	DP8PC572	144
DP8CTTLL4218	28	DP8CTTFR5760	27	DP8(C/V/U)PAWH3	135	DP8PC57U	145
DP8CTTLL4224	28	DP8CTTFR6415	27	DP8(C/V/U)PAWH4	135	DP8PC64	144
DP8CTTLL4230	28	DP8CTTFR6418	27	DP8(C/V/U)PO362	141	DP8PC642	144
DP8CTTLL4236	28	DP8CTTFR6424	27	DP8(C/V/U)PO363	140	DP8PC64U	145
DP8CTTLL4242	28	DP8CTTFR6430	27	DP8(C/V/U)PO364	140	DP8PC78	144
DP8CTTLL4248	28	DP8CTTFR6436	27	DP8(C/V/U)PO36CPF	176	DP8PC782	144
DP8CTTLL4260	28	DP8CTTFR6442	27	DP8(C/V/U)PO36S	141	DP8PC78U	145
DP8CTTLL5018	28	DP8CTTFR6448	27	DP8(C/V/U)PO422	141	DP8PCWH	144
DP8CTTLL5024	28	DP8CTTFR6460	27	DP8(C/V/U)PO423	140	DP8PCWH2	144
DP8CTTLL5030	28	DP8CTTFR7815	27	DP8(C/V/U)PO424	140	DP8PCWH36	144
DP8CTTLL5036	28	DP8CTTFR7818	27	DP8(C/V/U)PO42CPF	176	DP8PCWH42	144
DP8CTTLL5042	28	DP8CTTFR7824	27	DP8(C/V/U)PO42S	141	DP8PCWH50	144
DP8CTTLL5048	28	DP8CTTFR7830	27	DP8(C/V/U)PO502	141	DP8PCWH57	145
DP8CTTLL5060	28	DP8CTTFR7836	27	DP8(C/V/U)PO503	140	DP8PCWH64	145
DP8CTTLL5718	29	DP8CTTFR7842	27	DP8(C/V/U)PO504	140	DP8PCWH78	145
DP8CTTLL5724	29	DP8CTTFR7848	27	DP8(C/V/U)PO50CPF	176	DP8PCWHS14	144
DP8CTTLL5730	29	DP8(C/V/U)120PA362	203	DP8(C/V/U)PO50S	141	DP8PCWHS142	144
DP8CTTLL5736	29	DP8(C/V/U)120PA363	203	DP8(C/V/U)PO572	141	DP8PCWHS21	144
DP8CTTLL5742	29	DP8(C/V/U)120PA422	203	DP8(C/V/U)PO573	140	DP8PCWHS212	144
DP8CTTLL5748	29	DP8(C/V/U)120PA423	203	DP8(C/V/U)PO574	140	DP8PCWHS28	144
DP8CTTLL5760	29	DP8(C/V/U)120PA502	203	DP8(C/V/U)PO57CPF	176	DP8PCWHS282	144
DP8CTTLL6418	29	DP8(C/V/U)120PA503	203	DP8(C/V/U)PO57S	141	DP8PCWHU	145
DP8CTTLL6424	29	DP8(C/V/U)120PA572	203	DP8(C/V/U)PO642	141	DP8PO36	140
DP8CTTLL6430	29	DP8(C/V/U)120PA573	203	DP8(C/V/U)PO643	140	DP8PO42	140
DP8CTTLL6436	29	DP8(C/V/U)120PA642	203	DP8(C/V/U)PO644	140	DP8PO50	140
DP8CTTLL6442	29	DP8(C/V/U)120PA643	203	DP8(C/V/U)PO64CPF	176	DP8PO57	140
DP8CTTLL6448	29	DP8(C/V/U)120PA782	203	DP8(C/V/U)PO64S	141	DP8PO64	140
DP8CTTLL6460	29	DP8(C/V/U)120PA783	203	DP8(C/V/U)PO782	141	DP8PO78	140
DP8CTTLL7818	29	DP8(C/V/U)120PAG362	203	DP8(C/V/U)PO783	140	DP8POWH	140
DP8CTTLL7824	29	DP8(C/V/U)120PAG363	203	DP8(C/V/U)PO784	140	DP8PPC	143
DP8CTTLL7830	29	DP8(C/V/U)120PAG422	203	DP8(C/V/U)PO78S	141	DP8PRFN24	122
DP8CTTLL7836	29	DP8(C/V/U)120PAG423	203	DP8(C/V/U)POWH2	141	DP8PRFN30	122
DP8CTTLL7842	29	DP8(C/V/U)120PAG502	203	DP8(C/V/U)POWH3	140	DP8PRFN36	122
DP8CTTLL7848	29	DP8(C/V/U)120PAG503	203	DP8(C/V/U)POWH4	140	DP8PRFN42	122
DP8CTTFR3615	26	DP8(C/V/U)120PAG572	203	DP8(C/V/U)POWHCPF	176	DP8PRFN48	122

<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>
DP8PRFN60	122	DS1PFS	277, 443	DS3CMN4214	259	DS3ODSL1577214L	295
DP8SPO14	141	DS1PST	277, 443	DS3CMN4814	259	DS3ODSL1577214LT	303
DP8SPO21	141	DS1S 24	265	DS3CMN6014	259	DS3ODSL1643014L	298
DP8SPO28	142	DS1S 30	265	DS3CMN7214	259	DS3ODSL1643014LT	308
DPGPCG	172	DS1S 36	265	DS3CMSL3614L	260	DS3ODSL1643614L	298
DGPCFF	172	DS1S 42	265	DS3CMSL4214L	260	DS3ODSL1643614LT	308
DGPGBP(L/R)	172	DS1S 48	265	DS3CMSL4814L	260	DS3ODSL1644214L	298
DPRD15736(L/R)L	109	DS1S 54	265	DS3CMSL6014L	260	DS3ODSL1644214LT	308
DPRD15736(L/R)N	109	DS1S 60	265	DS3CMSL7214L	260	DS3ODSL1644814L	298
DPRD15742(L/R)L	109	DS1S 66	265	DS3CMSS3614L	259	DS3ODSL1644814LT	308
DPRD15742(L/R)N	109	DS1S 72	265	DS3CMSS4214L	259	DS3ODSL1646014L	298
DPRD15748(L/R)L	109	DS1SWM 30	267	DS3CMSS4814L	259	DS3ODSL1646014LT	308
DPRD15748(L/R)N	109	DS1SWM 36	267	DS3CMSS6014L	259	DS3ODSL1646614L	298
DPRD16436(L/R)L	109	DS1SWM 42	267	DS3CMSS7214L	259	DS3ODSL1646614LT	308
DPRD16436(L/R)N	109	DS1SWM 48	267	DS3CMSV3614L	260	DS3ODSL1647214L	298
DPRD16442(L/R)L	109	DS1WM 24	267	DS3CMSV4214L	260	DS3ODSL1647214LT	308
DPRD16442(L/R)N	109	DS1WM 30	267	DS3CMSV4814L	260	DS3ODSL2573021FL	296
DPRD16448(L/R)L	109	DS1WM 36	267	DS3CMSV6014L	260	DS3ODSL2573021FLT	305
DPRD16448(L/R)N	109	DS1WM 42	267	DS3CMSV7214L	260	DS3ODSL2573621FL	296
DPRD17836(L/R)L	109	DS1WM 48	267	DS3CMT(S/G)3614L	259	DS3ODSL2573621FLT	305
DPRD17836(L/R)N	109	DS2DW 30L	274	DS3CMT(S/G)4214L	259	DS3ODSL2574221FL	296
DPRD17842(L/R)L	109	DS2DW 36L	274	DS3CMT(S/G)4814L	259	DS3ODSL2574221FLT	305
DPRD17842(L/R)N	109	DS2DWDPL30	277	DS3CMT(S/G)6014L	259	DS3ODSL2574821FL	296
DPRD17848(L/R)L	109	DS2DWDPL36	277	DS3CMT(S/G)7214L	259	DS3ODSL2574821FLT	305
DPRD17848(L/R)N	109	DS2LKKT	277	DS3ODNS	296, 300, 305, 310	DS3ODSL2576021FL	296
DPRDIJPM	110	DS2OD 36L	291	DS3ODNS1573014	295	DS3ODSL2576021FLT	305
DPRD1SSB	110	DS2OD 42L	291	DS3ODNS1573014T	303	DS3ODSL2576621FL	296
DPS7V1418	56	DS2OD 48L	291	DS3ODNS1573614	295	DS3ODSL2576621FLT	305
DPS7V1424	56	DS2OD 54L	291	DS3ODNS1573614T	303	DS3ODSL2577221FL	296
DPS7V1430	56	DS2OD 60L	291	DS3ODNS1574214	295	DS3ODSL2577221FLT	305
DPS7V1436	56	DS2OD 66L	291	DS3ODNS1574214T	303	DS3ODSL2643021FL	300
DPS7V1442	56	DS2OD 72L	291	DS3ODNS1574814	295	DS3ODSL2643021FLT	310
DPS7V1448	56	DS2PF L18A	273	DS3ODNS1574814T	303	DS3ODSL2643621FL	300
DPS7V1460	56	DS2PF L18B	273	DS3ODNS1576014	295	DS3ODSL2643621FLT	310
DPS7V2118	56	DS2PF L24A	273	DS3ODNS1576014T	303	DS3ODSL2644221FL	300
DPS7V2124	56	DS2PF L24B	273	DS3ODNS1576614	295	DS3ODSL2644221FLT	310
DPS7V2130	56	DS2PF L30A	273	DS3ODNS1576614T	303	DS3ODSL2644821FL	300
DPS7V2136	56	DS2PF L30B	273	DS3ODNS1577214	295	DS3ODSL2644821FLT	310
DPS7V2142	56	DS2PM L18A	273	DS3ODNS1643014	298	DS3ODSL2646021FL	300
DPS7V2148	56	DS2PM L18B	273	DS3ODNS1643014T	308	DS3ODSL2646021FLT	310
DPS7V2160	56	DS2PM L18F	273	DS3ODNS1643614	298	DS3ODSL2646621FL	300
DPS7V2818	56	DS2PM L24A	273	DS3ODNS1643614T	308	DS3ODSL2646621FLT	310
DPS7V2824	56	DS2PM L24B	273	DS3ODNS1644214	298	DS3ODSL2647221FL	300
DPS7V2830	56	DS2PM L24F	273	DS3ODNS1644214T	308	DS3ODSL2647221FLT	310
DPS7V2836	56	DS2PM24L	247	DS3ODNS1644814	298	DS3ODSS	297, 302, 307, 312
DPS7V2842	56	DS2PM30L	247	DS3ODNS1644814T	308	DS3ODSS1573014L	295
DPS7V2848	56	DS2PM36L	247	DS3ODNS1646014	298	DS3ODSS1573014LT	303
DPS7V2860	56	DS2PM42L	247	DS3ODNS1646014T	308	DS3ODSS1573614L	295
DS1 OHL	268	DS2PM48L	247	DS3ODNS1646614	298	DS3ODSS1573614LT	303
DS1 VD	268, 291	DS2PM54L	247	DS3ODNS1646614T	308	DS3ODSS1574214L	295
DS1BS 24	267	DS2PM60L	247	DS3ODNS1647214	298	DS3ODSS1574214LT	303
DS1BS 30	267	DS2PM66L	247	DS3ODNS1647214T	308	DS3ODSS1574814L	295
DS1BS 36	267	DS2PM72L	247	DS3ODSL	297, 302, 307, 312	DS3ODSS1574814LT	303
DS1BS 42	267	DS2PPTC	277, 443	DS3ODSL1573014L	295	DS3ODSS1576014L	295
DS1BS 48	267	DS2PPTN	277, 443	DS3ODSL1573014LT	303	DS3ODSS1576014LT	303
DS1BS 54	267	DS2UM30L	263	DS3ODSL1573614L	295	DS3ODSS1576614L	295
DS1BS 60	267	DS2UM36L	263	DS3ODSL1573614LT	303	DS3ODSS1576614LT	303
DS1BS 66	267	DS2UM42L	263	DS3ODSL1574214L	295	DS3ODSS1577214L	295
DS1BS 72	267	DS2UM48L	263	DS3ODSL1574214LT	303	DS3ODSS1577214LT	303
DS1DWDPL	277	DS2UM54L	263	DS3ODSL1574814L	295	DS3ODSS1643014L	298
DS1EAKIT	247	DS2UM60L	263	DS3ODSL1574814LT	303	DS3ODSS1643014LT	308
DS1LKKT	277	DS2UM66L	263	DS3ODSL1576014L	295	DS3ODSS1643614L	298
DS1PBD	277, 443	DS2UM72L	263	DS3ODSL1576014LT	303	DS3ODSS1643614LT	308
DS1PCD	277, 443	DS2XPB	273	DS3ODSL1576614L	295	DS3ODSS1644214L	298
DS1PFD	277, 443	DS3CMN3614	259	DS3ODSL1576614LT	303	DS3ODSS1644214LT	308

<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>
DS3ODSS1644814L	298	DS3ODSV2573021FL	296	DS3PMSL4814L	251	DS3PMV72L	248
DS3ODSS1644814LT	308	DS3ODSV2573021FLT	306	DS3PMSL4821FL	253	DS3SMN3614	257
DS3ODSS1646014L	298	DS3ODSV2573621FL	296	DS3PMSL4821PL	254	DS3SMN4214	257
DS3ODSS1646014LT	308	DS3ODSV2573621FLT	306	DS3PMSL6014L	251	DS3SMN4814	257
DS3ODSS1646614L	298	DS3ODSV2574221FL	296	DS3PMSL6021FL	253	DS3SMN6014	257
DS3ODSS1646614LT	308	DS3ODSV2574221FLT	306	DS3PMSL6021PL	254	DS3SMN7214	257
DS3ODSS1647214L	298	DS3ODSV2574821FL	296	DS3PMSL6614L	251	DS3SMSL3614L	257
DS3ODSS1647214LT	308	DS3ODSV2574821FLT	306	DS3PMSL6621FL	253	DS3SMSL4214L	257
DS3ODSS2573021FL	296	DS3ODSV2576021FL	296	DS3PMSL6621PL	254	DS3SMSL4814L	257
DS3ODSS2573021FLT	305	DS3ODSV2576021FLT	306	DS3PMSL7214L	251	DS3SMSL6014L	257
DS3ODSS2573621FL	296	DS3ODSV2576621FL	296	DS3PMSL7221FL	253	DS3SMSL7214L	257
DS3ODSS2573621FLT	305	DS3ODSV2576621FLT	306	DS3PMSL7221PL	254	DS3SMSS3614L	257
DS3ODSS2574221FL	296	DS3ODSV2577221FL	296	DS3PMSS3014L	251	DS3SMSS4214L	257
DS3ODSS2574221FLT	305	DS3ODSV2577221FLT	306	DS3PMSS3021FL	253	DS3SMSS4814L	257
DS3ODSS2574821FL	296	DS3ODSV2643021FL	301	DS3PMSS3021PL	254	DS3SMSS6014L	257
DS3ODSS2574821FLT	305	DS3ODSV2643021FLT	311	DS3PMSS3614L	251	DS3SMSS7214L	257
DS3ODSS2576021FL	296	DS3ODSV2643621FL	301	DS3PMSS3621FL	253	DS3SMV3614L	258
DS3ODSS2576021FLT	305	DS3ODSV2643621FLT	311	DS3PMSS3621PL	254	DS3SMV4214L	258
DS3ODSS2576621FL	296	DS3ODSV2644221FL	301	DS3PMSS4214L	251	DS3SMV4814L	258
DS3ODSS2576621FLT	305	DS3ODSV2644221FLT	311	DS3PMSS4221FL	253	DS3SMV6014L	258
DS3ODSS2577221FL	296	DS3ODSV2644821FL	301	DS3PMSS4221PL	254	DS3SMV7214L	258
DS3ODSS2577221FLT	305	DS3ODSV2644821FLT	311	DS3PMSS4814L	251	DS3SMT(S/G)3614L	257
DS3ODSS2643021FL	300	DS3ODSV2646021FL	301	DS3PMSS4821FL	253	DS3SMT(S/G)4214L	257
DS3ODSS2643021FLT	310	DS3ODSV2646021FLT	311	DS3PMSS4821PL	254	DS3SMT(S/G)4814L	257
DS3ODSS2643621FL	300	DS3ODSV2646621FL	301	DS3PMSS6014L	251	DS3SMT(S/G)6014L	257
DS3ODSS2643621FLT	310	DS3ODSV2646621FLT	311	DS3PMSS6021FL	253	DS3SMT(S/G)7214L	257
DS3ODSS2644221FL	300	DS3ODSV2647221FL	301	DS3PMSS6021PL	254	DS3WMN3614	255
DS3ODSS2644221FLT	310	DS3ODSV2647221FLT	311	DS3PMSS6614L	251	DS3WMN4214	255
DS3ODSS2644821FL	300	DS3PML30L	247	DS3PMSS6621FL	253	DS3WMN4814	255
DS3ODSS2644821FLT	310	DS3PML36L	247	DS3PMSS6621PL	254	DS3WMN6014	255
DS3ODSS2646021FL	300	DS3PML42L	247	DS3PMSS7214L	251	DS3WMN7214	255
DS3ODSS2646021FLT	310	DS3PML48L	247	DS3PMSS7221FL	253	DS3WMSL3614L	255
DS3ODSS2646621FL	300	DS3PML60L	247	DS3PMSS7221PL	254	DS3WMSL4214L	255
DS3ODSS2646621FLT	310	DS3PML66L	247	DS3PMSV3014L	252	DS3WMSL4814L	255
DS3ODSS2647221FL	300	DS3PML72L	247	DS3PMSV3021FL	253	DS3WMSL6014L	255
DS3ODSS2647221FLT	310	DS3PMNS3014	251	DS3PMSV3021PL	254	DS3WMSL7214L	255
DS3ODSV	297, 302, 307, 312	DS3PMNS3021	253	DS3PMSV3614L	252	DS3WMSS3614L	255
DS3ODSV1573014L	295	DS3PMNS3614	251	DS3PMSV3621FL	253	DS3WMSS4214L	255
DS3ODSV1573014LT	304	DS3PMNS3621	253	DS3PMSV3621PL	254	DS3WMSS4814L	255
DS3ODSV1573614L	295	DS3PMNS4214	251	DS3PMSV4214L	252	DS3WMSS6014L	255
DS3ODSV1573614LT	304	DS3PMNS4221	253	DS3PMSV4221FL	253	DS3WMSS7214L	255
DS3ODSV1574214L	295	DS3PMNS4814	251	DS3PMSV4221PL	254	DS3WMSV3614L	255
DS3ODSV1574214LT	304	DS3PMNS4821	253	DS3PMSV4814L	252	DS3WMSV4214L	255
DS3ODSV1574814L	295	DS3PMNS6014	251	DS3PMSV4821FL	253	DS3WMSV4814L	255
DS3ODSV1574814LT	304	DS3PMNS6021	253	DS3PMSV4821PL	254	DS3WMSV6014L	255
DS3ODSV1576014L	295	DS3PMNS6614	251	DS3PMSV6014L	252	DS3WMSV7214L	255
DS3ODSV1576014LT	304	DS3PMNS6621	253	DS3PMSV6021FL	253	DS3WMT(S/G)3614L	256
DS3ODSV1576614L	295	DS3PMNS7214	251	DS3PMSV6021PL	254	DS3WMT(S/G)4214L	256
DS3ODSV1576614LT	304	DS3PMNS7221	253	DS3PMSV6614L	252	DS3WMT(S/G)4814L	256
DS3ODSV1577214L	295	DS3PMS30L	247	DS3PMSV6621FL	253	DS3WMT(S/G)6014L	256
DS3ODSV1577214LT	304	DS3PMS36L	247	DS3PMSV6621PL	254	DS3WMT(S/G)7214L	256
DS3ODSV1643014L	299	DS3PMS42L	247	DS3PMSV7214L	252	DS4LC1ANL24N	282
DS3ODSV1643014LT	309	DS3PMS48L	247	DS3PMSV7221FL	253	DS4LC1ANL30N	282
DS3ODSV1643614L	299	DS3PMS60L	247	DS3PMSV7221PL	254	DS4LC1ANL36N	282
DS3ODSV1643614LT	309	DS3PMS66L	247	DS3PMT(S/G)3614L	251	DS4LC1ANL42N	282
DS3ODSV1644214L	299	DS3PMS72L	247	DS3PMT(S/G)4214L	251	DS4LC1ANL48N	282
DS3ODSV1644214LT	309	DS3PMSL3014L	251	DS3PMT(S/G)4814L	251	DS4LC1ANL54N	282
DS3ODSV1644814L	299	DS3PMSL3021FL	253	DS3PMT(S/G)6014L	251	DS4LC1ANL60N	282
DS3ODSV1644814LT	309	DS3PMSL3021PL	254	DS3PMT(S/G)7214L	251	DS4LC1ANL66N	282
DS3ODSV1646014L	299	DS3PMSL3614L	251	DS3PMV30L	248	DS4LC1ANL72N	282
DS3ODSV1646014LT	309	DS3PMSL3621FL	253	DS3PMV36L	248	DS4LC1ANS42N	279
DS3ODSV1646614L	299	DS3PMSL3621PL	254	DS3PMV42L	248	DS4LC1ANS48N	279
DS3ODSV1646614LT	309	DS3PMSL4214L	251	DS3PMV48L	248	DS4LC1ANS54N	279
DS3ODSV1647214L	299	DS3PMSL4221FL	253	DS3PMV60L	248	DS4LC1ANS60N	279
DS3ODSV1647214LT	309	DS3PMSL4221PL	254	DS3PMV66L	248	DS4LC1ANS66N	279

<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>
DS4LC1ANS72N	279	DS4LC1BVS60L	279	DS4LC1CVS54L	280	DS4LC1DVS48L	281
DS4LC1ANV24N	286	DS4LC1BVS66L	279	DS4LC1CVS60L	280	DS4LC1DVS54L	281
DS4LC1ANV30N	286	DS4LC1BVS72L	279	DS4LC1CVS66L	280	DS4LC1DVS60L	281
DS4LC1ANV36N	286	DS4LC1BVV30L	287	DS4LC1CVS72L	280	DS4LC1DVS66L	281
DS4LC1ANV42N	286	DS4LC1BVV36L	287	DS4LC1CVV30L	288	DS4LC1DVS72L	281
DS4LC1ANV48N	286	DS4LC1BVV42L	287	DS4LC1CVV36L	288	DS4LC1DVV30L	289
DS4LC1ANV54N	286	DS4LC1BVV48L	287	DS4LC1CVV42L	288	DS4LC1DVV36L	289
DS4LC1ANV60N	286	DS4LC1BVV54L	287	DS4LC1CVV48L	288	DS4LC1DVV42L	289
DS4LC1ANV66N	286	DS4LC1BVV60L	287	DS4LC1CVV54L	288	DS4LC1DVV48L	289
DS4LC1ANV72N	286	DS4LC1BVV66L	287	DS4LC1CVV60L	288	DS4LC1DVV54L	289
DS4LC1BLL30L	282	DS4LC1BVV72L	287	DS4LC1CVV66L	288	DS4LC1DVV60L	289
DS4LC1BLL36L	282	DS4LC1CLL30L	284	DS4LC1CVV72L	288	DS4LC1DVV66L	289
DS4LC1BLL42L	282	DS4LC1CLL36L	284	DS4LC1DLL30L	285	DS4LC1DVV72L	289
DS4LC1BLL48L	282	DS4LC1CLL42L	284	DS4LC1DLL36L	285	DSCSWDB24	267
DS4LC1BLL54L	282	DS4LC1CLL48L	284	DS4LC1DLL42L	285	DSCSWDB30	267
DS4LC1BLL60L	282	DS4LC1CLL54L	284	DS4LC1DLL48L	285	DSCSWDB36	267
DS4LC1BLL66L	282	DS4LC1CLL60L	284	DS4LC1DLL54L	285	DSCSWDB42	267
DS4LC1BLL72L	282	DS4LC1CLL66L	284	DS4LC1DLL60L	285	DSCSWDB48	267
DS4LC1BLS42L	279	DS4LC1CLL72L	284	DS4LC1DLL66L	285	DT1ABY10242N	421
DS4LC1BLS48L	279	DS4LC1CLS42L	280	DS4LC1DLL72L	285	DT1ABY10248N	421
DS4LC1BLS54L	279	DS4LC1CLS48L	280	DS4LC1DLS42L	281	DT1ABY10842N	421
DS4LC1BLS60L	279	DS4LC1CLS54L	280	DS4LC1DLS48L	281	DT1ABY10848N	421
DS4LC1BLS66L	279	DS4LC1CLS60L	280	DS4LC1DLS54L	281	DT1ABY12042N	421
DS4LC1BLS72L	279	DS4LC1CLS66L	280	DS4LC1DLS60L	281	DT1ABY12048N	421
DS4LC1BLV30L	286	DS4LC1CLS72L	280	DS4LC1DLS66L	281	DT1ABY13242N	421
DS4LC1BLV36L	286	DS4LC1CLV30L	288	DS4LC1DLS72L	281	DT1ABY13248N	421
DS4LC1BLV42L	286	DS4LC1CLV36L	288	DS4LC1DLV30L	289	DT1ABY14442N	421
DS4LC1BLV48L	286	DS4LC1CLV42L	288	DS4LC1DLV36L	289	DT1ABY14448N	421
DS4LC1BLV54L	286	DS4LC1CLV48L	288	DS4LC1DLV42L	289	DT1ACX30	412
DS4LC1BLV60L	286	DS4LC1CLV54L	288	DS4LC1DLV48L	289	DT1ACX3017	412
DS4LC1BLV66L	286	DS4LC1CLV60L	288	DS4LC1DLV54L	289	DT1ACX3021	412
DS4LC1BLV72L	286	DS4LC1CLV66L	288	DS4LC1DLV60L	289	DT1ACX3036	412
DS4LC1BSL30L	282	DS4LC1CLV72L	288	DS4LC1DLV66L	289	DT1ACX3042	412
DS4LC1BSL36L	282	DS4LC1CSL30L	284	DS4LC1DLV72L	289	DT1ACX36	412
DS4LC1BSL42L	282	DS4LC1CSL36L	284	DS4LC1DSL30L	285	DT1ACX3617	412
DS4LC1BSL48L	282	DS4LC1CSL42L	284	DS4LC1DSL36L	285	DT1ACX3621	412
DS4LC1BSL54L	282	DS4LC1CSL48L	284	DS4LC1DSL42L	285	DT1ACX3636	412
DS4LC1BSL60L	282	DS4LC1CSL54L	284	DS4LC1DSL48L	285	DT1ACX3642	412
DS4LC1BSL66L	282	DS4LC1CSL60L	284	DS4LC1DSL54L	285	DT1ACX42	412
DS4LC1BSL72L	282	DS4LC1CSL66L	284	DS4LC1DSL60L	285	DT1ACX4217	412
DS4LC1BSS42L	279	DS4LC1CSL72L	284	DS4LC1DSL66L	285	DT1ACX4221	412
DS4LC1BSS48L	279	DS4LC1CSS42L	280	DS4LC1DSL72L	285	DT1ACX4236	412
DS4LC1BSS54L	279	DS4LC1CSS48L	280	DS4LC1DSS42L	281	DT1ACX4242	412
DS4LC1BSS60L	279	DS4LC1CSS54L	280	DS4LC1DSS48L	281	DT1ACX48	412
DS4LC1BSS66L	279	DS4LC1CSS60L	280	DS4LC1DSS54L	281	DT1ACX4817	412
DS4LC1BSS72L	279	DS4LC1CSS66L	280	DS4LC1DSS60L	281	DT1ACX4821	412
DS4LC1BSV30L	286	DS4LC1CSS72L	280	DS4LC1DSS66L	281	DT1ACX4836	412
DS4LC1BSV36L	286	DS4LC1CSV30L	288	DS4LC1DSS72L	281	DT1ACX4842	412
DS4LC1BSV42L	286	DS4LC1CSV36L	288	DS4LC1DSV30L	289	DT1ADX3030	413
DS4LC1BSV48L	286	DS4LC1CSV42L	288	DS4LC1DSV36L	289	DT1ADX303017	413
DS4LC1BSV54L	286	DS4LC1CSV48L	288	DS4LC1DSV42L	289	DT1ADX303021	413
DS4LC1BSV60L	286	DS4LC1CSV54L	288	DS4LC1DSV48L	289	DT1ADX303036	413
DS4LC1BSV66L	286	DS4LC1CSV60L	288	DS4LC1DSV54L	289	DT1ADX303042	414
DS4LC1BSV72L	286	DS4LC1CSV66L	288	DS4LC1DSV60L	289	DT1ADX3636	413
DS4LC1BVL30L	283	DS4LC1CSV72L	288	DS4LC1DSV66L	289	DT1ADX363617	413
DS4LC1BVL36L	283	DS4LC1CVL30L	284	DS4LC1DSV72L	289	DT1ADX363621	413
DS4LC1BVL42L	283	DS4LC1CVL36L	284	DS4LC1DVL30L	285	DT1ADX363636	413
DS4LC1BVL48L	283	DS4LC1CVL42L	284	DS4LC1DVL36L	285	DT1ADX363642	414
DS4LC1BVL54L	283	DS4LC1CVL48L	284	DS4LC1DVL42L	285	DT1ADX4242	413
DS4LC1BVL60L	283	DS4LC1CVL54L	284	DS4LC1DVL48L	285	DT1ADX424217	413
DS4LC1BVL66L	283	DS4LC1CVL60L	284	DS4LC1DVL54L	285	DT1ADX424221	413
DS4LC1BVL72L	283	DS4LC1CVL66L	284	DS4LC1DVL60L	285	DT1ADX424236	413
DS4LC1BVS42L	279	DS4LC1CVL72L	284	DS4LC1DVL66L	285	DT1ADX424242	414
DS4LC1BVS48L	279	DS4LC1CVS42L	280	DS4LC1DVL72L	285	DT1ADX4848	413
DS4LC1BVS54L	279	DS4LC1CVS48L	280	DS4LC1DVS42L	281	DT1ADX484817	413

<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>
DT1ADX484821	413	DT1ATY12042N	420	DT1CTY6030N	408	DVDP8424LN	334
DT1ADX484836	413	DT1ATY12048N	420	DT1CTY6036N	408	DVDP8424RN	334
DT1ADX484842	414	DT1ATY13242N	420	DT1CTY6624N	408	DVDP8430LN	334
DT1ARY10236N	419	DT1ATY13248N	420	DT1CTY6630N	408	DVDP8430RN	334
DT1ARY10242N	419	DT1ATY14442N	420	DT1CTY6636N	408	DVDP9024LN	334
DT1ARY10248N	419	DT1ATY14448N	420	DT1CTY7224N	408	DVDP9024RN	334
DT1ARY10836N	419	DT1ATY6024NS	405	DT1CTY7230N	408	DVDP9030LN	334
DT1ARY10842N	419	DT1ATY6030NS	405	DT1CTY7236N	408	DVDP9030RN	334
DT1ARY10848N	419	DT1ATY6036N	406	DT1CTY7824N	408	DVDP9624LN	334
DT1ARY12042N	419	DT1ATY6624NS	405	DT1CTY7830N	408	DVDP9624RN	334
DT1ARY12048N	419	DT1ATY6630NS	405	DT1CTY7836N	408	DVDP9630LN	334
DT1ARY13242N	419	DT1ATY6636N	406	DT1CTY8424N	408	DVDP9630RN	334
DT1ARY13248N	419	DT1ATY7224NS	405	DT1CTY8430N	408	DVDS6020LN	335
DT1ARY14442N	419	DT1ATY7230NS	405	DT1CTY8436N	408	DVDS6020RN	335
DT1ARY14448N	419	DT1ATY7236N	406	DT1CTY9024N	408	DVDS6620LN	335
DT1ARY6024NS	403	DT1ATY7824NS	405	DT1CTY9030N	408	DVDS6620RN	335
DT1ARY6030NS	403	DT1ATY7830NS	405	DT1CTY9036N	408	DVDS7220LN	335
DT1ARY6036N	404	DT1ATY7836N	406	DT1CTY9624N	408	DVDS7220RN	335
DT1ARY6624NS	403	DT1ATY8424NS	405	DT1CTY9630N	408	DVDS7820LN	335
DT1ARY6630NS	403	DT1ATY8430NS	405	DT1CTY9636N	408	DVDS7820RN	335
DT1ARY6636N	404	DT1ATY8436N	406	DTIS	415	DVDS8420LN	335
DT1ARY7224NS	403	DT1ATY8442N	406	DVDB6024LN	337	DVDS8420RN	335
DT1ARY7230NS	403	DT1ATY9024NS	405	DVDB6024RN	337	DVDS9020LN	335
DT1ARY7236N	404	DT1ATY9030NS	405	DVDB6030LN	337	DVDS9020RN	335
DT1ARY7824NS	403	DT1ATY9036N	406	DVDB6030RN	337	DVDS9620LN	335
DT1ARY7830NS	403	DT1ATY9042N	406	DVDB6624LN	337	DVDS9620RN	335
DT1ARY7836N	404	DT1ATY9624NS	405	DVDB6624RN	337	ET1OT3672	423
DT1ARY8424NS	403	DT1ATY9630NS	405	DVDB6630LN	337	ET1OT48120	423
DT1ARY8430NS	403	DT1ATY9636N	406	DVDB6630RN	337	ET1OT4896	423
DT1ARY8436N	404	DT1ATY9642N	406	DVDB7224LN	337	ET1OT54120	423
DT1ARY8442N	404	DT1BTL	415	DVDB7224RN	337	ET1OT60144	423
DT1ARY9024NS	403	DT1BTS	415	DVDB7230LN	337	ET1RCT3048	422
DT1ARY9030NS	403	DT1BXL	415	DVDB7230RN	337	ET1RCT3060	422
DT1ARY9036N	404	DT1BXL17	415	DVDB7824LN	337	ET1RCT3072	422
DT1ARY9042N	404	DT1BXL21	415	DVDB7824RN	337	ET1RCT3469	422
DT1ARY9624NS	403	DT1BXL36	415	DVDB7830LN	337	ET1RCT3479	422
DT1ARY9630NS	403	DT1BXL42	415	DVDB7830RN	337	ET1RCT3660	422
DT1ARY9636N	404	DT1BXS	415	DVDB8424LN	337	ET1RCT3672	422
DT1ARY9642N	404	DT1BXS17	415	DVDB8424RN	337	ET1RCT4284	422
DT1ASX3030	411	DT1BXS21	415	DVDB8430LN	337	ET1RCT4896	422
DT1ASX303017	411	DT1BXS36	415	DVDB8430RN	337	ET1RT30	422
DT1ASX303021	411	DT1BXS42	415	DVDB9024LN	337	ET1RT36	422
DT1ASX303036	411	DT1CK4	416	DVDB9024RN	337	ET1RT36C	422
DT1ASX303042	411	DT1CRY6024N	407	DVDB9030LN	337	ET1RT42	422
DT1ASX3636	411	DT1CRY6030N	407	DVDB9030RN	337	ET1RT48	422
DT1ASX363617	411	DT1CRY6036N	407	DVDB9624LN	337	ET1RT60	422
DT1ASX363621	411	DT1CRY6624N	407	DVDB9624RN	337	ET1ST22C	422
DT1ASX363636	411	DT1CRY6630N	407	DVDB9630LN	337	ET1ST2416	422
DT1ASX363642	411	DT1CRY6636N	407	DVDB9630RN	337	ET1ST30	422
DT1ASX4242	411	DT1CRY7224N	407	DVDP6024LN	334	ET1ST36	422
DT1ASX424217	411	DT1CRY7230N	407	DVDP6024RN	334	ET1ST42	422
DT1ASX424221	411	DT1CRY7236N	407	DVDP6030LN	334	ET1ST48	422
DT1ASX424236	411	DT1CRY7824N	407	DVDP6030RN	334	ET1ST60	422
DT1ASX424242	411	DT1CRY7830N	407	DVDP6624LN	334	LU1-C4242SS	383
DT1ASX4848	411	DT1CRY7836N	407	DVDP6624RN	334	LU1-C4848DD	383
DT1ASX484817	411	DT1CRY8424N	407	DVDP6630LN	334	LU1-C4848DS	383
DT1ASX484821	411	DT1CRY8430N	407	DVDP6630RN	334	LU1-C4848SD	383
DT1ASX484836	411	DT1CRY8436N	407	DVDP7224LN	334	LU1-C4848SS	383
DT1ASX484842	411	DT1CRY9024N	407	DVDP7224RN	334	LU1-C4860DS	383
DT1ATY10236N	420	DT1CRY9030N	407	DVDP7230LN	334	LU1-C4860SD	383
DT1ATY10242N	420	DT1CRY9036N	407	DVDP7230RN	334	LU1-C4860SS	383
DT1ATY10248N	420	DT1CRY9624N	407	DVDP7824LN	334	LU1-C4872DS	383
DT1ATY10836N	420	DT1CRY9630N	407	DVDP7824RN	334	LU1-C4872SD	383
DT1ATY10842N	420	DT1CRY9636N	407	DVDP7830LN	334	LU1-C4872SS	383
DT1ATY10848N	420	DT1CTY6024N	408	DVDP7830RN	334	LU1-C6048DS	383

<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>
LU1-C6048SD	383	LU1-S7218-A	378	LU1-Y42S-B	386	MU1-S4830-A	369
LU1-C6048SS	383	LU1-S7218-B	378	LU1-Y48S-B	386	MU1-S4830-B	369
LU1-C7248DS	383	LU1-S7224-A	379	LU1-Y60S-B	386	MU1-S5418-B	367
LU1-C7248SD	383	LU1-S7224-B	379	LU1-YTS	386	MU1-S5424-A	368
LU1-C7248SS	383	LU1-S7230-A	380	MB3-F18M	392	MU1-S5424-B	368
LU1-D36S-B	386	LU1-S7230-B	380	MB3-F18W	392	MU1-S5430-A	369
LU1-D42S-B	386	LU1-S7818-A	378	MB3-F24M	392	MU1-S5430-B	369
LU1-D48S-B	386	LU1-S7818-B	378	MB3-F24W	392	MU1-S6018-B	367
LU1-M48S-BLL	387	LU1-S7824-A	379	MB3-F30M	392	MU1-S6024-A	368
LU1-M48S-BRL	387	LU1-S7824-B	379	MB3-F30W	392	MU1-S6024-B	368
LU1-R3050-B	384	LU1-S7830-A	380	MM1-PD	164	MU1-S6030-A	369
LU1-R6330B	384	LU1-S7830-B	380	MM1-SF	164	MU1-S6030-B	369
LU1-R7530B	384	LU1-S8418-A	378	MM1UG	164	MU1-S6618-B	367
LU1-S10818-A	378	LU1-S8418-B	378	MM1WG	164	MU1-S6624-A	368
LU1-S10818-B	378	LU1-S8424-A	379	MM2-CG	164	MU1-S6624-B	368
LU1-S10824-A	379	LU1-S8424-B	379	MM2-CH	164	MU1-S6630-A	369
LU1-S10824-B	379	LU1-S8430-A	380	MM2-NCG	164	MU1-S6630-B	369
LU1-S12018-A	378	LU1-S8430-B	380	MSAMP1616	164	MU1-S7218-B	367
LU1-S12018-B	378	LU1-S9018-A	378	MU1-C4242SS	375	MU1-S7224-A	368
LU1-S12024-A	379	LU1-S9018-B	378	MU1-C4848DD	375	MU1-S7224-B	368
LU1-S12024-B	379	LU1-S9024-A	379	MU1-C4848DS	375	MU1-S7230-A	369
LU1-S2424-A	379	LU1-S9024-B	379	MU1-C4848SD	375	MU1-S7230-B	369
LU1-S2424-B	379	LU1-S9030-A	380	MU1-C4848SS	375	MU1-S7824-A	368
LU1-S3018-A	378	LU1-S9030-B	380	MU1-C4860DS	375	MU1-S7824-B	368
LU1-S3018-B	378	LU1-S9618-A	378	MU1-C4860SD	375	MU1-S7830-A	369
LU1-S3024-A	379	LU1-S9618-B	378	MU1-C4860SS	375	MU1-S7830-B	369
LU1-S3024-B	379	LU1-S9624-A	379	MU1-C4872DS	375	MU1-S8424-A	368
LU1-S3030-A	380	LU1-S9624-B	379	MU1-C4872SD	375	MU1-S8424-B	368
LU1-S3030-B	380	LU1-S9630-A	380	MU1-C4872SS	375	MU1-S8430-A	369
LU1-S3618-A	378	LU1-S9630-B	380	MU1-C6048DS	375	MU1-S8430-B	369
LU1-S3618-B	378	LU1-T48A-L	381	MU1-C6048SD	375	MU1-S9024-A	368
LU1-S3624-A	379	LU1-T48A-R	381	MU1-C6048SS	375	MU1-S9024-B	368
LU1-S3624-B	379	LU1-T48B-L	381	MU1-C7248DS	375	MU1-S9030-A	369
LU1-S3630-A	380	LU1-T48B-R	381	MU1-C7248SD	375	MU1-S9030-B	369
LU1-S3630-B	380	LU1-T54A-L	381	MU1-C7248SS	375	MU1-S9624-A	368
LU1-S4218-A	378	LU1-T54A-R	381	MU1-M48S-AL	377	MU1-S9624-B	368
LU1-S4218-B	378	LU1-T54B-L	381	MU1-M48S-AR	377	MU1-S9630-A	369
LU1-S4224-A	379	LU1-T54B-R	381	MU1-P72SA	374	MU1-S9630-B	369
LU1-S4224-B	379	LU1-T60A-L	381	MU1-P78DA	374	MU1-V3618-A	370
LU1-S4230-A	380	LU1-T60A-R	381	MU1-R3048-B	373	MU1-V3624-A	370
LU1-S4230-B	380	LU1-T60B-L	381	MU1-R3050-B	373	MU1-V3624-C	370
LU1-S4818-A	378	LU1-T60B-R	381	MU1-R6330B	372	MU1-V4224-A	370
LU1-S4818-B	378	LU1-T72A-L	381	MU1-R6330E	372	MU1-V4224-C	370
LU1-S4824-A	379	LU1-T72A-R	381	MU1-R7530B	372	MU1-V4230-A	370
LU1-S4824-B	379	LU1-T72B-L	381	MU1-R7530E	372	MU1-V4230-C	370
LU1-S4830-A	380	LU1-T72B-R	381	MU1-S2424-A	368	MU1-V42SS-A	371
LU1-S4830-B	380	LU1-V3618-A	382	MU1-S2424-B	368	MU1-V42SS-C	371
LU1-S5418-A	378	LU1-V3624-A	382	MU1-S3018-B	367	MU1-V4824-A	370
LU1-S5418-B	378	LU1-V4224-A	382	MU1-S3024-A	368	MU1-V4824-C	370
LU1-S5424-A	379	LU1-V4230-A	382	MU1-S3024-B	368	MU1-V4830-A	370
LU1-S5424-B	379	LU1-V4824-A	382	MU1-S3030-A	369	MU1-V4830-C	370
LU1-S5430-A	380	LU1-V4830-A	382	MU1-S3030-B	369	MU1-V48DS-A	371
LU1-S5430-B	380	LU1-W36AL	385	MU1-S3618-B	367	MU1-V48DS-C	371
LU1-S6018-A	378	LU1-W36AR	385	MU1-S3624-A	368	MU1-V48SS-A	371
LU1-S6018-B	378	LU1-W36BL	385	MU1-S3624-B	368	MU1-V48SS-C	371
LU1-S6024-A	379	LU1-W36BR	385	MU1-S3630-A	369	MU1-Y36S-AL	376
LU1-S6024-B	379	LU1-W42AL	385	MU1-S3630-B	369	MU1-Y36S-AR	376
LU1-S6030-A	380	LU1-W42AR	385	MU1-S4218-B	367	MU1-Y42S-AL	376
LU1-S6030-B	380	LU1-W42BL	385	MU1-S4224-A	368	MU1-Y42S-AR	376
LU1-S6618-A	378	LU1-W42BR	385	MU1-S4224-B	368	MU1-Y48S-AL	376
LU1-S6618-B	378	LU1-W48AL	385	MU1-S4230-A	369	MU1-Y48S-AR	376
LU1-S6624-A	379	LU1-W48AR	385	MU1-S4230-B	369	MU1-Y60S-AL	376
LU1-S6624-B	379	LU1-W48BL	385	MU1-S4818-B	367	MU1-Y60S-AR	376
LU1-S6630-A	380	LU1-W48BR	385	MU1-S4824-A	368	MU1-YTS	376
LU1-S6630-B	380	LU1-Y36S-B	386	MU1-S4824-B	368	MW2-R6330B	366

<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>	<i>pattern no.</i>	<i>page</i>
MW2-R6330E	366	MW2-S9624-A	362	MZ1-V6015	394
MW2-R7530B	366	MW2-S9624-B	362	MZ1-V6019	394
MW2-R7530E	366	MW2-S9630-A	363	MZ1-V6022	394
MW2-R8730B	366	MW2-S9630-B	363	MZ1-V7215	394
MW2-R8730E	366	MW2-V3618-A	365	MZ1-V7219	394
MW2-S2424-A	362	MW2-V3624-A	365	MZ1-V7222	394
MW2-S2424-B	362	MW2-V3624-C	365	RDOTK1	227
MW2-S3018-B	361	MW2-V4224-A	365		
MW2-S3024-A	362	MW2-V4224-C	365		
MW2-S3024-B	362	MW2-V4230-A	365		
MW2-S3030-A	363	MW2-V4230-C	365		
MW2-S3030-B	363	MW2-V4824-A	365		
MW2-S3618-B	361	MW2-V4824-C	365		
MW2-S3624-A	362	MW2-V4830-A	365		
MW2-S3624-B	362	MW2-V4830-C	365		
MW2-S3630-A	363	MZ1-B3015	393		
MW2-S3630-B	363	MZ1-B3019	393		
MW2-S4218-B	361	MZ1-B3022	393		
MW2-S4224-A	362	MZ1-B3615	393		
MW2-S4224-B	362	MZ1-B3619	393		
MW2-S4230-A	363	MZ1-B3622	393		
MW2-S4230-B	363	MZ1-B4215	393		
MW2-S4818-B	361	MZ1-B4219	393		
MW2-S4824-A	362	MZ1-B4222	393		
MW2-S4824-B	362	MZ1-B4815	393		
MW2-S4830-A	363	MZ1-B4819	393		
MW2-S4830-B	363	MZ1-B4822	393		
MW2-S5418-B	361	MZ1-B5415	393		
MW2-S5424-A	362	MZ1-B5419	393		
MW2-S5424-B	362	MZ1-B5422	393		
MW2-S5430-A	363	MZ1-B6015	393		
MW2-S5430-B	363	MZ1-B6019	393		
MW2-S6018-B	361	MZ1-B6022	393		
MW2-S6024-A	362	MZ1-B6615	393		
MW2-S6024-B	362	MZ1-B6619	393		
MW2-S6030-A	363	MZ1-B6622	393		
MW2-S6030-B	363	MZ1-B7215	393		
MW2-S6618-B	361	MZ1-B7219	393		
MW2-S6624-A	362	MZ1-B7222	393		
MW2-S6624-B	362	MZ1-B7815	393		
MW2-S6630-A	363	MZ1-B7819	393		
MW2-S6630-B	363	MZ1-B7822	393		
MW2-S6636-B	364	MZ1-E2415-W/U	395		
MW2-S6636-R	364	MZ1-E2419-W/U	395		
MW2-S7218-B	361	MZ1-E2422-W/U	395		
MW2-S7224-A	362	MZ1-E3015-W/U	395		
MW2-S7224-B	362	MZ1-E3019-W/U	395		
MW2-S7230-A	363	MZ1-E3022-W/U	395		
MW2-S7230-B	363	MZ1-IS	164		
MW2-S7236-B	364	MZ1-S2415-W/U	395		
MW2-S7236-R	364	MZ1-S2419-W/U	395		
MW2-S7824-A	362	MZ1-S2422-W/U	395		
MW2-S7824-B	362	MZ1-S3015-W/U	395		
MW2-S7830-A	363	MZ1-S3019-W/U	395		
MW2-S7830-B	363	MZ1-S3022-W/U	395		
MW2-S7836-B	364	MZ1-SS	164		
MW2-S7836-R	364	MZ1-V3615	394		
MW2-S8424-A	362	MZ1-V3619	394		
MW2-S8424-B	362	MZ1-V3622	394		
MW2-S8430-A	363	MZ1-V4215	394		
MW2-S8430-B	363	MZ1-V4219	394		
MW2-S9024-A	362	MZ1-V4222	394		
MW2-S9024-B	362	MZ1-V4815	394		
MW2-S9030-A	363	MZ1-V4819	394		
MW2-S9030-B	363	MZ1-V4822	394		

Selling Policy

	This Selling Policy supercedes all previous selling policies. Prices, discounts and product offerings are subject to change without notice.
Terms & Conditions of Sales	Sales by Knoll, Inc. or Knoll North America Corp. ("Seller") of Knoll Product Lines (hereinafter "Products") within the United States and Canada are made only on the terms which are contained in this Selling Policy. Seller hereby gives notice of its objection to any different or additional terms and conditions. This sale is expressly conditional upon Purchaser's assent to the terms and conditions set forth below. Additional terms and conditions may apply to KnollStudio and KnollTextiles orders. These terms and conditions may be modified or supplemented only by a written document signed by an authorized representative of Seller. These terms and conditions supercede any prior and/or contemporaneous agreements or correspondence between Purchaser and Seller. Written quotations expire thirty (30) days from the date of issuance and can be withdrawn by written notice anytime during that period. Where Purchaser and Seller have entered into the Knoll Electronic Terms and Conditions, all orders, acknowledgements, invoices and other business communications placed or transmitted in accordance with the Knoll Electronic Terms and Conditions shall be deemed to be in writing and signed and shall be valid for all purposes as if they were originated and maintained in documentary form.
Ordering Information	All orders must be in writing. The product pattern number(s) contained on Seller's order acknowledgement shall be the final expression of the order.
Order Confirmation	A purchase order is not binding on Seller until Purchaser has received Seller's order confirmation or acknowledgment.
Pricing Policies	List prices are subject to change without notice. List prices shall be those prices in effect on the date of receipt of a complete purchase order unless shipment is requested more than ninety (90) days after order entry in which case prices in effect on the date of shipment apply. List prices include specified freight costs. Unless specified in writing by Seller, no other charges are included in Seller's list prices.
Taxes	All sales, use, excise and other taxes applicable to the sale of the Products shall be paid by Purchaser. If Purchaser claims an exemption from any tax, Purchaser shall submit to Seller the appropriate exemption certificates.
Terms of Payment	Payment for one hundred percent (100%) of the net order amount is due within thirty (30) days of the date of invoice, which is generally issued upon shipment. In case of any discrepancies, such as shortages, and Seller is notified in writing within ten (10) days of receipt of Product, only that portion may be deducted and the balance paid. For orders greater than \$100,000 net, a fifty percent (50%) deposit is due at the time of order placement, with the remainder due within thirty (30) days of the date of invoice. KnollStudio orders less than \$2,000 require payment for one hundred percent (100%) of the net order amount (including any applicable sales tax and charges for inside delivery, special packaging, etc.), due at time of order placement. For KnollStudio orders greater than \$2,000, a one-half (50%) deposit is due at time of order placement with the remainder (including any applicable sales tax and charges for inside delivery, special packaging, etc.) due prior to shipment. If, in the judgment of Seller, Purchaser's financial condition does not justify the terms of the payment, Seller may require full or partial payment in advance. Past due accounts shall be charged one and one-half percent (1.5%) per month, or the highest rate permitted by law, whichever is less, and will be added to the outstanding balance. In the event Purchaser defaults on payment, Purchaser shall be liable for all collection costs, including reasonable attorney's fees and costs.
Changes and Cancellation	Purchase orders may not be changed or cancelled, in whole or in part, without prior written consent of Seller. Changes may effect delivery dates. Expenses incurred because of changes shall be charged to Purchaser. In the event of cancellations, Purchaser will be liable for reasonable cancellation charges established by Seller. Orders for special Product, orders including "COM" (hereinafter defined) material and orders pursuant to expedited delivery programs, may not be canceled.
Freight Prepaid	Freight is prepaid and included in the price of all Products, except KnollTextiles, within the 48 contiguous United States for orders placed with Knoll, Inc. and within Canada, excluding the Yukon, Northwest Territories, Nunavut and Newfoundland for orders placed with Knoll North America Corp. Packing is tested for rigorous motion and transportation but is not guaranteed to protect furniture from all conditions. If special packaging is required for any reason, please consult with your sales representative or dealer. Seller shall select the method of shipment and routing. Freight for all KnollTextiles orders is prepaid and added to the invoice.
Delivery/Freight Charges	Shipments outside the contiguous 48 United States and Canada shall be shipped F.O.B. Origin. For shipments outside the contiguous United States and Canada, Purchaser is responsible for the cost of freight from point of embarkation, including any handling and transportation charges incidental to loading at the point of departure and unloading at the final destination. Conditions beyond the control of Seller, including weather, available facilities and traffic conditions, may affect exact time of delivery. Seller shall not be responsible for specific carrier delivery date or time unless it has made a specific delivery commitment, in writing. Nonstandard methods of shipment and/or additional services are available upon request. Purchaser will be billed for the differential cost of any special services in excess of standard surface carrier freight costs. Premium charges, at Purchaser's request, will be added for airfreight, exclusive use of vehicle and extra, export or special packaging. Accessorial charges will be added for inside delivery, extra labor, reconsignment and redelivery. Partial shipments may be made and invoiced by Seller.
Claims	All shipments for Knoll Products within the contiguous United States and Canada are F.O.B. Origin. All risk of loss passes to Purchaser at time of delivery to carrier. Purchaser shall inspect all Products upon receipt and notify Seller within ten (10) working days after receipt of any damage or defects which are, or should be, apparent from an inspection of the Product and its packaging. Failure of Purchaser to notify Seller during the ten (10) working day period shall constitute acceptance of the Products and waiver of any apparent defects, errors or shortages. For all claims relating to Product damaged in transit or for any other claims relating to or arising out of the transportation of the Product, Purchaser must seek recovery from the carrier and Seller has no liability to Purchaser for such claims. Seller may, upon request, assist Purchaser with filing of such claims with the carrier, but Seller will not be liable for any of these transportation related claims.
Seller's Security Interest	Until Seller receives the full payment for the Product, Seller shall have a security interest in the Product. Purchaser agrees to perform all acts, including but not limited to the execution and filing of documentation, which may be necessary to perfect and assure the security interest of Seller.
Returns	The return of Products without a written authorization by Seller shall not be accepted. To receive authorization for Product return, please call Customer Service. All Products that are returned pursuant to a valid authorization shall be subject to a twenty-five percent (25%) of list restocking charge. Products not currently offered for sale by Seller (including COM) shall not be authorized for return. All returned Products must be unused, in original condition and in the original Seller packing cartons. No refund or credit shall be given for damaged Products.
Held Orders/Storage	If Purchaser requests that an order be held or delayed, prices and terms and conditions in effect at the time of shipment shall apply. If Purchaser requests a delay after the time when Seller can defer production, Purchaser will be invoiced for the Product, payable in accordance with standard terms, when the order is ready for shipment. Seller may transfer the Product to storage, in which case all expenses incurred in connection with storage, including demurrage, preparation for storage, storage charges and handling shall be payable by Purchaser upon submission of invoices by Seller. Risk of loss to the Product shall pass to the Purchaser upon delivery of the Product into storage.

Selling Policy

Customer's Own Material	A Purchaser who requests a fabric or other surface material not standard to Seller's line of Products ("COM") must submit samples of the requested material to Seller prior to entry of a purchaser order. Seller shall determine if the material is suitable to its manufacturing processes and meets any requirements of Underwriters Laboratories. If the COM is acceptable, Seller will then establish a price for using the COM or the Product in question. For a description of the procedures for submitting samples and testing, contact customer resources or your sales representative. Seller shall have no responsibility for the appearance, condition, performance, durability, colorfastness or any other physical attribute of the COM. Purchaser shall indemnify and hold Seller harmless for any damages, injuries or losses arising out of or related to use of the COM on the Product.
Warranty	Seller warrants to the original Purchaser only that the Products Seller manufactures and sells to Purchaser are free of defects in workmanship and materials, during the applicable warranty period set forth below. Warranty period set forth below is for 24-hour, 7 days a week, multi shift use (includes parts and labor to repair). Should any failure to conform with this limited warranty appear to a Product listed below during the applicable warranty period from the date of shipment, Seller shall, upon prompt written notice, repair or replace, at its option and costs, the affected part or parts. <i>Product and Period of Warranty</i> <i>Lifetime: Antenna Workspaces, AutoStrada, Calibre, Crinion Open Table, Currents, Dividends Horizon, Morrison, Reff Profiles laminate, Rockwell Unscripted, Series 2 Storage, Template, Quoin and other non-wood components (except cascade edge worksurfaces, operational parts, controls, electrical, Lighting, Series 2 Veneer Front Storage, digital locks, upholstery, textiles and leathers, special or custom products, see below)</i> <i>12 Years: Chadwick, Generation by Knoll, k. task, Life, Moment, MultiGeneration by Knoll, Ollo, ReGeneration by Knoll, Remix, and Toboggan seating (except seating upholstery, textiles, leathers and finishes, see below).</i> <i>10 Years: Anchor Storage except digital locks, Antenna Workspaces, AutoStrada, Crinion Open Table, Dividends Horizon, Dividends Horizon Satellite Surfaces, Reff Profiles, Rockwell Unscripted, Quoin wood components, Template wood components, Series 2 Veneer Front Storage, cascade edge worksurfaces, Wood Casegoods (The Graham Collection) (except wood casegoods upholstered surfaces, see below), Reuter overheads, Reuter vertical storage, KnollExtra Sapper Monitor Arm Collection, Sapper XYZ Monitor Arm Series, Adjustable keyboard mechanisms and platforms, Communication Boards (except fabric board textiles, cork and FilzFelt, see below), Smokador collection (except leathers, see below), Orchestra Universal Systems Accessories, k. lounge structural components, KnollStudio Pixel and Propeller, Tone bases and k.screens.</i> <i>5 Years: Operational parts, controls, electrical, Lighting (except light ballasts, bulbs and power supply, see below), special or custom product, wood veneer products and plywood, Currents handcrank, KnollStudio, Rockwell Unscripted wire bases, Spark Series seating structural elements, structural elements of all KnollStudio outdoor products including all Richard Schultz designed products, KnollExtra CPU holders and all universal storage drawers and Power Collection, k. bench (except changes in finish, see below) and k. stand bases (except changes in finish, see below).</i> <i>3 Years: Rockwell Unscripted upholstery (except textiles and leather), Office Seating upholstery, textiles, leathers and finishes. Fabric boards textiles and Smokador Collection leathers, KnollExtra Pop Up Screens.</i> <i>2 Years: Anchor Storage digital locks, Quoin digital locks, all other KnollExtra product and KnollTextiles Ultrasuede.</i> <i>1 Year: Light ballasts, bulbs and power supply, seating upholstered arm pads and soft arm pads, wood casegoods upholstered surfaces. KnollStudio, outdoor product finishes, k. lounge upholstery and k. lounge fabric. Rockwell Unscripted fabric and accessories, Spinneybeck leathers, and KnollTextiles upholstery except Ultrasuede.</i> This warranty does not apply to: • Damage caused by a carrier other than the Seller. • Normal wear and tear or acts or omissions of parties other than Seller (including user modification, improper use or installation of Products). • COM or other third party materials applied to Products. • Products not installed by or under the auspices of a Knoll Dealer. • Dramatic temperature variations or exposure to unusual conditions. • Changes in surface finishes, including colorfastness due to aging or exposure to light. • Except as specifically noted above, textiles and upholstery supplied by KnollTextiles and Spinneybeck FilzFelt (consult current price lists for applicable warranties). Natural variations occurring in wood, marble, and leather shall not be considered defects, and the Seller does not guarantee the colorfastness or matching of the colors, grains or textures, or surface hardness of such materials. The Seller also does not guarantee the colorfastness of fiberglass panel surfaces. THE EXPRESS WARRANTIES CONTAINED HEREIN ARE IN LIEU OF ALL OTHER WARRANTIES, EXPRESS OR IMPLIED, INCLUDING ANY WARRANTIES OF MERCHANTABILITY AND FITNESS FOR PARTICULAR PURPOSE AND ALL OTHER WARRANTIES ARISING FROM COURSE OF DEALING OR USAGE OF TRADE. The remedies provided above are the Purchaser's sole remedies for any failure of Seller to comply with its obligations regarding the workmanship of its Products. Correction of any nonconformity in the manner and for the period of time provided shall constitute complete fulfillment of all liabilities of Seller, with respect to or arising out of the Product furnished hereunder.
Delay/Force Majeure	Seller shall not be liable for failure to perform or for delay in performance due to fire, flood, strike or other labor difficulty, act of God, act of war or terrorism, act of any governmental authority or of the Purchaser, riot, embargo, fuel or energy shortage, wrecks or delay in transportation, inability to obtain necessary labor, materials or manufacturing facilities from usual sources or failure of suppliers to meet their contractual obligations, or due to any cause beyond its reasonable control. If any such event occurs, Seller may extend delivery dates by a period of time necessary to overcome the effect of such delay, allocate available Product or cancel any purchase order.
Compliance with Law	PURCHASER IS SOLELY RESPONSIBLE FOR COMPLIANCE WITH ALL APPLICABLE FEDERAL, STATE AND LOCAL LAWS, ORDINANCES, REGULATIONS, RULES AND STANDARDS RELATING TO THE INSTALLATION, MAINTENANCE, USE AND OPERATION OF THE PRODUCTS.
Patents	Subject to the following provisions, Seller shall, at its own expense, defend or, at its option, settle any claim, suit or proceeding brought against the Purchaser, and/or its vendees, mediate and immediate, so far as based on an allegation that any Product or any part thereof furnished hereunder constitutes a direct or a contributory infringement of any claim of any patent of the United States or Canada. This obligation shall be effective only if Purchaser shall have made all payments then due hereunder and if Seller is notified promptly in writing and given authority, information and assistance for the defense of said claim, suit or proceeding. Seller shall pay all damages and costs awarded in such suit or proceedings so defended. The foregoing indemnity does not apply to the following: • Products supplied according to a design other than that of Seller, and which is required by the Purchaser. • Combination of the Product with another product not furnished hereunder unless Seller is a contributory infringer. • Any settlements of a suit or proceeding made without Seller's written consent.
Limitations of Liability	SELLER, ITS CONTRACTORS, AUTHORIZED DEALERS AND SUBCONTRACTORS OR SUPPLIERS OF ANY TIER SHALL NOT BE LIABLE TO PURCHASER FOR ANY SPECIAL, INDIRECT, INCIDENTAL OR CONSEQUENTIAL DAMAGES ARISING FROM A BREACH OF THIS AGREEMENT. Purchaser's remedies set forth herein are exclusive and the liability of Seller with respect to the breach of this agreement or any contract entered into between the parties pursuant hereto shall not exceed the price of the Product or part on which such liability is based.

KnollKey Lock Program

KnollKey Lock Program General Information

Following is the KnollKey lock policy, applicable to all products.

Knoll furniture can be ordered keyed-alike or random keyed. Key-alike and random keying instructions cannot be mixed on any single order. Only one of the two instructions can be used on an individual order. When an order is submitted with mixed (key-alike and random) instructions, Knoll will release the order as key-alike only and lock cores will have to be specified separately.

Key-alike

For the convenience of the user, furniture may be keyed alike at no charge. Write "Key-alike" in the description of your purchase order for any pedestal, overhead, file or other item you wish to have keyed alike.

Using the key-alike instructions, order cores and keys as line items on your purchase order. Do NOT submit a key-alike form. The Knoll East Greenville Lock Center will select key numbers from the standard range of K 001 - K 250. Key numbers will not be repeated unless over 250 sets are ordered. Lock cores keyed-alike will ship separately from the product, ready for field installation.

There is no charge for key-alike orders if placed with the furniture order.

IF THE KEY-ALIKE ORDER IS NOT PLACED AT LEAST TWO WEEKS PRIOR TO THE FURNITURE SHIP DATE, A \$50 HANDLING CHARGE AND AIR FREIGHT CHARGES WILL APPLY.

If product is ordered and shipped random-keyed, additional lock cores for key-alike are billable.

Random-Keying

To specify product keyed-random, write "key-random" in the product description. Random-keyed product is shipped with the lock core factory installed. A shrouded key is included. Random means no effort has been made to match key numbers, or to make them different.

Keys

A Knoll shrouded key is shipped with every lock core. 250 Key numbers are available. For numbers above 250, contact Custom Product Development. Additional keys and key blanks are available. See service parts for more information.

Master Keying

Knoll locks can be controlled by means of a master key. There is no additional per-lock charge for master keying. A letter of approval from the client must accompany orders for master keys.

Installing Lock Cores

Lock cores can be installed or removed in the field by using a change key. Cores must be in the unlocked position to be removed. See service parts for change key pattern number and pricing.


Lock Distribution

All orders for key-alike lock cores/keys are packaged and shipped from the East Greenville Lock Center, regardless of where the pedestals, overhead, or other units are produced. Random keyed product will have cores factory-installed.

How to Specify Key-Alike

Following is an example of how to specify key-alike for a cluster of 10 workstations.

Step 1 - Using the project floorplan, count the number of locks in each workstation.



Step 2 - Count the number of workstations with the same quantity of locks. Group together the workstations with a like number of locks.

5 workstations with 2 locks per station
3 workstations with 4 locks per station
2 workstations with 5 locks per station

Step 3 - For the first group (5 sets of 2 locks), enter the number of workstations in the quantity column.

Qty	Pattern #	Description	Unit List	Ext. List
5				

Step 4 - Then enter the pattern number "KSPEC_ _" and add a suffix for the number of locks for that group (i.e., for 2 locks per station, add the suffix "2"). Up to 30 lock cores are available in a set (i.e., KSPEC 30).

Qty	Pattern #	Description	Unit List	Ext. List
5	KSPEC 2	Set of 2 cores/keys	N / C	N / C

Step 5 - Repeat for other groups.

Qty	Pattern #	Description	Unit List	Ext. List
5	KSPEC 2	Set of 2 cores/keys	N / C	N / C
3	KSPEC 4	Set of 4 cores/keys	N / C	N / C
2	KSPEC 5	Set of 5 cores/keys	N / C	N / C

Your Key instructions are complete.

Knoll will select key numbers for each set from 250 available numbers. Additional key numbers are available through Custom Product Development. **For additions to existing installations, specify desired key numbers in the description.**

Service Parts

Pattern #	Description	List Price
KKEY_ _ _	Shrouded Key Specify key number desired	\$10
KBLANK	Shrouded Key Blank	\$10
KSPECB_ _ _	Retrofit Universal Core/Key Specify key number desired	\$22
KCHANGE	Change Key	\$10
HLKRKMASTER*	Master Key	\$10

*Note: A letter of approval on company letterhead from the client must accompany all orders for master keys.

General Ordering Information

The Products

This guide encompasses all standard products for this product group.

Sizes

Dimensions listed in this guide are indicated as:

H = height

W = width

D = depth

Dia. = diameter

Rad. = radius

Pricing

All prices shown are list.

How to Order

Select pattern numbers and quantities required for your complete installation. Product questions can be addressed in the specific sections of this guide or by contacting your sales representative or customer resource representative at 1-800-343-5665.

Next, select options (if required), along with colors and finishes appropriate to each product. Reference the Finishes and Fabrics pages for color designations.

On large installations, an item's "designated area" can be specified to assist in product organization and handling.

To expedite complete / correct entry of your order, be certain all pattern numbers, quantities, colors and area identifications are completely specified. Also, include complete purchase order numbers, bill-to and ship-to addresses, a contact name and specific factory shipping dates required.

Mail all orders to:

Knoll, Inc.
1235 Water Street
P.O. Box 157
East Greenville, PA 18041
Attention: Order Entry

Once your order is entered at Knoll, an acknowledgment will be mailed to you. You will be advised of your scheduled shipping date within five days of the original acknowledgment. If it is necessary to revise your order, please contact your customer resource representative.

Sustainability Statement

Sustainable design is a key component of Knoll's environmental focus. Our commitment to social responsibility and a healthy environment has prompted us to further articulate our longstanding environmental programs and, with encouragement and support from our colleagues in the industry, we have re-energized our focus on such "green" initiatives as life cycle analysis and LEED™ certification. Knoll is proud to have contributed to projects that have received LEED certification from the U.S. Green Building Council.

For the latest information on Knoll products that help our customers achieve LEED certification, log on to knoll.com, click on "About Knoll" and then "Environmental Focus."