

TRENWYTH

an Oldcastle® company

premium architectural masonry units

Specifications

Mesastone®

Part 1 – General

SUBMITTAL

Submit color samples for selection from manufacturer's group A, B, C, D or E. Submit product literature, certifications, test reports and full size sample(s) of each color specified.

QUALITY ASSURANCE

Certifications: Concrete blocks for finishing shall conform to ASTM C90. All units contain Trenwyth-approved integral water-repellent CMU admixture at the time of manufacture.

Mold and moisture resistant, Mesastone units will last the life of the building (never paint or refinish). No VOC's. Available in a wider color selection, custom colors and unique shapes and sizes, Mesastone units are ideal for interior and exterior applications. The structural integrity of the unit results in a one-step, single trade installation process. Mesastone units are distributed nationally.

Fire Resistance: Define hourly ratings required by NCMA TEK Notes, available at www.trenwyth.com.

Field Constructed Mock-Ups: Construct a sample panel, no less than 4' x 4', of units of each color and size to be used in the project.

Trenwyth requires ordering a full size unit to illustrate color and texture for approval.

Trenwyth Industries requires a sample panel be installed at the jobsite prior to installation of any Trenwyth product. This panel will represent both the quality of the product and the workmanship to be expected for the project. The panel must be approved by either the owner or architect for the project. Trenwyth will provide 4" units for a 4' by 4' sample panel at no cost for the material (not including freight to site).

DELIVERY, STORAGE AND HANDLING

Mesastone units shall be delivered to the jobsite on covered banded pallets with cardboard between layers. Store pallets in single stacks on level ground and cover with waterproof covering (e.g., tarpaulins) to protect the blocks from inclement weather. Handle blocks carefully to avoid breakage and damage to the finished surfaces.

PROJECT/SITE CONDITIONS

Protection of Work: Cover walls each day after installation to keep open walls protected and dry. After units are installed they should be protected from damage by other trades

performing operations that can stain or otherwise damage the finished surfaces by covering walls with plastic. Corners should be protected from damage after installation by covering them with plywood.

Part 2 – Products

PRODUCT NAME

Mesastone® textured concrete masonry units.

MANUFACTURER

Trenwyth Industries (800) 233-1924
One Connelly Road, Emigsville, PA 17318

Trenwyth Industries (800) 358-3003
3400 E. Bungalow Road, Morris, IL 60450

Trenwyth Industries (800) 331-9823
4626 N. 42nd Avenue, Phoenix, AZ 85019

RELATED MATERIALS

Colored matching or contrasting mortar is available at Trenwyth Industries. Consult NCMA TEK Notes, available at www.trenwyth.com, for mortar type and specifications. In all exterior mortar, use matching Trenwyth-approved water-repellent mortar additive, following manufacturer's instructions. Consult manufacturer for recommendations.

SIZES AND SHAPES

Nominal 2", 4", 6", 8", 10" and 12" standard block thickness are available as well as all standard block shapes. High-strength units for special structural requirements, over-sized units, and metric shapes and sizes are also available.

Masonry cleaners

Use Burnished Custom Masonry Cleaner by PROSOCO (dilute 1 part to 15 parts clean water), carefully following manufacturer's instructions. Available at Trenwyth Industries. **Do not powerwash.**

CAUTION! Never use Muriatic Acid solution or any cleaner containing acid on units.

Part 3 – Execution

LAYING MASONRY WALLS

Draw blocks from more than one pallet at a time during installation. All exterior mortar shall include matching water-repellent additive added to each batch in the appropriate dosage rates for mortar type (M, S or N) per manufacturer's instructions. Refer to NCMA TEK Notes, available at



premium architectural masonry units

Specifications

Mesastone®

www.trenwyth.com, for Hot and Cold weather construction practices.

Lay units using the best concrete masonry practices. Install only quality units; reject all defective units as defined by ASTM C90. Lay blocks with the faces level, plumb and true to the line strung horizontally at the ground face. Units shall have uniform, 3/8"-wide joints both horizontally and vertically on the finished side of the wall. Tool joints neatly after they are finger-hard to make them straight and uniform. Size and place cut pieces appropriately to maintain consistency and bond. Complete masonry construction using procedures and workmanship consistent with the best masonry practices.

INSTALLATION

Lighting: Provide adequate lighting for masonry work by placing all lighting at a reasonable distance from the wall for even illumination. Do not use trough lighting.

Cutting: Make all unit cuts, including those for bonding, holes, boxes, etc., with motor-driven masonry saws, using either an abrasive or diamond blade. Cut neatly and locate for best appearance.

Mortar Bedding and Jointing:

1. Lay units with full mortar coverage on head and bed joints taking care not to block cores to be grouted or filled with masonry insulation.
2. Tool all mortar joints when thumbprint hard into a concave configuration.
3. Care should be taken to remove mortar from the face of masonry units before it sets.
4. Tuckpoint the joints of scored units for proper appearance. All exterior scored units must be tuckpointed to prevent water penetration. **NO RAKE JOINTS.**

FLASHING OF MASONRY WORK

Install flashing at locations shown in the plans and in strict accordance with the details and the best masonry flashing practices.

WEEP HOLES AND VENTS

Install weep holes and vents at proper intervals at courses above grade and at any water stops over windows, doors and beams. Consult NCMA TEK Notes, available at www.trenwyth.com, for additional flashing information.

INSPECTION

The textured faces shall conform to the requirements of ASTM C90 when viewed from a distance of twenty (20) feet at right angles to the wall with normal lighting.

CLEANING

Keep walls clean daily during installation using brushes. Do not allow excess mortar lumps or smears to harden on the finished surfaces. Harsh cleaning methods after walls have been erected may mar the surface of the blocks.

FINAL CLEANDOWN

Clean the completed walls with PROSOCO Burnished Custom Masonry Cleaner (dilute 1 part to 15 parts clean water), strictly following the manufacturer's instructions — including thorough rinsing. Do not use acid or abrasives on the finished surfaces. Failure to strictly follow manufacturer's instructions can result in permanent damage to the finished faces. **Do not powerwash.**

High-pressure power washing may interfere with the performance of the integral water-repellent additives and cause efflorescence. (Maximum psi is 50)

MAINTENANCE

Mesastone units, properly installed and cleaned, need virtually no maintenance other than routine cleaning. For tough stains, contact manufacturer for specific cleaning recommendations.

Installation Recommendations

Consult NCMA TEK Notes, available at www.trenwyth.com, for proper installation of concrete masonry units.

Limitations

- The facing is not intended for use as an impervious surface.
- Acid solutions and HCL acid-based cleaners should not be used as a cleaning agent or in direct contact with the facing.

To download a printable version of these specifications, please visit <http://www.trenwyth.com>.